

FEBRUARY 1986

VOL. 4, No. 2 \$3.95

FOR IBM PERSONAL COMPUTER USERS

# TECH JOURNAL<sup>®</sup>



**3278/79 EMULATION**

**EXPANDED MEMORY**

**3-D DRAWING WITH MEGA CADD**

**DATA MANAGER: REVELATION**

**SETS IN ASSEMBLY LANGUAGE**




0



# We'll Send You a Bug ...

Because...that's the only way you'll get any after using H.E.L.P.™



**H.E.L.P.™** is a multi-window C programming environment which runs in virtual memory under MS-DOS.

## Stops Bugs...Interactively

Say "Good-bye" to errors which have been halting your compilations. H.E.L.P.™ will hunt down bugs, explain the error in plain English, offer suggestions and corrective measures...and will even make the corrections automatically with the press of a key. Upon making the correction, H.E.L.P.™ then goes on looking for the next problem.

## Batch Mode

As an option, you may place several programs on a module list...put H.E.L.P.™ into batch mode...then stand back! Automatically, H.E.L.P.™ will locate bugs and create an error list. From this error list you may print it, save it, and/or correct the errors interactively.

## Checks For Consistencies

H.E.L.P.™ will examine your code across modules to check the usage of externals as well as functions and parameter usage. This means your modules will pass through the linker with far fewer errors.

MS DOS is a registered trademark of Microsoft, Inc.  
H.E.L.P. is a trademark of Everest Solutions, Inc.

**Order Line 800-621-0854 ext 923**



**Everest Solutions**

3350 Scott Blvd. Bldg 58  
Santa Clara, CA 95051  
(408) 986-8977

Where there's H.E.L.P.™ there's help!!

H.E.L.P.™ tracks every step you make...press the help key and you are presented with a window full of assistance. There's even a Help Search Key so that you can look up any topic or string within the help subsystem.

H.E.L.P.™ will positively find every syntax and semantic error which would have caused your code to fail at compilation.

## Have It Your Way

Navigate through all the incredible features of H.E.L.P.™ using POP-UP menus...or you may by-pass the menus by binding commands to keys... (user definable).

## Full-Blown Editor

Edit code in as many windows as you want...there are no limitations! Move or copy text within a window or to an entirely different window.

## Virtual Memory

H.E.L.P.™ uses the power of main frames running in virtual memory... this means you may create a program or work space larger than the actual RAM memory of your system.

Please send me \_\_\_\_\_ copies of H.E.L.P.

NAME \_\_\_\_\_

ADDRESS \_\_\_\_\_

CITY \_\_\_\_\_ ZIP \_\_\_\_\_

STATE ( ) \_\_\_\_\_


PHONE ( ) \_\_\_\_\_

☐ VISA ☐ M/C

Account # \_\_\_\_\_

Exp. date \_\_\_\_\_

Order Line  
800-621-0854 ext. 923



H.E.L.P.™ makes your computer feel like a main frame... and increase productivity by 300% and more.



# ZIM 2.5 A DBMS REVOLUTION

Have you been looking for perfect data management that you can enjoy on your own terms? Then you've probably already heard of ZIM 2.4 — the most powerful database system available. Until now. Because ZIM 2.5 is here.

ZIM 2.5 is a fourth generation application development tool which makes it possible to expand the capabilities of your micro beyond what you've ever imagined. ZIM mirrors the complexities of the real world by letting you develop as many and as varied applications as you could possibly need.

*"ZIM is...a successful migration of mainframe ideas and needs to a micro. (ZIM) proves not only that the job can be done but also that it can be done well. ZIM provides a reference against which current and future data bases can be judged."* James Creane, Data Based Advisor/July 1985.

**Speed**  
ZIM breaks the speed limit — between 3 and 50 times faster than industry leaders in sorting and joining files within the data-base. ZIM's internal architecture, and the implementation of its strategy analyzer and priority-driven buffering ability, ensure that data is processed in the most efficient manner possible.

**Portability**  
ZIM is the only database management system with 100% application portability for single-user and multi-user configurations. ZIM is available under PC-DOS, Concurrent PC-DOS, UNIX, XENIX, and QNX. Never again will you be required to re-write your applications for different operating systems environments.

## Power

ZIM's high-level language lets you build user commands which implement applications without the necessity and cost of additional programming tools. ZIM's forms facility and extensive report generator permit completely menu-driven applications. Completed compiled, applications use the Runtime System, leading to fast execution, preventing unauthorized access or modifications, and decreasing cost and memory requirements.



## Flexibility

ZIM gives you unprecedented simplicity and flexibility. ZIM commands parallel simple English sentences, making it easy to learn and use. Other features include automatic updates of all indexes, multi-user support, and an extensive range of validation, editing and masking facilities. ZIM's limits are only those of your hardware, operating system and imagination. And with ZIM 2.5, your database is no longer limited to a single hard disk.

*"ZIM is (a) well-conceived, soundly-implemented, thoroughly professional system. Its design evidences a strong commitment to consistency and to the goal of natural nonprocedural user interaction."*

Richard M. Foard, PC Tech Journal,  
October 1985.

**ZIM 2.5 — DATA  
MANAGEMENT AT  
ITS BEST**



1785 Woodward Drive  
Ottawa, Ontario K2C 0R1  
(613) 727-1397




**ZANTHE**  
INFORMATION INC

CIRCLE NO. 148 ON READER SERVICE CARD





# If lightning still scares you, you're using the wrong file manager.



## Be sure. Btrieve.<sup>®</sup>

Lightning may strike. But it doesn't have to destroy your database.

**Btrieve<sup>®</sup>** file management offers automatic file recovery after a system crash. So accidents and power failures don't turn into database disasters. Your Btrieve-based applications will come up when the lights come back on.

**Fast.** Btrieve is lightning fast, too. Its b-tree file structure automatically balances—you never waste time reorganizing the index. And Btrieve is written in Assembly language especially for the IBM PC. The result: electrifying speed on file maintenance routines. Applications that run fast. Users who don't waste time waiting.

**The standard for networking.** When your application requires multi-user file sharing, Btrieve/N (network version) sets the standard for the industry's most popular LANs: IBM's PC Network, Netware, PC Net and EtherSeries. And now Btrieve sets the standard for multi-user systems: XENIX, Multi-

Link Advanced and others. Btrieve/N offers **safe** network file management that coordinates simultaneous updates and protects against lost data.

**Fully-relational data management.** Using SoftCraft's entire family of products gives you a complete, fully-relational database management system. Rtrieve<sup>™</sup> adds report writing capabilities for generating the reports you need. Xtrieve<sup>™</sup> speeds users through database queries with interactive, on-screen menus—no command language or special syntax.

**For professional programmers.** Btrieve is the fast, reliable answer for all your application development. In any development language—BASIC, Pascal, COBOL, C, FORTRAN and APL. With multikey access to records. Unlimited records per file. Duplicate, modifiable, and segmented keys.

With Btrieve, you can develop better applications faster. And know they'll be safe if lightning strikes.

## NO ROYALTIES


*Suggested retail prices: Btrieve, \$245; Btrieve/N, \$595; Xtrieve, \$195; Xtrieve/N, \$395; Rtrieve, \$85; Rtrieve/N, \$175. Requires PC-DOS or MS-DOS 1.X, 2.X, or 3.X.*

*Btrieve is a registered trademark and Xtrieve and Rtrieve are trademarks of SoftCraft Inc.*


**SC**  
**SoftCraft Inc.**

P.O. Box 9802 #917  
Austin, Texas 78766  
(512) 346-8380 Telex 358 200





88



108



66

## EMULATING THE 3278 / ROGER ADDELSON

These eight packages are worthy of consideration for systems using PCs as workstations in an IBM mainframe environment.

48

## EXPANDABLE MEMORY / TED MIRECKI

The danger of PCs becoming obsolete because of insufficient memory is lessened by the Expanded Memory Specification.

66

## THREE-DIMENSIONAL MODELING / VICTOR E. WRIGHT

MEGA CADD's wire frame modeler, called the Design Board Professional, turns the IBM PC into a 3-D modeling machine.

88

## SET IMPLEMENTATION / TOM SWAN

Assembly language programmers may be pleasantly surprised when they borrow a concept from higher-level languages: sets.

108

## STORAGE ON A CARD / THOMAS V. HOFFMANN

Plus Development Corporation has squeezed a 10MB 3 1/2-inch Winchester disk and controller onto a single expansion card.

139

## STORAGE EXPANSION FOR THE AT / THOMAS V. HOFFMANN

IBM's new 30MB fixed disk, included with its model 239 PC/AT, is also available as an upgrade for the original AT or the 239.

147

## VENIX: SETTING UNIX STANDARDS / AUGIE HANSEN

The development of AT&T System V-compatible VENIX for the PC/XT and PC/AT is a positive step toward a common UNIX.

153

## A DATA MANAGER DESIGNED FOR COMPLEX APPLICATIONS / KENT PHELPS

Interfacing with minicomputers is one feature of the powerful Revelation, a PICK-inspired data manager by Cosmos.

160

11

### DIRECTIONS

*Impressions from COMDEX*

15

### LETTERS

31

### PRODUCT OF THE MONTH

*The Hardcard*

32

### TECH RELEASES

45

### TECH NOTEBOOK

*Tracing Expanded Memory*

181

### PROGRAMMING PRACTICES

*Filters and Finite Machines*

193

### LEGAL BRIEF

*The Total Solution*

197

### BOOK REVIEWS

*Teaching Computers  
to Think*

200

### TECH BOOK

206

### TECH MART

209

### CALENDAR

211

### READER SERVICE CARD



# PRODUCTIVITY TOOLS

From Opt-Tech Data Processing

NEW

## On-Line Help

NEW

A comprehensive utility for adding help windows to your programs. It provides an efficient method for storing help screen messages in libraries and includes standard routines for interfacing your programs with these libraries.

Help windows are displayed in a fraction of a second. You have total control over the contents of the window, its position on the screen and the display colors used. On-Line Help automatically restores your screen when the operator presses a key.

On-Line Help can be interfaced with interpreted Basic and all popular compilers.

On-Line Help includes a Help Library Manager, Library Interface Routines and source code examples. **\$149.**

## Opt-Tech Sort

High performance sort/merge utility can be used as a stand-alone program or called as a subroutine to most languages.

Supports unlimited filesizes, multiple input files and fixed or variable length records. Many special file types are supported including Btrieve and Dbase. Up to nine sort control fields (ascending or descending), all common data types supported. Output file can be full records, keys or pointers.

Written in assembly language for **high performance**. Example: 4,000 128 byte records sorted to give key and pointer in 30 seconds. **\$99.**

## Scroll & Recall

Allows you to conveniently scroll back through data that has gone off the top of your display screen. Up to 27 screens of data can be recalled or written to a disk file (great for documenting systems operations).

Allows you to easily recall and edit your previously entered DOS commands and data lines without re-typing.

Scroll & Recall is very easy to use. It's a resident utility that's always there when you need it! **\$69.**

All programs fully documented and are compatible with the IBM-PC, XT, AT and compatible machines using the DOS operating system.

Visa, M/C, Check, Money Order, COD  
or Purchase Orders accepted.

Quantity and Dealer Discounts Available

To order or to receive additional  
information write or call:

**Opt-Tech Data Processing**

P.O. Box 678 - Zephyr Cove, NV 89448  
(702) 588-3737

# TECH JOURNAL

VOL. 4, NO. 2

**PUBLISHER:** Newton Barrett  
**EDITOR:** Will Fastie

### EDITORIAL

**MANAGING EDITOR:** Marjory Spraycar  
**EXECUTIVE EDITOR:** Julie Anderson  
**TECHNICAL EDITORS:** Jeff Duntmann, Caroline Halliday  
**ASSOCIATE TECHNICAL EDITOR:** Dan Beale  
**SENIOR COPY EDITOR:** Susan Holly  
**COPY EDITOR:** Gail Shaffer  
**PROOFREADER:** Kathleen Peddicord  
**CONSULTING EDITOR:** Thomas V. Hoffmann  
**CONTRIBUTING EDITORS:** Steven Armbrust, Don Awalt, Michael Covington, Richard Foard, Ted Forgeron, Augie Hansen, Ted Mirecki, Max Stul Oppenheimer  
**ADMINISTRATIVE ASSISTANT:** Paula Lamberti  
**EDITORIAL ASSISTANT:** Carole Autenzio

### ART & PRODUCTION

**ART DIRECTOR:** Ina Saltz  
**ASSOCIATE ART DIRECTOR:** Sharon Reuter  
**ASSISTANT ART DIRECTOR:** Sandra Ray  
**ART SECRETARY:** Sabrina Reynolds  
**ADVERTISING PRODUCTION MANAGER:** Lisa Franey Ducey  
**EDITORIAL PRODUCTION COORDINATOR:** Eve Hinderer

### ADVERTISING SALES

**ADVERTISING DIRECTOR:** Rita Burke  
**MARKETING COORDINATOR:** Julie Henderson  
**ADVERTISING COORDINATOR:** Michele Fischetti  
**DISTRICT MANAGERS:** Rosemarie Caruso, Jan Schultz—East Coast; Lisa Kampfmann—Midwest; Ted Babr, Bill Bush, Phyllis Egan—West Coast  
**ACCOUNT REPRESENTATIVES:** Pat Toobey, Jane Anderson—East Coast; Arlene Braithwaite—Midwest; Pam Sigal, Jane Anderson—West Coast

### CIRCULATION

**CIRCULATION MANAGER:** Charles Mast  
**CIRCULATION SALES DEVELOPMENT:** Daniel Rosensweig  
**MEDIA MANAGER:** Melinda Kendall

### ZIFF-DAVIS PUBLISHING COMPANY

**PRESIDENT:** Kenneth H. Koppel  
**VICE PRESIDENT, Operations:** Baird Davis  
**VICE PRESIDENT, Creative Services:** Herbert Stern  
**VICE PRESIDENT, Circulation:** Alicia Marie Evans  
**VICE PRESIDENT, Circulation Services:** James Ramaley  
**VICE PRESIDENT, Marketing Services:** Ann Pollak Adelman  
**VICE PRESIDENT:** Hugh Tietjen  
**MARKETING MANAGER:** Ronnie Sonnenberg  
**BUSINESS MANAGER:** Gary A. Gustafson  
**EDITORIAL DIRECTOR:** Ernest F. Baxter

### ZIFF COMMUNICATIONS COMPANY

**PRESIDENT:** Philip B. Korsant; **EXECUTIVE VICE PRESIDENT:** James D. Dunning, Jr.; **SENIOR VICE PRESIDENTS:** Philip Sine, Kenneth H. Koppel; **VICE PRESIDENTS:** Laurence Usdin, Rory Parisi, William L. Phillips, J. Malcolm Morris, Steven C. Feinman; **TREASURER:** Selwyn Taubman; **SECRETARY:** Bertram A. Abrams

### EDITORIAL OFFICE

PC TECH JOURNAL, The World Trade Center, Suite 211, Baltimore, MD 21202.  
301/576-0770. FAX (group 3): 301/576-9603. MCIMail: PCTECH. PCTECHline:  
301/576-PCITJ. Telex: 6502565932 MCI.

### ADVERTISING OFFICES

(East Coast/Midwest) One Park Ave., New York, NY 10016. 212/503-5185.  
(West Coast) 3460 Wilshire Blvd., Los Angeles, CA 90010. 213/387-2100;  
11 Davis Drive, Belmont, CA 94002. 415/598-2290.

### SUBSCRIPTION INQUIRIES

PC TECH JOURNAL, P.O. Box 2968, Boulder, CO 80321. Subscription service:  
800/525-0643, 303/447-9330. Back issues: send \$7.00 per copy to PC TECH  
JOURNAL, Back Issues, One Park Avenue, New York, NY 10016.

PC TECH JOURNAL (ISSN 0738-0194) is published monthly, \$29.97 for one year, \$52.97 for two years, \$69.97 for three years. Additional postage \$12 for Canada & Foreign by Ziff-Davis Publishing Company, One Park Avenue, New York, NY 10016. Second-Class Postage paid at New York, NY and at additional mailing offices. POSTMASTER: Send address changes or subscription inquiries to P.O. Box 2968, Boulder, CO 80321.

PC TECH JOURNAL is an independent journal, not affiliated in any way with International Business Machines Corporation. IBM is a registered trademark of International Business Machines Corp. Entire contents Copyright © 1986 Ziff-Davis Publishing Company. All rights reserved; reproduction in whole or in part without permission is prohibited. Direct written requests to Jean Lamensdorf, Licensing Manager, Reprints/Rights & Permissions, One Park Avenue, New York, NY 10016.





# Introducing Periscope II

## Professional Debugger with Break-out Switch

30-Day  
Money-Back Guarantee

### What Users Say:

"Very powerful for debugging and testing. Great product! Better than Atron by far."

—Wynn Bailey

[Periscope is] "the most essential element of my 'developer's tool box' . . . Every PC used for development at Microstuf has a Periscope board installed and in use on a daily basis . . . Anyone trying to write software on a PC who's not using Periscope is wasting either time, money, or both."

—Jeff Garbers

Now there are TWO Periscopes! The original "board" model includes the write-protected RAM board. It is called Periscope I. The new "software" model does not include the write-protected RAM board. It is called Periscope II. We specify 'I' or 'II' only for features not in both models.

**Periscope is "Always there with just a push of the button."** Install the switch and software, then go about business as usual. Until your system hangs or the keyboard locks up or you just get curious about what's going on . . . then press the break-out switch and Presto! Periscope's debugging power is at your command. When you return to the executing program, it won't even know that Periscope has been there.

**Save time with symbols and source code.** They give you a roadmap through memory! Periscope uses names—symbols—from your program so you don't have to remember addresses. It displays source code and line numbers from high-level languages, too. You save hours of time because you access what you need with familiar names!


**Can debugging be fun?** With Periscope it can! Here's why:

**It's Fast!** Written entirely in assembler to save you time.

**It's Easy!** Commands similar to Debug's, optional on-line help, quick-reference card, tutorial, 150+ page manual, and support direct from the author—all you need to get up to speed quickly.

**It's Flexible!** You can:

- Enter Periscope via break-out switch, program loader, or assigned keys
- Define up to four windows for data, register, stack, and disassembly information; change them any time
- Display memory in ASCII, byte, word, double word, integer, or signed integer
- Design your own templates to display memory in easy-to-read formats
- Customize Periscope with your own programs via the user exit capability
- Assign frequently-used commands to function keys



*The break-out switch really sets Periscope II apart from typical software-only debuggers. It installs easily, without taking an extra slot.*

**It's all there!** Periscope includes all the standard debugger features, plus extras like supporting the use of one or two monitors, enabling you to search for address references, etc. The latest version includes new and enhanced features to help you debug your programs faster and easier than ever before:

<b>New!</b>	In-line Symbolic Assembler
<b>Enhanced!</b>	75+ Breakpoint Options
<b>New!</b>	Traceback
<b>Enhanced!</b>	Optional Windows
<b>New!</b>	Source-Level Debug
<b>New!</b>	View text files
<b>New!</b>	EGA Support
<b>New!</b>	User Exits
<b>New!</b>	8087/80287 Status
	Much More!

**Periscope's unique breakpoint power forces bugs out from where they hide!**

With over 75 breakpoint options, including both temporary and sticky code breakpoints, you'll find elusive bugs fast. For instance, you can break on register, byte and word values; stop on execution of source lines and interrupts; break on reads and writes to ranges of I/O ports and ranges of memory using various tests. The memory breakpoint is great for debugging C programs with broken pointers. You can even write your own custom breakpoint tests!

**Periscope requires:** An IBM PC, XT, AT or close compatible; DOS 2.0 or later; 128K RAM; Disk Drive; an 80-column Monitor.

### What Reviewers Say:

"This product is a reliable and useful tool for any programmer's workshop. A number of innovative, helpful features are yours for the taking."

—Programmer's Journal

"Periscope has excellent on-line help. We were impressed by Periscope's very fast response in all its operations. It is a pleasure to use, and a refreshingly different product . . . offers great value and unique advantages."

—Boston Computer Society

**Debug any program, any time!** Periscope is, in one user's words, "Robust". Use it to debug almost any program, even device drivers, memory-resident, and non-DOS programs. Debug when DOS is broken; debug DOS. Periscope won't let you down when you need it.

**User calls Periscope I "Bulletproof"!**

The installation program in Periscope I loads the crucial debugger software into the RAM board and write-protects it. No runaway program can touch this code! Coupled with the break-out capability and the built-in reliability of the software, this protection gives you the most powerful crash recovery system available.

"**Outstanding value for the services offered**" writes one user. "**Worth the price!**" writes another. With the 30-Day Money-Back Guarantee, you can't lose! If you're not satisfied with Periscope for any reason, just return it within 30 days of receipt for a full refund.

**Periscope I:** Board, Switch, Software, Manual, Reference Card . . . Just \$295.00

**Periscope II:** Switch, Software, Manual, Reference Card . . . . . Only \$145.00

**The U.S. Navy gets Periscopes from us . . . shouldn't you? Order today!**

**For Immediate Shipment Or More Information, Call Toll-Free**



**800-722-7006**



**Get Your Programs Up and Running:**

**UP PERISCOPE!**

**DATA BASE DECISIONS**

14 Bonnie Lane • Atlanta, GA 30328  
404/256-3860



# Achieving a LAN Milestone.

## Comprehensive Fault Tolerance for LANs.

In the development of any product or system, only a select few breakthroughs or advancements in technology are significant enough to qualify as milestones. Novell's introduction of System Fault Tolerant (SFT) NetWare is one of those milestones.

What makes SFT NetWare so significant? After all, other fault tolerant systems preceded the development of SFT NetWare. Even more important, who needs fault tolerance?


### Data Disaster

Anyone who cannot afford to lose valuable data stored in a computer system needs fault protection. Whether for more traditional mini and mainframe systems or the office automation newcomer, local area networks, protecting against loss of data is a number one priority.

As the number of LAN systems being used to share information in business and industry continues to rapidly increase, the importance of LAN fault tolerance grows. Because as more and more data is stored and shared in a LAN system, the specter of a major data disaster looms larger and larger. And the need to avert such a disaster becomes critical.

While the distributed processing environment of personal computer

LANs provides users with many inherent fault tolerant features, failure can still occur. By greatly reducing the possibility of failure



and providing recovery capabilities, SFT NetWare represents a technological leap in fault protection for LANs. The result of that leap is higher system dependability to accompany the high degree of system flexibility and performance already provided by NetWare-supported local area networks.

### Affordability

To make fault tolerance affordable for all LAN users, Novell designed SFT NetWare to utilize off-the-shelf components. In addition, the company wrote SFT NetWare to support 25 major LAN hardware systems.

These two important SFT NetWare characteristics effectively reduce the cost of SFT NetWare to a mere fraction of the cost of other fault tolerant systems. Instead of having to pay for a complete, new proprietary system to get fault protection, in most cases LAN users can now simply add fault tolerance capabilities to their existing LAN systems.

And three varying levels of SFT NetWare allow users to tailor their fault tolerant LAN systems to their specific needs and budgets.

### SFT NetWare Level I

Level I provides basic directory and data fault prevention for LAN systems at a minimal startup cost.

Through several specific functions like redundant directory structures, read-after-write verifications, and error detection and correction, SFT NetWare Level I protects and preserves data in case of disk media failure.

A particularly innovative function of Level I is Hot Fix. If a faulty area of the disk is encountered during the read-after-write verification, it is marked as "bad" and listed in the bad block table. The data is then relocated to a known good area without affecting the normal operation of the workstation and server interchange of information.



## SFT NetWare Level II

While the Level I Fault Tolerant System is designed to prevent basic directory and data faults, Level II provides an additional measure of safety through mirroring and duplication of all data. At this level, fault tolerant data storage for the LAN is accomplished either by duplicate storage units on a single controller (mirroring), or by doubled components, including controllers, drives and power supplies (duplexing).

Having duplicate drives, controllers and channels allows "split seeks" to occur on disk reads. The server examines each read request and determines which drive can respond to service the request most quickly. When two or more read requests are presented to the server, they split and occur simultaneously, effectively doubling the system read performance.

## SFT NetWare Level III

Level III combines all of the LAN fault tolerant functions of Levels I and II with duplexed file server operation. Two file servers are interconnected using high-speed bus transfer hardware.

If one server fails, the other server automatically takes over network operation. When the failed server is repaired, it resumes its normal network functions. The entire sequence is completed without downtime or loss of data, and is totally transparent to the user and to the application software running on the workstation.

## Transaction Tracking System

A major feature of SFT NetWare Levels II and III is the Transaction Tracking System (TTS). TTS ensures that the LAN system views data-

base changes as a single unit of work (a transaction) which will be either wholly completed or wholly backed out.

If a system failure occurs during a transaction, TTS rolls back all database changes made by the transaction, returning the database to its previous point of consistency. Only the failed transaction is lost, leaving the database in its original form (before the transaction was begun).

During normal operation, TTS records periodic "snapshots" of

**"Anyone who cannot afford to lose valuable data stored in a computer system needs fault protection."**

its database files, as well as an audit trail of updates made since the most recent snapshot. In the event of a catastrophic system failure, TTS performs a rollforward recovery, restoring data to the point of the last snapshot, then applying the audit trail to reconstruct remaining files from the archive copies.

With TTS functioning, virtually any real-time application—such as spread sheets, accounting systems, database managers—can be implemented on the LAN system with disaster prevention.

## Summary

The impact of SFT NetWare on the

future of local area networking is most significant. Just as the file server revolutionized the industry and set a standard of LAN performance, System Fault Tolerant NetWare is setting a new standard of LAN reliability.

With that reliability comes all the functionality of NetWare LAN Operating System software. Advantages like unsurpassed speed, multilevel security, and over 2,000 available applications. Plus DOS 3.1 compatibility, allowing NetWare to run any applications written for the IBM Networks.

And because SFT NetWare runs on 25 major LAN hardware systems and utilizes off-the-shelf components, an affordable system of fault tolerant data protection is available right now for the majority of LAN system users.

Although no LAN system can guarantee against any failure, SFT NetWare makes enormous strides in reducing the possibility of failure. This major milestone in LAN technology means greater

safety of LAN system data and improved efficiency in LAN operation, for surprisingly little cost.

For more information, order the SFT NetWare Technical Description by writing or calling:

**Novell, Inc.**  
748 North 1340 West  
Orem, Utah 84057  
(801) 226-8202






# It's amazing what you can reveal when you strip.

Introducing a shape that's about to turn on an entire industry.

The Softstrip™ data strip. From Cauzin.

This new technology allows text, graphics, and data to be encoded on a strip of paper, then easily entered into



The Cauzin Softstrip System Reader replaces tedious typing by scanning the strip and reading it into your computer.

your computer using a scanning device called the Cauzin Softstrip™ System Reader.

Creating a simple, reliable and cost efficient way to distribute and retrieve information.

Softstrip data strips, like those you see here, can contain anything that can be put on magnetic disks.

Facts. Figures. Software programs.

Video games. Product demonstrations.

Sheet music.



The Cauzin Softstrip System Reader is now compatible with the IBM PC, Apple II and Macintosh.

A single strip can hold up to 5500 bytes of encoded data.

It can stand up to wrinkles, scratches, ink marks, even coffee stains.

And it can be entered into your computer with a higher degree of reliability than most magnetic media.

Simply by plugging the Cauzin Reader into your serial or cassette port and placing it over the strip.

The reader scans the strip, converts it to computer code, and feeds it into any standard communication interface.

Because strips are so easy to generate, most of your favorite magazines and books will soon be using them in addition to long lists of program code.


And you'll be able to enter programs without typing a single line.

There is also software for you to generate your own strips.

Letting you send everything from correspondence to business information using our new technology.

Find out how much you can reveal by stripping. Just take this ad to your computer dealer for a demonstration of the Cauzin Softstrip System Reader.

Or for more information and the name of the dealer nearest you, call Cauzin at 1-800-533-7323. In Connecticut, call 753-0150.



Soon everyone will be stripping as data strips appear in popular magazines, computer books and text books.



Cauzin Systems, Inc.  
835 South Main St., Waterbury, CT 06706

CIRCLE NO. 156 ON READER SERVICE CARD



**Here are two programs  
you can run by stripping.  
Just take this ad to  
your dealer for a  
demonstration.**

**1 TURBO PASCAL GRAPHICS DEMO**

These strips contain all the source code for a Turbo Pascal™ program to demonstrate graphics. To use it on an IBM PC or compatible, read in the strips with a Softstrip™ Reader and then treat just like any other Source file for Turbo Pascal. (If you don't have a PC or Turbo Pascal, you can still read the source code. The file is standard ASCII text.)

**2 STRIP DEMO WITH LOTUS**

These strips contain a complete LOTUS™ worksheet file that demonstrates and explains the power of Softstrip™ technology. To view the demo, just read the strips into an IBM PC or compatible and retrieve them from a blank LOTUS worksheet (eg. /FR).

**Softstrip**

**Softstrip**

1a

1b

2a

2b



# Atron's PC/AT Bugbusters

*Hardware-assisted Software Debuggers for Bullet-proof PC/AT-based Products*

## A BUGBUSTER STORY

Brad Crain, a project manager at Software Publishing (the people who developed both PFS:WRITE and PFS:FILE), relates the following: "On Friday, March 22, 1985, I was about to get on an airplane with Jeff Tucker, who was co-author of PFS:WRITE with me, and fly to IBM's Boca Raton, Florida facility. For a week, we had been unsuccessfully trying to isolate a bug in a new software product. In a last, desperation move, I set up an early-Saturday morning appointment with ATRON.

"Three of us walked through ATRON's door at 8:00 the next morning. Using ATRON's hardware-assisted debugging tools, we had the problem identified and fixed by 10:30AM."

Mr. Crain concludes: "We'd never have found the bug with mere

software debuggers, which have the bad habit of getting over-written by the very bugs they're trying to find. It doesn't surprise me that almost all the top-selling software packages were written by ATRON customers. Now that they've broadened their PC family of debuggers to include a PC/AT debugging tool, those of us seriously into 80286 development are greatly relieved."

## ARE YOU TRYING TO DO SOMETHING SCAREY?

Like developing your AT-based software product in the dark? Without professional debugging tools?

Seven of the ten top-selling software packages listed by the *THE WALL STREET JOURNAL*\* were produced by ATRON customers. The PC PROBE™ bugbuster (\$1595) accounts for much of this success. Now that the PC/AT is the new standard for advanced commercial and scientific development, ATRON is proud to announce the AT PROBE™ bugbuster (\$2495). It has even more debugging capabilities than the PC Probe.

## HOW BUGBUSTERS KEEP YOU FROM GETTING SLIMED

The AT PROBE is a circuit board that plugs into your PC/AT. It has an umbilical which plugs into your 80287 socket and monitors all processor activity.

Since AT PROBE can trace program execution in real time, and display the last 2048 memory cycles, you can easily answer the questions: "How did I get here?" and "What are the interrupts doing?"


It can solve spooky debugging problems. Like finding where your program overwrites memory or I/O - impossible with software debuggers.

You can even do source-level debugging in your favorite language, like C, Pascal or assembler. And after your application is debugged, the AT PROBE's performance-measurement software can isolate your application's bottlenecks.

Finally, the AT PROBE has its own 1-MByte of memory. Hidden and write-protected. How else could you develop that really large program, where the symbol table would otherwise demand most of your PC/AT memory.

## BORLAND'S PHILIPPE KAHN: "THERE WOULDN'T BE A SIDEKICK™ WITHOUT ATRON'S DEBUGGERS."

So why waste more time reading though your program listing for the ten thousandth time, trying to find why your program starts howling with every full moon. Be like BORLAND, get your Atron bugbuster today and bust bugs tomorrow.



**atron**  
THE DEBUGGER COMPANY

20665 Fourth Street • Saratoga, CA 95070 408/741-5900

\*WSJ, June 24, 1985, reporting Softsel figures. © 1985 by ATRON. PC PROBE™ and AT PROBE™ ATRON. SIDEKICK™ Borland. IBM Corp. owns numerous trademarks. Ad by TRBA.

CIRCLE NO. 203 ON READER SERVICE CARD



# Impressions from COMDEX

*Surprises? Not many, but we did find some indicators of future direction.*

Without a doubt, the Fall COMDEX has become the desktop computer industry's most important trade show. The proof is in the judge's mouth: although many vendors griped about last year's mediocre turnout, the show's dullness, the high cost of show space, and the miserable weekend scheduling, COMDEX this year drew at least as many vendors, filling the entire convention center and four hotels with exhibits. On Friday, the middle day of five, the aisles were crowded; attendance seemed heavier than last year.

*PC Tech Journal* added to that attendance. Six of our editors and five of our contributing editors spent a full three days on the show floor scouring booths for even a hint of excitement. Brief comments from the other editors are presented on the next page; here are my impressions.

**Atari 520ST.** It may seem strange for me to report on an entirely different product line, but concentrating, as we do, on the IBM standard is sometimes like wearing blinders because the standard makes new developments seem natural, almost expected. Seeing other work on other types of computers is refreshing and provides different perspectives.

The new Atari might actually succeed *if* Atari can keep the cash flowing and *if* the 520 is built well and *if* distribution can be developed and maintained, etc.—all big *ifs*. At COMDEX, Atari had a slew of third-party software developers take over its booth to show their wares. It was an impressive sight. Ataris could even be found in other booths. And, best of all (for Atari, that is), neither Commodore nor its Amiga was anywhere in sight.

The prevailing opinion is that the low cost of the ST, as compared with Amiga, is the lure. The ST is a closed machine; such vibrant aftermarket activity can mean only that developers believe in the hardware. This is an interesting lesson for the low-end players. I




ILLUSTRATION • MACIEK ALBRECHT

would have to have a *very* good reason to suggest buying a PCjr now.

**Expanded memory.** The biggest surprise for me was the widespread acceptance that the Lotus/Intel/Microsoft Expanded Memory Specification (LIM EMS) has received. In just a little more than six months, 30 major programs either have been converted or are undergoing work to make them compatible with the expanded memory spec.

Some companies are building software products that can *execute* out of EMS. At first, the product was largely touted as a place for *data* because Lotus announced that 1-2-3 version 2.0 would support EMS, thus allowing larger spreadsheets to be constructed. Expanding the executable memory space is much more important, however, if judged by nothing else than the popularity of resident software and the ability of products such as Microsoft Windows to run more than one program, with performance directly dependent on available executable memory. A RAM disk helps Windows a lot, but not having to swap at all is the bigger benefit.

Skeptical at first, I now consider the LIM EMS a de facto standard. The close connection between Intel and Microsoft implies that EMS will be more tightly coupled with the operating environment in the future, perhaps even

soon. That may be the most important result of Intel's strategy.

This must be embarrassing for IBM. The after-market has spoken loudly by demanding a longer life for the six million or so PCs out there. IBM didn't deliver. Intel and its partners did. **\$800 memory.** The shocker of the show was the announcement from TheSys of an add-in memory board holding 8MB of RAM. Actually, the board has 12MB on it; 4MB are used for ECC. Fully populated, this board costs \$800. And it is EMS-compatible. Want more? It is CMOS. Not content? TheSys also introduced a 16MB solid-state hard disk—a box full of RAM with your choice of disk interface. Buy the unit, plug it into your hard-disk controller, and away you go with a hard disk that boasts an average access time of 10 microseconds (about 8,000 times faster than the XT hard disk). Again, it is CMOS and can be backed up with batteries.

The memory chip used in this product is one megabit, but it is packaged in a unique fashion. The package contains 10 chips: 8 for data, 1 for parity, and 1 spare, for a total of 1MB per package. The package is the size of a stick of chewing gum and just a tad thicker, so 12 of them fit nicely on a PC board. This is a proprietary TheSys technology, so don't look for it from



other vendors unless TheSys takes on equity partners (a distinct probability) or turns generous enough to license the product (I wouldn't).

This kind of RAM capacity bodes well for all kinds of workstation products, from graphics to artificial intelligence. It also bodes well for data management products, which can be greatly improved in performance if the data are RAM resident. I am willing to bet that Borland will break all speed records in getting Reflex to use EMS for just that reason. With this kind of memory available, look for other applications that we haven't thought about before to pop up on PC-class machines.

The TheSys products will be available in the second quarter of 1986.

**Windows.** In what Microsoft labeled a "bizarre event," with funnyman John Dvorak presiding and with VP Steve Ballmer laying his job on the line for one last time, the company roasted itself over the two-year delay in delivering Windows—a nice touch. And just to make sure that people believed it this time, Microsoft gave away about \$40,000 worth of Windows to its invited guests.

Hoopla aside, Windows popped up (pulled down?) everywhere. I was most impressed to see it on the Vectra PC, Hewlett-Packard's new AT clone. HP has a strong presence in the lab and scien-

tific markets; it is, in effect, endorsing Windows to a very technical community of users who are interested in graphics and realtime support.

A big job still lies ahead for Microsoft. We must wait and see what kind of software the after-market provides and how long it takes for Microsoft to get code running in EMS. Windows is not yet a standard; more time (and nail biting on Ballmer's part) is required before we will know for sure.

**Standards.** I was very depressed to see more new printers. Oh, they were nice, but they are built without any consideration for a standard software interface. The only ray of sunshine seems to be that GSS's VDI software is embedded in some of the new entries.


This is getting silly, folks. It's about time for a committee and a de facto standard. Really. I'm starting to get mad. **Miscellaneous.** IBM went California with its booth. Instead of the stark, high-tech look of previous exhibits, it was dressed in muted pastels with a little bit of neon thrown in for good measure. No blue in sight. This may be the tip of a corporate image overhaul.

I noticed a reduced interest in accelerator boards. This may be due to the high interest in EMS as a way of extending the PC's life, as well as to the fact that adding one of these boards

often reduces a 100-percent pure IBM to the status of a clone. It may also be due to the fact that those of us who want to upgrade are out of slots. Spending six grand to upgrade the PC does not make much sense when that amount of money will buy an AT.

Network activity was high in the wake of the IBM Token-Ring announcement. PC to mainframe was not much in evidence, which is not surprising for a show catering to dealers (as in computer, not card).

The data management arena produced three items of news. Many firms announced multiuser/network versions of their products, a sign that network activity in the coming year will be high. Ashton-Tate announced dBASE III Plus, a natural evolution from dBASE III that can stand on its own legs, but the announcement seemed defensive, as if A-T felt that Ansa's Paradox had to be answered feature by feature. Unify announced a DOS version of its product, significant because of its penetration in the UNIX marketplace.

Finally, we were gratified at *PC Tech Journal's* acceptance. We ran out of copies of the two issues we displayed in our booth, and we were delighted to see so many vendors displaying "As seen in ..." placards of the ads they have run with us. Thanks. 

## THE AGENTS REPORT

Stepping over so many laser printers in order to see the rest of the show can only spell out (alas, in 300 DPI) only one thing: exciting advances to come for publishers.

—Marjory Spraycar

As data managers move down from mainframes and minis to the microcomputer, I see a growing sophistication in meeting the needs of serious developers and a blending of the virtues of each world.

—Julie Anderson

Laser printers were everywhere, with Tall Tree's JLASER driver board the most notable product in that area.

—Jeff Duntemann

The industry is recognizing the difference between graphics programs and true CAD systems. It was exciting to see products like VersaCAD and CAD MASTER responding with refinements to their products.

—Caroline Halliday

COMDEX '85 spanned the range from practical to exotic; for \$2,000 you can have a PC/AT clone, a 550 Meg laser disk system, or a Voice Recognition package.

—Dan Beale

Everything I saw fit on or ran in the IBM PC. Even Apple and Data General connect to the PC. Laser printers and software were plentiful, as were compact-disk ROMS. I was bowled over by the IBM PC Story Board.

—Tom Hoffmann

The most visible trend is the increasing conformance to new standards as attested to by the numerous AT clones and by the widespread acceptance of the Lotus-Intel memory specifications. I saw a lot of laser printers—but no good prices.

—Steven Armbrust

Cheap, dense, high-speed memory is coming out of adolescence as evidenced by half-height RAM disks

complete with batteries. I expect shortly to see all this memory put to qualitatively different uses.

—Richard Foard

I noticed that the knowledge and expertise of people manning the booths were inversely proportionate to the size of the booth. Unfortunately, at COMDEX most of the booths were very large.

—Ted Forgeron

I was pleased to see the merging of UNIX and DOS exemplified by Insight from UNIDOS Systems Corporation and OS Merge, a feature of AT&T's new UNIX System V.


—Augie Hansen

What makes COMDEX worthwhile are the vendors who occupy a small part of a larger company's booth or those too small even to share a booth. Their products are often new to me and display real creativity.

—William J. Hunt



# "We're giving away 1,000 computers to prove a point about the MASTERFLIGHT™ mass storage system."



## The XT Giveaway.

In fact, buy our MASTERFLIGHT and we'll give you a Kamerman Labs XT™ at no extra charge! It's our way of demonstrating that MASTERFLIGHT is the finest mass storage system sold. PC Tech says, "After testing all 14 tape drives, the authors concluded that... Kamerman Labs units are the clear winners."\*

## This is it!

Inside the MASTERFLIGHT, you've got everything you need. A high performance hard disk system with up to 60 megabytes of storage. A 60 megabyte streaming tape drive that backs up 10 megabytes in just 2½ minutes,

"approaching the theoretical maximum speed possible for the hardware."\*\*

That's not all, add a power director, surge protector, noise filter, security lock and you've got it—packed into a 2½" high unit that "can fit easily above the computer without raising the monitor to skyscraper levels."\*\*

## Take it away.

Kamerman Labs' reputation for quality, service and price can't be topped. By any measure, we beat the competition. Phone today for more information. Don't forget to ask about our XT's, internal hard disks and tapes, and accelerator boards.

## ORDER TODAY

Call 800-522-2237, Oregon and Alaska call 503-626-6877. Domestic inquiries ask for Dept. 235. International inquiries ask for Dept. 213

### Compare:

Vendor	Product	Capacity in MBytes	Drive	Tape	XT Giveaway	Power Director	Surge Protector/Filter	Security Lock	1/2 Height Enclosure	Price
Kamerman Labs, Inc.*	Masterflight™ 20/60	20	60	Yes	Yes	Yes	Yes	Yes	Yes	\$2,495.00
Corvus Systems, Inc.*	TLC Trimline Combo*	20	60	No	No	No	No	No	Yes	3,295.00
Tallgrass Technologies, Corp.*	Hardfile 5025*	25	60	No	No	No	No	No	No	3,660.00
Tecmar*	Q60W20*	20	60	No	No	No	No	No	No	3,495.00
Mountain Computer, Inc.*	FileSafe*	20	27	No	No	No	No	No	No	3,195.00
Kamerman Labs, Inc.	Masterflight 30/60	30	60	Yes	Yes	Yes	Yes	Yes	Yes	Call
Kamerman Labs, Inc.	Masterflight 40/60	40	60	Yes	Yes	Yes	Yes	Yes	Yes	Call
Kamerman Labs, Inc.	Masterflight 60/60	60	60	Yes	Yes	Yes	Yes	Yes	Yes	Call

### IBM® XT Compatible Kits

XT-KIT1	64k system unit, keyboard	\$599.00
XT-KIT2	XT-KIT1, 640k, 1 floppy drive and controller	799.00
XT-KIT3	XT-KIT2, monitor, monochrome card	Call

Internal hard disk systems and tape systems from 399.00



3% service charge for credit cards  
XT Giveaway Offer expires March 31, 1986  
Pricing subject to change without notice



# Kamerman Labs

CIRCLE NO. 244 ON READER SERVICE CARD

7861 SW Cirrus Drive, Beaverton, OR 97005  
(503) 626-6877 Telex 501 886

IBM® XT is a registered trademark of International Business Machines. Masterflight™ and Kamerman Labs XT™ are trademarks of Kamerman Labs, Inc.  
\*Sigma Designs, Inc.\* and Tecmar also mentioned, PC Tech, Nov. 1985. \*\*PC Tech, Nov. 1985.

© 1985 Kamerman Labs, Inc.



# Now You Know Why **BRIEF**™ is **BEST**

**“BRIEF, The Programmer's Editor, is simply the best text editor you can buy.”** John Dvorak, INFOWORLD 7/8/85

## The Program Editor with the **BEST** Features

Since its introduction, BRIEF has been sweeping programmers off their feet. Why? Because BRIEF offers the features **MOST ASKED FOR** by professional programmers. In fact, BRIEF has just about every feature you've ever seen or imagined, including the ability to configure windows, keyboard assignments, and commands to **YOUR** preference. One reviewer (David Irwin, DATA BASED ADVISOR) put it most aptly, “(BRIEF)... is quite simply the best code editor I have seen.”

**Solution Systems™**

### **“A bona fide Undo...”**

Steve McMahon, BYTE 3/85

As Mark Edwards describes in DR. DOBB'S JOURNAL (11/85), “BRIEF has an outstanding undo facility. The default configuration allows the last 30 editing commands to be undone. This number can be raised to a maximum of 300 commands. Until you reach this maximum or run out of RAM, every command you issue can be undone. So if you make ten changes and then realize that the first one was an error, you can undo all the changes back to the mistake... Needless to emphasize, this facility can save endless grief.”

**No other editor has this capability.**

### **Every Feature You Can Imagine**

Compare these features with your editor (or any other for that matter).

- FAST
- Full UNDO (N Times)
- Edit Multiple Large Files
- Compiler-specific support, like auto indent, syntax check, compile within BRIEF, and template editing
- Exit to DOS inside BRIEF
- Uses all Available Memory
- Tutorial
- Repeat Keystroke Sequences
- 15 Minute Learning Time
- Windows (Tiled and Pop-up)
- Unlimited File Size –(even 2 Meg!)
- Reconfigurable Keyboard
- Context Sensitive Help
- Search for “regular expressions”
- Mnemonic Key Assignments
- Horizontal Scrolling
- Comprehensive Error Recovery
- A Complete Compiled Programmable and Readable Macro Language
- EGA and Large Display Support
- Adjustable line length up to 512

### **Program Editing YOUR Way**

A typical program editor requires you to adjust your style of programming to its particular requirements – NOT SO WITH BRIEF. You can easily customize BRIEF to your way of doing things, making it a natural extension of your mind. For example, you can create ANY command and assign it to ANY key – even basic function keys such as cursor-control keys or the return key.

### **The Experts Agree**

Reviewers at BYTE, INFOWORLD, DATA BASED ADVISOR, and DR. DOBB'S JOURNAL all came to the same conclusion – **BRIEF IS BEST!**

Further, of 20 top industry experts who were given BRIEF to test, 15 were so impressed they scrapped their existing editors!

NOT COPY PROTECTED

### **MONEY-BACK GUARANTEE**

Try BRIEF (\$195) for 30 days – If not satisfied get a full refund.  
**TO ORDER CALL (800-821-2492)**

SOLUTION SYSTEMS, 335-P WASHINGTON ST., NORWELL, MA 02061, 617-659-1571

BRIEF is a trademark of UnderWare





## STORAGE MEDIUM

I really cannot see what all the fuss is about in the article "Moving up to Tape" (Steven Armbrust and Ted Forgeron, November 1985, p. 62).

Some day, hard-disk technology (and tape backup) will be a thing of the past. Today's event is the concept employed by IOMEGA in its removable cartridge system. The Bernoulli Box is expensive, but hard-disk storage was considered likewise at one time.

When we considered storage needs for our central services/data processing department, hard disk was the last thing we looked at. For versatility, ease of use (including backup), value, and ruggedness, the Bernoulli Box was first. We currently employ one system (two-cartridge, 10MB each), but should we consider more storage later, the Bernoulli Box will be our choice again.

I asked myself, as I read your article, who really wants to put up with even the possibility of head crashes and/or selecting the right backup system? Not me, not us, not ever.

Dan Davis  
Bank of Leleta  
Eureka, CA

*No one denies that cartridge disks have their place. Their removability lends them neatly to securing sensitive data, and backup is done simply by copying all the files on one cartridge to another. Also, with multiple cartridges, a limitless amount of data can be stored. However, in the configuration you describe, a maximum of 20MB of data can be on-line at one time and a maximum file size is imposed equal to the capacity of one cartridge, or 10MB.*

*Nonremovable hard disks are available in large capacities, with some vendors offering disks that allow files greater in size than the DOS-imposed 32MB barrier. As for reliability, head crashes may occur on cartridge-based systems as well as nonremovable hard*

*disks; the Bernoulli Box and the IBM 10MB fixed-disk drive each have an MTBF of 8,000 hours. As tape backup becomes easier, faster, and cheaper, its popularity will increase.*

*Each type of mass storage carries with it a set of advantages and disadvantages that must be weighed against individual needs.*

—JA

## COBOLS AND ORANGES

After reading "COBOL Performs" by Ted Mirecki in your August 1985 issue (p. 107), I feel that the author makes several errors in his presentation and does not have a feel for the micro-computer market. These errors divide into two classes: improper comparisons, coupled with inadequate testing, and lack of understanding of what micro-computers are capable of performing.

The author made an apples-and-oranges comparison of mbp COBOL 7.0 with the latest versions of REALIA COBOL, Microsoft COBOL, and Micro Focus COBOL, all of which came out after version 9.0 of the mbp product.

Speed comparisons made by the author were largely meaningless because the 1,000- and 1,500-line programs are too small to give a true test of relative speeds. Both Ryan-McFarland COBOL and Microsoft COBOL slow down after about 2,500 lines of code. In fact, mbp actually will compile the larger programs faster than RM.

On the second point, Mr. Mirecki apparently believes the microcomputer is little more than a toy and envisions the user with two floppy disks. This is not in accord with the facts if the article really meant to cover "serious business uses." I have never heard of an accounting program of any consequence that runs satisfactorily on two floppy disks, in lieu of a hard disk. These programs also require a hard disk for development. In addition, the author did not give any attention to multiuser consid-

erations. Because most serious micros used in business will probably be used in a multiuser environment, this omission is serious.

Micro Focus COBOL boasts two products, ANIMATOR and FORMS, which are not of much use in development. ANIMATOR, while ingenious, is not needed to develop programs. This debugging utility is most useful in checking out poorly designed programs. It is my feeling that the remedy is to design programs with more structure and modularity rather than embalming bad practices. We look for errors by examining source code; it takes less than 10 minutes.

The FORMS program is of little use on our dynamic screens. Tests of this program indicated that FORMS works best on static, simple screens. When dynamic screens are used, the program becomes cumbersome.

Our evaluation of Micro Focus indicates it has one important omission making it generally unsuitable for interactive programs on a microcomputer. According to information from the company, its compiler lacks an UPDATE command or routine. This routine allows a single-key acceptance of unchanged data in a field, without retyping. It is used continually by the operator and its omission is a serious problem. This is not a problem on a mainframe or a minicomputer where batch processing is the rule, but it is fatal for interactive programming.

Most COBOL articles in the micro-computer press have been written by someone who hates COBOL and who probably has never written a line of code in the language. It is refreshing to read an article by an author who obviously understands COBOL. Next time, get someone with a micro background.

Gordon R. Page  
Vice President  
Real-time Accounting, Inc.  
Gladwyne, PA



*This is the first time I have been accused of considering the microcomputer a toy. Most of the time, I am accused of considering the mainframe an outdated dinosaur. The truth lies somewhere in between. To address each of Mr. Pages' points in turn:*

*I did not make comparisons to mbp COBOL version 7; the tables and the text specifically refer to version 9. As was noted in the last installment of the series, the evaluation of mbp COBOL was deferred until this latest version be-*

*came available. According to the release date supplied by mbp, it was the most recent of the COBOLs reviewed.*

*The sizes of the test programs were chosen in this range because I am philosophically opposed to programs longer than 2,000 lines. COBOL programmers may gasp in disbelief, but I have found that it is possible to write commercially useful programs of this length. Yes, I could have compiled longer programs downloaded from a mainframe, but the nontrivial ones were either interactive,*

*making use of CICS and IMS calls not supported on a micro, or batch oriented, not of the type useful in the micro environment.*

*If Mr. Page infers that I do not know his segment of the microcomputer market, then I plead guilty. But there is more than one microcomputer market. According to some reports, the majority of microcomputers are not equipped with hard disks and are not networked. I know of many "kitchen table" software companies and of even more small businesses for which the purchase of any computer system, let alone multiple hard-disk systems, is a major expenditure. Somehow, it seems that the use of a single dual-floppy-disk microcomputer by a small business is more "serious" (to the business, if not to the installer) than the use of a network of hundreds by a Fortune 500 company.*

*Mr. Page is certainly entitled to his opinion that the ANIMATOR and FORMS utilities are useless. FORMS, like any automated programming aid, becomes cumbersome at the limit. It is easy to say that well-designed programs do not need debuggers—because they do not have bugs; but in the meantime, let's consider how many mortal programmers prefer scanning the source code to using interactive debuggers.*

*It's quite true that Micro Focus COBOL does not have an UPDATE function to indicate the accepting of the current contents of a screen field without changes. It does not need one. This capability is inherent in the screen handling built into the language, as is amply demonstrated by the example program included with the compiler.*

*In the conclusion of the COBOL series, I pointed out that the final evaluation of a compiler must be made by the user who must live with it. This left open the possibility of conclusions different than my own. I do not question the expertise of anyone who prefers a product that is not my favorite.*

—Ted Mirecki

## HE FOUND ANOTHER FIND

Although the article "A Good Find" by Mark Ackerman (October 1985, p. 85) and the supporting program are great, Mr. Ackerman's statement, "...DOS has no facility for finding such a file..." bothered me. Perhaps Microsoft's intent of the following DOS commands were not as I have presented them, but they accomplish the job.

To obtain directory information:

chkdsk [d:]/v find "UPPER\_CASE\_STRING"



# FLASH

**\$49.95**

## SPEED UP YOUR COMPUTER!

NOT COPY PROTECTED

Increase the **speed** of your computer by as much as **4-8 times**. Why buy a PC AT when all you may need is some **FLASH**. **FLASH** is just that, it gives disk accesses in a **FLASH**. Every PC owner can't be without **FLASH** once the powers of **FLASH** are discovered. The program is totally invisible to the user. There is nothing to learn. Make your floppies **faster** than a hard disk. Make your hard disks faster than ever before. Allows the user to have sub-directories on his floppies without the usual loss of speed. **FLASH** will also tell you just how much faster you are running than you would have been without **FLASH**. **FLASH** is handcrafted in ASSEMBLER. Upgrade your computer with **FLASH**. Batch files will **fly** like they had wings. Save wear & tear on expensive program disks.

You'll be so **amazed** with your improved performance, you will want to call us to tell us so!

"The novice and expert alike will consider **FLASH** their most valued utility."

**DAVE LEE REED**  
President, **SOFTWARE MASTERS**

BENCHMARKS for different programs utilizing **FLASH**

	W/O FLASH	W/FLASH
WORD STAR	2.0	0.33
BASICA	2.7	0.40
LINKING	113.8	6.00
SORTING FILES	105.0	27.00

When **FLASH** increases your speed it generally makes you run **3-5 times** faster. In favorable conditions like the ones above **FLASH** can make your PC run **6-16 times** faster! PC's over the world are screaming for **FLASH**. Reach the speed of a RAM DISK, without their disadvantages. If you think you DON'T need **FLASH**, call us and tell us why!

Order Line 1-800-25-FLASH  
Info Line 1-317-253-8088  
MC, Visa, Check, C.O.D.    
For: IBM PC, AT, XT, JR, or clone.



**Reg. Price.....\$69.95**  
**Limited Time.....\$49.95**  
add 4.00 shpng hndl  
Software Masters  
6223 Carrollton Ave.  
Indpls., IN 46220

## THE UTILITY ROOM

- |  |        |       |
|--|--------|-------|
| ■ <b>Spool-Master</b> , ram printer spooler. Multiple copies, handles single sheets, any buffer size.  | 49.95  | 19.95 |
| ■ <b>Buffer-Master</b> , keyboard buffer extender from 15 to 2000 key type ahead.  | 29.95  | 14.95 |
| ■ <b>Super-Ram-Disk</b> , set up MULTIPLE ram disks and as MANY as you want.   | 49.95  | 14.95 |
| ■ <b>Calc-Pad</b> , ram resident calculator, hex octal binary and decimal. Works in ANY graphic mode. Unlimited parenthesis nesting. Many functions. | 49.95  | 24.95 |
| ■ <b>Sort-Merge-Copy</b> , a super sort utility. Use it stand alone or call it from ANY language.  | 150.00 | 49.95 |
| ■ <b>Unprotect</b> , unprotects basic programs.  | 49.95  | 19.95 |
| ■ <b>Data-Path</b> , Have paths setup to find your data and overlay files. Works with ALL programs.  | 49.95  | 19.95 |
| ■ <b>MoreHard</b> , gain up to 10%-50% more hard disk space! ALL programs work in harmony with each other.   | 49.95  | 19.95 |

## SUPER-ED Version 3.0

- |   |   |
|---|---|
| ■ Do <b>ANY DOS</b> command or <b>RUN ANY</b> program from within <b>SUPER-ED</b> . | ■ Editing commands & colors & more are fully user configurable. |
| ■ Turbo Pascal like environment for <b>ANY</b> language.                            | ■ <b>ON-LINE</b> language-specific user definable <b>HELP</b> . |
| ■ <b>MULTI-FILE</b> window editing. Move & copy between file windows.               | ■ Full featured editor with <b>WORD STAR</b> like commands.     |
| ■ Extensive Find & Replace usage.   | ■ Fully utilizes sub-directories.                               |
| ■ <b>ON-LINE</b> editing <b>HELP</b> .  | ■ Supports keyboard <b>MACROS</b> .                             |
|   | Reg. Price <b>\$59.95</b>                                       |
|   | Limited Time <b>\$29.95</b>                                     |

We believe in the highest quality software at the lowest possible price!  
Turbo Pascal is a trademark of Borland intl. Word Star is a trademark of Micro Pro intl.



Make Any Computer Do Exactly What You Want With McGraw-Hill's

# Contemporary Programming & Software Design Series

## From Writing Your Own Programs to Modifying Existing Software, Here's the New, Easy, and Low Cost Way to Unlock the Secrets of Your Computer

Whether you use computers for business, for personal applications, or for fun, off-the-shelf programs will never do everything you want them to do for you. That's because they were written by programmers to satisfy what they perceived as the needs of the greatest number of potential users—often missing some or many of your specific needs.

That's why McGraw-Hill's new Contemporary Programming and Software Design Series teaches you how to create your own software . . . either from scratch or by making key modifications to existing programs.

There is nothing magical about it. You learn the process of building a computer program step-by-step with McGraw-Hill *Concept Modules* sent to you one at a time, once a month. Each of the ten modules in the Series takes you through an important step in the development of the structure and detailed logic of a program, including testing, debugging, and documentation.

## Unique Interactive Hands-On Instruction

Each module includes an easy-to-understand guide PLUS a 5¼" floppy disk containing typical programs and interactive instruction that you can run on any IBM or IBM-compatible computer for hands-on experience.




completed this program yourself.

But there's more. Special graphics on your screen work in conjunction with the accompanying guide to amplify, illustrate, and deepen your understanding of software design principles.

## Learn the Foundation of All Computer Languages


Although the Series teaches you programming procedures, it is not aimed at



any one language or machine. Why? Because 95% of the programming process is carried out using design techniques that are independent of a specific language or machine. Nevertheless, we include enough training in BASIC and machine language to get you started. You'll find that the whole process of learning new languages will be greatly accelerated once you complete the Series.

## Create a Complete, Customized Family Financial Package As You Learn

The sample programs you work with throughout the Series are excellent learning tools. But they're more than that. By combining the sample programs onto one master disk, you'll create your own family financial package that will help you balance your budget, figure loan amortization, and much more. And — of course — you'll be able to further modify your financial package to fit your own specific needs!



## 15-Day No-Risk Trial

To order your first module without risk, send the postage-paid card today. Examine the first module for 15 days and see how the Series will help you make any computer do exactly what you want it to do!



If someone has beaten you to the card, write to us for ordering information about the Contemporary Programming and Software Design Series.

## McGraw-Hill Continuing Education Center

3939 Wisconsin Avenue  
Washington, DC 20016

IBM is a registered trademark of International Business Machines, Inc.





As examples using the default drive  
chkdsk/v|find "AUBURN.LTR"

will display all CHKDSK output lines  
containing AUBURN.LTR, and

chkdsk/v|find "AUBURN"

will display all lines containing  
AUBURN. For searching a particular  
directory, use:

chkdsk/v|find "\\LETTERS\\AUBURN"

However, searching for all files with ex-  
tension .ltr within the directory letters  
requires an addition pipe, as in:

chkdsk/v|find "LETTERS\\"|find ".LTR"

William E. Smith  
San Diego, CA

*Thank you for your clever suggestion.  
Obviously, these commands are useful,  
and are good candidates for batch files.  
We ran Mr. Ackerman's program be-  
cause it automates the process and per-  
forms the search as fast as possible.*

—WF

#### FORTRAN EXCHANGES

I read with interest the article titled  
"FORTRAN Options" by Alan Howard in  
the October 1985 issue (p. 149). We

have used all four of these compilers  
and came to approximately the same  
conclusions, but differ in detail, perhaps  
due to differences in versions.

We obtained our Professional  
FORTRAN compiler, version 1.1, from  
Ryan-McFarland. (I don't know how RM  
version numbers correspond to those  
assigned by IBM.) It has two runtime li-  
braries, not one. If Mr. Howard had run  
larger benchmark programs (more  
code, not more memory or time), he  
might have discovered that Professional  
FORTRAN frequently reports "error  
8003 Internal Compiler Error: The com-  
piler has detected an internal inconsis-  
tency in its data. This should not oc-  
cur..." When it works, the RM FORTRAN  
compiler produces the fastest and  
smallest code of the four reviewed, but  
it isn't much use to us because it won't  
compile our programs. We agree that  
RM's debugger is excellent.

The DRI FORTRAN compiler was  
too full of bugs to be useful, and DRI  
was unwilling to provide errata lists that  
would have assisted work-arounds.

As Mr. Howard mentioned,  
Microsoft FORTRAN compiles only the  
subset standard, which for many appli-  
cations is substandard. We don't use it  
unless a customer insists.

We use the Lahey FORTRAN com-  
piler almost exclusively for several rea-  
sons: It runs faster by far than any of  
the others. It doesn't seem to have  
nearly as many bugs, and when we dis-  
cover a bug, Lahey Computer Systems is  
very responsive. We did not find it nec-  
essary to tell the linker to include the  
Lahey runtime executive F77L.OBJ first.  
Otherwise, we agree with Mr. Howard.

We applaud the author's early at-  
tention to transportability and his recog-  
nition that FORTRAN is the only serious  
vehicle for it. But we wonder at his sin-  
cerity when he advocates allowing ex-  
tensions that both violate the standard  
and invite portability problems. In par-  
ticular, the equivalence (explicitly or via  
common) of character and noncharacter  
data types makes it impossible to trans-  
port codes between machines that do  
not have the same word length. Some  
machines don't have 16- or 32-bit words  
—the UNIVAC 1100 and Honeywell  
6000 have 36-bit words; CDC 6000/7000/  
Cyber machines have 60-bit words. We  
believe portability is possible only by  
adherence to the standard. Language ex-  
tensions are nice, but the compiler  
should diagnose their use unless di-  
rected otherwise. (The compiler *must*  
diagnose them if it is to conform to

# WINDOWS FOR DATA™

## Featuring One-Step Data Entry♦

Now you can code fast, powerful data  
entry windows, improve user  
convenience – reduce input errors.

All the power, convenience and  
flexibility of the #1 window utility for  
the IBM PC. Our WINDOWS FOR C™  
combined with a professional window-  
based data entry system.

Complete control over screen display  
and entry of data within a convenient  
flexible window environment.

WINDOWS FOR C    WINDOWS FOR DATA  
(Includes WINDOWS FOR C)

<b>PCDOS</b>	<b>\$ 195</b>	<b>\$ 295</b>
<b>PC/XENIX</b>	<b>\$ 395</b>	<b>\$ 595</b>
<b>UNIX</b>	<b>CALL</b>	<b>CALL</b>

WINDOWS FOR DATA™ provides versatile,  
easy-to-use data entry functions that operate  
within windows.

#### CAPABILITIES INCLUDE:

- Pop-up data entry windows
- Multiple field types
- Data validation functions
- Field-specific & context-sensitive help
- Lotus-style menu design
- Single field entry option
- Date, time and string utilities
- Dynamic control of data-entry environment

- ♦ User input to data-structure variables  
without intervening code.



**Vermont  
Creative  
Software**

21 Elm Ave.  
Richford, VT 05476  
802-848-7738, ext. 21

Full source available. Master Card & Visa accepted. Shipping \$3.50. VT residents add 4% tax.



# Flashy Programs.

TELEPHONE ORDER ENTRY FORM

Salesperson: \_\_\_\_\_ Ship To: \_\_\_\_\_

Today's Date: \_\_\_\_\_ Zip: \_\_\_\_\_

Acct Num	Ship Date	Ship Via	FOB Point	Terms	Order Number

Quantity	Item Num	Description

Take Your Selection  
Ask Record To File  
Exit/Display Last Record  
Go To Previous Record  
Press F10 Exit

ABC Computer Company  
New Client Information List

Company: \_\_\_\_\_ Billing Rate: \$ \_\_\_\_\_

Contact: \_\_\_\_\_ Telephone: \_\_\_\_\_

Title: \_\_\_\_\_

Address: \_\_\_\_\_

City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_

Referred By: \_\_\_\_\_ New Account(Y or N): \_\_\_\_\_ Auth Code: \_\_\_\_\_

ABC Computer Company  
New Client Information List

Account #: \_\_\_\_\_ Salesman: \_\_\_\_\_ Today's Date: \_\_\_\_\_

Company: \_\_\_\_\_ Billing Rate: \$ \_\_\_\_\_

Contact: \_\_\_\_\_ Telephone: \_\_\_\_\_

Title: \_\_\_\_\_

Address: \_\_\_\_\_

City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_

Referred By: \_\_\_\_\_ New Account(Y or N): \_\_\_\_\_ Auth Code: \_\_\_\_\_

Enter Selection  
Edit record  
Previous record  
Next record  
EXIT

THE SOFTWARE BOTTLING COMPANY OF NEW YORK  
New Client Information List

Account #: \_\_\_\_\_ Salesman: \_\_\_\_\_ Today's Date: \_\_\_\_\_

Company: \_\_\_\_\_

Contact: \_\_\_\_\_

Title: \_\_\_\_\_

Address: \_\_\_\_\_

City: \_\_\_\_\_

Referred By: \_\_\_\_\_

Comments: \_\_\_\_\_

Completion Date: \_\_\_\_\_ Invoice Sent: \_\_\_\_\_ Payment Received: \_\_\_\_\_

\*\*\* POP-UP Help Screen Number One \*\*\*

Enter data into the fields exactly as you see it here. Do not worry about making a mistake all data is error-checked as it is entered. It is impossible to make a mistake!

ABC Bottling Company  
Job Estimation and Control Program

Enter Job Description

Job Number: \_\_\_\_\_

Surface Type: \_\_\_\_\_

Size Length: \_\_\_\_\_

Thickness: \_\_\_\_\_

Climate: \_\_\_\_\_

You WILL Need The Following Parts

Part Number	Amount Needed	Amount Available	Balance This Job

Ask for selection  
Amount for selection  
Exit this screen  
Next Record  
EXIT

BILL TO: \_\_\_\_\_

SHIP TO: \_\_\_\_\_

ACCOUNT #	SHIPER	ORDERED	SHIP VIA	TERMS	FLUSH-UP ORDER

QUANTITY	PC	DESCRIPTION	TIME	PRICE	AMOUNT

COMMENTS: \_\_\_\_\_

DATE: \_\_\_\_\_ TIME: \_\_\_\_\_

dBASE • Turbo Pascal • BASIC • C • COBOL • Fortran • Lotus 1-2-3...

## FLASH CODE™

The most powerful program developer for dBASE II and dBASE III ever developed.

**DRAW** any screen design with our advanced screen editor. Use Flash Code and see how incredibly easy screen design can be.

**GENERATE** complete programs automatically. Based on your screen designs, Flash Code can write your whole dBASE program.

**FLASH-UP WINDOWS™** Menus and Help Windows add a new dimension to your dBASE programs. Create them instantly with our window editor. Use the FlashUp™ module to have windows pop-up throughout your dBASE applications.

For dBASE II and dBASE III. \$150.

"...a truly remarkable product. Brand-new, state-of-the-art and actually fun to use. The windows make it an even more amazing product."

Cary N. Prague, Author

"Beyond programming with dBASE III"

"Destined to replace QUICKCODE™"  
MicroNews/Views, Nov. 85

## SCREEN SCULPTOR™

You can create screens in minutes...then Screen Sculptor writes the program.

Move pieces of the screen around, select colors from a menu, draw boxes and lines, paint, repeat last character in any direction. And more!

Specify variable names, data types, acceptable data ranges, pictures for edit checking, etc.

Screen Sculptor then generates an actual program source code based on your screen design. Use it as is or modify it.

For BASIC, Turbo Pascal, IBM/Microsoft Pascal. \$125.

"...so well done that you may not need to refer to the manual."

"...an exceptional product that fills a real need in the development of new programs."  
Computer Language

## NEW! FLASH-UP WINDOWS™

An incredibly flexible and powerful tool for Flash-Up Menus and Flash-Up Help Windows!

Every program, every application becomes more sophisticated and easier to use with Flash-Up Windows.

Use the window editor to instantly create windows. Change their size, location, color...all automatically. Specify a string of characters or control codes to send back to your application program.

The windows can be flashed-up directly by your program OR by the user with the keyboard. Windows can even call other menus or help windows.

An absolute necessity for BASIC, Turbo Pascal, C, R:BASE, COBOL, Fortran, dBASE, Lotus 1-2-3...

Introductory price. Only \$75.  
(Until 3/31/86)

CIRCLE NO. 192 ON READER SERVICE CARD

## No Risk Demo Offer!

Here's a no-risk offer. Order now and you'll also get a full demo disk. Use the demo and the manual for 30 days. If you don't love it, return the package for a full refund.

Credit card orders call 24 hrs/day  
1(800) 824-7888, operator 268.

All other orders and inquiries call or write  
Software Bottling Co., 6600 L.I. Expwy,  
Maspeth, NY 11378. 718-458-3700.



THE  
SOFTWARE  
BOTTLING  
COMPANY  
OF NEW YORK


Requires an IBM PC, XT, PC AT or true compatible, 256K



# 97% of all PC owners use the functions of QuadEGA+.

## QuadEGA+. The "All-in-One" graphics board.

QuadEGA+ combines onto one board the four most-popular video display standards. The standards used by practically every PC owner. Monochrome text, monochrome graphics, color graphics, and the new Enhanced Graphics with 16 colors out of a palette of 64.



**NOW SHIPPING**  
with a special bundle offer  
on Windows by Microsoft

## Totally Compatible

With all this power, you can use your present software and also be prepared for the future. QuadEGA+ delivers across the board compatibility with numerous standard software packages as well as new EGA-Supported software like Lotus 1-2-3™ v2.0, Symphony™ v1.1, Flight Simulator™, Framework II™, AutoCAD™, GEM™, Microsoft Windows™, Microsoft Word™, and hundreds more.

## Better Value

QuadEGA+ works great with standard monochrome or RGB color monitors as well as the new enhanced color displays. And crisp color and text in EGA mode eliminates eye strain. But best of all, while QuadEGA+ features all the power of the 256K IBM Enhanced Graphics Adapter, it's priced like the 64K version.


To see the QuadEGA+ (1) difference for yourself, just visit your local Quadram dealer. Or contact us at One Quad Way, Norcross, Georgia 30093; 404-564-5566.

Quadram and the Quadram logo are registered trademarks of Quadram Corporation. QuadEGA+ is a trademark of Quadram Corp. IBM is a registered trademark of International Business Machines, Inc. Lotus 1-2-3 and Symphony are trademarks of Lotus Development Corp. Flight Simulator and Framework are trademarks of Ashton-Tate Corp. GEM is a trademark of Digital Research, Inc. Wordstar is a trademark of MicroPro, Inc. Windows and Word are trademarks of Microsoft, Inc. Hercules is a trademark of Hercules Graphic Products, Inc.

(1) Short card availability limited through Feb. 1986. Long card available now.




## IBM® Enhanced Graphics Adapter




640 x 350

## IBM® Color Graphics Adapter




320 x 200

## Hercules™ Graphics Adapter



720 x 348

## IBM® Monochrome Text Adapter



640 x 350



Federal Information Processing Standard 69, in which conformity is legally, but not practically, necessary if the compiler is to be used by the federal government directly or under contract.)

The remarks about file size in connection with the pentathlon benchmark program are misleading. The extra information in the files to support FORTRAN BACKSPACE statements are necessary in any case because the RECL= specification in the OPEN statement can be used only with the ACCESS='DIRECT' specification (see page 12-20, lines 14-16 of the standard).

His remarks also may indicate some uncertainty in program design. If the file size is "two to five times the expected 15,000 bytes," then he must have written one-byte records. One of the most elementary techniques to improve performance of I/O-bound programs is blocking of several records into one before transferring the data. This technique was first used with magnetic tape to overcome start-stop delays, where it also resulted in using less tape because of the absence of inter-record gaps. But it is equally applicable to disk to avoid rotational latency delays, and, in this instance, to reduce the space required for record framing.

W. Van Snyder  
Jet Propulsion Laboratory  
Pasadena, CA

*The compiler error 8003 in the IBM compiler was covered in the article. Because it only appeared once in my testing I chose not to make a big issue of it. Each of the compilers tested failed at least once. It is disturbing to learn that this particular error is more widespread than I observed.*

*Whether F77L.OBJ must be placed first in the link command is a small point; the main point is that it must be included. The examples and directions that appear in the documentation all indicate that it should be first.*

*Portability is a serious concern, but then so is getting a system implemented. There is at least one FORTRAN program that has files that include both numeric and character data. The trade-offs between portability and usable implementation must be weighed carefully as part of the system design.*

*The reader notes that the file used for the pentathlon is comprised of one-character records. As explained in the text, the choice of using single-character records was based on the structure of the pentathlon program in the review of the C compilers. The listing that was*

## Make your PC or AT into a COMMUNICATING WORKSTATION for only \$85

Use **ZAP**, the Communications System for Technical Users  
COMPLETE Communications for PROGRAMMING and ENGINEERING

EMULATION of graphics and smart terminals is combined with the ability to TRANSFER files reliably, CAPTURE interactive sessions, and transmit MESSAGES while also being able to swap between your mini or mainframe session and your PC application. SUSPEND a line to run a PC application. Reconfigure features to fit the communications parameters and keyboard requirements of the host computer software. Complete technical documentation helps you understand and fit ZAP to your style.

### HIGHLIGHTS OF ZAP:

- Emulate TEKtronix 4010/14 and DEC VT 100, 102, 52 including variable rows and columns, windows, full graphics, even half tones.
- Reliable *file transfer* to/from any mainframes and PCs including KERMIT and XMODEM protocols plus you get a full copy of KERMIT. Transfer *speeds* ranging from 50 to 38,400 BAUD. Session control include *printer dumps* and *save to disk*.
- **MACRO** and **Installation files** ("scripts") controllable by you.
- EMACS, EDT and VI "Script" files are included. ZAP is also used with other popular software including graphics products like DISPLA and SAS/GRAPH.
- **CONFIGURABLE** to communications, terminal features on the "other end"; 1, 2 stop bits; 5, 6, 7 or 8 data bits; parity of odd, even, none, mark and space; remap all keys including the numeric pad and standard keyboard, set any "virtual" screen size.
- Full **PC/MSDOS** access to run any command or program that will fit in your systems memory. ZAP takes less than 64K.
- 9 Comm ports are supported by ZAP. Plus full color in text and graphics make use of the IBM color, EGA cards, or Hercules Monochrome.

**ONLY  
\$85**

Full refund if not satisfied  
during first 30 days.

**Solution  
Systems™**

335-P Washington St.  
Norwell, Mass. 02061  
617-699-1571  
800-821-2492

CIRCLE NO. 130 ON READER SERVICE CARD

## **C** What you've been missing. . .

### Interactive-C™


#### Revolutionary New Programming Development System

At last, a full-function, professional-quality C development system to optimize your creative abilities. Stop waiting for editors, compilers, and linkers that waste your valuable time. Stop debugging in hex at the machine level. Easily **DOUBLE** or **TRIPLE** your productivity with this totally-integrated, fully-interactive programming environment:

- Complete K & R interpreter
- Full-screen program editor
- Source-level symbolic debugger
- Command processor shell
- Execution profiler

**Interactive-C** requires an IBM PC or 100% compatible, MS-DOS 2.0 or later, and 256K RAM. **Interactive-C** is available for only \$249 and comes with a **risk-free 30 day money back guarantee**.

Enjoy the combination of **power, flexibility, and ease of use** that will make **Interactive-C** the most valuable productivity tool you own. Order Today.



- Single or dual CRT configuration
- Multi-window user interface
- 40x25 and full-screen graphics support
- Detailed syntax & run-time diagnostics
- Precise cursor error positioning
- Trace, breakpoints & data watchvalues
- Several varieties of STEP
- Full-screen traceback
- Command-level "immediate" mode
- Multiple source files
- Compiled module interface
- Much, Much, More!!

For more information or to place an order contact:



**IMPACC Associates, Inc.**  
P.O. Box 93  
Gwynedd Valley, PA 19437  
215-699-7235




Trademarks: IBM - International Business Machines; MS-DOS - Microsoft Corp.; Interactive-C - IMPACC Associates

CIRCLE NO. 132 ON READER SERVICE CARD



# IBM COMPATIBILITY at a not so IBM price



## TECH PC/AT ..... \$1999

### PRICE INCLUDES:

- 6MHz 80286 CPU
- 512K
- One, 1.2 MB Floppy Drive
- 8 Expansion Slots
- 195 Watt Power Supply
- Complete MS DOS, PC DOS, Xenix Compatibility
- Runs Lotus 123, dBase III Framework and all other popular AT Software.
- ONE YEAR WARRANTY!!

### OPTIONS:

Tech PC/AT with 20MB Hard Disk ..... **\$2399**

Tech PC/AT with 20MB Hard Disk, Monochrome Monitor, Hercules® Compatible Mono/Graphics Card ..... **\$2599**

Also available with 6-8 MHz Switchable CPU, Tape Backups, Modems, Large Hard Disks, and Networking Systems.

## TECH TURBO PC/AT ..... \$2399

6-8 MHz Switchable 80286 CPU

## TECH TURBO PC/XT ..... \$1099

### PRICE INCLUDES:

- 4 to 7 MHz Software Switchable CPU
- 640K
- Two, 360K DS/DD Floppy Disk Drives
- 8 Expansion Slots
- 135 Watt Power Supply
- ONE YEAR WARRANTY!!

### OPTIONS:

Tech Turbo PC/XT with 20MB Hard Disk ..... **\$1699**

Tech Turbo PC/XT with 20MB Hard Disk, Monochrome Monitor and Hercules® Compatible Mono/Graphics Card ..... **\$1899**

## TECH PC/XT ..... \$799

### PRICE INCLUDES:

- 4.77 MHz CPU
- 256K
- Two, 360K DS/DD Floppy Drives
- 8 Expansion Slots
- 135 Watt Power Supply
- ONE YEAR WARRANTY!!

### OPTIONS:

Tech PC/XT with 20MB Hard Disk ..... **\$1399**

Tech PC/XT with 20MB Hard Disk, Monochrome Monitor, Hercules® Compatible Mono/Graphics Card ..... **\$1599**

TELEX: 272006

Answer Back-TECH

FAX: 714/556-8325

Visa, MasterCard, Check Accepted

**TECH PC PERSONAL COMPUTERS**

**714/754-1170**

2131 S. HATHAWAY, SANTA ANA, CA 92705

©1985 TECH PC

\*Hercules is a registered trademark of Hercules Computer Technology.

\*IBM, IBM PC, XT, and AT are registered trademarks of International Business Machines Corp.

CIRCLE NO. 240 ON READER SERVICE CARD

## LETTERS

provided of the pentathlon program is also a clear indication that single-character records are used. I would note that the following sentence hit the editing room floor: "The file copy test is included for completeness because most FORTRAN files are not organized as a series of one-byte records."

—Alan Howard

Thank you for reviewing F77L version 1.1, Lahey Computer Systems' implementation of the FORTRAN 77 standard. We would like to make the following corrections and comments.

There is an error in table 1 under CHARACTER\*n: F77L CHARACTER length may be as large as 65,519, not 16,383.

Since version 1.1 (last shipped during March 1985), LCS has made many improvements to F77L, including an expanded manual that we are shipping with version 1.36, our current release.

Our version 2.0 includes the ability to address arrays and/or commons larger than 64KB, as well as faster, smaller generated code and the completed Source On-Line Debugger (SOLD) package. SOLD displays the FORTRAN source code while tracing and allow displaying, modifying, and monitoring the changing of variables and array elements (by name, not address) without recompiling and relinking.

We have noted that F77L executed faster in 6 of the 14 tests and the total execution time for IBM was 529.62 seconds compared to Lahey's 303.40—43 percent faster overall.

Finally, we were disappointed that the review did not include testing a production program of meaningful size. We are certain that our fast compile speed (users report four to seven times faster than IBM/RM on medium and large programs), mainframe extensions, and excellent diagnostic messages would have impressed the reviewer as much as they impress our users. They report that compile speed is more significant on a personal computer than it is on a mainframe.

Thank you again for helping more people find out about F77L.

Thomas M. Lahey

President

Lahey Computer Systems, Inc.

The error in table 1 is mine. As Mr. Lahey states, character variables may be up to 65,519 characters in length; 16,383 is the maximum length of a character constant in a data statement. While his claim of being 43 percent faster than the IBM/RM compiler on the

tests may be true, I think it is a misleading statistic and cannot be used to make a general conclusion. I had hoped to include results of larger programs; however, the effort to put any of the larger programs into a form compatible with all four compilers was well beyond the scope of this review.

—Alan Howard

In converting a very large mainframe FORTRAN program to the IBM PC, I have been living for more than a year with some of the compilers Alan Howard reviewed. I would therefore like to add my observations to his.

I have found two disturbing features of the IBM compiler (I have been using the Ryan-McFarland incarnation). One is that the following construction

```
OPEN(UNIT=IFILE,FILE=FNAME,
      STATUS='OLD')
CLOSE(UNIT=IFILE,
      STATUS='DELETE')
```

will not delete an existing file. Inserting an ENDFILE IFILE statement between these two lines will solve the problem.

The other feature is that writing a long unformatted record on a file will abort with an error message, *unless* you call the executable file with a command line parameter R/n where *n* is the number of bytes you want to write, clearly an absolute nuisance.

With the IBM FORTRAN a carriage return is *not* inserted at the end of a formatted write, but if followed by another formatted write, a blank line will appear in between, *unless* a plus sign (+) is coded as the first character in the second FORMAT statement. This is also a nuisance and can cause serious problems whether or not you have data printed by the program in between. I will take the Microsoft approach of an extra character (which is, incidentally, the backslash, not the dollar sign) to suppress carriage returns.

With the Microsoft compiler, on the other hand, I had a crazy abort with a message about the stack full or the heap invalid that was never resolved, but magically disappeared when I switched from version 3.2 to 3.3.

Dr. George Szentirmai  
Santa Clara, CA

Dr. Szentirmai's comment on file delete is true for IBM FORTRAN compiler; the others work correctly. The problem he points out on carriage return control is, again, my error.

—Alan Howard





for yourself!

The C language, a solid foundation for professional software development and Programmer's Connection is your expert source. We specialize in programmer's development tools for IBM Personal Computers and take pride in providing our customers with the finest in selection, availability, price and service. Most of our products come with our 30 day No Risk Guarantee. Here's a closer look at a few selected C products.

### **C Complete Eco-C Development System by Ecosoft, Inc.** LIST OURS 100 89

Complete small model C program development system with compiler, integral CED editor, developer's library with complete source code and ISAM file management library. This new release of the Eco-C88 compiler incorporates many C language enhancements including prototyping, enum and void data types, plus structure passing and assignment. The compiler produces fast executing code and supports automatic sensing of 8087/287 at runtime. It generates either assembler code or object modules that can be linked by the MS-DOS linker. The programming environment is very similar to Turbo Pascal. When the compiler encounters an error, the message is given in English and the CED editor automatically places the cursor on the offending code. Tiered error checking allows you to set the level of semantic errors output by the compiler. The developer's library comes with complete source code more than 220 functions (many are System V compatible). This is the ideal first C compiler for anyone who now programs in Turbo Pascal. Requires 256K memory.

### **C Microsoft C Compiler** 395 259

High performance C compiler that supports register variables, granular runtime libraries and automatic optimization to produce very compact and fast native code. There is an extensive library that implements most UNIX System V functions. It supports small, medium and large memory models, library mix models with NEAR and FAR pointers, DOS pathnames, I/O redirection, file sharing and record locking. There are three math libraries consisting of a floating point emulator, 8087/287 coprocessor support and an alternate package for added speed on systems without a math coprocessor. The system is source code compatible between DOS and XENIX and comes with runtime libraries, a linker and a library manager. Object modules may be linked with those produced by Microsoft Fortran, Pascal and Macro Assembler (MASM). Use the SYMDEB debugger that comes with the separately available Microsoft Macro Assembler (\$109) for source-level debugging of C programs.

### **C Lattice C Compiler from Lattice, Inc.** New 500 CALL

New release of the popular, industry standard C compiler that features faster compilation, more efficient code generation, support for 80186/286 instructions and inline support of 8087/287 instructions. It now supports void, enum, unsigned as a modifier and function prototype checking. The library contains more than 325 functions compatible with UNIX, XENIX and the proposed ANSI standard, plus extensive support for MS-DOS versions 2. + and 3. +. Other useful Lattice C features include support for nested comments, extended symbol length and multiple memory models. It comes with an object module disassembler, a function extract utility, a full set of libraries for each supported memory model, sample programs and extensive documentation. This industry-standard compiler has a wide range of C utilities supporting it including Lattice's own source level debugger C-SPRITE (\$159). This package is published by Lattice, Inc., the company that actually wrote the Lattice C compiler and comes with complete manufacturer's technical support. Requires 128K memory.

### **C Instant C from Rational Systems** 495 379

Extremely fast C interpreter system that is 10 to 1,000 times faster than others in published benchmarks. It comes with an integral full screen editor that displays syntax errors and allows for instant correction. Type in any C expression, statement or function call for direct execution with the results displayed immediately. You can link in OBJ and LIB files — interpreted code can call object code and vice versa. Multi-window and multi-CRT support allow for easy development of screen and graphics applications. Powerful source-level debugging capabilities include many varieties of stepping and conditional breakpoints. Many compile and run-time checks are made automatically. This is a complete C development system that can even make its own standalone EXE files. Comes with library source code, additional standalone editor and full technical support from Rational Systems.

### **C C-terp by Gimpel Software**

Complete, professional C interpreter/semi-compiler with an easy-to-use programming environment similar to Turbo Pascal. It comes with a fast, built-in, configurable editor with multi-file capabilities, interfile move and copy, search and replace, etc. The interpreter is highly configurable and can link in user object modules and commercial or host libraries. With this system, you can call compiled C or assembler functions from within the interpreter. Interactive debugging capabilities allow setting of breakpoints, tracing, single-stepping and direct execution of C expressions. Requires 256K memory. Specify C compiler: Microsoft, Lattice, Mark Williams, Computer Innovations or Aztec.

LIST OURS  
300 249  
45 39

Complete Demo System

### **C c-tree by FairCom**

Highly portable b-tree functions for multi-key ISAM file management in C. There are low level functions for directly accessing data and index files and high level functions for creating and manipulating ISAM files. It comes as complete C source code that can be compiled with almost any C compiler or computer. It supports record locking for multi-users, variable length records, reuse of deleted record space, duplicate and unique key fields and much, much more. There are no royalties on generated code. A super way to provide high speed file access to your C programs.

395 329

### **C Windows for C by Vermont Creative Software**

Comprehensive and fast screen windowing functions for C programs. You can create, scroll, overlap and easily manage any number of multiple, differently colored windows. It provides for rapid screen changes with excellent memory management and supports horizontal and vertical scrolling, logical video attributes, color control, highlighting and window names. Other features include status line management, string output with word wrap and autoscroll, formatted string output, off-screen updating, print windows, keyboard input and a library of over 65 building block subroutines. It's compatible with TopView and the IBM Enhanced Graphics Adapter. Functions are included for pop-up menus and help files. This is an excellent package to bring high performance windowing to your C-based systems. Specify C compiler: Microsoft, Lattice, Mark Williams, Computer Innovations, DeSmet or Aztec.

For MS-DOS 195 139  
For XENIX 395 359

### **C Windows for Data by Vermont Creative Software**

Combines all the capabilities of Windows for C with an integrated set of versatile, easy-to-use data entry functions that operate within windows. Features include one-step data entry, multiple field types, flexible data validation, single field entry, field-specific and context-sensitive help, protected text areas and much, much more. Various field data types are supported including string, character, integer, long, floating point, boolean, time, date and decimal. Input pictures and masks may be specified for each field and the keys used by the powerful field editor may be redefined at will. Use the Lotus-style menu capability in conjunction with the data entry functions to provide a complete end-user interface. Also includes utilities for string, date and time manipulation. Includes Windows for C. Specify C compiler: Microsoft, Lattice, Mark Williams, Computer Innovations, DeSmet or Aztec.

For MS-DOS 295 259  
For XENIX 595 539

### **C The Greenleaf Functions**

Library of over 200 useful C utility functions for disk and file I/O, video effects, cursor, printer, string manipulation, string I/O, keyboard and more. New features include automatic installation and enhanced documentation. Includes complete source code and no royalties on generated code. Specify C compiler: Microsoft, Lattice, Mark Williams, Computer Innovations, DeSmet, Wizard or Aztec.

185 139

### **C The Greenleaf Comm Library**

Asynchronous communications support functions for C programs. Polled and interrupt mode, XMODEM protocol, modem control, Tx and Rx ring buffers and support for up to 8 ports. Functions mostly written in assembler for speed. New features include automatic installation and enhanced documentation. Includes complete source code and no royalties on generated code. Specify C compiler: Microsoft, Lattice, Mark Williams, Computer Innovations, DeSmet, Wizard or Aztec.

185 139

**CALL TOLL FREE: U.S. 800-336-1166**  
**CANADA 800-225-1166 OH 216-877-3781**  
CIRCLE NO. 176 ON READER SERVICE CARD  
**programmer's connection**

Be sure to turn the page for the largest advertised selection of programmer's development tools for IBM Personal Computers and compatibles. ►



# programmer development tools

2/86

## NO SHIPPING CHARGE

When shipping via standard United Parcel Service.

## NO HANDLING CHARGE

Orders are expertly prepared for a safe trip in state, out of state or out of the country.

## NO INSURANCE FEE

All shipments within the United States are insured for their full value.

## NO RISK

If dissatisfied with purchase, return it within 30 days for a refund. See our NO RISK GUARANTEE for details.

### apl and utilities

	LIST	OURS
APL+PLUS/PC System by STSC	595	449
APL+PLUS/PC Tools Vol 1 by STSC	295	239
APL+PLUS/PC Tools Vol 2 by STSC	150	129
APL2C by Lauer Software	150	139
Btrieve by SoftCraft	250	199
Financial/Statistical Library by STSC	275	219
Pocket APL by STSC	95	79
STATGRAPHICS by STSC	695	539

### artificial intelligence

Expteach by Intellware	Complete System	475	399
EXSYS Expert System Development Software		395	339
Golden Common LISP by Gold Hill		495	Call
Insight I by Level Five Research	AI Primer	95	79
Insight II by Level Five Research		485	399
Methods Prototyping Utility by Digitalk		250	219
muLISP by Microsoft		250	189
Prolog-86 by Solution Systems		125	Call
Prolog-86 Plus by Solution Systems	New	195	Call
UNXLISP by Cybermetrics	New	70	59

### assemblers and debuggers

8088 Assembler w/Z-80 Translator by 2500 AD	100	89	
Advanced Trace-86 by Morgan Computing	175	149	
Codesmith-86 Debugger by Visual Age	145	129	
Microsoft Macro Assembler with utilities	150	109	
Pasm86 Marco Assembler by Phoenix Software	295	219	
Periscope Debugger by Data Base Decisions	295	269	
Periscope II by Data Base Decisions	New	145	129
Pfinish Performance Analyzer by Phoenix	395	289	
Pfix-86 Plus Symbolic Debugger by Phoenix	395	289	
The PROFILER by DWB Associates	New version	125	109
Turbo EDITASM Fast Assembler by Speedware	99	89	
Visible Computer: 8088 by Software Masters	70	59	

### basic language

<b>BetterBASIC</b> by Summit Software .....	200	169
8087 Math Support .....	99	89
Btrieve Interface .....	99	89
Run-time Module .....	250	239
<b>Microsoft QuickBASIC Compiler</b> .....	99	79
<b>Professional BASIC</b> by Morgan Computing .....	99	79
8087 Math Support .....	50	47
<b>True Basic</b> from Addison-Wesley .....	150	119
Run-time Module .....	500	459

### blaise products

Asynch Manager for C or Pascal	175	139
C Tools	125	109
C Tools 2	100	89
Combination package	Special Price	175 149
Exec Program Chainer	95	84
Pascal Tools	125	109
Pascal Tools 2	100	89
Turbo ASYNCH for Turbo Pascal	100	89
Turbo POWER TOOLS for Turbo Pascal	100	89
View Manager for C or Pascal	275	219
with Source Code	Special Price	295 239

### c interpreters

C-terp by Gimpel Software	300	249
Instant C by Rational Systems	500	379
Introducing C by Computer Innovations	125	109
Run/C Lite from Lifeboat	150	109
Run/C Professional from Lifeboat	250	199

### c compilers

<b>c compilers</b>	LIST	OURS
<b>C-86 Compiler</b> by Computer Innovations . . . . .	395	299
<b>Datalight C Compiler</b> . . . . .	60	49
<b>DeSmet C Compiler w/Source Debugger</b> . . . . .	159	145
<b>Eco-C Development System</b> by Ecosoft . . . . .	100	89
<b>Lattice C Compiler</b> from Lattice . . . . .	500	Call
<b>Lattice C</b> from Lifeboat . . . . .	500	299
<b>Let's C Compiler</b> by Mark Williams . . . . .	75	69
<i>with csd Source Level Debugger</i> . . . . .	150	129
<b>MWC-86</b> by Mark Williams . . . . .	495	379
<b>Microsoft C Compiler</b> . . . . .	395	259
<b>Wizard C</b> by Wizard Systems . . . . . <i>Includes lint</i>	450	389

### c utilities

APT Toolkit by Shaw American Technology	395	339
Asynch Manager by Blaise Computing	175	139
Basic_C Library by C Source	175	139
Btrieve by SoftCraft	250	199
C Cross Reference Generator by Lattice	50	39
C-Food Smorgasbord by Lattice	150	109
The C Library by Kris Jamsa Software	New	90 79
C Power Packs by Software Horizons	Call	Call
C-Sprite Program Debugger by Lattice	175	139
C to dBase by Computer Innovations	150	139
C Tools by Blaise Computing	125	109
C Tools 2 by Blaise Computing	100	89
c-tree by FairCom	395	329
C Utility Library by Essential Software	185	139
CI Probe Source Level Debugger	225	199
CI ROM Pack for C-86	195	149
Curses Screen Manager by Lattice	125	109
with Source Code	250	219
dBC dBase File Manager for C by Lattice	250	199
with Source Code	500	395
db_VISTA Single-User DBMS by Raima	195	159
with Source Code	495	429
db_VISTA Multi-User DBMS by Raima	495	429
with Source Code	990	849
Entelekon C Function Library	130	119
Entelekon C Windows	130	119
Entelekon Superfonts for C	50	45
Entelekon Combination Package	200	179
ESP for C and Pascal	200	159
FirstTime for C by Spruce Technology	295	229
GraphicC by Scientific Endeavors	250	209
The Greenleaf Functions	185	139
Greenleaf Comm Library	185	139
The HAMMER by OES Systems	195	179
H.E.L.P. by Everest Solutions	395	329
MetaWINDOWS by Metagraphics	150	139
Multi-Halo by Media Cybernetics	Royalties	250 189
On-line Help from Opt-Tech Data	New	149 119
PANEL by Roundhill	Library Source Available	295 234
PC Lint by Gimpel Software	139	109
Polytron C Library	99	79
Pre-C Lint Utility by Phoenix	395	289
Scientific Subroutine Library for C by Peerless	175	139
TopView Toolbasket by Lattice	250	199
with Source Code	500	395
View Manager for C by Blaise Computing	275	219
with Source Code	Special Price	295 239
Vitamin C by Creative Programming	150	139
Windows for C by Vermont Creative Software	195	139
Windows for Data	Includes Windows for C	295 259

### cross assemblers

We carry over 25 different cross assemblers from 2500 A.D.

6800 XASM by 2500 AD	200	165
8080 XASM by 2500 AD	200	165
68000 XASM by 2500 AD	300	249
Z-80 XASM by 2500 AD	200	165

### fortran compilers and utilities

Microsoft Fortran	Links with Microsoft C	350	229
RM/Fortran by Ryan-McFarland		595	399
Btrieve by SoftCraft		250	199
FORLIB-PLUS by Alpha Computer Service		70	59
Multi-Halo by Media Cybernetics	Royalties	250	189
PANEL Screen Designer by Roundhill		295	234
PolyFortran Tools by Polytron		179	139
Scientific Subroutine Library by Peerless		175	139
The Statistician by Alpha Computer Service		295	269
Strings and Things by Alpha Computer Service		70	59

### lattice products

These products receive support and updates directly from Lattice Inc. Lattice C is in stock and ready for shipment.

<b>Lattice C Compiler</b> .....	500	Call
<b>C Cross Reference Generator</b> .....	50	39
<b>C-Food Smorgasbord Function Library</b> .....	150	109
<b>C-Sprite Debugger</b> ..... <i>Now Supports Source Level</i>	175	139



# for the IBM-PC/XT/AT and compatibles.

## cont. lattice products

	LIST	OURS
Curses Screen Manager	125	99
with Source Code	250	199
dBC dBase File Manager for C	250	199
with Source Code	500	395
LMK Make Facility	195	149
RPG II Compiler	New	750 595
SecretDisk Disk Security	New	60 49
SideTalk Resident Communications	New	120 95
Text Mgmt Utils (GREP/DIFF/ED/WC/Extract/Build)	120	95
TopView Toolbasket Function Library	250	199
with Source Code	500	395

## microsoft products

C Compiler	395	259
COBOL Compiler	700	495
Fortran Compiler	350	229
Macro Assembler w/utilities	150	109
Microsoft Windows	99	89
MS Sort	195	149
muLISP	250	189
Pascal Compiler	300	219
QuickBASIC Compiler	99	79

## other languages

ALICE by Software Channels	New	95	Call
Janus/ADA C Pack by R&R Software		95	89
Janus/ADA D Pack by R&R Software		900	699
Level II COBOL by Micro Focus		750	599
Modula-2/86 by Logitech		495	399
PC/Forth by Laboratory Microsystems		150	119
PC/Forth+ by Laboratory Microsystems		250	209
Professional COBOL by Micro Focus		3000	2395

## phoenix products

In stock and ready for immediate shipment.

Pasm86 Macro Macro Assembler	295	219
Plink-86 Overlay Linker	395	289
Pre-C Lint Utility	395	289
Pfantasy Pac	995	895
Pfinish Performance Analyzer	395	289
Pfix-86 Plus Symbolic Debugger for Plink-86	395	289
Plink-86 Plus Overlay Linker	New	495 359
Pmaker Program Development Manager	195	139
Pmate Macro Text Editor	225	159
Ptel Binary File Transfer Program	195	139

## polytron products

Polytron C Library	99	79
PolyFortran Tools by Polytron	179	139
PolyLibrarian Library Manager	99	79
PolyLibrarian II Library Manager	149	129
PolyMake UNIX-like Make Facility	99	79
PolyOverlay Overlay Optimizer	99	79
PolyXREF Cross Reference Utility	219	179
PolyXREF	129	109
PVCS Polytron Version Control System	395	359
PVMFM Polytron Virtual Memory File Manager	199	179

## softcraft products

Btrieve /SAM File Manager	250	199
Btrieve/N for Networks	595	469
Rtrieve Report Generator for Btrieve	85	79
Rtrieve/N Report Generator for Btrieve/N	175	159
Xtrieve Query Utility for Btrieve	195	169
Xtrieve/N Query Utility for Btrieve/N	395	299
OPT-Tech Sort by Opt-Tech Data Processing	99	84

## text editors

Brief from Solution Systems	195	Call
Epsilon by Lugaru	195	165
ESP for C and Pascal	200	159
FirstTime for C by Spruce Technology	295	229
FirstTime for MS Pascal by Spruce Technology	245	199
FirstTime for Turbo by Spruce Technology	75	69
KEDIT by Mansfield Software Group	125	109
Pmate by Phoenix	225	159
SPF/PC by Command Technology Corp	195	165
Vedit by Compuview	150	119
Vedit Plus by CompuView	225	180
XTC Text Editor by Wendin	99	89

## turbo pascal and utilities

	LIST	OURS
Turbo PASCAL by Borland International	70	49
Turbo PASCAL w/8087 or BCD	110	79
Turbo PASCAL w/8087 & BCD	125	85
FirstTime for Turbo by Spruce Technology	75	69
Multi-Halo by Media Cybernetics	Royalties	250 189
On-line Help From Opt-Tech Data	New	149 119
Screen Sculptor by Software Bottling	125	99
Turbo ASYNCH by Blaise Computing	100	89
Turbo Holiday Jumbo Pack	All 6 items below	245 219
Turbo PASCAL	70	49
Turbo DATABASE TOOLBOX	55	49
Turbo EDITOR TOOLBOX	New	70 59
Turbo GAMEWORKS TOOLBOX	New	70 59
Turbo GRAPHIX TOOLBOX	55	49
Turbo TUTOR	35	29
Turbo Holiday Pack	Turbo PASCAL/Database/Tutor	125 99
Turbo New Pack	Editor/Gameworks	95 79
Turbo POWER TOOLS by Blaise Computing	100	89
TurboPower Utilities by TurboPower Software	95	89
TurboRef by Gracon Services	50	45
TurboWindow by MetaGraphics	50	39
XTC Text Editor by Wendin	99	89

## wendin products

Operating System Toolbox	Build your own OS	99	89
PCUNIX Operating System		99	89
PCVMS Operating System	Similar to VAX/VMS	99	89
XTC Text Editor	Includes Pascal source code	99	89

## xenix system v by sco

Xenix 86 Development System	For XT	495	449
Xenix 86 Operating System	For XT	495	449
Xenix 86 Text Processing Package	For XT	195	179
Complete Xenix 86 System	Combined Package	1085	969
Xenix 286 Development System	For AT	495	449
Xenix 286 Operating System	For AT	495	449
Xenix 286 Text Processing Package	For AT	195	179
Complete Xenix 286 System	Combined Package	1085	969

## xenix languages and utilities

APL+PLUS/UNIX System by STSC	For AT only	995	795
Btrieve by SoftCraft		595	469
c-tree by FairCom		395	329
Microsoft BASIC Interpreter		350	279
Microsoft COBOL Compiler		995	795
Microsoft Fortran Compiler		495	389
Microsoft PASCAL Compiler		495	389
PANEL Screen Designer by Roundhill	For AT only	595	539
Windows for C by Vermont Creative Software		395	359
Windows for Data by Vermont Creative Software		595	539

We are open until 5 p.m. Pacific Time,  
(8 p.m. Eastern).

Purchase Orders are accepted from qualified accounts  
at no extra charge.

Visa and MasterCard are accepted with no surcharge  
applied. Please include card expiration date when  
ordering by mail. Account is charged when shipped.



**U.S. 1-800-336-1166**

**CANADA 1-800-225-1166**

**OHIO 1-216-877-3781**



## OUR NO RISK GUARANTEE

If you are not completely satisfied with your purchase  
you may return it within 30 days. All returned  
products must meet our standards for being in new,  
resellable condition including all paperwork and  
unused registration card. Products including source  
code are generally excluded by the manufacturer from  
this guarantee. Please ask for specific details when  
placing your order.

Prices are subject to change without notice.



# programmer's connection

1 3 6 SUNNYSIDE STREET / HARTVILLE / OHIO / 4 4 6 3 2  
CIRCLE NO. 175 ON READER SERVICE CARD



# If you want to run software with graphics on your monochrome monitor, we have some bad news.

**A**s we're sure you've been told, the only way to run software with graphics on a monochrome monitor is to buy a graphics card.

For \$499, the Hercules Graphics Card runs these best-selling programs:

Ashton-Tate, *Framework*

BPS, *Overhead Express*

Lotus Development, *1-2-3, Symphony*

MicroSoft, *MicroSoft Flight Simulator, MicroSoft Word, MicroSoft Chart*

Software Products Int., *Open Access*

Software Publishing, *PFS: Graph*

Sorcim, *Supercalc 3*


In monochrome only.



# And some good news.

**F**or \$395, the Paradise Modular Graphics Card runs all these programs. In monochrome. And in color.

Arrays/Continental Software, *Ultra File*  
Ashton-Tate, *Framework*  
BPS, *Overhead Express*  
Brightbill-Robert, *Graphix Partner*  
Chang Labs, *GraphPlan*  
Dow Jones & Co., *Dow Jones Market Analysis*  
Lotus Development, *1-2-3*, *Symphony*  
MicroPro, *Chartstar*, *Planstar*  
MDBS, *Knowledge Manager*  
Microsoft, *Basic Compiler*, *Basic Interpreter*, *Chart*, *Flight Simulator*, *Project*, *Word*  
PC Software of San Diego, *Executive Picture Show*  
Prentice-Hall, *Execuvision*  
Schuchardt Software Systems, *Intecalc*, *Intemate*, *Intepert*, *Inteplan*, *Inteword*  
Softrend, *Aura*  
Software Products Int., *Open Access*  
Software Publishing, *PFS:Graph*  
Sorcim, *SuperCalc 3*  
Summa Software, *Winning On Wall Street: Trader's Forecast*, *Winning On Wall Street: Trader's Data Manager*  
Advanced Ideas, *The Game Show*, *Master Match*, *Tic Tac Show*  
CBS Software, *Big Bird's Special Delivery*, *Dinosaur Dig*, *Ernie's Magic Shapes*  
Davidson & Associates, *Math Blaster!*, *Word Attack!*  
Designware, *The Grammar Examiner*, *Math Maze*, *Language Arts*, *Spellicopter*, *States & Traits*, *Trap-a-zoid*  
Developmental Learning Materials, *Alien Addition*, *Alligator Mix*, *Demolition*, *Division*, *Dragon Mix*, *Meteor Multiplication*, *Minus Mission*  
Eduware, *Algebra 1*, *Algebra 2*, *Algebra 3*, *Algebra 4*, *Algebra 5*  
Individual Software, *Professor Pixel*, *The Instructor*, *The Typing Instructor*  
Knoware, *Knoware*  
Scarborough Systems, *Mastertype*, *Songwriter*  
Learning Co., *Addition Magician*, *Magic Spells*, *Moptown Parade*, *Number Stomper*, *Reader Rabbit*  
Scholastic, *Turtle Tracks*  
Sierra On-Line, *Dragon's Keep*, *Troll's Take*  
Simon & Schuster, *Typing Tutor III*  
Spinnaker Software, *Alphabet Zoo*, *Delta Drawing*, *Fraction Fever*, *Hey Diddle Diddle*, *Kids on Keys*, *Kindercomp*, *Rhymes & Riddles*, *Story Machine*



**The Paradise Modular Graphics Card runs all the popular programs Hercules does, plus 150 more.**

Springboard, *Early Games for Young Children*, *Make a Match*, *Piece of Cake Match*, *Quizagon*

Thoroughbred Software, *Exploring the Amazing Food Factory*, *The Fascinating Story of Cell Growth*, *How Plants Grow*, *Migrating Molecules*, *Mastering Units of Measurement*, *Photosynthesis*

Unicorn Software, *Funbunch*, *Ships Ahoy*, *Ten Little Robots*

Digital Research, *DR Logo*

Energtonics, *Energraphics*

Fox & Geller, *dGraph*, *OZ*

Graphic Communication, *Graphwriter BASIC*, *Graphwriter Combination*, *Graphwriter Extension*

Harvard Associates, *P.C. Logo*

Innovative Software, *Fast Graphs*

Mouse Systems, *PC Paint*

PC Software of San Diego, *PC Crayon*

Peachtree Software, *Business Graphics System*  
Arktronics, *Jane*

Eagle Software Publishing, *Personal Financier*

Monogram, *Dollars and Sense*

Penguin Software, *Graphics Magician*

Sierra On-Line, *Homework*

Adventure Enterprises, *Sea Dragon*

Atarisoft, *Centipede*, *Defender*, *Dig Dug*, *Donkey Kong*, *Pac Man*, *Robotron*, *Stargate*

Avalon Hill Game Company, *Andromeda Conquest*, *Computer Football Strategy*, *Computer Stocks & Bonds*, *V.C.*, *Voyager*

Broderbund Software, *Serpentine*

CBS Software, *Match-Wits*, *Mystery Master: Murder by the Dozen*

Hayden Software, *Sargon III*

Innovative Design Software, *Pool 1.5*

Intelligent Statements, *Asylum*

Microlab, *Crisis Mountain*, *Death in the Caribbean*, *Dino Eggs*, *High Rise*, *Miner 2049er*

Muse Software, *Castle Wolfenstein*

Odesta, *Backgammon*, *Checkers*, *Chess*, *Odin*

Origin Systems, *Ultima III*

Orion Software, *J-Bird*

PC Software of San Diego, *Championship Blackjack*

Penguin Software, *The Quest*

Priority Software, *Forbidden Quest*

Scarborough Systems, *Buck Rogers*, *Congo Bongo*, *Star Trek*

Sentinent Software, *Cyborg*

Sierra On-Line, *BC's Quest of Tires*, *Championship Boxing*, *CrossFire*, *Dark Crystal*, *Frogger*, *King's Quest*, *Oil Well*, *Ultima II*, *Ulysses and the Golden Fleece*

Sir Tech, *Wizardry*

Sirius Software, *Buzzard Bait*

Spectrum Holobyte, *Gato*

Spinnaker Software, *Snooper Troops #1*, *Snooper #2*

Sublogic, *"Night Mission" Pinball*

**I**t's true, Hercules only runs 10 of the 161 programs with graphics for the IBM PC carried by SOFTSEL®, the largest distributor of micro computer products.

Since the Paradise Modular Graphics card is 100% compatible with the IBM color graphics standard, it'll run virtually every program written for the PC. In monochrome. And in color. Now and in the future.

And we give you a \$50 trade-in allowance on your old Hercules or IBM card.

So see your dealer or call us. And get some good news for a change.

## PARADISE

S Y S T E M S , I N C

CIRCLE NO. 230 ON READER SERVICE CARD

Paradise Systems Inc., 217 East Grand Ave., South San Francisco, CA 94080  
(800) 822-2020 Ext. 248 (CA) or (800) 527-7977 Ext. 248 (Outside CA)



## News about the Microsoft Language Family

**New Microsoft® LISP Offers a Complete LISP Programming Environment**

Microsoft has extended its six-year relationship with Soft Warehouse, Inc. of Hawaii by renewing the licensing agreements for muLISP™ and muMATH™ products. Microsoft LISP, the newly updated release of Microsoft muLISP, is the most powerful LISP development environment available for MS-DOS® today. Not only is Microsoft LISP three times faster than its competitors, it also allows larger artificial intelligence programs and expert systems to be developed. The new LISP provides over 400 Common LISP functions, macros, special forms, and control variables. Microsoft LISP comes with an integrated window-oriented LISP editor and debugger, tutorial lessons, and several demonstration LISP programs.

**Mixed Memory Model Dynamic Allocation in Microsoft C—Part 1**

The standard method of dynamic heap allocation in C is provided by the *malloc* and *free* library routines. In Microsoft C this has been extended to allow mixed memory model dynamic allocation and deallocation in both *near* and *far* heaps for all memory models by using the undocumented routines below:

```
extern char near* _nmalloc(unsigned int);    /*near heap*/
extern void _nfree(char near*);             /*near heap*/
extern char far* _fmalloc(unsigned int);    /*far heap*/
extern void _ffree(char far*);              /*far heap*/
```

For example, a small memory model C program can be written that can dynamically allocate and access more than 64K of data by using far heap allocation and far pointers. Similarly, the efficiency of large model programs can be improved by using near pointers and the near heap. However, with mixed model programming, care must be taken when accessing library routines that take pointers for parameters.

Part II to follow next month.

**Microrim's R:BASE™ 5000 Developed in Microsoft FORTRAN and C**

The core R:BASE 5000 database management system product contains about 40,000 lines of Microsoft FORTRAN code. New modules for R:BASE were developed in Microsoft C. Fred Gray, Microrim's Director of Development said, "Interlanguage calling allows us to migrate our code from FORTRAN to C without having to rewrite the entire product at once."


Microrim also provides the R:BASE Program Interface, which is a library of relocatable FORTRAN routines for accessing R:BASE databases. The interlanguage calling support in Microsoft FORTRAN, Pascal, and C allows application developers to call any routine in the Program Interface.

**Write to:** MICROSOFT Languages Newsletter  
10700 Northup Way, Box 97200  
Bellevue, WA 98009 for product and update information  
**Or phone:**  
(800) 426-9400. In Washington State and Alaska,  
call (206) 828-8088. In Canada, call (800) 387-6616.

**Latest DOS Versions:**

Microsoft C	3.00
Microsoft COBOL	2.10
Microsoft FORTRAN	3.31
Microsoft Macro Assembler	4.00
Microsoft Pascal	3.31
Microsoft QuickBASIC	1.00





# The Hardcard

*By assuming connection to the IBM PC, this hard-disk-on-a-card offers exceptional speed, reliability, and ease of use.*

The 10MB hard disk, once a great luxury, is rapidly becoming a minimum requirement for serious use of the IBM PC. Important new software products, such as Microsoft Windows, can be installed on floppy disks, but they leave little room for anything else. Microtec's Professional Pascal compiler, for example, is a 566KB .EXE file—larger than a single 360KB floppy diskette. In the coming years, attention will be focused on the system with the hard disk.

Adding a hard disk to the PC is not a trivial matter. One floppy-disk drive must be removed (and replaced by the hard-disk drive), and two data cables must be run and connected to a controller board that must be installed in a vacant slot. Typically the PC's 63.5-watt power supply must be enhanced or replaced by a more potent supply. In addition, the user often is unwilling to forgo dual-floppy-drive convenience and so replaces the remaining full-height floppy-disk drive with a pair of half-height drives. These changes leave the user with a lot to buy, a lot to do, and, more importantly, a lot that can go wrong. Given the available components, however, this would seem to be the simplest method.

The only easier method would be to build a hard disk onto a PC bus expansion card, but that's impossible—or so it appeared before the midsummer 1985 announcement of Plus Development's Hardcard. No one had expected this product, and for a long time no one believed that a shock-resistant hard-disk system could be made only 1½ inches thick. Plus, however, delivers a product that is everything it claims to be and more. For this reason, *PC Tech Journal* has named the Hardcard as its February 1986 Product of the Month.

The Hardcard is as ambitious a piece of design work as the PC itself was conservative. Half of the device's 20 ICs are custom-designed, surface-mounted chips on an extremely dense

board layout. The layout precludes the use of traditional discrete bypass capacitors and requires the tiny leadless surface-mounted chip variety instead.

The drive mechanism is a wonder of mechanical compaction. It is an entirely new design; little has been borrowed from traditional hard disks. Apart from being small, fast, and simple, it is also rugged, capable of withstanding shocks of 100 g without damage. The read/write heads automatically park themselves and lock into a protected

through noisy environments. The controller board must have matching machinery to communicate with the hard disk itself. The Hardcard does away with the standard interface and assumes that it always will be connected to one standard, well-known bus: the IBM PC bus. Eliminating noisy paths and unnecessary components cannot help but produce a more reliable device.

By assuming connection to the IBM PC, the Hardcard disk can be formatted at the factory to a standard DOS format, eliminating one installation step and a possible source of user confusion and error. Its pervasive reliance on the standard set for the PC is a factor in the Hardcard's success as a piece of engineering. The PC standard itself may not be brilliant, but it is a standard that is thoroughly understood, well documented (thanks largely to IBM's open-architecture policy), and represented in the field by millions of PCs and close compatibles.

Plus Development's commitment of a major piece of ground-up development work in mass storage to a single computer is quite a leap of faith. The Hardcard is the first mass-storage peripheral that cannot be installed on different computer architectures. Risk is involved in any such commitment, but the dividends in reliability and ease of installation are considerable.

However, the premium exacted for this convenience and reliability—\$1,095—is too high for 10MB. As similar products appear with off-the-shelf standard interfaces, the competition may help to bring its price down. However, their economies of complexity, reliability, and size will not be as great as Hardcard's; further, Plus's innovative optimization about the IBM PC standard will give it an edge for some time. (The Hardcard is reviewed in more detail in this issue of *PC Tech Journal*; see "Storage on a Card," Thomas V. Hoffmann, p. 139.)

## PRODUCT NAME

Hardcard

## COMPANY

Plus Development Corporation

## ADDRESS

1778 McCarthy Boulevard  
Milpitas, CA 95035

## TELEPHONE

408/946-3700

## PRICE

\$1,095

position when power is removed, a further precautionary feature. The reliability figure quoted for the Hardcard is a new high for hard-disk subsystems: an MTBF of 25,000 hours.

But good design is only one factor; the use of considerably fewer parts accounts for more. The Hardcard can reduce the number so drastically partly because the function of what might have been a hundred ICs has been combined into a handful of custom LSI chips. Furthermore, Hardcard dispenses with a great deal of the hardware overhead of a standard hard-disk interface.


To accommodate widely varied host computer requirements, typical hard-disk units must present a standard interface to the outside world. This interface must be able to pass signals reliably at great speed over long cables



## Hardware, software, and other developments for the IBM PC family



Anchor Automation's 1200-bps modem



IBM Wheelprinter E

### FROM IBM

The **IBM PC Voice Communications Option** consists of an adapter card and control program that, combined with applications software, give PC users new voice and telephone management capabilities. Software is available to control applications by voice command, to create and store personal telephone directories, to use the PC for automatic dialing, to play back telephone messages via the PC, to convert text to synthetic speech, and to gain access to mail and calendar information. \$1,250.

Also from IBM, the **Personal Telephone Manager** connects a PC to a telephone and allows users to create and store personal telephone directories. With a single keystroke, the user can instruct the PC to dial a directory number. The package consists of an adapter card and an application program. Adapter, \$325; program, \$70.

Electrophotographic technology allows the **IBM Pageprinter** to print text and graphics at speeds of 12 pages a minute. The Pageprinter attaches to most PCs and can be used as a text-only printer for the IBM System/38 and two models of the System/36. It also can serve as a full-function text and graphics printer with larger systems and, with an optional sharing card, can be attached to eight PCs in a single office and to all the systems connected on a LAN. \$7,490.

The **IBM Wheelprinter E**, uses a cartridge print wheel to produce letter-quality text on correspondence and multipart forms. It is designed for both home and office use. \$699.

In addition, the company's new **DisplayWrite 3 version 1.1** allows more efficient exchange of information with other IBM systems, such as the System/36. It gives users greater capabilities for converting DisplayWrite 3 text to and from revisable-form text and to final-form text. \$450.

**Rolm Corporation**, an IBM company, has announced **Juniper II**, an integrated voice/data communications complement to the PC, PC/XT, and PC/AT, that provides compatibility with IBM's Personal Services/PC and PROFS/PC Connection, which are PC-resident communication packages. Juniper II allows PC users to transfer information to and from a host computer or another PC at speeds of up to 9600 bps. Other features include: IBM 3270 and DEC VT100 terminal emulation capabilities; one-touch log on for data calls; two-way speakerphone; and powerful digital telephone functionality. The package consists of a multifeatured digital telephone, an adapter card, connector cabling, and software. \$1,295.

Also from Rolm comes the **3270 CTPA (coax-to-twisted-pair adapter)** that allows IBM 3270 terminals to be connected to control units using telephone twisted-pair wiring. Customers now have the option of using previously installed telephone wire to connect terminals. \$100 per connection. *IBM Corp., Information Systems Group, Rye Brook, NY 10573; Contact the local IBM dealer, 800/426-2468*

CIRCLE 319 ON READER SERVICE CARD

Another group of products from **IBM**, collectively called **A Realtime Interface Co-Processor (ARTIC)**, enhances the processing capabilities of industrial computers in a manufacturing environment. ARTIC includes a coprocessor with 128KB of user memory, a control program that supports concurrent processing of as many as 253 tasks, DOS support, a communications subsystem that provides a link between applications programs and terminal devices controlled by communications tasks, and a developer's kit.

*IBM Corp., Manufacturing Systems Products, Boca Raton, FL 33432; Contact the local IBM dealer, 800/426-2468*

CIRCLE 320 ON READER SERVICE CARD

IBM also has announced price increases on 139 of its more than 475 programs for the PC family. Most of the increases, based on single-unit prices, are between 8 and 10 percent. Software affected includes operating systems, and educational, entertainment, and business programs. Among those not affected are the firm's Personally Developed Software and most of the Assistant, Personal Decision, and Business Management Series. *IBM Corp., Entry Systems Division, Boca Raton, FL 33432; Contact the local dealer, 800/426-2468*

CIRCLE 321 ON READER SERVICE CARD

### HARDWARE

The **Signalman Secure 12** is an intelligent 1200-bps modem with a built-in security callback system. Introduced by **Anchor Automation, Inc.**, the Secure 12 can operate as either a secure or a standard modem and conforms to the Hayes command structure, which allows both unattended and manual data transmission from virtually any external computer or terminal. \$499.

*Anchor Automation, Inc., 6913 Valjean Avenue, Van Nuys, CA 91406; 818/997-7758*

CIRCLE 325 ON READER SERVICE CARD


The **Persyst SuperCharger**, a combination high-speed 8086 microprocessor and 512KB high-speed 16-bit memory board, has been introduced by **Emulex Corporation**. The 8086 chip runs at either 9.54 MHz or 4.77 MHz; the speed can be selected by the user or by software. The memory board allows large spreadsheets and programs to load and operate quickly and reduces the processing time required for programs such as Lotus 1-2-3 and Symphony. \$995. *Emulex Corp., 3545 Harbor Blvd., Costa Mesa, CA 92626; 800/EMULEX 3; in California, 714/662-5600*

CIRCLE 327 ON READER SERVICE CARD





Quadram's 72MB internal hard-disk drive




XTC Tape Cartridge System

**Adaptec, Inc.** has announced the **ACB-2070A**, an encoding/decoding hard-disk controller board for the PC and PC/XT. The ACB-2070A plugs into a PC expansion slot or replaces the existing XT controller board and boosts disk-drive capacity by 50 percent. It provides 30MB of storage capacity in 20MB drives and supports an increased data-transfer rate of 7.5MB per second. The board's other features include automatic configuration, sector-level defect handling, large disk logical partitioning, and pre-programmed BIOS. \$165.

*Adaptec, Inc., 580 Cottonwood Drive, Milpitas, CA 95035; 408/946-8600*

CIRCLE 336 ON READER SERVICE CARD



ACB-2070A by Adaptec, Inc.

A group of XENIX and UNIX hardware and software products for the PC/AT has been introduced by **Bell Technologies**. The **XTC Tape Cartridge System** provides 45MB or 60MB of high-speed tape backup for an AT with standard one-quarter-inch tape cartridges. The **B86**, an 86MB hard-disk drive, has an average access time of 28 milliseconds and formats disks to 72MB. It is fully compatible with the AT running DOS or XENIX, and users booting from the B86 can utilize the entire disk as a single volume. The new Bell **RAM2** card provides 2MB of RAM as well as an optional parallel and serial port capability on the same card. In addition, it offers parity checking across the entire memory range, and memory mapping is switch selectable. RAM2 uses 120 ns DRAM

parts and is compatible with the **8MHZ System Clock Upgrade**, also new. This upgrade product includes a collection of four crystals that can replace the main system clock crystal on the AT and uses a special speed-selection process. XTC, \$1,695; B86, \$2,495; RAM2, \$745; System Clock Upgrade, \$45.

*Bell Technologies, 44870 Osgood Road, Fremont, CA 94539; 415/659-9097*

CIRCLE 323 ON READER SERVICE CARD

**Quadram Corporation** launched a new storage products division with the introduction of the **QuadDrive** line of full- and half-height hard-disk drives. Available in 10MB, 20MB, and 72MB versions for the PC and PC/XT, and in 20MB and 72MB versions for the PC/AT, the new drives are internal units that come with menu-driven software, a controller card, and complete documentation. For the PC or XT: 10MB, \$945; 20MB, \$1,195; 72MB, \$3,995. For the AT: 20MB, \$1,095; 72MB, \$3,795.

*Quadram Corporation, One Quad Way, Norcross, GA 30093; 404/923-6666*

CIRCLE 322 ON READER SERVICE CARD

The **XP/48 Graphics Extension Processor** from **Superset, Inc.** provides the PC, PC/XT, and PC/AT with full 48-bit, virtual-memory mainframe graphics capabilities. This graphics system features 4,096-by-4,096 resolution (16.7 million simultaneous colors) and a library that includes bars, exploded pies, shaded fonts, three-dimensional surfaces and axes, shaded states and counties, world maps, log, polar, and calendar axes, grids, and spline and polynomial curves. Also included are full digitizer support, user-extendable publication-quality fonts, multipass rasterization with half toning, paneling and color separation, and drivers for more than 100 devices. \$170,000.


*Superset, Inc., 11025 Roselle Street, San Diego, CA 92121; 619/452-8665*

CIRCLE 324 ON READER SERVICE CARD

**ATLAS**, a mass-storage, high-speed, disk-drive/disk-controller system, has been introduced by **Alpha Data Inc.** The system combines the Alpha Data 160MB disk-drive unit with the enlarged capacity Interphase Maverick controller board and appropriate software to provide 54 read/write heads on three disk-drive platters and instant access to 1MB of information in 18 milliseconds. 128MB system with Maverick, \$10,850; 160MB system, \$11,850.

*Alpha Data Inc., 20750 Marilla Street, Chatsworth, CA 91311; 818/882-6500*

CIRCLE 338 ON READER SERVICE CARD




ATLAS disk-drive/disk-controller system

**Orchid Technology, Inc.** announced a new line of multifunction boards that conform with the Lotus/Intel/Microsoft expanded memory specification. The boards feature high-capacity disk caching and print spooling. **ECCELL**, designed for the PC/AT, provides error-correction code capabilities, a total memory capacity of 12MB, and switchless installation. **Conquest** for the PC and PC/XT is a multifunction board, an expanded memory board, and an optional LAN adapter board. The third product is a compact board that is designed for installation in the short slot of the PC or the PC/XT. **CramRAM** is both a multifunction board and a memory board that provides 2MB of memory. ECCELL, \$595; optional daughtercard, \$145; Conquest, \$395; CramRAM, \$395.

*Orchid Technology, Inc., 47790 Westinghouse Drive, Fremont, CA 94539; 415/490-8586*

CIRCLE 326 ON READER SERVICE CARD





Alliance system by Matrix



Model 9000 Business Keyboard by Enigma

A new PC/AT compatible keyboard, the **Model 9000 Business Keyboard**, has been introduced by **Enigma Research, Inc.** Its features include: 40 user-programmable function keys; standard selectric layout with extra large Return and Shift keys; dedicated numeric keypad with a separate Return key, complete set of mathematical symbol keys, and separate control, Alt and Shift keys; LEDs on the CapsLock, NumLock, ScrollLock, and Print Echo On/Off keys; tactile feedback; and breakover feel. \$295.

*Enigma Research, Inc., 4534 Vista del Monte, Suite 104, Sherman Oaks, CA 91403; 818/784-0343*

CIRCLE 330 ON READER SERVICE CARD


The **Alliance Series**, introduced by **Matrix Communications**, is a low-cost, easy-to-install alternative to LANs. The system links 20 PCs, allowing them to share peripherals such as printers, modems, and disks. It is based on a programmable intelligent cluster controller that connects PCs via RS-232 interfaces at 115 Kbps, and offers the features of a LAN with asynchronous communications, such as file sharing, peripheral sharing, and a central clock and calendar. An additional 480KB buffer is available that allows the cluster controller to perform print spooling and electronic mail functions. Two software packages are included with the system: a utility program for administering the network and an interface program that allows each microcomputer to access the network. Eight-port model, \$895; each additional four-port module, \$349. *Matrix Communications, 112-116 Washington Street, Marblehead, MA 01945; 617/639-1211*

CIRCLE 331 ON READER SERVICE CARD

A portable Winchester disk drive analyzer designated **Model 506** has been introduced as the first in a new line of technology test equipment from **KJ Instruments, Inc.** This analyzer allows

test engineers to configure all test parameters in any sequence. Test programs can be entered and stored in nonvolatile memory, then selected for use with switches on the analyzer's front panel. In operation, it furnishes realtime test data on any ST506/412 compatible drive and tests fixed, removable, or fixed/removable Winchester models, including 5.25-, 3.9- and 3.5-inch units. Model 506 can operate by modem or extend to a network of eight test stations managed by one PC equipped with an eight-port RS-232 board. \$3,500. *KJ Instruments, Inc., 22981 Alcalde Drive, Laguna Hills, CA 92653; 714/768-3070*

CIRCLE 335 ON READER SERVICE CARD



KJ's Model 506 Winchester disk drive analyzer

A package that implements IBM's LU6.2 protocol has been announced by **Network Software Associates, Inc.** The **AdaptSNA LU6.2** lets a PC, PC/XT, or PC/AT communicate and transfer files in an IBM SNA/SDLC network. It supports PC-to-mainframe and PC-to-PC communications. AdaptSNA can be purchased as software only or as a package with a modem and SDLC interface hardware on a plug-in board. Software only, \$795; package, \$1,590.

*Network Software Associates, Inc., 22982 Mill Creek, Laguna Hills, CA 92653; 714/768-4013*

CIRCLE 339 ON READER SERVICE CARD

The result of a joint development program between **Texas Instruments** and **IBM**, the **TMS380** is a LAN adapter chip set. It provides standardized interfaces for attaching computers, terminals, telecommunications equipment, and other information processing devices to IBM's token-ring network. The TMS380 meets ANSI/IEEE specifications. It provides a 4 million-bps data rate when read over telephone twisted pair, shielded twisted pair, or fiber optics. The chip set includes three TMS380 chips, documentation, admission to a design workshop, and adapter tools. \$1,985.

*Texas Instruments, Semiconductor Group (SC-512), P.O. Box 809066, Dallas, TX 75380; 800/232-3200, ext. 700*

CIRCLE 328 ON READER SERVICE CARD

**Ungermann-Bass, Inc.** has expanded its Net/One product line to include an implementation of the emerging office automation LAN standard token ring. Called **Net/One Token Ring**, it permits users to configure a 4 million-bps multiple-ring LAN system that includes server support for hosts, terminals, printers, and modems, workstation support for devices based on the Intel Multibus and the IBM PC bus, distributed wiring concentrator support, and network management. Network bridges allow nodes in different rings to communicate. Starter system, \$47,750.

*Ungermann-Bass, Inc., 2560 Mission College Blvd., Santa Clara, CA 95050; 408/496-0111*

CIRCLE 329 ON READER SERVICE CARD

The **P2400-HC**, an addition to **Novation, Inc.**'s Professional Series modem line, runs at 2400 bps and uses only one-half of a slot in any PC. This modem uses surface-mount technology and can support error-correcting protocols and security features. \$695.

*Novation, Inc., 20409 Prairie Street, Chatsworth, CA 91311; 213/996-5060*

CIRCLE 333 ON READER SERVICE CARD



SAVE OVER 30% ON OUR GIFT PACKS!  
60-DAY MONEY-BACK GUARANTEE

# How Borland's Three New Holiday Packs Will Fill Your Stocking Without Emptying Your Piggybank.

Three special packs with dazzling discounts that will help get you into a Holiday mood. You can get some of Turbo, most of Turbo, or all of Turbo—including the two newest members of the Turbo family, Turbo GameWorks™ and Turbo Editor Toolbox™. You also get our unmatched 60-day money-back guarantee, quality products that aren't copy-protected.

## **TURBO NEW PACK \$95.00.**

You get the two exciting new members of the Turbo Pascal family,

- TURBO GAMEWORKS, Chess, Bridge, and Go-Moku, complete with source code and a 200-page manual.
- TURBO EDITOR TOOLBOX, all the building blocks to make your own editors and word processors, complete with source code and a 200-page manual.

## **TURBO HOLIDAY PACK \$125.00.**

You get all three of the Turbo family classics for only \$125.00 (about a 30% discount). Turbo Pascal 3.0 and Turbo Tutor and Turbo DataBase Toolbox—all for just \$125.00.

- TURBO PASCAL combines the fastest Pascal compiler with an integrated development environment.
- TURBO TUTOR teaches you step-by-step how to use Turbo Pascal with commented source code for all program examples on diskette.
- TURBO DATABASE TOOLBOX offers three problem-solving modules for your Turbo Pascal programs: Turbo Access, Turbo Sort, and GINST, which generates a ready-to-run installation program that lets you forget about adapting your software to specific terminals.

## **TURBO HOLIDAY JUMBO PACK \$245.00.**

This is it—the whole thing, the entire Turbo family including its two newest members. You get:

- Turbo Pascal
- Turbo Graphix Toolbox
- Turbo Tutor
- Turbo DataBase Toolbox
- Turbo GameWorks **NEW!**
- Turbo Editor Toolbox

and you pay only \$245.00 for all six! Which means that you're getting everything at only about \$40 a piece. Quite a holiday deal. (And if you already own one or several members of the Turbo family, be creative—nothing can stop you from buying the Jumbo Pack, picking out the ones you already have and giving the rest as holiday gifts to family and friends. At these prices you can afford to give to others and to yourself.) Speaking of Holidays, this offer lasts until March 31, 1986. (At Borland, we like to make the Holidays last.)



4585 SCOTTS VALLEY DRIVE, SCOTTS VALLEY,  
CA 95066 PHONE (408) 438-8400 TELEX 172373

CIRCLE NO. 250 ON READER SERVICE CARD

Copyright 1985 Borland International BI-1017B

Turbo Pascal and Turbo Tutor are registered trademarks and Turbo DataBase Toolbox, Turbo Graphix Toolbox, Turbo Editor Toolbox, Turbo GameWorks, and MicroStar are trademarks of Borland International, Inc. WordStar is a trademark of MicroPro International Corp. Multi-Mate is a trademark of Multi-Mate International Corp. Microsoft is a registered trademark and Word is a trademark of Microsoft Corp. WordPerfect is a trademark of Satellite Software International.



## **NEW! TURBO GAMEWORKS \$69.95.**

Our new Turbo GameWorks offers games you can play and replay without Turbo Pascal or revise and rewrite with Turbo Pascal 3.0. We give you the source code, the manual, the diskettes and the competitive edge. Chess, Bridge and Go-Moku. State-of-the-art games that let you be player, referee, and rules committee all at once because you have the Turbo Pascal source code. Learn exactly how the games are made—so you can go off and make your own. And Turbo GameWorks is the only quality game you can buy that is not copy-protected. Sold separately, only \$69.95. (Just \$47.50 if you buy the Turbo New Pack.)

## **NEW! TURBO EDITOR TOOLBOX \$69.95.**

Build your own word processor—for only \$69.95! You get ready-to-compile source code, a full-featured WordStar™-like word processor, and a 200-page manual that tells you how to integrate the editor procedures and functions into your programs. With Turbo Editor Toolbox, you can have the best of all word processors. You can make WordStar behave like Multi-Mate. Support windows just like Microsoft's Word. And do it as fast as WordPerfect does it. Incorporate your new 'hybrids' into your programs to achieve incredible control and power. Sold separately, only \$69.95. (If you buy the Turbo New Pack, the price drops to just \$47.50.)

## **Holiday Gift Packs, Turbo GameWorks™ & Turbo Editor Toolbox™**

Available at better dealers nationwide. Call (800) 556-2283 for the dealer nearest you. To order by Credit Card call (800) 255-8008, CA (800) 742-1133.

Make checks payable to:  
Borland International.

The holiday packs include an upgrade coupon for both options so you get BCD and 8087 support for \$39.95 (regularly \$55.00).

Carefully describe your computer system!

My computer's name and model is: \_\_\_\_\_  
Mine is: ☐ 8-bit ☐ 16-bit  
I use: ☐ PC-DOS ☐ MS-DOS  
☐ CP/M-80 ☐ CP/M-86

The disk size I use is: ☐ 3 1/2" ☐ 5 1/4" ☐ 8"

Name: \_\_\_\_\_  
Shipping Address: \_\_\_\_\_  
City: \_\_\_\_\_ Zip: \_\_\_\_\_  
State: \_\_\_\_\_ Telephone: \_\_\_\_\_

NOTE: Turbo Editor Toolbox and Turbo GameWorks are available for the IBM PC and true-compatibles using Turbo Pascal 3.0 ONLY.

**NOT COPY-PROTECTED**


	Quantity
* Turbo Holiday Jumbo Pack	\$245.00
* Turbo Holiday Pack	\$125.00
* Turbo New Pack	\$95.00
Pascal	\$69.95
Pascal w/8087	\$109.90
Pascal w/BCD	\$109.90
Pascal w/8087 and BCD	\$124.95
Turbo DataBase	\$54.95
Turbo Graphix	\$54.95
Turbo Tutor	\$34.95
Turbo Editor	\$69.95
Turbo GameWorks	\$69.95

These prices include shipping to all U.S. cities. All foreign orders add \$10 per product ordered.


Amount: (CA add 6% tax) \_\_\_\_\_  
Payment: ☐ VISA ☐ MC ☐ Check ☐ Bank Draft  
Credit Card Expiration Date: \_\_\_\_\_ / \_\_\_\_\_  
Card # \_\_\_\_\_

COD's and Purchase Orders will not be accepted by Borland International. California residents: add 6% sales tax. Outside USA: add \$10 and make payment by bank draft, payable in U.S. dollars drawn on a U.S. bank. H6





PC212A/1200 internal modem by Qubie'




PractiCorp's new database

The **PC212A/1200** internal modem and the **PC212A/1200E** external modem from **Qubie'** combine a 300-baud chip with a 1200-baud chip to produce 103/212A compatible modems. This design results in lower manufacturing costs, increased reliability, and better communications over marginal-quality telephone lines. Both models are compatible with Hayes modems. PC212A/1200, \$179; PC212A/1200E, \$199.

*Qubie', 4809 Calle Alto, Camarillo, CA 93010; 800/821-4479; in California, 805/987-9741*

CIRCLE 334 ON READER SERVICE CARD



Qubie' PC212A/1200E external modem

Debugging support for software developers writing code for the PC/AT running in protected mode is available from **Atron**. This software debugger runs on **AT PROBE**, a hardware-assisted debugging tool that plugs into the PC/AT, and allows developers to take full advantage of the capabilities of the 80286 microprocessor. Debugging features provided include hardware breakpoints and realtime trace of program execution. AT PROBE, \$2,495; protected-mode software option, \$975.

*Atron, 20665 Fourth Street, Saratoga, CA 95070; 408/741-5900*

CIRCLE 337 ON READER SERVICE CARD

With the **AT-Quiet X-Tend RT202-PC**, test and development engineers and technicians can monitor and debug circuit cards on the PC/AT without inject-

ing noise or voltage drops. This four-layer extender card with power supply decoupling capacitors from **Rancho Technology** can be used for field service, prototype testing and calibration, quality testing, and engineering development. All signals are labeled with both the pin number and the signal mnemonic. Also available is the **RT201-PC**, designed for use with the PC and PC/XT. RT202-PC, \$155; RT201-PC, \$135.

*Rancho Technology, 10238 Monte Vista, Rancho Cucamonga, CA 91701; 714/987-3966*

CIRCLE 332 ON READER SERVICE CARD

## SOFTWARE

The release of a powerful new database, **PractiBase**, has been announced by **PractiCorp International Inc.** Features include a full programming language, ability to convert and read dBASE II files and programs, access of up to three files at one time, and handling of as many as 60 fields per record with an unlimited number of records. PractiBase can handle 2,000 characters per record and 254 characters per field. Other features include the ability to generate customized reports, handle customized input and calculations, and provide data entry check. \$99.95.

*PractiCorp International Inc., The Silk Mill, 44 Oak Street, Newton Upper Falls, MA 02164; 617/965-9870*

CIRCLE 344 ON READER SERVICE CARD

From **GENESIS Software** comes **GENESIS 1.0**, an applications environment for the PC, PC/XT, and PC/AT with 256KB minimum memory, a hard disk at C:, DOS 3.0, and BASICA 3.0 or higher.

GENESIS provides a utility for organizing all software in easy-to-use menus that may be nested to 10 levels with 12 items per menu. Menus may directly access .COM, .BAT, and .EXE files, other menus, and interpreted BASIC pro-

grams; subdirectories are supported. A login/logoff time accounting system, which tracks time by user and project with password protection, and a system manager for maintenance of the user, project, and time-used files and control of the menus are included. \$29.95.

*GENESIS Software, 416 Murdock Road, Baltimore, MD 21212; 301/377-0082*

CIRCLE 341 ON READER SERVICE CARD

**Version 2.0 of db\_Vista**, the database management system for software development in C under DOS or UNIX, has been announced by **Raima Corporation**. db\_VISTA 2.0 includes source code, a royalty-free runtime license, three months of extended applications support, and product updates. This version features multiuser capability; transaction processing, which allows related changes to be written to disk; an interactive database access utility; the ability to import and export dBASE II/III and ASCII files; and an improved manual. Multiuser version with source code, \$990; without, \$495. Single-user version with source code, \$495; without, \$195. Demo version with manual, \$50.

*Raima Corp., 11717 Rainier Avenue S., Seattle, WA 98178; 800/843-3313 (dial 700-992 at the tone); 206/772-1515*

CIRCLE 348 ON READER SERVICE CARD

A virtual memory system for programs designed to the Lotus/Intel/Microsoft expanded memory specification has been announced by **SYSCOMP**. Called **Micro VMS**, this system uses the computer's fixed disk or RAM disk to simulate the presence of one or more expanded memory boards in the system. Program operation under Micro VMS is slower than if an expanded memory board were installed. Among the programs supported by the system are Lotus's Symphony 1.1 and 1-2-3 2.0. \$75.

*SYSCOMP, 8825 Aero Drive, Suite 210, San Diego, CA 92123; 619/277-0400*

CIRCLE 349 ON READER SERVICE CARD



NEW FROM BORLAND

# Borland Introduces Reflex, The Greatest Analytical Tool Since The Couch

## INTRODUCING REFLEX, THE ANALYST.

If you use Lotus 1-2-3™, dBASE® or PFS File™, you need Reflex™—because it's a totally new way to look at your data. It shows you patterns, relationships and interrelationships you didn't know were there, because they were hidden in data and numbers.

Reflex is the first database that separates the trees from the forest. The first database that understands that what you see depends on how you look at it.

The first database that probes relationships—then shows them to you in various graphic forms—scatter, line, bar, stacked bar and pie charts.

The first database to break the bonds of traditional DBMS (Data Base Management Systems) and give a dramatic visual turn to data analysis.

Reflex makes graphic leaps far beyond 1-2-3. With Reflex, when you look, you see.

## HOW THE CRITICS REACT TO REFLEX

"The next generation of software has officially arrived."

**Peter Norton, PC Week**

"Reflex is one of the most powerful database programs on the market; its multiple views; interactive windows and graphics, great report writer, pull-down menus and cross tabulation make this one of the best programs we have seen in a long time...The program is easy to use and not intimidating to the novice...Reflex not only handles the usual database functions such as sorting and searching, but also 'what-if' and statistical analysis...it can create interactive graphics with the graphics module. The separate report module is one of the best we've ever seen."

**Marc Stern, InfoWorld**

"What you see, then, is an interesting hybrid of a database and a spreadsheet that is ideal for analyzing tabular data."

**Adam B. Green, InfoWorld**

"More flexible than spreadsheets, this easy-to-use database analysis package presents information with visual clarity...Reflex is for you. The flexibility of switching between different views of the data lets you see relationships you may have previously overlooked...Without 'what-if' analysis, key variables—such as cost of goods sold or travel expenses—may be out of hand but unnoticed. The type of analysis to uncover such a foible is awkward to do on a spreadsheet; yet, it may mean the difference between success and failure in a competitive situation."

**Ira H. Krakow, Business Computer Systems**

## REFLEX OPENS MULTIPLE WINDOWS WITH NEW VIEWS AND GRAPHIC INSIGHTS.

You use Reflex's Form View to build your database; the List View lets you put data in tabular List form; the Graph View gives you instant interactive graphic representations; the CrossTab View gives you amazing "cross-referenced" pictures of the links and relationships hidden in your data. Report View allows you to import and export data to and from Reflex, 1-2-3, dBASE, PFS File and other applications and prints out information in the formats you want. In fact, Report View is probably the best 1-2-3 report generator you can buy today. It's also the cheapest—and you're getting all the other features free.

The commands for all five Views are consistent—so you're not stuck learning five different ways to get something done. And because Reflex uses advanced windowing techniques, you can see several views on the screen at the same time—without having to switch back and forth. You get the picture—and the pictures—all at once—if that's the way you want to look at things.

Modify a number and all your Views—List, Form and Graph—are immediately updated, on-screen. Changing a number changes the picture—which is mighty handy when you're analyzing (let's say) sales figures by salesperson; or you're in "What-if?" country asking yourself "What if we could add 2.5% in January sales?" "Show me."

"Give me the picture." "Show me what happens when we shift 11% of Nebraska's inventory to the new store in Hawaii."

"Show me how many Gizmo 28's we have in every store in every state as of midnight last night and what happens to our East Coast stocks if the shipping strike lasts more than a week." "Show me."

So Reflex shows you. Instant answers. Instant pictures. Instant analysis. Instant understanding.

## HOW IN THE WORLD CAN BORLAND SELL A PHENOMENAL PRODUCT LIKE REFLEX FOR ONLY \$99.95?

At \$495.00, Analytica's original price, Reflex was a bargain. Acclaimed by critics and praised by users, Reflex also got our attention at Borland International. We were so impressed by Reflex that we bought the company!

To celebrate that, we're making business software history by offering Reflex—FOR A LIMITED TIME—for ONLY \$99.95! (Offer good through March 31, 1986).

That's \$395.05 off the original price—which is a pretty good return on your toll-free phone call.

We think Reflex should be an "automatic product," a "standard" that every PC owner should own. That's why we priced it at \$99.95. Naturally we've added our 60-day money-back guarantee and Borland's Reflex is not copy-protected.



**BORLAND**  
INTERNATIONAL

4585 Scotts Valley Drive, Scotts Valley CA 95066  
Phone (408) 438-8400 Telex 172373

CIRCLE NO. 251 ON READER SERVICE CARD

Trademarks: Reflex is a trademark of BORLAND/Analytica Inc. Lotus is a registered trademark and Lotus 1-2-3 is a trademark of Lotus Development Corporation. dBASE is a registered trademark of Ashton-Tate. PFS is a registered trademark and PFS File is a trademark of Software Publishing Corporation. IBM PC, XT, AT, PC-DOS and IBM Color Graphics Adapter are registered trademarks of International Business Machines Corporation. Hercules Monochrome Graphics Card is a trademark of Hercules Computer Technology.

**REFLEX™** THE ANALYST™

NOT COPY-PROTECTED

To order by Credit Card call (800) 255-8008, CA (800) 742-1133.  
Available at better dealers nationwide. Call (800) 556-2283 for the dealer nearest you.

YES! Rush  
Reflex to me.  
Send me \_\_\_\_\_ copies.

**60-DAY  
MONEY-BACK  
GUARANTEE**

**\$99.95**

This price includes shipping to all U.S. cities. All foreign orders add \$10 per product ordered.

System requirements.  
IBM® PC, XT, AT and compatibles. 384K RAM minimum. IBM Color Graphics Adapter®, Hercules Monochrome Graphics Card®, or equivalent. PC DOS® 2.0 or greater. Hard disk and mouse optional.

Subtotal \_\_\_\_\_  
(CA res. add \$6 tax per copy) \_\_\_\_\_  
Amount Enclosed: \_\_\_\_\_  
Payment VISA MC BankDraft Check  
Credit Card Exp. Date \_\_\_\_\_  
Card # \_\_\_\_\_

Name: \_\_\_\_\_  
Shipping Address: \_\_\_\_\_  
City: \_\_\_\_\_ Zip: \_\_\_\_\_  
State: \_\_\_\_\_ Telephone: \_\_\_\_\_

COD's and Purchase Orders WILL NOT be accepted by Borland. California residents: add 6% sales tax.  
Outside USA: add \$10 and make payment by bank draft, payable in US dollars drawn on a US bank.

Copyright 1985 Borland International BI-1020 A





# Manx Aztec C86 is the best C for MS-DOS and you can prove it yourself!

*"A compiler that has many strengths ... quite valuable for serious work"*  
Computer Language review, February 1985

## Manx Aztec C86 - The C For MS-DOS

Manx Aztec C86 is clearly the best C software development system for MS-DOS. Aztec C86 is the only C compiler for MS-DOS that provides the level of performance, features, documentation, and support required for serious, professional software development. You can prove it yourself. All you have to do is order Aztec C86 from Manx, evaluate it, and, if you like it, keep it. If you don't like it, send it back within 30 days and we'll cancel your order.

If you keep your Manx Aztec C86, as 99% do, you'll be in with the best company.

## Manx Aztec C86 Features:

**Optimized C compiler:** Unsurpassed for code quality and speed. Optionally generates 80186 and 80286 code. Full K & R.

**Symbolic Debugger:** Execution trace, break points, display data in floating point, integer, character, or hex format. Evaluate expressions. Detect illegal memory stores, modify memory/registers, disassemble code.

**Manx AS86 Macro Assembler:** Supports macros, 8086, 80186, and 80286 instructions in Intel format. Fast execution.

**LN86 Overlay Linker:** Links small, large, and mixed memory model routines, supports overlays, and options for producing ROM based code.

**Librarian:** Build and modify personal or system run time libraries.

**8087/80287 Sensing Library:** One library simulates floating point, another assumes the presence of an 8086 or 80287 math chip, the third senses the existence of a math chip, and if it finds one it uses it.

**Profiler:** Provides a run time analysis of your code to pinpoint code segments to optimize.

**UNIX Library:** Compatible with UNIX C. Fast I/O. Terminal I/O can be buffered or unbuffered.

**DOS Library:** Time and date functions, program forking (exec), program chaining, directory commands, I/O port support, sysint support, BIOS functions, and BDOS functions.

**Screen & Graphics Library:** Screen and cursor functions. Fast routines for drawing lines, circles, ellipses, points, and setting colors.

**CP/M-86 Library (-c):** Produce programs for CP/M-86.

**Large Memory Model:** Manx Aztec C86 supports programs and data of any size. Global data has a max size of 64k.

**Intel Object Option:** Interface to software that requires Intel object format, such as PLINK86.

**Z (vi) Source Editor (-c):** Fast, powerful editor, Macro capabilities, undo, ctags, buffers for commands and data, and all the bells and whistles that make vi fanatics fanatical.

**ROM Support Package (-c):** Startup routine, linker options for separate placement of code and data, special utilities like the Intel HEX Utility, documentation, and library source.

**Library Source Code (-c):** UNIX, screen, graphics, and math function libraries.

**Mixed Memory Models (-c):** Mix large code and small data, small code and large data, or mix within type.

**UniTools (-c):** The UNIX utilities make, diff, and grep.

**One year of updates (-c):** As new versions are released, updates are automatically sent.

**Technical Support:** Manx has a full time staff to provide support via telephone & bulletin board.

Items marked -c are special features of the Aztec C86-c system.

Manx Aztec C86 is available in four configurations: Manx Aztec C86-c, Manx Aztec C86-d, Manx Aztec C86-p, and Manx Aztec C86-a. The -p and -a systems are not intended for commercial work and do not incorporate the same compilers as the -c and -d systems. All systems are upgradable.

Aztec C86-c Commercial System	\$499
Aztec C86-d Developer's System	\$299
Aztec C86-p Personal System	\$199
Aztec C86-a Apprentice System	\$ 49

## Manx Cross Development Systems

Manx Aztec C compilers are available as native or as cross development systems for PC-DOS, MS-DOS, Macintosh, CP/M-86, CP/M-80, TRSDOS, Apple II, and Commodore 64/128.

Cross development involves two computer systems: the development system (HOST) and the execution system (TARGET). This method is useful when the TARGET machine is slower or more limited than the HOST.

**HOSTS:** VAX UNIX (\$3000), PDP-11 UNIX (\$2000), MS-DOS (\$750), CP/M (\$750), Macintosh (\$750), CP/M-68k (\$750), XENIX (\$750).

**TARGETS:** MS-DOS, CP/M-86, Macintosh, CP/M-68k, CP/M-80, TRS-80 3 & 4, Apple II, Commodore C64, 8086/80x85 ROM, 68xxx ROM, 8080/8085/Z80 ROM, 65xx ROM.

Additional TARGETS are \$300 to \$500 (non VAX) or \$1000 (VAX). Call for information, on cross development to the 68000, 65816, Amiga, C128, CP/M-68K, VRTX, and others.

## How To Become a Manx Aztec C User

Call 1-800-221-0440 or 1-800-832-9273 (800-TEC WARE). In NJ or outside the USA call 201-530-7997. Orders can also be telexed to 4995812.

Payment can be by check, COD, American Express, VISA, Master Card, or Net 30 to qualified customers.

Orders can also be mailed to Manx Software Systems, Box 55, Shrewsbury, NJ 07701.

**For More Information:** call 1-800-221-0440, or 201-530-7997, or write to Manx Software Systems.

Manx maintains a large professional staff to service and support Manx users. You will get fast delivery and great service dealing directly with Manx.

## Support Software for Manx Aztec C86

**C-tree \$395:** B-tree database system. Easy to use. Available for Aztec C for MS-DOS, Macintosh, CP/M-86, CP/M-80, and others. Includes source.

**PHACT \$250:** Powerful database system. Available for Manx Aztec C compilers for MS-DOS, CP/M-86, CP/M-80, and Macintosh.

**PANEL \$295:** Create screens via simple, powerful editing commands. Select colors, edit fields. Directly input data to a multi-keyed file utility included with the system.

**SunScreen \$99:** Create and modify formatted screens easily. Validate fields, select colors, create screens for both the color and monochrome cards. With library source SunScreen is \$199.

**WindScreen \$149:** Combines SunScreen with a powerful window utility.

**Windows for C \$195:** Versatile window utility that supports IBM PC compatible and some non-compatible environments.

**AMBER Windows \$99:** Powerful, low priced window package.

**HALO \$250:** The ultimate C graphics package. It supports viewports, shapes, and multiple graphics cards. A less expensive version is available for just the PC mono and color cards.

**FirstTime \$295:** Syntax checking while you edit greatly shortens compile time.

**Pre-C \$395:** Powerful Lint-like utility locates structural and usage errors. Easily checks multiple files for bad parameter declarations and other interface errors. Lint users will find the user interface a dream come true.

**PC-LINT \$98:** Lint-like utility that supports large memory models, has clear error messages, and executes quickly, has lots of options and features that you wouldn't expect at this low price.

**Greenleaf Functions \$185:** Source for over 200 C and assembler functions. They are great, they work, they are used extensively, and are economically priced. Clear documentation and easy to use interface round out an impressive package.

**C Utility Library \$185:** C and assembler source for screens, windows, color graphics, asynch communications, and more. The color graphics and speed of this package are impressive.

**Plink-86 \$395:** MS-DOS linkage editor for producing and maintaining overlaid programs. It works with Aztec C86 in Intel object format mode.

## 30 Day Guaranty:

Any Manx Aztec development system can be returned within 30 days for a refund if it fails to meet your needs. Restrictions are that the original purchase must be directly from Manx, shipped within the USA, and the package must be in new condition. Returned items must be received by Manx within 30 days. A restocking fee may be required.

## Discounts:

There are special discounts available to professors, students, and consultants. A discount is also available on a "trade in" basis for users of competing C systems.

## Manx Aztec C Distribution:

In the USA, Manx Software Systems is the exclusive distributor of Aztec C. Telephone or mail order sales other than through Manx are unauthorized.




To order or for information call:

# 800-221-0440


UNIX is a registered TM of Bell Laboratories. Lattice TM Lattice Inc. C-tree TM Phact Assoc. C1 Optimizing C86 TM Computer Innovations, Inc. MACINTOSH, APPLE TM APPLE, INC. Pre-C, PLINK 86 TM PHOENIX, HALO TM Media Cybernetics, Inc. C-tree, PC-Lint TM GIMPLE Software, WindScreen, SunScreen TM SunSoft, PANEL TM Roundhill Computer Systems Ltd. WINDOWS FOR C TM Creative Solutions. XENIX, MS TM MICROSOFT INC. CP/M TM DRI, AMIGA, C64, C128 TM COMMODORE INC.

CIRCLE NO. 208 ON READER SERVICE CARD





Enhanced Ptel communications



By Merrill Street Software/BCC, Inc.

**SCI Corporation** announced that it has constructed a software package that permits PC software to operate on IBM mainframe computers without modification. **VirtualPC**, written in IBM 370 assembly language, emulates both the microcomputer and the associated hardware of the PC, as well as the PC BIOS. VirtualPC consists of a software 8088 emulator, a control program and resident debugger for controlling the simulation, a set of routines that intercept requests for I/O services and perform the services using the host operating system, and display software that simulates the functions of an IBM monochrome display adapter by mapping the output of PC programs onto host-connected IBM 3270 workstations. The package supports programs that write directly to display memory. Price pending negotiations with vendors.

*SCI Corporation, 2039 Carrhill Road, Vienna, VA 22180; 703/938-0731*

CIRCLE 347 ON READER SERVICE CARD

**SuperBatch**, from **Merrill Street Software Division of BCC, Inc.**, integrates applications programs and MS-DOS batch filing capabilities to provide turn-key application system capabilities for microcomputers. SuperBatch is an extended batch file processor that moves among virtually any applications programs, but never interferes with their operation. It can store and execute an infinite number of keyboard commands and can run at any speed. Images can be held on the screen. \$79.95.

*Merrill Street Software Division of BCC, Inc., 251 Merrill Street, Birmingham, MI 48011; 313/645-5280*

CIRCLE 345 ON READER SERVICE CARD


A new on-line software update capability and support, plus a line-oriented script language and forward and backward scrolling have been added to **Phoenix Computer Products Corporation's Ptel** communications package. Ptel is

the first universal binary transfer program for the PC, PC/XT, PC/AT, and compatibles running DOS 2.0 or later. All popular protocols are supported, including ASCII, XMODEM, Modem7, Telink, and Kermit. \$195.

Also from Phoenix comes a high-performance linkage editor designed especially for programmers working with large, complex programs. Called **Plink 86 plus**, the new linker features overlay caching, object file merging, overlay reloading upon function return, and automatic allocating of library modules to overlay structures. \$395.

An advanced version of Phoenix's **Pfix 86 plus** symbolic debugger that offers programmers in MS-DOS environments configurable menus, configurable keys, and tracebacks to save trace histories is available. Pfix 86 plus can debug terminate-and-stay resident programs and operating system I/O drivers. \$395. *Phoenix Computer Products Corporation, 320 Norwood Park S., Norwood, MA 02062; 617/762-5030*

CIRCLE 346 ON READER SERVICE CARD



Pfix 86 plus advanced debugger

**Concurrent Sciences, Inc.** has introduced a new MS-DOS version of its software debugger **SOFT-SCOPE**. This new version supports all five of the new DOS languages introduced by Intel Corporation: C, Pascal, FORTRAN, PLM, and ASM. SOFT-SCOPE debugs code generated by the Intel high-level languages and

provides a true source code interface to the software developer. It reports breakpoints and stepping with the actual source line, including comments, corresponding to the next line to be executed. SOFT-SCOPE can display automatically all variable types, including Pascal records, PLM and C structures, multidimensional arrays, and real types. Structure and array references may be partially qualified, resulting in a formatted display showing the name of each field and its current contents. Also provided is a terminal interface that allows all debugger interaction to be redirected to a second console, giving the program being debugged exclusive use of the main console. \$500.

*Concurrent Sciences, Inc., P.O. Box 9666, 106 E. Third Street, Moscow, ID 83843; 208/882-0445*

CIRCLE 350 ON READER SERVICE CARD

### **Relational Database Systems, Inc.**

(RDS) has announced an agreement with IBM Corporation in which IBM will market three RDS products that run under the Interactive Executive for the System/370 (IX/370) operating system on IBM mainframes. IX/370 is the IBM implementation of UNIX System V. IBM will market **Interactive Executive Informix**, a relational database; **IX Informix Embedded Query Facility for C**, an interface between the Informix database and the C language; and **IX Informix Embedded Query Facility for COBOL**, an interface between the database and COBOL. These products use a query language similar to the SQL in IBM's SQL/DS and DB2. IX Informix, \$48,000; C Query Facility, \$36,000; COBOL Query Facility, \$36,000.


*Relational Database Systems, Inc., 4100 Bobannon Drive, Menlo Park, CA 94025; 415/322-4100*

CIRCLE 342 ON READER SERVICE CARD


*IBM Corporation; Contact the local IBM dealer, 800/426-2468*

CIRCLE 343 ON READER SERVICE CARD





RM/COBOL-8X



DesignAid by Nastec

**Ryan-McFarland Corporation** has announced an advanced COBOL compiler for microcomputers that offers the combined advantages of portable application code and high-speed execution, and includes IBM mainframe COBOL extensions and key features in the ANSI X3.23 198x COBOL standards proposal.

**RM/COBOL-8X** eliminates the 64KB program size restrictions to enable smaller systems to handle mainframe applications. RM/COBOL 2.0 developers can use a special compatibility switch that lets the compiler ignore new language features, such as ANSI 85 extensions. Full development system, \$1,250; runtime only, \$300.

*Ryan-McFarland Corporation, 609 Deep Valley Drive, Rolling Hills Estates, CA 90274; 213/541-4828*

CIRCLE 340 ON READER SERVICE CARD

**PC Utilities** has released a **machine code utility** that sorts 1,000 alphanumeric strings in one second on the PC/AT; it effectively adds a sort command to BASIC. File I/O is left to the user, permitting optimum performance by the applications software. It is limited by the maximum memory available or the upper limit of the operating system. PC Utilities can modify the source code with interface to other languages. Contact the company for prices.

*PC Utilities, 20 Laxey Road, Horfield, Bristol BS7 0JA, England; 0272/520423-731796*


CIRCLE 355 ON READER SERVICE CARD

**TEKMAR** is a graphics library for use with the PC and Tecmar Graphics Master; it includes functions that can be called from programs. Produced by **Advanced Systems Consultants**, this library is written in assembly language and FORTRAN for speed, portability, and flexibility. TEKMAR requires Microsoft FORTRAN 3.3 or Lahey Computer Systems' F77L. (A version for IBM's Professional FORTRAN is under development.) In addition to

the high-level graphics library, applications such as a contour-finding program are included. \$195.

*Advance Systems Consultants, 18653 Ventura Blvd., Suite 351, Tarzana, CA 91356; 818/407-1059*

CIRCLE 354 ON READER SERVICE CARD



TEKMAR screen

A set of related utilities designed to help software developers keep track of changes to the source code of computer programs has been released by **Quilt Computing**. Called **Software Revision Management System (SRMS)**, it allows the user to retrieve specific versions of a program from a common archive, apply changes to the source, and reinstate the source in the archive while recording when, why, and where changes were made. All versions of the program under development are stored in a single SRMS library, without duplication of common code or text. Any number of comments can be associated with each version in the archive. SRMS supports the archiving of programs written in BASIC, FORTRAN, Pascal (including Turbo Pascal), C, and assembly language. \$99.95.

*Quilt Computing, 7048 Stratford Road, Woodbury, MN 55125; 612/739-4650*

CIRCLE 351 ON READER SERVICE CARD

New development tools and capabilities have been announced for **Nastec Corporation's DesignAid**. **SafeSpan** pro-

vides a bridge between DesignAid and PSL/PSA (problem statement language/problem statement analyzer). With PSL/PSA and DesignAid as a front end, system developers can work with structured analysis and design notation without needing to be fluent in the syntax of PSL statements used as input to the host-based PSA. \$1,700.

**JaDesign** supports IBM's Joint Applications Design (JAD) methodology through PC implementation of the JAD forms, procedures, and methods. During the JAD session, the PC captures all user-view prototypes, screens, reports, and associated documentation. \$5,000 by site license.

**Version 3.2 of DesignAid** adds automated balancing for Yourdon data flow diagrams and an enhanced Design Dictionary to catalog the hierarchical data and process structures captured during the balancing process. \$6,900. *Nastec Corporation, 24681 Northwestern Highway, Southfield, MI 48075; 313/353-3300*

CIRCLE 352 ON READER SERVICE CARD

A software facility that gives third-party computers a connection into IBM's next-generation networking scheme has been introduced by **The Orion Group, Inc.** The **sna62 Peer Communications Facility** implements IBM SNA "peer-to-peer" communications protocols (LU 6.2 and PU 2.1). These protocols enable microcomputers, minicomputers, and mainframes, as well as terminals, file servers, and other devices, to exchange data directly. The facility is written in C under UNIX V.

*The Orion Group, Inc., 1912 Bonita Way, Berkeley, CA 94704; 415/548-0947*

CIRCLE 353 ON READER SERVICE CARD

*The material that appears in Tech Releases is based on vendor-supplied information. These products have not been reviewed by the PC Tech Journal editorial staff.*



# CD ROM

**The First International Conference on CD ROM**  
**sponsored by Microsoft Corporation**

## PLAN NOW TO ATTEND

Be part of this important conference March 4-7th in Seattle. The focus will be wide-ranging, with a host of key authorities examining current and future CD ROM issues affecting book publishers, information providers, software developers, hardware, disc, and drive manufacturers.

## KEYNOTE SPEAKERS

William H. Gates, Microsoft      Gary A. Kildall, Activenture

## FEATURED SPEAKERS

Jane Brown, BRS	Arlin Raedaeke, Reference Technology
Robert Carr, Ashton Tate	Francois Robineau, Editions France Image Logiciel
Peter Cook, Grolier Academic American Encyclopedia	Edward Rothchild, Rothchild Consultants
Stan Cornyn, The Record Group	David Roux, Datext
James DeVries, Laser Video	Edward Schmid, Digital Equipment Corporation
Stuart B. Flexner, Random House	Richard Schwarz, Dun & Bradstreet
John Gale, Information Workstation Group	George Wallace, McGraw-Hill
Stan Honey, ETAK	Howard R. Webber, Houghton Mifflin
Philippe Kahn, Borland International	Michael Zibart, Ingram Book Company
Kathleen Lane, Dataquest	William Zoellick, TMS
Leonard Laub, Vision Three	
Jan Lewis, Palo Alto Research Group	Registration price:
Michael Liebhold, Apple Computer	\$799 (before Feb. 1);
Thomas Lopez, Cytation	\$899 thereafter
Gerald Lowell, Library of Congress	
Tom Kelly, 3M Corporation	To register, call:
Alan Meckler, Meckler Publishing	800 323-7616; In California,
David Mastrandrea, Hewlett Packard	818 707-0102
Rick Meyer, DIALOG	or telex: 298912 TII UR
Dominic J. Miccolis, World Book Encyclopedia	
Robert Moes, North American Philips	For additional information, call:
Michel Motro, VIFI International/Larousse	Min S. Yee, Conference Chairman
Hernan Orano, Smithsonian Institution, NASM	or Steve Lambert, Conference Coordinator
	206 828-8080

Microsoft Corporation  
10700 Northup Way  
Bellevue, WA 98004

**MICROSOFT®**



**Revelation® is a classic case of 'you get what you pay for.' It costs a bit more than most, but it gives you the best there is.**

— PC Magazine, September 4, 1984

If you think that dBASE III Plus™ or R:base 5000™ is the solution to your information processing needs, consider for a moment the expectations you and your company should have for your next database management system.

**For starters, it needs to network.**

Revelation is ready to network now on IBM®'s PC Network, 3COM's EtherSeries™ and networks running Novell NetWare.™ So you can choose the best hardware for your company's unique needs.

Network Revelation also locks data at the record level. That's a critical capability that means the difference between a working network and disappearing data.

**Make sure that it has an excellent command of the language.**

R/Design, Revelation's application generator is your ticket to the most powerful applications running on PC's. That's because R/Design steps you through the entire application generation process, from defining databases to writing the documentation. And when you're done, Revelation will compile your application in R/Basic source code, a complete, structured relational language.


**Find out how easily you can retrieve information.**

With R/List, Revelation's query language, you ask questions in plain English. Simple sentences produce detailed reports in just about any format you can imagine.

And while you're at it, ask Revelation about its variable-length fields, unlimited files and fields, data dictionaries, and high-speed compiler. You'll find all the tools you need for serious applications development. With prices starting at only \$1495\* for a complete four-user system, Network Revelation gives you *more* than you paid for.

\*Suggested U.S. price.

IF YOU CHOOSE A WIMPY  
DATABASE THAT'S UNABLE TO  
KEEP PACE WITH OUR  
GROWING COMPANY, YOU'LL  
HAVE TO CHANGE YOUR NAME  
AND MOVE TO PARAGUAY!





## A comparison between R:base 5000, dBASE III Plus and Revelation

	Revelation	R:base 5000	dBase III
Maximum Characters/Record	65000	1530	4000
Maximum Fields/Record	65000	400	128
Relational Operators	9	6	6
Data Dictionary	Yes	Yes	No
Procedural Language	Yes	Yes	Yes
Variable Length Fields	Yes	No	No
Multiple Values in Fields	Yes	No	No
Report Writing Features:			
A) Access to Date/Time	Yes	Yes	No
B) Row or Column Formats	Yes	Yes	No
C) Accessible Tables	6000	40	10
Password Security	Yes	Yes	No
Definable Data Entry Rules	Yes	Yes	No
Mainframe Communications <sup>(1)</sup>	Yes	No	No
Application Generator	Yes	Yes	Yes
Procedural Language Compiler	Yes	No	Yes <sup>(2)</sup>
Run-Time Module	Yes	Yes	Yes
Network Version	Yes	Yes	Yes

1) From original manufacturer. 2) Extra cost option not available on network version. dBase III Plus is a trademark of Ashton-Tate. R:Base 5000 is a trademark of MicroRIM, Inc. IBM is a registered trademark of International Business Machines Corporation. NetWare is a trademark of Novell, Inc. EtherSeries is a trademark of 3COM Corporation.

## It's your choice: The vice presidency or Paraguay

Cosmos' worldwide network of sales representatives stand ready to show you the incredible power of Revelation. Call today to schedule a career altering demonstration or to request an evaluation copy.

Cosmos, Inc., 19530 Pacific Hwy. S.  
Seattle, WA 98188, (206)824-9942,  
Telex:9103808627 (Cosmos WA)



# COSMOS™

CIRCLE NO. 112 ON READER SERVICE CARD

HOWEVER, IF YOU FIND ONE THAT CAN GROW  
AS WE GROW, EVEN NETWORK, YOU JUST  
MIGHT BE OUR NEXT VICE PRESIDENT!  
WHY ARE YOU SMILING?





# C Programmers: Here are 7 ways You can be more productive

Dear Microcomputer Programmer,

Let me tell you how you can find and choose the best development software for your needs — software that will help you:

\* Speed your development efforts

\* Write even better programs

\* Increase productivity

\* Reduce your programming frustration

All you have to do is consider one of these seven products for C programmers (or the 97 other C compilers, interpreters, support libraries, debuggers, or addons we offer). Then call one of our knowledgeable consultants - toll free - for details, comparisons, or for our specially prepared packets on C, C Libraries, or C Productivity Tools.

There is no obligation. You risk nothing with our moneyback guarantee of satisfaction.

Yours for more productive programming, — Bruce W. Lynch, President

## Even for Small Files:

**Convenient,  
Fast Access**

**CBTREE™— Only \$99**

Why spend time writing file management code when you can use consistent, flexible, documented, professional function? Even multiuser record locking and variable-length records are supported.

Full, balanced Btree support includes use of multiple keys, unlimited number and length of keys.

Use this powerful ISAM, even if you've previously done without.

Learn how to write systems for managing large files by using CBTREE source as a guide. Modify it and transfer it to another operating environment without royalties.

## Why Lattice C™? From Lifeboat Associates

Trade mags such as Byte and PC Tech have nearly outdone themselves in praising Lattice C's speed and compactness.

With compilers for the Amiga, Z80, 370, 8086, plus cross tools, Lattice C is the standard. More support products than any other compiler make "reinventing" unnecessary.

Lattice C is a full implementation of K&R. It is compatible with any 8086 or 8088 and now has a 286 compile option.

Seven different memory models enable you to select the appropriate combination of address-ability & efficiency to suit a particular situation.

Other specs include automatic sensing of an 8087 chip; Fork function; and complete I/O routines.

MSDOS \$289

## Get File Access with TIGHTER Control

**db.VISTA™ Data Management**

Full source, no royalties and "normal" indexed file management are part of db.VISTA. Get more for the price of only an ISAM.

You can minimize data stored and access records even faster and more logically than just using indexes. Example: address and transaction data should not require redundant storage of customer names or numbers. Use pointers. Related data fields point to other related groups - the "network model" of data.

Use db.VISTA as a "normal ISAM" or save programming time, access time and file size. Lattice, C86, Williams, Desmet, Microsoft C.

MSDOS Multiuser source \$995, Object \$495

Single user source \$450, Object \$169

Unix, Xenix, & MacIntosh versions also available. Call for details.

## The FASTEST C Development Plus full source level Debugging

**Lattice compatible: Instant-C™**

Even 5000 line programs can be handled using Instant C. Link in external .OBJ files like HALO, PANEL, or your own. Special technology makes changing & testing faster than Turbo PASCAL. "Incremental compilation" saves you substantial development time.

In addition to being the Most Interactive C available, Instant C provides fast execution. Instant C executes a well known benchmark in less than 35 seconds while no other interactive C environment known takes less than 20 minutes!

Detect errors quickly. An error message will appear on the same screen with your source code. Compile-time errors are displayed with full source and the cursor is set to the exact problem spot. Execution time errors are also displayed with full source — no more clumsy machine language debugging. Debugging is always in the C languages. You can single step a statement-at-a-time. Get full source backtraces; and set any number of conditional breakpoints.

The integrated full screen editor is always instantly available.

This full, interactive K&R C environment tests programs so fast it might change your whole concept of programming productivity. And it comes with complete library source.

Try Instant C with a full 31 day moneyback guarantee.

MSDOS: \$445

## SORT/MERGE Files for Clean, Fast Maintenance

**with OPT-TECH SORT™**

Performance should not suffer with DOS or other "free" sorts. ISAMs alone are slow when 10% or even less is changed/added.

OPT-TECH includes:

- CALLable and Standalone use
- C, ASM, BAS, PAS, FTN, COBOL

- Variable and fixed length

- 1 to 9 fields to sort/merge

- Autoselect of RAM or disk

- Options: dBASE, BTRIEVE files

- 1 to 10 files input

- No software max for # Records

- All common field types

- By pass headers, limit sort

- Inplace sort option

- Output = Record or keys

Try what you're using on an XT: 1,000 128 byte records, 10 byte key in 33 seconds. MSDOS \$85

## Fast File Access with Source Variable Length Fields Save Space CIndex™ ISAM Product Line

C-Index contains a high performance ISAM, balanced B + Tree indexing system and variable length fields. The result is a complete data storage system to eliminate tedious programming and add efficient performance to your programs.

Features include random and sequential data access, virtual memory buffering, and multiple key indexes.

With no royalties for programs you distribute, full source code, and variable length fields C-Index/Plus fits what you are likely to need.

Save time and enhance your programs with C-Index/Plus. MSDOS \$349. With C-Index/File for \$89, or/Pro for \$179.

## Make REAL TIME Programming Practical Csharp Realtime Toolkit™

Data acquisition, process control, robotics and devices monitoring applications become practical with Csharp!

Full source code helps tailor programs to various boards and applications.

Reentrant, interrupt handling routines help schedule and react. Fast graphics routines help visualize what is happening.

Control multiple ports reliably, schedule tasks based on events, manage priorities — all with modular, tested, & reliable routines.

Assess and manage the state of hardware at the object level. Let Csharp handle the details.

Portable C source.

MSDOS \$600

## THE PROGRAMMER'S SHOP

128 Rockland Street  
Hanover, Massachusetts 02339

**800-421-8006**

In Mass. 800-442-8070 617-826-7531

If you call for our advice, you must be completely satisfied with the product you purchase from The Programmer's Shop. If not, you will receive a refund or replacement. Call now for details or our new catalog.



## 56


## Tracing Expanded Memory

*A user can keep tabs on the allocation of expanded memory within a system.*

Users may find it helpful to keep track of the amount of memory provided by an expanded memory specification (EMS) board that actually is being used. Program XMEM.ASM, shown below, displays the total expanded memory in the system, the amount allocated for particular applications, and the amount remaining. (See "Expandable Memory," p. 66.)

## LISTING: XMEM.ASM

```
PTOTAL EQU 42H ;DEFINE EMM FUNCTION CODES
PCOUNT EQU 4BH
PBYPROC EQU 4DH
DISPLAY MACRO ;DISPLAY STRING AT DS:DI
    MOV DX,DI
    MOV AH,9
    INT 21H
ENDM
EMMCALL MACRO FUNCT
LOCAL NOERR
    MOV AH,FUNCT
    INT 67H ;PERFORM EMM FUNCTION
    OR AH,AH ;TEST FOR ERRORS
    JZ NOERR
    LEA DI,ERR$ ;IF ERROR, EXIT W/MESSAGE
    JMP EXIT
NOERR: ;CONTINUE HERE IF NO ERROR
ENDM
CODE SEGMENT
    ASSUME CS:CODE, DS:CODE, ES:CODE
    ORG 100H
XMEM PROC
    JMP PASTDATA
ERR$ DB 'Expanded Memory Error',13,10,'$'
TOTAL$ DB ' 0 K Total Expanded Memory',13,10,'$'
EACHK$ DB ' K used by process'
PRNUM$ DB 0,0,0,0,0,13,10,'$'
FREE$ DB ' K free',13,10,'$'
EMMNAME DB 'EMMXXX0' ;NAME OF EMM DEVICE DRIVER
FREEPAGES DW 0 ;UNALLOCATED PAGE COUNT
PAGES DW 256 DUP (0,0) ;ARRAY OF PAGE COUNTS
PASTDATA:
    PUSH ES
    MOV AX,3567H ;GET INT 67 VECTOR
    INT 21H
    MOV DI,10 ;POINT TO DEVICE NAME
    LEA SI,EMMNAME ;POINT TO EMM NAME
    MOV CX,8
    CLD
    REPE CMPSB ;IS EMM INSTALLED?
    LEA DI,TOTAL$ ;MSG IN CASE IT ISN'T
    JNE EXIT ;EXIT IF NO EMM
    POP ES
    EMMCALL PTOTAL ;DETERMINE TOTAL PAGE COUNT
    MOV AX,DX ;PAGE COUNT RETURNED IN DX
    MOV FREEPAGES,AX ;SAVE IT
    LEA DI,TOTAL$
    CALL P2K ;CONVERT PAGES TO K
    DISPLAY
    LEA DI,PAGES ;POINT TO ARRAY OF PAGE COUNTS
    EMMCALL PBYPROC ;GET PAGES PER PROCESS EJE
```

The program determines if EMS is installed, then uses EMM function 3 to report the size of expanded memory present. Function 14 is invoked to fill an array with the ID of each application as well as the number of pages allocated to it. After the array is filled, function 12 is used to return the number of processes currently using expanded memory. 

```
EMMCALL PCOUNT ;GET EMM PROCESS COUNT
MOV CX,BX ;PROCESS COUNT TO CX
JCXZ X2 ;SKIP IF NO EMM PROCESSES
    MOV SI,DI ;POINT SI TO PAGE ARRAY
X1: LODSW ;GET PROCESS ID
    CBW ;CONVERT LOW BYTE ONLY
    LEA DI,PRNUM$
    CALL I2ASC ;CONVERT # TO ASCII
    LODSW ;GET PAGES FOR THIS PROCESS
    SUB FREEPAGES,AX ;UPDATE FREE PAGE COUNT
    LEA DI,EACHK$
    CALL P2K ;CONVERT PAGES TO ASCII K
    DISPLAY ;DISPLAY PROCESS COUNT
    LOOP X1 ;CONTINUE FOR ALL PROCESSES
X2: MOV AX,FREEPAGES
    LEA DI,FREE$
    CALL P2K
EXIT: DISPLAY ;DISPLAY LAST MESSAGE
    INT 20H ;THAT'S ALL, FOLKS
XMEM ENDP
P2K PROC
    SHL AX,1 ;BYTES = PAGES * 16
    SHL AX,1
    SHL AX,1
    SHL AX,1
I2ASC: PUSH DI ;ENTER HERE IF # IS NOT PAGES
    PUSH CX
    CLD
    PUSH AX
    MOV AL,' ' ;BLANK OUT STRING
    MOV CX,6
    REP STOSB
    DEC DI ;POINT AT STRING END
    MOV BX,10 ;BASE TEN DIVISOR
    POP AX ;GET BINARY NUMBER INTO AX
    STD ;MOVE BACKWARDS THRU STRING
DIVLOOP: CWD ;CONVERT TO DBL WORD IN DX,AX
    DIV BX ;QUOTIENT IN AX, REMNDR IN DX
    XCHG AX,DX ;EXCHANGE QUOT & REM
    OR AX,30H ;CONVERT TO ASCII DIGIT
    STOSB ;STORE ASCII CHAR IN STRING
    MOV AX,DX ;RESTORE QUOTIENT TO AX
    OR AX,AX ;TEST IF MORE DEC DIGITS
    JNZ DIVLOOP
    POP CX ;RESTORE & EXIT
    POP DI
    CLD
    RET
P2K ENDP
CODE ENDS
END XMEM
```



# THE PROGRAMMER'S SHOP™

helps save time, money and cut frustrations. Compare, evaluate, and find products.

## SERVICES

- Programmer's Referral List
- Dealer's Inquire
- Compare Products
- Newsletter
- Help find a Publisher
- Rush Order
- Evaluation Literature FREE
- Over 700 products
- BULLETIN BOARD - 7PM to 7AM 617-826-4086

## AI - Expert System Dev't

ExpertEASE - Develop by describing examples of how you decide. Call  
EXSYS - All RAM, Probability. Why. Trees, Solid, files, popular PCDOS \$359  
1st Class - by example, interfaces \$250  
INSIGHT 1 - Probabilities, required thresholds, menus, fast PCDOS \$ 79  
INSIGHT 2 - adds backward, forward, partitions, dB2, lang. access. PCDOS \$399  
Others: APES (\$359), Advisor (\$949), ES Construction (\$100), ESP (\$845), Experteach \$399. Expert Choice (\$449), more.

## AI-LISP

GC LISP - "Common", rich. List Our  
Interpreter - Interactive Tutorial \$495 Call  
LARGE Model - 2 to 15 meg. \$695 \$649  
Compiler and LM. Interp. \$1190 1045  
ExperLisp - Interpreter: Common LISP syntax, lexical scoping, toolbox, graphics. Native Code COMPILER.512K MAC \$465  
TLC LISP - "LISP-Machine" - like, all RAM, classes, turtle graphics, 8087, compiler. CPM-86, MSDOS \$225  
TransLISP - formerly LISP-86 \$ 75  
WALTZ LISP - "FRANZ LISP" - like, big nums, debug, CPM-80 MSDOS \$149  
Others: IQ LISP (\$155), BYSO (\$125), MuLISP-86 (\$199)

## AI-PROLOG

ARITY PROLOG - full, debug, ASM, C, virtual. Compiler \$795 MSDOS \$350  
MicroProlog - enhanced \$229  
MPROLOG - Rich syntax, editor, segment work space, portable. PCDOS \$725  
Professional MicroProlog MSDOS \$359  
TransPROLOG - Learn Fast. Standard, tutorials, samples MSDOS Call  
Others: Prolog-1 (\$359), Prolog-2 (\$1895),

## AI-OTHER

METHODS - SMALLTALK has objects, windows, browser, inspector. PCDOS \$239  
QNIAL - Combines APL with LISP Library of sample programs included. Source or binary. PCDOS \$375  
SNOBOL4 + -great for strings, patterns: MSDOS \$ 85

## FEATURE

TransLisp - "Common subset, tutorial, editor, PP, trace. Best to learn. All MSDOS Only \$ 75

## Free Literature - Compare Products

Evaluate products. Compare competitors. Learn about new alternatives. One free call brings information on just about any programming need. Ask for any "Packet" or Addon Packet ☐ AI ☐ ADA. Modula ☐ BASIC ☐ C ☐ COBOL ☐ Editors ☐ FORTH ☐ FORTRAN ☐ PASCAL ☐ UNIX/PC or ☐ Debuggers, Linkers

## BASIC

ACTIVE TRACE, DEBUGGER - BASICA, MBASIC, interactive, well liked MSDOS \$ 79  
BASCOM-86 - Microsoft 80/86 \$279  
BASIC DEVELOPMENT SYSTEM - (BDS) for BASICA; Adds Renum. crossref, compress. PCDOS \$115  
BetterBASIC all RAM, modules. structure. BASICA - like PCDOS \$169  
8087 Math Support \$ 89  
Run-time module \$459  
CADSAM FILE SYSTEM - full ISAM in MBASIC source. MSDOS \$ 75  
CB-86 - DRI CPM86, MSDOS \$419  
Data Manager - full source MSDOS \$325  
InfoREPORTER - multiple PCDOS \$115  
Prof. Basic - Interactive, debug PCDOS \$ 89  
8087 Math Support \$ 47  
QuickBASIC by Microsoft - Compiles full syntax of IBM BASICA, 640K, PCDOS \$ 85  
TRUE Basic - ANSI PCDOS \$109  
Run-time Module \$459

Ask about ISAM, other addons for BASIC

## COBOL

Macintosh COBOL - Full MAC \$459  
MBP - Lev II, native MSDOS \$885  
MicroFocus Prof. - full PCDOS Call  
Microsoft Version II - upgraded. Full Lev. II, native, screens. MSDOS \$500  
Realia - very fast MSDOS Call  
Ryan McFarland - portable MSDOS \$695

## Editors for Programming

BRIEF Programmer's Editor - undo, windows, reconfigure PCDOS Call  
C Screen with source 80/86 \$ 75  
EMACS by UniPress - powerful, multifile, windows, DOS, MLISP, programming. Source: \$949 \$299  
Entry Systems for C PCDOS \$325  
Epsilon - like EMACS, PCDOS \$169  
Kedit - like XEDIT PCDOS \$115  
FirstTime by Spruce - Improve productivity. Syntax directed for Turbo (\$69), Pascal (\$229), or C (\$239)  
PMATE - power, multitask 80/86 \$159  
VEDIT - well liked, macros, buffers, CPM-80-86. MSDOS PCDOS \$119  
XTC - multitasking PCDOS \$ 95

Ask about Atari ST, Amiga

## RECENT DISCOVERY

Visual Computer: 8088 - Simulates demos or any .exe, Com. Debugger. 350 pg. tutorial \$ 59

## C Language - Compilers

BDS C - solid value, fast CPM80 \$125  
C86 by CI - 8087, reliable MSDOS Call  
Consulair Mac C w/toolkit MAC \$299  
ECO C/88 MSDOS \$ 59  
Lattice C - from Lifeboat MSDOS \$289  
Lattice C - from Lattice MSDOS \$339  
Mark Williams - debugger MSDOS \$379  
Megamax - tight, full MAC \$239  
Microsoft C 3.0 - new, MSDOS \$259  
Q/C 88 by Code Works - Compiler source, decent code, cross/native MSDOS \$295  
Wizard C - Lattice C compatible, full sys. III, lint, fast. MSDOS \$379

## C Language - Interpreters

C-terp by Gimpel - full K & R., OBJ and ASM, large progs. MSDOS \$249  
INSTANT C - Source debug, Edit to Run-3 seconds MSDOS \$399  
Introducing C - Interactive C to learn fast, tutorial PCDOS \$115  
Professional Run/C has Run/C plus ability to create add-in libraries. (Lattice C compatible) and load/unload them. MSDOS \$199  
Run/C - improved MSDOS \$109

## C Libraries - General

Blaise C Tools 1 (\$109), C Tools 2 \$ 89  
C Food by Lattice - ask for source \$119  
C\*LIB by Vance \$129  
C Utilities by Essential - Comprehensive screen graphics, strings, file handling, memory mgmt. Source. MSDOS \$139  
Entelekon C Function Library \$119  
Entelekon C Windows \$119  
Entelekon Superfonts for C \$ 45  
Greenleaf Functions - portable, ASM \$149  
Polytron - for Lattice, ASM source \$ 99  
Software Horizons - Pack 1 \$129

## C Libraries - Communications

Asynch by Blaise \$149  
Greenleaf - full, fast \$149  
Software Horizons - pack 3 \$119

## C Libraries - Files

FILES: C Index by Trio - full B + Tree, vary length field, multi compiler /File is object only \$ 89  
/Pro is partial source \$179  
/Plus is full source \$349  
CBTREE - multiuser record locking, sequential, source, no royalties \$99



# THE PROGRAMMER'S SHOP™

provides complete information, advice, guarantees and every product for Microcomputer Programming.

We support MSDOS (not just compatibles)  
PCDOS, Xenix-86, CPM-80, Macintosh,  
Atari ST, and Amiga.

## C Libraries - Files Cont

dbVISTA - full indexing, plus optional  
record types, pointers, Network.  
Object only - MS C, LAT, C86 \$179  
Source - Single user \$459  
Source - Multiuser \$929

## C Support - Systems

Basic C Library by C Source \$139  
C Debug - Source debuggers - by  
Complete Soft (\$269), MSD (\$149).  
C Sharp - well supported, Source,  
realtime, tasks MSDOS \$600  
C ToolSet - DIFF, xref, source \$135  
Lattice Text Utilities \$105  
The HAMMER by OES Systems \$179  
H.E.L.P. By Everest Solutions \$329

## C - Screens, Windows, Graphics

Curses by Lattice PCDOS \$110  
CView - input, validate PCDOS \$195  
C Power Windows PCDOS \$130  
Databurst - C or Basic PCDOS \$215  
GraphiC - source in C MSDOS \$219  
Topview Toolbasket by Lattice \$219  
View Manager for C by Blaise \$219  
Windows for C - fast \$149  
Windows for Data - validation \$219

## DEBUGGERS

Advanced Trace-86 by Morgan  
Modify code on fly. \$149  
CODESMITH - visual, interactive  
debugger. Symbolize, modify  
and rewrite Assembler \$119  
Periscope I Debugger by Data Base  
Decisions - own 16K \$269  
Periscope II Debugger - load after  
"bombs", symbolic, "Reset Box,"  
2 Screen PCDOS \$119  
Pfix-86 Plus Symbolic Debugger by  
Phoenix - windows \$289  
SOURCE PROBE by Atron for  
Lattice, MSC, Pascal. Windows  
single step, 2 screen, log file. \$395

## Feature

Panel Screen Generator - Create  
screen with editor, generates  
code. Full data validation,  
windows, no royalties. Specify  
Lattice, MSC, C86, MS Fortran  
or PASCAL \$239

## SERVICE: FREE NEWSLETTER

Software development and AI on micros: trends, forecasts, controver-  
sies, innovations, and techniques. Plus an announcement of 80 NEW  
tools. CALL for the "Newsletter Packet."

## Fortran & Supporting

Forlib + by Alpha - graph, comm. \$ 59  
Fortran >> C - FORTRIX creates  
maintainable translations. MSDOS \$995  
MACFortran by Microsoft - full '77 \$239  
MS Fortran \$239  
No Limit - Fortran Scientific \$129  
PolyFortran - xref, pp, screen \$149  
Prospero - '66, reentrant \$390  
RM Fortran - enhanced "IBM Ftn" \$429  
Scientific Subroutines - Matrix \$149  
Statistician by Alpha \$269  
Strings and Things - registers, shell \$ 59

## Multilanguage Support

BTRIEVE ISAM MSDOS \$199  
CODESIFTER - Execution PRO-  
FILER. Spot bottlenecks. Symbolic.  
automatic. PCDOS \$109  
MultiHALO Graphics-Multiple video  
boards, printer, rich. Animation,  
engineering, business.  
ANY MS language, Lattice, C86 \$189  
For Turbo \$ 89

PLINK 86 - a program-independent  
overlay linker to 32 levels for all MS  
languages, C86 and Lattice. \$299  
Pfinish Performance Analyzer  
by Phoenix \$219  
Profiler by DWB Associates \$109  
PS MAKE by UniPress \$ 79  
Screen Sculptor - slick, thorough,  
fast, BASIC, PASCAL. PCDOS \$109  
ZAP Communications - VT 100, TEK  
4010 emulation, full xfer. PCDOS \$ 85

## TURBO PASCAL and SUPPORT

BORLAND: Turbo 3.0 \$ 49  
3.0 with 8087 or BCD \$ 79  
3.0 with 8087 and BCD \$ 85  
Turbo Graphix - graphs, windows \$ 39  
Turbo Toolbox or Editor \$ 55  
Turbo Tutor \$ 29  
TURBO... Asynch by Blaise, full \$ 89  
MetaWindow by Metagraphics \$ 49  
Power Tools by Blaise - library \$ 89  
Power Utilities - profiler, pp \$ 89  
Professional - interrupts, macros, \$ 50  
OTHERS: Screen Sculptor (\$99),  
Pascal Pac (\$100), Tidy (\$45),  
Multi Halo (\$89).

## RECENT DISCOVERY

dbASE to C translator: dbx -  
no royalties, add-on ISAM.  
Library Pioneer it MSDOS \$ 350  
Source \$1000

## OTHER LANGUAGES

APL + PLUS/PC \$469  
ED/ASM-86 by Oliver Computing.  
Integrated editor/assembler/debugger  
w/8087 support. MSDOS \$ 85  
HS/FORTH - '79 & '83 Standards, full  
RAM, ASM, BIOS, interrupts, graph,  
multi-task, optimizer MSDOS \$250  
Ideal APL PCDOS \$469  
MacASM - fast \$99  
MasterForth by MicroMotion - floating  
point and relocater extensions  
available: Call MAC or PCDOS \$125  
MS MASM - improved MSDOS \$109  
Mystic Pascal - fast MSDOS \$ 64  
Paragon PASCAL - for performance:  
extensions like "packages", "Iterators",  
5 memory models. 64 bit 8087 strings.  
Space vs. speed optimization options.  
MSDOS \$895  
PASM - by Phoenix MSDOS \$239  
PL1-86 - Ansi subset \$499  
Prospero Pascal - full ISO + MSDOS \$390  
Turbo Edit ASM \$ 85

## XENIX-86 & SUPPORT

Basic - by Microsoft \$295  
Cobol - by Microsoft \$895  
Fortran - by Microsoft \$429  
Xenix Complete Development System Call

## OTHER PRODUCTS

CPRINT - by ENSCO \$ 50  
DoubleDOS - concurrent Call  
Faster C - scrap your linker \$ 95  
HTest/HFormat - thorough XT Fix \$119  
Microsoft Windows \$ 75  
Norton Utilities \$ 69  
Opt Tech Sort - sort, merge MSDOS \$ 85  
Polymake - Directly execute or GEN a  
batch file, batch, interactive.  
MSDOS \$129  
Texsys - control source MSDOS \$ 89

Note: All prices subject to change without notice.  
Mention this ad. Some prices are specials. Ask about  
COD and POs. All formats available.

Call for a catalog, literature, advice and service you can trust

**NEW HOURS**

8:30 AM - 8:00 PM EST.

**800-421-8006**

**THE PROGRAMMER'S SHOP™**

128 - P Rockland Street, Hanover, MA 02339

Mass: 800-442-8070 or 617-826-7531 1285

"We at Sunspot are thrilled to know  
that there is a store that can cut through  
all the "bull", and find us the products  
that most computer stores know nothing  
about. Keep up the good work."

— Arland Hensler  
Sunspot



# Emulating the 3278

*Users need PCs that function both as stand-alone units and as workstations for mainframe communication. The choices currently available that provide 3278/79 terminal emulation are many.*

ROGER ADDELSON





The trend in terminals is changing from the dedicated slave to the multipurpose workstation. As such, the PC provides local computing power and access to the mainframe for programs, databases, and electronic mail. The mainframe can act as a central data repository, enabling non-networked PCs to share information through file transfer.

The PC may be implemented as a workstation in several ways. Where the need exists and the topology is feasible, the local area network (LAN) connected via a gateway to the mainframe is a popular choice. Under a LAN, each workstation must function independently as both a mainframe terminal and a local PC. In cases where a LAN is not practical or necessary, 3278/79 terminal emulation may be the answer.

The 3278/79 terminal (information display system) is a workhorse for IBM mainframes. This high-speed intelligent terminal offers full-screen capability. Most corporate 3278/79 terminals are connected from host mainframes via coaxial cable to a 3274/76 cluster controller, which then communicates with the mainframe over a high-speed binary synchronous line. This communication often is accomplished under IBM's system network architecture (see "SNA Strategies," Art Krumrey, July 1985, p. 40.) Emulation of the 3278/79 is essential to workstations operating in an IBM mainframe environment. A PC can emulate a 3278/79 through

- a LAN gateway, where a device on the LAN serves as a 3274/76 controller and each PC emulates a 327x terminal. (See figure 1.)

- dial-in 3276 emulation, where a single PC is used to emulate both a cluster controller and a 327x terminal. This option also uses telephone lines and modems. (See figure 2.)
- coaxially connected 327x terminal emulation, where a single PC is directly connected to a cluster controller and acts as a 327x device. (See figure 3.)



The dial-in option provides the 3278/79 emulation—and is the only option when cluster controllers are not available—but the maximum transfer speed is only 2400 baud even with recently released modems. This can be frustrating with program files of 50KB to 100KB or full 1,920-character screens.

The last method is the obvious choice when LAN gateways are not present but 3274/6 cluster controllers are.



PHOTOGRAPH BY MARC DAVID COHEN



**FIGURE 1:** *Emulation via LAN Gateway***FIGURE 2:** *Connection via 3276 Emulation*

In figure 1, a device on the LAN (not necessarily a PC) emulates a 3274/76 cluster controller and connects to the mainframe via a high-speed line. In figure 2, a PC emulates both 3278/79 terminal and 3276 cluster controller. This method is not economical if the cost of the line is high.

The coaxially connected emulators are attached to IBM 3274/6 cluster controllers and communicate with them at speeds of 2.63MB per second. The controllers communicate with the mainframe at speeds ranging from 9600 baud with a leased line to 56Kbaud on a T1 carrier to direct channel connect speeds of up to 3MB per second.

This article evaluates eight coaxially connected 3278/79 emulation hardware/software packages currently on the market. This review is confined to boards distributed by the original makers to avoid comparing a board with itself under another label.

#### SERVICES RENDERED

The basic service supplied by an emulator board with software is a functional duplication of the 3278/79 terminal on a

PC with monochrome or color adapters and monitors. The several terminal models available differ in the number of characters displayed: 1,920 (24 lines by 80 characters); 2,560 (32 lines by 80 characters); 3,564 (27 lines by 132 characters); or 3,640 (43 lines by 80 characters); with regular or extended attribute bytes for the 3278 and base (4) or enhanced (16) color for the 3279. Models 3278-2 and 3279-2A are the most common display systems and the most widely emulated. Some boards emulate several 3278/79 models.

Some 3279 terminals also offer graphics adapter support, permitting terminal display of mainframe-generated color graphics. Some mainframe software packages (GDDM—Graphical Data Display Manager—and SAS GRAPH, for example) require this support; a few


of the 3279 emulators make it available as an added feature.

Users, however, also need to transfer local PC data to the host mainframe and vice versa. This raises many questions: Are file transfers supported under CMS? Under TSO? Can binary files such as load modules be transferred, or only text files? Because the files are stored in ASCII on the PC and in EBCDIC on the mainframe, are the data automatically translated between the two character encoding schemes? Is integrity (error) checking performed during the transfer? Is there a mainframe software component to the file transfer? If so, how is it installed? These and other questions are answered in various ways by the 3278/79 emulator packages.

Consider the PC keyboard. Its layout is different from that of the



**FIGURE 3:** *Mainframe Connection through Cluster Controller*



This configuration is common practice in large 3278/79 terminal installations. It permits 3278/79 terminals to be mixed with emulator-equipped PCs.

3278/79; therefore, each 3278/79 key must be mapped onto a corresponding key on the PC. If every 3278/79 key is not duplicated on the PC emulator, then a degree of 3278/79 functionality is lost. Most of the emulators duplicate 90 percent of the standard keys and functions, with the exception of the Cursor Select and Screen Print keys. Cursor Select allows a terminal without a light pen to simulate an entry in a pen-selectable field, an important factor in many CICS applications. Screen Print allows a 3278/79 to dump screen images to a printer connected to the 3274/6 controller. Most emulators do not support this function, but provide screen dumps to a printer connected directly to the PC.

A workstation PC must operate simultaneously as a 3278/79 terminal and a stand-alone computer. Most emulators

accomplish this through memory-resident software that allows the user to switch between 3278/79 sessions and DOS with a "hot key." DOS reentrancy problems limit the screen-image capture feature in resident emulator software; because of this, many packages also offer a nonresident mode, in which switching to a 3278/79 session requires reloading the emulation software each time. Note, however, that because most 3278/79 boards have on-board processors and memory, exiting a nonresident session does not mean a loss of connection or session with the host.

Ease of installation is an important consideration, particularly when specialized software must be installed on the mainframe. A user experienced only with applications programs on the PC needs clear, step-by-step documentation

on the mainframe file-transfer component. This job should fall under the realm of the systems software group; but in many cases, the PC user is unsupported by the MIS department.

The installation of the board itself is also a concern. Because all PCs are not configured identically, a unique interrupt level for the emulation board is not always possible, and neither is a unique address for the board's memory. Although the board may be set to a default interrupt level and address at the factory, it must permit easy reconfiguration during installation—generally with the use of DIP switches and jumpers. The documentation must be clear, pointing out potential conflicts with system resources such as serial or parallel ports or BIOS routines. The product should include diagnostics to test the emulator in case of initial malfunctions. Table 1 lists the products' features.

### EMULATION EVALUATION

These 3278/79 emulation packages were tested on an IBM 3081-D mainframe running OS/MVS, TSO, and ISPF. They were attached to a 3274 cluster controller communicating via a T1 carrier to a remote 3705 communications controller using IBM's SNA protocol.

**IBM 3278/79 Emulation Adapter.** IBM sells the full-length, single-slot board, control program, and mainframe components of the file-transfer software separately. The package emulates only the 3278-2 and the 3279-2A/S2A, which means it is limited to four colors and does not support mainframe graphics in 3279 emulation. The installation of the mainframe software is better left to a systems specialist in spite of the clarity of the documentation. However, even the neophyte could handle the step-by-step instructions for creating a working diskette and starting up the emulation software.

The IBM file-transfer program is excellent. It is supported under both VM/CMS and MVS/TSO and uses the same protocol and mainframe software as the IBM 3270-PC. This protocol has been adopted by several other manufacturers of 3278/79 boards and has become a de facto standard. The program supports the transfer of both text and binary files of varying record lengths on both the mainframe host and the PC, and includes extensive validity checking. Files are transferred rapidly in 4,096-byte blocks. In addition, the program is able to perform ASCII/EBCDIC translations.

The memory-resident emulator software functions well, permitting the user to switch easily between a DOS




# The graphics card in your AT was actually made for a mere PC.



There's never been a graphics card made especially for the AT. So everyone has had to limp along with graphics cards made for the PC.

*Introducing the first monochrome graphics card actually made for the AT.*



But now you don't have to put an 8-bit card in your 16-bit system anymore. And you can still get full Hercules™ and HBASIC™ compatibility.

Not only that, now you don't need a memory card to bring your AT up to 640K, either.

Because our High Speed Monochrome Graphics/Memory Adapter is not only the first high-speed, 16-bit video adapter for the AT, it also adds up to 384K memory to the AT.

■ Screen updating three times faster ■ High-resolution graphics

(720 x 348) ■ Superior 9 x 14 IBM-standard characters ■ 64K screen memory for bit-mapped graphics ■ Parallel printer port.

It's the AT of graphics cards.

For more information about the Classic High Speed Monochrome Graphics/Memory Adapter and the name of your nearest dealer, phone 408/434-9333. Because if you're not with Classic you're not where it's really AT.

**CLASSIC**  
Everything you always wanted from IBM.

Classic Technology Corporation  
2090 Concourse Dr., San Jose, CA 95131  
408 434-9333, FAX 408 434-0674

IBM is a registered trademark of International Business Machines Corporation. CLASSIC is a trademark of Classic Technology Corporation.

CIRCLE NO. 142 ON READER SERVICE CARD



**TABLE 1:** 3278/79 Emulators Features Comparison

	IBM	PERSYST	LINKUP	FORTE	ATTACH.	IRMA	IDEA.	PCOX
3278/79 models emulated	2	2	2	2,3,4	2,3,4,5	2,3,4	2	2,3,4,5
Mainframe color graphics	No	No	No	Yes	No	No	No	No
3278 keyboard	Full <sup>a</sup>	Part. <sup>a</sup>	Full	Full	Full	Full	Full	Full
International keyboards	No	Yes	No	Yes	Yes	No	No	Yes
Keyboard reconfiguration	No	Yes	Yes	Yes	Yes	Yes	Yes	No
Supports 3274 Entry Assist	Yes	No	No	No	No	Yes	No	Yes
Light-pen support	No	No	No	No	No	Yes	No	No
IBM compatible support	No	Yes	Yes	Yes	Yes	Yes	Yes	Yes
Printer support								
On controller	Yes	No	No	No	Yes	Yes	Yes	Yes
Local	No	Yes	Yes	Yes <sup>b</sup>	Yes	Yes	Yes	Yes
Screen image to disk	No	Yes <sup>b</sup>	Yes <sup>b</sup>	Yes <sup>b</sup>	Yes	Yes	Yes	Yes
File transfer								
Slow—editor oriented	No	Yes	Yes	No	Yes	Yes	Yes	Yes
Fast—mainframe program	Yes	No	No	Yes	Yes	Yes	No	Yes
Ease of installation								
Hardware	Good	Good	Fair	Good	Good	Good	Good	Good
Software	Good	Good	Fair	Good	Good	Good	Good	Good
FTP	Good <sup>c</sup>	Poor	Poor	Good <sup>c</sup>	Good <sup>c</sup>	Good <sup>c</sup>	Good	Good <sup>c</sup>
Changeable I/O address, memory address, interrupt	No	Yes	No	Yes	Yes	No	No	Yes
BASIC access to board	No	No	No	No	No	Yes	Yes	Yes
Diagnostic programs	No	Yes <sup>d</sup>	Yes <sup>d</sup>	Yes	Yes	No	Yes	Yes
Documentation								
Installation	Good	Good	Poor	Excel.	Good	Excel.	Excel.	Excel.
Operational	Good	Good	Poor	Excel.	Good	Excel.	Excel.	Excel.
Troubleshooting	Poor	Good	Poor	Excel.	Good	Poor	Excel.	Excel.
Overall performance	Good	Fair	Good	Good	Excel.	Excel.	Good	Excel.

<sup>a</sup> No Cursor Select key.<sup>b</sup> Only in nonresident mode.<sup>c</sup> Requires mainframe knowledge.<sup>d</sup> Only on power-up.

IBM's emulator, while a good performer, is feature poor in comparison. Only FORTE PJ supports mainframe color graphics.

session and a 3278/79 session with Alt-Esc. Other key combinations let the user reboot DOS while retaining the emulation session or completely suspend the DOS session. The user also may start up the PC with only a 3278/79 session and initiate DOS later.

IBM's 3278/79 Emulation Control Program redefines the PC keyboard to include virtually all functions of the 3278/79 keyboard (U.S. English only; international versions are not supported). The only important key missing is Cursor Select, which prevents the use of this emulator in some CICS applications. The IBM emulator is one of the few that supports 3274 Entry Assists.

This package does have its shortcomings. For example, although the emulator permits output to a printer attached to the cluster controller, it has no provision for screen dumps from a 3278/79 session to a local printer attached to the PC. Another convenient feature offered by many emulators but absent in the IBM emulator is the ability to save screen images to the PC's disk.

Further, the interrupt vectors (50H through 57H) and I/O port (2D0H through 2DFH) used by the IBM board are permanently set. Any applications or other boards that use these addresses may not operate concurrently; applications that write directly to the video buffer also can cause conflicts. But a more serious problem is presented by the 3278/79 Emulation Control Program, which examines the ROM BIOS for the IBM copyright message. If the message is not found in ROM, the program returns to DOS with an error message—the product is incompatible with anything but an actual IBM PC.

The emulation package also falls short in another area: no diagnostic routines are provided and the troubleshooting documentation is at an elementary level. For example, if the answer to the question "Did the program load successfully?" is no, the user is advised to "Contact the point of purchase of your PC3278 Control Program."

**Persyst/Emulex COAX/3270.** Persyst, a division of Emulex, Inc., produces the



COAX/3270, which includes a single-slot, full-sized board and emulation software. The COAX/3270 File Transfer Program, written by CDI Systems, Inc., is sold as a separate product. Like the IBM emulator, the COAX/3270 can duplicate but a few 3278/79 models, in this case, the 3278-2 or 3279-S2A/S2B. It provides base color support only and no mainframe graphics.

The file-transfer package comes on a diskette with an awkward copy-protection scheme. The first attempt to create a working disk, following the directions in the package, produced an unsuccessful copy—the program would not run. A second attempt was thwarted by the protection scheme, which allowed only one copy. A call to CDI Systems, Inc. (not Persyst) produced a code that permitted another copy. This time the batch files were examined and a minor error corrected; the working copy was made by executing each step manually.

The COAX/3270 file-transfer package works with both CMS and TSO. The CMS version supports only text files; the



# Choosing a remote 5251 emulator is easy:



## The biggest or the best.

### The fastest, smallest and most efficient way to connect your PC to the System 34/36/38.

When you need to work with system data, you want an emulator that's up to speed. At 19,200 bps, the PC 5251/PLUS™ from Emerald Technology transfers files faster than any other Model 12 emulator—it's twice as fast as a standard 5251 terminal!

The PC 5251/PLUS was developed by Software Systems, Inc., experts in PC-System/3X communications. PLUS is streamlined to require 1/3 the memory of IBM's emulator and still offer all these features:

**Hot Key**—Lets you switch from PC to emulator mode and back with the stroke of a key.

**Keystroke Files**—Lets you predefine responses to system prompts for automatic or unattended operation.

**Small Size**—Lets you use the short slots on an IBM PC, XT, AT or compatibles.

**Light Pen Support**—An alternative to keyboard input for special applications.

**File Transfer Support**—Works with SSI's Emulator Transfer Utility™ for high speed bidirectional file transfer.

Backed by extensive technical support from the System/3X specialists, Emerald Technology's PC 5251/PLUS is not the biggest, but the best. Call today for a dealer near you.  
(206) 462-8200

*The best solutions. The best support.*

**Emerald**  
Technology Group Inc.



TSO version supports text and binary files. Both use the mainframe editor (XEDIT for CMS, EDIT for TSO). Each of these editors allows files of varying record lengths to be transferred. However, because this package has no host-based file-transfer software, validity checking is *not* performed during the transfer. Under the CMS option, files are transferred by records rather than in large blocks, which makes transfer much slower. Like IBM, COAX/3270 handles the ASCII/EDCIC conversion. The speed of file transfer under TSO depends upon an installation's TSO EDITOR work-file size. The larger the work file, the faster the transfer. The rates can approach those of IBM.

The installation for this package is well documented. All of the files on the distribution diskette are explained, and instructions are given for backing up the files and creating a working disk. The emulation software is written by Persyst, not CDI, and it is *not* copy protected; its installation went smoothly. In addition, the user may reconfigure the address of the board's 32KB memory (initially C0000H-C7FFFH) and the interrupt level (initially level 3) via DIP switches and jumper blocks.

The emulator performed as promised, although the screen behaved strangely while capital letters were being entered. (The cursor went to the bottom left screen position after each keystroke of an uppercase character.) It includes some important features, such as screen image capture to the local printer, or, if the emulator is not memory resident, to disk; extensive on-line help; and the ability to run in resident or nonresident mode. In resident mode, the user may switch to and from the DOS session using the Shift-Shift combination. Note, however, that this poses a potential conflict with SideKick, which also uses Shift-Shift.

The COAX/3270 software comes with a redefinition of the PC keyboard to the functions of the 3278/79 keyboard (U.S. English edition). The package also includes definitions for the British, French, German, Italian, and Spanish keyboards. Or, the user may create keyboard definitions using a utility program provided in the package. In spite of all this, several important 3278/79 keyboard features are missing from the COAX/3270 keyboard definition, including Apostrophe, Attn, Ident, NumLock, Sys Req, and, as in the case of IBM, Cursor Select.

The hardware provides a self-test diagnostic feature at power-up, but this is as far as the diagnostics go. No rou-

tines are included to test for a correct installation. A brief appendix in the manual gives limited but well thought-out hints for troubleshooting.

**LINKUP System COAX.** Information Technologies, Inc. produces this system, which includes a single-slot, full-sized board, emulation software, and file transfer software as an option (at extra cost). Although the documentation states that LINKUP emulates a 3278-2 display station only, 3279-S2A emulation can be achieved using the color redefinition utility provided in the package. However, ITI's emulator does not provide support for 3279 graphics.

As with the Persyst COAX/3270, LINKUP's optional file-transfer software was written by CDI Systems. The programs exhibit similar features and appear to function identically: the LINKUP program has a similar copy protection scheme and it supports both CMS (text only) and TSO (text and binary) via the

**T**hrough memory-resident software, most emulators allow the user to switch between 3278/79 sessions and DOS with a "hot-key" combination, typically Shift-Shift.

mainframe editors. Its limitations also are similar: it has no validity checking, and it operates slowly in CMS and only moderately faster in TSO.

The hardware installation instructions consist of two sentences: "Instructions for installing option boards, such as LINKUP Coax, in IBM Personal Computers are provided in the options section of the IBM Personal Computer Hardware Reference Library *Guide to Operations*. For installation of the LINKUP Coax in IBM-compatible personal computers, refer to the computer manufacturer's user documentation for specific instructions on installing option boards." No information about board addresses, interrupt levels, or possible conflicts with other peripherals or programs is provided; nor are instructions for backing up the diskette or making a working copy included. A neophyte may feel forced to use the distribution diskette, a dangerous situation.

Nevertheless, the LINKUP emulator is a versatile package. The appearance of

the 3270 status line is much like that of the IRMA board (see below), with excellent graphic representation of the status line symbols. The emulator operates in memory-resident and nonresident modes. In resident mode, some of the extended features, such as screen image capture to disk, do not function. The package provides hot keys for the conversion between modes, to switch between DOS and 3278 sessions, to convert from color to monochrome display, and to capture screen images to local printers in either mode.

The LINKUP software offers a rather complete U.S. English keyboard. Although it does not support international versions, it does include a utility that allows the user to redefine the 3270 keyboard in any manner. In addition to the standard keys offered, LINKUP includes such useful extras as Attn, Sys Req, Ident, Test, and (for CICS users) Cursor Select. It even has equivalents of the 3278 cursor fast movement keys.

The manual for this package is extremely poor. It has no information on error messages, diagnostics, or troubleshooting, but it does list a telephone number for technical support. The hardware does offer two innovative, firmware-based diagnostic tests: a power-on test (which was not seen in action because the evaluation board functioned properly) and a coax test that is invoked from the keyboard with the results displayed in the status line.

**FORTE PJ (3278/79).** This product from Forte Data Systems includes a single-slot, full-sized board and software that allows the PC to emulate 3278 models 2, 3, and 4 and 3279 models S2A, S2B, or S3A with seven-color extended highlighting in all terminal modes. Only Attachmate (see below) offers a wider range of emulation. Options sold separately include file transfer packages under either CMS or TSO, multiple session windowing and 3270-PC emulation, and 3279-S3G emulation (which permits full color graphics support).

The optional file-transfer package includes a diskette for the PC software and a 1600-bpi magnetic tape for the mainframe software. The documentation includes well-written installation instructions for both. The mainframe instructions are presented in an orderly fashion, but knowledge of JCL, CLISTS, ISPF (if installed), and system specifics is required. Installation of the PC software also is straightforward and, in fact, is included as one step in the general installation of the FORTE PJ emulator.

Forte offers two separate file transfer products for CMS and TSO. This



# AW...

# WHAT THE HECK!

## ProDesign II The Easy to Use CAD System!


ProDesign II is one of the most advanced CAD packages available for microcomputers. We think it's absolutely the easiest to use. With competitive CAD systems priced at \$1500 to \$2500, we were posed with the problem of setting our price.

ProDesign II works a wide variety of digitizers and mouse devices. It works with nearly any plotter or printer available for the IBM PC. ProDesign II can produce plotter quality drawings on ordinary dot matrix printers - a feature found exclusively on ProDesign II. ProDesign II utilizes a virtual screen 4 times the size of the physical screen to make it practical to produce drawings on a normal resolution IBM monitor. ProDesign II is truly an outstanding CAD package for the IBM PC and compatibles. The question we had to answer was: Even though we had a better product, should we price it higher than the other CAD systems on the market?

We did market studies and calculations. We consulted with experts. We drew charts and graphs. We used the finest spreadsheet programs money could buy. When it came right down to it, we still didn't know what to sell ProDesign II for. \$2995? \$2495? \$1995? We even considered \$995.

Then, in the great American tradition, we said, "AW...WHAT THE HECK! Let's see the other guys beat this price!" ProDesign II costs \$299. At that price, you can't go wrong!



## AW...WHAT THE HECK! \$299.95



THE SPACE SHUTTLE DISCOVERY

## B1 BOMBER

THIS DRAWING WAS PRINTED ON AN  
EPSON RX-80 DOT MATRIX PRINTER.  
RESOLUTION IS .005" -  
MORE THAN 4 MILLION DOTS!  
BETTER THAN MANY PLOTTERS!



Why should you get ProDesign II? Four simple reasons:

1. ProDesign II is easy to use. You won't have to spend weeks learning simple functions.
2. ProDesign II works with the hardware YOU own. ProDesign II supports most printers and plotters available for the IBM PC, as well as a wide variety of digitizers and mouse devices.
3. ProDesign II can produce plotter quality output on ordinary dot matrix printers. (The B1 Bomber above was printed on an Epson RX-80.)
4. ProDesign II is priced 70% to 80% below competitive products!

What do you need to run ProDesign II? An IBM PC or compatible with 512K RAM and graphics capability.

How do you get ProDesign II? See your local computer dealer or contact us.

ProDesign II - The Easy to Use CAD System!

**American Small Business Computers**  
118 South Mill  
Pryor, Oklahoma 74361  
**918/825-4844**

CIRCLE NO. 103 ON READER SERVICE CARD



evaluation pertains only to the TSO product, TSO-Fortenet (although a Forte representative affirmed that CMS-Fortenet is similar.) TSO-Fortenet is the most powerful file-transfer package in this field. In addition to allowing both varying-length-text and binary-file transfer between the PC and the mainframe, it also supports transfer to the MVS SYSOUT and INTERNAL READER. Transfers to SYSOUT permit the user to send PC files directly to mainframe output devices such as laser printers or high-speed line printers. Transfers to the INTERNAL READER permit mainframe batch jobs stored on the PC to be submitted directly to the mainframe. The product supports both ACF2 and RACF security systems. TSO-Fortenet has only one major limitation: it will work only when FORTE PJ is running in non-memory-resident mode.

In spite of this, TSO-Fortenet offers a variety of special features. It functions in TSO's native READY mode and includes full support for ISPF with six easy-to-use menu screens. It includes a series of mainframe CLISTs for batch uploading and downloading, the most powerful of which is BACKUPHD, used to back up directly to the mainframe all the files in specific PC directories. As a result, streaming tape or any other PC-based backup systems are unnecessary.

Forte's file-transfer facility, with both mainframe and PC components, includes extensive validity checking during transfers. Its 4,096-byte block size permits a faster rate than some of the other record-oriented packages. The documentation includes descriptions of the ASCII-to-EBCDIC and EBCDIC-to-ASCII tables that Fortenet uses to accomplish all of its character translation.

The FORTE PJ emulator functions well and all of its features work as documented. When using a color graphics board and color monitor, the emulator comes up in 3279 mode without requiring the user to define the colors. The status line includes items not found on the 3278/79 line, such as a resident mode indicator, which shows if PJ is memory-resident, and a model number indicator, which shows the current emulation model. FORTE PJ uses the Shift-Shift hot key to switch between 327x and DOS sessions. Its emulator includes many of the extended features found in other packages: screen image capture to disk, local screen print, initiation of resident mode, and diagnostic tests. Users should note, however, that these extended features and file-transfer functions are available *only* in non-memory-resident mode.

FORTE PJ is one of the few emulators to provide all of the functions of a 3278/79 keyboard, including Cursor Select. With the custom configuration program FDSCONF, the user can change the model emulation, keyboard layout, video interface and monitor type specification, color, and attributes, base address, printer port, foreign country keyboard and display, extended attribute support, and PC model. In addition to the default U.S. English keyboard, FORTE PJ also supports the Austrian/German, Belgian, Brazilian, Danish, Finnish, international, Italian, Portuguese, Spanish, U.K. English, Norwegian, Swedish, and French keyboards.

This product's manual is one of the most complete. Offering detailed step-by-step instructions on both hardware and software installation, it takes the user through diskette backup and working copy generation. The system comes with standard default values for PC type,

**F**ORTE PJ's TSO-Fortenet is the most powerful file transfer product in the field, but it runs only in non-memory-resident mode.

interrupt level, 3278/79 model type emulation, and other necessary parameters. It determines the base I/O address, video interface type, monitor type, and printer port from the motherboard DIP switch settings. Any of these parameters can be changed with FDSCONF.

The manual also has extensive, well thought out sections on diagnostics, troubleshooting, and error messages, including an excellent discussion of potential base I/O address conflicts with other boards. The package contains an installation diagnostic program and troubleshooting routines.

**Attachmate 3-N-1 3270 COAX Adapter.** Attachmate offers the most versatile emulation boards and software on the market. Its 3-N-1 adapter is so named because it will run not only Attachmate's own software, but also software for the IBM 3278/79 emulator board and the IRMA board. (Some features of IBM's and DCA's software are not available when running on the 3-N-1; tables summarizing supported and unsupported features are included in the manual.) The documentation indicates that 3-N-1

will run PC-Focus from Information Builders, Goldengate from Cullinet, Interactive PC Link from McCormack & Dodge, and Tempus Link from Micro Tempus. Attachmate's 3270-PC emulation software also is interchangeable with the IBM adapter and the IRMA board. The 3-N-1 adapter with Attachmate's emulation program will emulate models 2, 3, 4, and 5 of both the 3278 and 3279, thus providing the widest emulation range of all packages tested. Its only significant shortcoming is that it does not offer the 3279 graphics support available with the FORTE PJ.

The file-transfer routine, included with the package's PC 3270 Emulation Program, offers support both for a proprietary file-transfer protocol using TSO's EDIT or CMS's XEDIT (similar to LINKUP or Persyst COAX/3270) and the host-supported protocol that is available with IBM's 3278/79 Emulation Control Program and 3270-PC. IBM host programs required are number 5664-281 for CMS, 5665-311 for MVS TSO, and 5798-DHQ for CICS (MVS/VM DOS). The editor-based transfers are slow, have no validity checking, and only provide support for text file transfers; they require no additional software and no mainframe installation. The host-supported routines are fast and include extensive validity checking, but they require the additional IBM programs and mainframe expertise for installation.

The Attachmate PC 3270 emulation program offers many features beyond the standard 3278/79 emulation. Because it also emulates a 3270-PC, it can accommodate seven active windows, including four simultaneous host terminal and printer sessions, two notepads, and a PC window running DOS (any version from 2.0 to 3.1). The emulation software is always resident, and rather than using traditional hot keys to move between DOS and 3278/79 sessions, the user jumps among the seven windows using the 3270-PC-style window management keys. However, it will function at a similar level to the other products using only two active windows: one for DOS and one for the host.

Attachmate's emulator includes many other extended features, such as 3270 printer emulation (LU3 print controls for a 3287 with a 2,048-byte buffer size), screen-image capture to either disk or local printer, and data block copying between windows. Its window management commands—jump, corner, size, add, delete—are virtually identical to those for the 3270-PC.

The Attachmate software has a unique copy-protection scheme. If the



# JLASER

## THE LASER PRINTER SOLUTION

DATA TRANSFORMS *Brings*

### TYPESETTING & GRAPHICS TOGETHER AT LAST!


Presenting the magical team of the Tall Tree Systems' JLASER™ card and our Printrix™ software.

Printrix is a powerful multi-page typesetting tool. It's quick. The average time per page is just 2 to 3 minutes - so your time spent waiting won't drag on and on. It's resourceful. Able to accept standard ASCII and native textfiles from most major word processors, it adds both the ease of menu-driven options and the power of text-embedded commands to produce state-of-the-art output. It's clever. Features include: graphic insertions, mail merge, file chaining, macro definitions, and multiple headers/footers, as well as all the font manipulation and page formatting power you'd expect in a professional system. It shares Fontrix's extensive library of fonts - now numbering over 150 - and comes with its own starter set of 20 fonts.

Fontrix has gained wide recognition as a versatile typesetting, with unparalleled freedom of character positioning and on-screen, WYSIWYG (What You See Is What You Get) editing. Type and graphics may be mixed on the same workspace, making it ideal for complex single-page layouts. The wealth of drawing and painting routines, enormous work area, electronic cut-and-paste, font editor, mouse interface and other fine features bring Fontrix to the forefront of PC graphics technology.

This entire page was typeset using PRINTRIX and the JLASER card. The graphics were created with FONTRIX, and printed through PRINTRIX.


PRINTRIX and FONTRIX are trademarks of Data Transforms Inc. 616 Washington Street Denver, CO 80203 (303) 832-1501 Call or write for more information. JLASER is a trademark of Tall Tree Systems Inc.



When we introduced JLASER, we knew it was the ultimate solution to current laser printer limitations. Like all good things, it's catching on fast. The list of software companies that back JLASER is expanding rapidly. We are pleased to welcome this latest addition to our growing software family of JLASER supporters.

JLASER is a controller that piggybacks onto a JRAM-3 or AT-3 two megabyte memory board giving laser printers the speed and versatility they were meant to have. It plugs directly into the printer engine of the H-P Laserjet™ or other Canon-based printers. Our interface transfers bit-mapped images from RAM, bypassing the on-board print buffer and most of the control circuitry. It opens up a creative new world of graphics and multiple type font combinations, and still gives you plenty of RAM to use for programs, data, and electronic disk.

JLASER is the powerful, economical, and efficient solution to all your laser printer problems.



**TALL TREE SYSTEMS**  
1120 San Antonio Road  
Palo Alto, CA 94303  
(415) 964-1980

CIRCLE NO. 193 ON READER SERVICE CARD



software is being used with an IBM or IRMA board, a key disk is required in drive A:. If it is being used with the 3-N-1 board, the key is located in the firmware on the board. The 3270-PC emulation program includes an extensive configuration utility that covers many languages (U.K. English, French, Italian, Austrian/German, and Spanish, in addition to the default, U.S. English), user keyboard mapping, adapter board and host window session parameter selection, and window profiles. All 3278/79 keys are supported except Cursor Select and the fast arrow keys.

The installation goes smoothly because of complete and well-written documentation. Instructions for both hardware and software discuss I/O and memory address considerations and compatibility limitations. When emulating the IRMA board, 3-N-1 uses I/O addresses 220H-227H and memory addresses CE000-CFFFF; for the IBM board, it uses I/O addresses 2D0H-2D7H (the IBM board has no on-board memory, hence no memory mapping). The 3-N-1's I/O and memory addresses can be changed via jumper blocks.

The two manuals contain well-written sections on troubleshooting and error handling. The 3-N-1 diagnostic test program, provided with the board, lets the user verify installation and pinpoint operational problems that occur afterward. The diagnostic has both a stand-alone and on-line mode and tests all major functional areas of the adapter, including PC-to-adapter I/O control, shared memory, the coax processor, and the coax-peripheral interface. Attachmate's diagnostic program is the most thorough of those tested.

**IRMA 3270 board.** Digital Communications Associates' IRMA board, with its E78 Emulation Software, was the first 3278/79 emulator on the market. It has evolved into one of the most complete packages available. The IRMA package can emulate 3278/79 models 2, 3, and 4, which equals or surpasses all boards except the Attachmate 3-N-1.

In addition to the extended features (such as screen-image capture to disk and printer, keyboard configuration, and file transfer) offered on many boards, IRMA is the only product to provide full light-pen support. It does so through emulation of Cursor Select to simulate a light-pen selection. In addition, when the E78 terminal emulator is used with the IBM Color Graphics Adapter and a light pen (such as the pen by FTG Data Systems) is connected to the adapter, it fully emulates the IBM selector pen option on the 3279.

IRMA supports data entry to IBM mainframes through character-oriented serial devices attached to the COM1 serial port. The interface permits such options as bar code or optical character readers and touch input screens (such as the one manufactured by Touch Technology). For displays equipped with special character generator ROMs (which are available from DCA or STSC), IRMA supports the IBM APL/1 character set and keyboard.

Like 3-N-1, IRMA offers two file-transfer protocols. IRMALink FT78X, a program that comes standard with the E78 software, uses XEDIT on the host running VM/CMS and TSO EDIT on an MVS/TSO host. It operates similarly to the editor-based file-transfer programs provided by other manufacturers, and supports text and limited binary file transfers. Editor-based transfers are nat-

**D***CA's IRMA has evolved into one of the most complete 3278/79 emulation packages available.*

urally slow, but IRMALink uses POWERINPUT in XEDIT to improve performance on file uploads. (POWERINPUT allows "stream" character input without waiting for prompts.) The binary mode is used for transfers from PC to PC by uploading to the host from one PC and downloading to another. Archival storage of PC files on the mainframe is done in the same way. However, the transfer of binary files that the host can recognize is *not* supported.

The problem is that 8-bit bytes cannot be transmitted through mainframe editors, which deal only in 7-bit characters. (The high bit usually is usurped in some sort of parity-checking scheme.) PC binary files must be converted into two 7-bit characters before uploading through XEDIT or TSO EDIT. The character files stored on the mainframe are restored automatically to binary form when they are downloaded to a PC. For the mainframe to use them, a conversion utility must be written on the mainframe end to reassemble the character pairs into the original 8-bit bytes. DCA does not provide such a utility, nor do any of the other vendors employing a similar conversion scheme.

DCA does, however, bundle IRMALink FT/TSO and FT/CMS with the IRMA

board to handle binary file transfers. IRMALink is a high-speed file-transfer software package with both micro and mainframe components. The mainframe portion is distributed via two media: diskette and 1600-bpi magnetic tape. The diskette-based software can be uploaded using FT78X; the tape-based files can be unloaded using mainframe utilities. TEST.TXT, a file that is included on the distribution diskette, tests the file-transfer function.

FT/TSO can be run using either menu or single-command format. The former makes FT/TSO menu driven and allows access to the transfer type assigned by FT/TSO and to the transfer parameters. The latter makes FT/TSO command driven, and does not allow changing transfer types or parameters.

IRMALink FT/TSO provides for the transfer of binary and text files of varying lengths. It supports both sequential and partitioned data sets. Through the use of predefined parameters (block size, LRECL, record size, and so on) each transfer requires only a fairly simple command. The predefined parameter file can be modified via a menu screen invoked by a function key.


IRMA's E78 emulator program can be activated with four options: basic E78 program, E78 with screen-save capabilities, E78 with screen-store and recall capabilities, and E78 with both screen save and screen store. Screen save records the screen image on disk; screen store stores the screen image in dynamic memory for recall anytime while E78 is active. Once activated, E78 defaults to nonresident mode. It is switched to resident using a hot key. In resident mode, the user can switch between 3278/79 and DOS sessions using another hot key. Like other packages, E78 does not offer the screen-image save function in resident mode. However, DCA is the only firm to compensate for this by allowing the user to activate simultaneously both the resident and non-resident forms of the emulator program. In resident mode, the user simply switches to the DOS session and initiates E78 again and is in nonresident mode. (When in simultaneous mode, the emulator uses twice the amount of memory, that is, 192KB.)

IRMA's E78 software provides complete 3278/79 emulation of the U.S. English keyboard. Using the GENX utility the keyboard and screen type can be reconfigured for APL, TEXT, and DATA ENTRY ASSIST (the latter is supported by IRMA and IBM only). GENX also defines the light pen, 3278/79 model, color, COM port, and PC look-alike




# ONLY SEATTLE TELECOM & DATA solves the expanded memory and speed problems of the IBM PC/XT.

- 2MB EMS Memory • 16 Bit Data (PC-286 Support)
- Both Intel & AST Specifications Support



- Fully compatible with both Lotus/Intel/Microsoft E.M.S. 3.2, and AST/Quadram Enhanced E.M.S.
- 0-2 megabytes expandable memory on one board
- Compatible with Lotus 1-2-3, Version 2.0, Symphony, Version 1.1 and Framework, Version 2.0
- 100% PC-DOS Compatible
- One Year Warranty



**N**ow, you can solve your memory and speed problems with TOP Board™ from Seattle Telecom & Data. **TOP Board** is the only E.M.S. Board to either run 8 Bit or 16 Bit wide in the IBM PC/XT. It is the only board available that can be **powered by the PC-286** card. Create larger Spreadsheets and Data base files on your IBM PC or compatible, and run programs such as Lotus,™ Symphony™ and Framework™ **three times as fast** as the IBM PC/XT.

The TOP Board is fully compatible with the Lotus/ Intel/

Microsoft Expanded Memory Specification **and** the AST Enhanced E.M.S. specification. TOP Board's unique design provides an efficient and flexible paging scheme for greater performance with E.M.S. applications and multitasking software.

TOP Board offers the flexibility of using 2MB on one board taking up only one slot!!

TOP Board comes with optional daughter boards that give users the flexibility of E.M.S. memory **Plus<sup>A</sup>** with a serial/parallel ports and clock calendar\* or

E.M.S. memory **Plus<sup>B</sup>** with an Enhanced Graphics Adapter.\*\*

TOP Board can be used as a standalone E.M.S. board or it can be driven by the **Powerful PC-286 Accelerator Board**. By connecting the TOP Board with the PC-286 you will have solved the two biggest problems facing microcomputer users — **Memory and Speed!!**

**CALL (206) 883-8440**

**STD**

SEATTLE TELECOM & DATA, INC.  
2637 151st Pl. N.E.  
Redmond, WA 98052

\* Available 1st quarter '86  
\*\* Available 2nd quarter '86

Top Board and PC 286 are trademarks of STD. Framework is trademark of Ashton-Tate. Lotus 1-2-3 and Symphony are trademarks of Lotus Development Corporation. IBM PC/XT is a trademark of International Business Machines Corp.



patches for the 8086. IRMA does not support international keyboards.

For operations assistance, DCA's manuals are among the best. They take the user from elementary instructions for diskette duplication to an extensive technical reference outlining the board's architecture and the internal workings of the E78 software. The documentation contains BASICA subroutines for accessing IRMA's screen buffer. The board is addressed as an I/O device on the system unit bus with device code of 220H through 227H; one drawback is that these addresses are fixed and cannot be changed.

Another of the very few disappointments is IRMA's minimal troubleshooting support. The package contains no diagnostic programs and the manual devotes only three sparse pages to diagnostics, troubleshooting, and error conditions. The conditions discussed were too general, even though the discussions themselves are good.

**IDEAcomm 3278.** This package from IDEA Associates, Inc. includes a full-size, single-slot 3278 emulator board, emulation software, and a file-transfer package that supports MVS/TSO and VM/CMS. IDEAcomm 3278 enables the PC to emulate a 3278-2 or a 3279-S2A/S2B with eight-color support. It does not support mainframe color graphics.

The file-transfer facility, XFER, allows transfers in both directions in a MVS/TSO or VM/CMS mainframe environment. This program, as other emulators, performs transfers using the mainframe editors and therefore provides no mainframe component for validity checking. The file-transfer program is menu driven, allowing the user to select send or receive, text or binary files, record length and format, host data-set name, and PC file name.

Binary transfers are accomplished by converting each 8-bit byte into two 7-bit characters and transmitting the characters. If the remote system is a PC also running XFER, XFER will convert the two characters back into the original 8-bit byte. Otherwise, the transmitted data must be converted into binary data by a translator program (which is not supplied—it must be written by the user). As described earlier, the binary mode may be used to store PC binary files on the host for later downloads, but uploaded files cannot be used on the host itself. IDEAcomm also has a batch file-transfer facility, RUNFER, with which the user creates RUNFER.BAT, a file that contains information on multiple files to be uploaded and downloaded. This feature is helpful since the

file-transfer facility is editor based and therefore relatively slow.

IDEAcomm 3278 includes some unique and excellent features. From a 3278/79 session and without switching to DOS, the user can print and display PC files, obtain a PC directory listing, and access on-line help. The emulator also supports such features as screen-image capture to disk, locally connected printers, and controller-connected printers. With this product's screen capture to disk, the screen image is captured in a single 1,920-byte file complete with all the 3278/79 screen attribute bytes. These bytes are the same as IBM's except that the second-highest order bit (bit 6) of the attribute byte is always 1.

In addition to the stand-alone non-memory-resident mode, IDEAcomm 3278 also has a memory-resident mode. This mode makes the IDEAcomm program part of DOS, thus allowing the user to switch between 3278/79 sessions and DOS using a hot key.

The software emulates a full 3278 keyboard, including Cursor Select. The configuration utility supports keyboard remapping, but does not include support for international versions. This utility also allows the emulator to simulate power off when the IDEAcomm is exited, define the printer (local or con-

*With the IDEAcomm 3278 emulator package, the user can print and display PC files from a 3278 session without switching to DOS.*

troller connected), and define the color for screen attributes.

The well-written documentation made installation easy for both hardware and software. It includes extensive descriptions of the interface between the IDEAcomm board and the PC, which uses I/O ports 3E8H through 3EAH and memory address E000H through EFFFH. The structure used to pass information between the two is described, and tips are offered on writing low-level application program drivers to interface to the 3270 display on the board. The manual also discusses the BASICA support subroutine included on the distribution diskette.

The manual has several sections on diagnostic testing using software in-

cluded in the package. The program is thorough and easy to use, and its documentation well written, although quite technical for the novice.

**PCOX/PLUS.** CXI's PCOX was among the earliest 3278/79 emulators on the market. PCOX/PLUS is a significantly enhanced version of the original product. The hardware is reduced to a half-size board, the only one tested. CXI's package is quite versatile, emulating 3278/79 models 2, 3, 4, and 5. Like IRMA and the IBM board, PCOX/PLUS supports the Entry Assist feature. It does not, however, support mainframe graphics or the PC light pen.

The control program partially emulates the 3270-PC with one host session, one DOS session, and two notepad sessions. Notepad data may be cut and pasted to other sessions or windows, and may be combined with keyboard entries. The contents of the notepad windows may be saved to disk or sent to a local (PC) printer.

CXI sells the PCOX 3270 Series File Transfer package separately. Like Attachmate's 3-N-1, the PCOX/PLUS offers support for basic file transfer based on TSO EDIT and CMS XEDIT, and an advanced protocol running on the mainframe under TSO and CMS. CXI does not support CICS-based file transfers.

The editor-oriented file transfer programs are easily implemented using TSO CLISTS or CMS XEDIT scripts. The basic protocol is slow, has no error checking, and does not handle binary files. Installations using ACF/VTAM support for data communications can take advantage of the default maximum record size for the TRANSFER LIMIT.

The advanced file-transfer protocol is well thought out and fast. Installation is complex and should be attempted only with the help of systems programmers. CLISTS, JCL, and some 370 source code and object code must be uploaded using the basic file-transfer routines. Modification of the CLISTSs, JCL, library, and data set names and assembly and link editing must be done in order to complete installation.

Although this advanced protocol does not follow the IBM standard, it is very versatile. It supports standard ASCII text transfers (like the basic protocol) and several other modes. The compressed mode replaces up to 64 successive occurrences of the same character by a three-character sequence: escape, count, and character. On the host, this sequence is expanded to the original string. The binary (transparent) mode transfers an exact image of each byte. The file-transfer program translates each



# BetterBASIC Version 2.0

## "I Wrote It, And I Recommend It."

*"BetterBASIC has evolved into a programming environment which is completely compatible with GW BASIC and PC BASICA when running on IBM PCs and compatibles. Now you can easily load your old BASIC programs into BetterBASIC. BetterBASIC gives programmers use of the full memory of the computer and a structured language with true procedures and functions—like PASCAL and C. I wrote BetterBASIC and I recommend it."*

Ivar Wold, President • Summit Software Technology Inc. • Norwood, MA

### ACCESS FULL MEMORY—

BetterBASIC accesses the full memory of the computer enabling you to overcome Microsoft's 64K barrier.

### INTERACTIVE

**COMPILER**—BetterBASIC compiles to an intermediate code giving you five to six times the speed of traditional BASICs. There is immediate feedback on line entry.

**COMPATIBLE**—Version 2.0 of BetterBASIC is GW-BASIC, PC-BASICA compatible when running on IBM


PCs. BetterBASIC is easy to learn because the syntax is the same.

**STRUCTURE**—Create well-organized programs using procedures and functions that are easily identified and understood.

**NOT COPY PROTECTED**—Install BetterBASIC on your hard disk. BetterBASIC is licensed to the programmer, so you can compute at work and at home using the same copy of BetterBASIC.

**USER DEFINED KEYWORDS**—The BetterBASIC language can be extended by adding your own procedures and functions to the language as keywords.

**RUNTIME SYSTEM**—Creates stand-alone EXE. files. Developers can distribute their programs written in BetterBASIC without royalties.



**SAMPLE DISK**—Contains a tutorial, a demo, and allows you to use an abbreviated form of BetterBASIC. It also contains a 60 page on-line mini manual.

**AND MORE**—Such as DOS and BIOS ROM calls, Chaining, Overlays, Local and Global Variables, Recursion—Graphics and Windows—You can define up to five windows. Optional 8087/80287 Math Chip Support. **LIBRARIES**—Write reusable code.

### TECHNICAL SUPPORT—

Available to all registered users.

**BetterBASIC** Runs on IBM PC, XT, AT and all IBM-compatibles. Ask your local dealer for BetterBASIC or call 1-800-225-5800.

In Canada call 416-469-5244. Also available for the Tandy 1000, 1200 and 3000 at Tandy/Radio Shack stores.

### PRICES:

Better BASIC	\$199
8087/80287 Math Module	\$99
Runtime System	\$250
Sample Disk with Tutorial	\$10

# Better BASIC.

## Because It's The Best.

**Summit Software Technology, Inc.™**

106 Access Road, Norwood, MA 02062

MasterCard, Visa, Checks, Money Order, C.O.D. accepted and P.O. on approval.

BetterBASIC is a registered trademark of Summit Software Technology Inc.

IBM PC, XT, AT, are registered trademarks of International Business Machines Corp. Tandy is a registered trademark of Tandy Corp.

(If you're using BetterBASIC and would like to be featured in one of our ads, please write to the Director of Advertising at Summit.)

CIRCLE NO. 196 ON READER SERVICE CARD



three-byte group to four bytes of 3270 buffer codes, which are translated by the 3274/76 cluster controller (or cluster control program if in DFT mode) to EBCDIC. This is reconverted by the host-end software to the original three-byte groups. The user may specify compressed mode on this operation before three-byte translation to further speed up transfers. Finally, CXI offers an offset transfer mode for files that will be processed by ISPF. This replaces the first six or eight bytes of each record for some file types (COBOL, for example) with a sequence number.

Like many of the others, the PCOX/PLUS emulator program cannot save screen images to disk while memory resident. The advanced file-transfer package must be loaded from the host session to save screen images. In addition to interactive file transfers, PCOX/PLUS also supports command-mode transfers via PC batch files created by the CXI Batch File Generator.

The PCOX 3278/79 Control Program supports many of the 3270-PC's functions, including windows, jumping and enlarging windows, cut and paste, and changing screens. The control program functions only in memory-resident mode. Like Attachmate, hot keys for moving between emulation sessions do not apply because the software allows jumping among windows. The program supports complete 3278/79 keyboard emulation, including Cursor Select, all entry assist features, and most 3270-PC keys. CXI defines many international keyboards, including U.S. English, Austrian/German, Belgian, Canadian French, Danish, Finnish, French, Italian, Japanese-English, Norwegian, Spanish, Swedish, and U.K. English. It does *not* support user-defined keyboards.

Installation instructions are complete and the operation went smoothly. The board is factory set to IRQ level 2, DMA 1, and I/O ports 3EE and 3EF. These specifications can be changed to avoid conflicts with other boards.

The manuals are well written and offer a complete section on diagnostics. The emulation software contains a menu of excellent maintenance functions including interface reset, diagnostics, and a memory-dump facility. The diagnostics also can be accessed from the File Transfer Program.


PCOX/PLUS is a solid product with excellent file transfer and the best diagnostic functions of any board tested.

## A STRONG FIELD

IBM's 3278/79 emulator has a fast, industry-standard file-transfer package and the mainframe component also supports the 3270-PC. However, because the software does an environment check, it cannot be used on non-IBM machines. In this case, the Attachmate 3-N-1 is a good alternative; it supports the IBM file-transfer protocol, runs in non-IBM compatibles, and simulates the 3270-PC as well. In configurations where slots are scarce, CXI's PCOX/PLUS could be the only choice.

Another board that deserves recognition is the FORTE PJ emulator. Although many other vendors offer better packages overall, two features distinguish the FORTE PJ: it is the *only* board that offers 3279 color graphics, and it has the fastest and most versatile file transfer program. It should be given serious consideration by the user who performs numerous transfers, who is interested in hard disk backup, or who needs to transfer files directly to SYSOUT of the mainframe's internal reader.

An evaluation such as this cannot overlook the progenitor of all 3278/79 emulators, the IRMA board. IRMA has evolved into the best board on the market overall. It supports most of the features found in the other packages and is the only board to fully support light pens. It is also one of only three that supports Entry Assist. Its file-transfer routines are solid and quick, even though they are proprietary and run only on the IRMA and 3-N-1 boards. IRMA's only other significant flaws are its poor troubleshooting and lack of diagnostic routines. However, DCA's support line was easily accessible and the personnel knowledgeable.

Emulation of 3278/79 display stations can be effected with many variations. Some users require color to support customized mainframe software; others may need or want 3279 color graphics or light-pen support. Virtually every 3278/79 feature is offered by one or more of these packages; this is a matter of selecting the combination that best answers needs. Of course, an important part of any purchase is making sure the product does what it says it will do. The manufacturing quality for each of these boards is quite high, as might be expected in a maturing micro-computer hardware market. IBM has set high standards, and because they are being met so boldly by third party vendors, users may select from among many quality products, such as the packages in this field. 

*Techland Systems' BLUELYNX 3270 will be reviewed in an upcoming issue.*

*Roger Addelson is the assistant director of academic computing at Loyola University in Chicago. He holds a bachelor of science degree in system science.*

**Attachmate 3-N-1 3270 COAX Adapter:**  
\$1,195  
Attachmate Corporation  
3241 118th SE  
Bellevue, WA 98005  
206/644-4010  
CIRCLE 309 ON READER SERVICE CARD

**FORTE PJ (3278/79): \$1,195**  
CMS/TSO file-transfer package per CPU:  
\$1,000  
Corporate license: \$5,000  
Forte Data Systems  
2205 Fortune Drive  
San Jose, CA 95131  
800/233-3278; 408/945-9111  
CIRCLE 311 ON READER SERVICE CARD

**IBM 3278/79 Emulation**  
Adapter: \$905

**IBM Corporation**  
P.O. Box 1328  
Boca Raton, FL 33429-1328  
Contact the local IBM dealer;  
800/426-2468  
CIRCLE 312 ON READER SERVICE CARD

**IDEAcomm 3278: \$995**  
IDEA Associates, Inc.  
35 Dunham Road  
Billerica, MA 01821  
617/663-6878  
CIRCLE 313 ON READER SERVICE CARD

**IRMA 3270 board: \$1,195**  
Digital Communications Associates, Inc.  
1000 Alderman Drive  
Alpharetta, GA 30201  
404/442-4000  
CIRCLE 314 ON READER SERVICE CARD

**LINKUP System Coax: \$495**  
ITI—Information Technologies, Inc.  
7850 E. Evans Road  
Scottsdale, AZ 85260  
800/431-3460; 602/998-1033  
CIRCLE 315 ON READER SERVICE CARD

**PCOX/PLUS: \$1,145**  
CXI, Inc.  
3606 W. Baysshore Road  
Palo Alto, CA 94303-4229  
800/225-PCOX; 415/424-0700  
CIRCLE 310 ON READER SERVICE CARD

**Persyst/Emulex COAX/3270: \$1,095**  
Emulex Corporation  
3545 Harbor Blvd.  
Costa Mesa, CA 92626  
714/662-5600  
CIRCLE 316 ON READER SERVICE CARD




# Diary of an

I traded my 16K machine and all those disks for Lotus® 1-2-3 and 256K. And immediately got the urge to merge. I started by merging regional statements in Maine. But before I could get to Iowa, I ran out of gas.

At 512K, I discovered what the coordinates IV169 looked like. I was so far out there it felt like I was walking on the moon. It didn't take long to find out 512K was nothing more than a walk around the block.

640K! Loads of space until I fell in love with integrated software and was back to cutting up files again. Sure, the other functions make my worksheet more persuasive, but I'm back to slugging in and out disks. Shades of 16K.



Old war stories of how you fought your way up through the memory ranks are great to remember as long as you don't have to relive them. And you don't.

Thanks to one incredible breakthrough. Above™ Board PS.

Above Board is the memory board that drove the Lotus®/Intel/Microsoft® expanded memory specification, Infoworld's 1985 Peripheral Product of the Year.

From Intel. The company that has driven more standards than all of the other chip shops put together.

Above Board PS has the parallel and serial ports, clock, print buffer, and RAM disk you'd expect from a conventional multifunction board.


But why buy a conventional board when Above Board PS can take you from 256K all the way to 1.5 megabytes in one fell swoop, without even pausing for a breath at 640K.

So you don't need to hot-wire your way to the top anymore. With Above Board PS, the split worksheet is history. The new norm is windowing, pop-ups, and



# overachiever.

I'm on my way to 1.5 MB and I'm not looking back. Monster spreadsheets, killer models, Microsoft® Windows, and all kinds of pop-up utilities so I can juggle a bunch of balls at once.



RAM speed on everything—even databasing and word processing.

The second-biggest difference between Above Board PS and conventional multifunction boards is the unconventional warranty on it. Five years instead of the usual two.

Ease of installation is nothing to sneeze at either. Its software installs with as few as three keystrokes. It even intelligently customizes your memory allocation.

Above Board PS is part of a family of products

for the IBM PC, XT, AT and compatibles.


You can buy them at your favorite computer store. Or call 800-538-3373 for the names of dealers near you.

And re-write the book on overachieving.

Help for the overachiever.

**intel®**





# Expandable Memory

TED MIRECKI

When applied to computers, Parkinson's first law—"work expands to fill the time available for its completion"—translates into "work expands to exceed the available memory." When the IBM PC was announced, its specifications called for up to 256KB of memory. At the time, this seemed more than adequate, but IBM soon admitted that this was an artificial limit and that, in fact, 640KB was quite possible. Certainly no one would dream of using any more memory than this.

Then along came resident utilities, spreadsheets, integrated software pack-


ages, and, above all, task-switching systems such as TopView and Windows that began pushing at the 640KB limit. The PC/AT promises relief from this problem in the future, but until the debut of an operating system that runs in protected mode, that remains only a promise. In the meantime, the several million PCs and PC/XTs are stuck with "only" 640KB. Or are they?

To illustrate how the PC's memory space can be expanded, consider the memory map shown in figure 1. The 8088 processor has the capability to address up to 1MB of memory with hex

addresses of 00000 to FFFFF. For this discussion, this megabyte space is defined as a collection of 16 segments of 64KB each. Individual segments are identified by the high-order hex digit of the address of any byte within that segment. Thus, addresses between 00000 and 0FFFF are in segment 0, those between 10000 and 1FFFF are in segment 1, and so on up to segment F. When the memory is populated with 64KB chips, each segment is implemented as one bank of nine chips.

In its infinite wisdom, IBM decided that 640KB, or the ten segments 0





*The Expanded Memory Specification provides a standard bank-switching approach for developers to follow when they are creating software for PCs with expanded memory; two primary hardware implementations of the EMS are tested.*

through 9, would be all that users would ever need. The remaining segments A through F were reserved for system use. Initially, only segments B and F were accounted for: B for video memory, F for ROM containing the BASIC interpreter and the system BIOS. Gradually, the other segments also were assigned functions. Segment C received the hard-disk BIOS, segments D and E became the home of the PCjr's ROM cartridges, and segment A was assigned to the IBM Enhanced Graphics Adapter (it was always reserved for additional video memory). The system scans

addresses C8000H through E0000H during the power-on self test for additional valid ROM modules. These could originate from adapter boards including the EGA or a network.

Contrary to widely disseminated wisdom, the limit of 640KB did not arise from any inherent limitation of DOS, but from IBM's design choice to lay claim to the top 384KB of the address space. On a system without an EGA, it is possible to add RAM in segment A, run a utility to tell DOS of the new memory size, and compute with all 704KB under DOS control (the TI Pro-

fessional, an MS-DOS machine, is designed this way). Furthermore, if IBM had put the video memory into segment E instead of B, then a system without a hard disk could be loaded with up to 896KB (14 segments, 0 through D). The only requirements for DOS memory are that it be contiguous and not populated with ROM chips.

The seemingly haphazard sprinkling of video memory and ROM code throughout segments A through F, however, does not leave enough contiguous memory to make a useful addition to system memory. The solution is to use



## EXPANDABLE MEMORY

bank switching, a technique long used by Apple and CP/M systems to overcome the 64KB limitation inherent in their microprocessors. Bank switching is not new to the PC; for some time boards have been available with up to 2MB, as has software that runs RAM drives and print buffers outside of the normal 640KB address space (see "Enhancement by JRAM-2," Don Awalt, *PC Tech Journal*, March 1985, p. 92).

The problem with bank switching is that, in order to make use of extra memory, programs must be specially written for a particular switching scheme, including the location, size, and number of page frames. Heretofore, no one scheme has been popular enough to attract widespread software development. The Lotus/Intel/Microsoft Expanded Memory Specification (LIM EMS) promises to change that, however. EMS has attracted so much attention not because it is a technological breakthrough, but because Lotus Development Corporation (the maker of Lotus 1-2-3 and Symphony), Intel Corporation (the manufacturer of microprocessor ICs for the PC and AT), and Microsoft (the developer of DOS), have enough clout to impose a standard that many software developers can be expected to follow. Even without IBM, these three companies represent the major forces in hardware and software in the PC world. IBM's attitude toward EMS is not known, but its pact with Microsoft for the joint development of any future operating systems is a hopeful sign that IBM does not have overt plans to torpedo the EMS efforts.

EMS was developed jointly by Lotus and Intel; Microsoft joined in later. Microsoft's interest bodes well for the incorporation of the standard into future versions of the operating system. At Microsoft's request, the latest version of the specification (version 3.2) has been enhanced to facilitate its use at the operating system level.

The LIM EMS has attracted not only support from software developers, but competition from hardware vendors as well. AST Research, Quadram, and Ashton-Tate have jointly issued their own specification (AQA EMS), which claims to be a superset of the LIM specification that offers the user more capabilities. Enhancements often have been the death of standards, but the LIM and AQA entries may be sufficiently compatible to coexist.

The compatibility of the LIM and AQA specifications has been improved in version 3.2. The primary incompatibility resides in the different hardware



The boards can have various memory configurations. Above, left to right: the AST RAMpage! PC version, AT version, and Intel's Above Board.

designs of the boards. But direct access to the hardware is no longer necessary, and applications may make full use of expanded memory using only the software interface that is common to both. If an AQA EMS board and its software faithfully implement that interface, they should support applications written for the LIM specification, provided the application is well-behaved according to the rules of the base specification. The converse, however, is not true: applications written specifically for the capabilities provided by the AQA specification will not run on an LIM board. Theoretically, the AQA version is more flexible, allowing better integration with the operating system, but the preferred version will be the one ultimately to run more EMS applications.

Either version of the EMS is applicable to both the PC and the AT, because it is implemented in the first megabyte of address space accessible to both machines. Why does the AT, which is inherently capable of addressing up to 16MB in hardware and several gigabytes through software, need a bank-switching scheme? Until an operating system becomes available to manage those megabytes, application programs must manage them on their own. Several possibilities exist for doing that, and some ways may be incompatible with others in coresident and multi-tasking implementations. In other words, standards are needed here just as they are for bank switching. If memory is to be extended beyond that con-

trolled by the operating system, the bank-switching approach has the advantage of being applicable to the large installed base of PCs.


An important point to note here is the distinction made by the EMS between different types of memory. It uses the following definitions, the first and second of which follow IBM's usage. *Conventional*, or *normal*, memory is the 1MB of linear address space accessible to the PC and the AT in real address mode. This is subdivided into user memory (up to 640KB) and system memory. *Extended* memory is the linear memory between 1MB and 16MB accessible in the AT's protected address mode. The EMS is not concerned with this memory. *Expanded* memory is the paged memory implemented through bank switching, as described in the EMS specifications.

Extended memory boards have been available for the AT since its introduction, but besides RAM disks, print buffers, and the XENIX operating system, not much software exists to take advantage of them. Expanded memory boards for both the PC and the AT are now available, as is the applications software that uses them. For the AT, expanded memory boards typically provide both extended and expanded memory. The most flexible approach, implemented on some of the newer boards, is to allow switching between the two types of memory with software control rather than by hardware switches. This approach could allow the

PHOTOGRAPH • PETER FORBES/BLAKESLEE LANE




**FIGURE 1: PC Memory Map**



The first 640KB of system memory is reserved for user RAM. The additional six segments of 1MB of addressable memory that DOS can address are reserved. However, gaps often occur that can be used by expanded memory boards.

**FIGURE 2: The LIM EMS Implementation**




The Lotus/Intel/Microsoft EMS allocates four contiguous page frames (of 16KB each) in a vacant area of segments C through E. The expanded memory page is then viewed in one of the page frames.



# BUSINESS SYSTEM 286

*33% Faster than IBM's Powerful PC AT*



**SYSTEM 286  
STARTING AT  
\$1995.<sup>00</sup>**



## THE ALR SYSTEM 286

The ALR System 286 is based on the advanced 80286-8 16 bit microprocessor with a system clock rate of 8MHz. This performance results in running most IBM® PC or XT software up to 350 % faster: In seconds you'll be able to recalculate large spreadsheets and instantly load files.

Compatibility by Design. At Advanced Logic Research, the System 286 was designed to be 100 % IBM PC AT bus compatible with full attention paid to the BIOS ROMs resulting in total support of IBM DOS 3.0, 3.1 and Xenix™ operating systems.



## 2MEGA BYTE USER MEMORY

The System 286 CPU Board can be expanded to a full 2 megabytes of parity checked user memory. This saves you valuable expansion slots and reduces your total system cost. With the addition of the award winning ALR Challenger you will be able to expand your total system memory to an incredible 15 megabytes.

# WITH FULL DEALER SUPPORT

**CONTACT ALR FOR INFORMATION ON A DEALER NEAR YOU!**

XENIX™ is a registered trademark of MicroSoft Corporation  
IBM® is a registered trademark of IBM Corporation

# ALR

**ADVANCED LOGIC RESEARCH, INC.  
2991 E. WHITE STAR AVE.  
ANAHEIM, CA 92806  
(714) 666-2951**

CIRCLE NO. 104 ON READER SERVICE CARD



## EXPANDABLE MEMORY

EMS boards to become extended memory boards when a new operating system becomes a reality.

Two boards that implement the EMS, from Intel and AST, both involved in developing the specifications, will be evaluated later in this article with associated software; Lotus Symphony version 1.1, will provide an example of an EMS application. Other boards supporting the EMS are listed in an accompanying sidebar. They were not reviewed by *PC Tech Journal*.


### EMS DETAILS

The EMS is embodied in a specification document, available free of charge from any of the three participating companies. The document defines the functions provided by the expanded memory software and describes how to write programs that use expanded memory. Functional descriptions of the hardware and the low-level, bank-switching procedures (meant for hardware vendors), once part of the specification, have been removed from the current revision (version 3.2). The document consists of 80 pages written in the style of the *DOS Technical Reference* manual. It does, however, include more explanations and program examples than the DOS book. The layout could use improvement, but generally the information should be clear to the experienced assembly language programmer.

The EMS supports four memory boards, each with 2MB, for a total of 8MB of expanded memory. This memory is organized in pages of 16KB, with up to 128 pages per board. The LIM version has four contiguous page frames, allowing access to 64KB at a time (see figure 2). The base page frame is assigned, either by hardware or software switching, to an address in segments C, D, or E. This address must be on a 16KB boundary and at the beginning of a 64KB block free of other memory (ROM or RAM). So the first requirement for using the EMS is the availability of 64KB contiguous bytes in the system's ROM space. Even a system with every conceivable ROM-driven accessory leaves this much free, but memory boards that populate segments D and E with RAM for use by RAM drives and print buffers may cause a conflict.

The AQA EMS has 64 page frames instead of four (see figure 3). The first four are assigned to a contiguous 64KB block in the ROM space, then additional frames are assigned to all remaining, though not necessarily contiguous, 16KB blocks in segments A through E. Addresses in segment B not used by


**FIGURE 3:** *The AQA EMS Implementation*



The AST/Quadram/Ashton-Tate EMS conforms with the LIM EMS in that the first four page frames are the same as the LIM specification, although additional page frames can be allocated in any other unused 16KB block of memory.



# KNOWLEDGE man/2<sup>®</sup>



## LETS YOU GET TODAY'S WORK DONE ... AND PLAN FOR TOMORROW



KnowledgeMan/2, the most advanced business software available, lets you be more

productive than ever before and in less time. These powerful business capabilities, tightly fused into a single program, work together for you:

- ☐ Relational data management
- ☐ Spur-of-the-moment inquiry
- ☐ Spreadsheets
- ☐ Statistical analysis
- ☐ Forms management
- ☐ Programming language
- ☐ Options for creating graphs, processing text, generating reports, painting forms, mouse processing and remote communications.

KnowledgeMan/2's four user interfaces make it easy for you... and all your business people... to work with KnowledgeMan/2:

- ☐ Menus, help screens and easy-to-use documentation guide your every step, if you're just beginning.
- ☐ Direct commands for the power user, with help available when you want it.
- ☐ K-Chat, the optional natural language interface, for asking for information in plain English.
- ☐ Procedural programming for the advanced user.

Get KnowledgeMan/2 working for you today. And start planning for tomorrow.

KnowledgeMan/2 is available for IBM PC, XT, AT and compatibles with PCDOS, 16-bit micros with MSDOS or CP/M-86. Special versions are available for UNIX multi-user operating systems and IBM, 3Com and Novell Local Area Networks (LANs).

For the name of the KnowledgeMan/2 dealer near you, call or write Micro Data Base Systems, Inc./ Marketing & Sales, P.O. Box 248, Lafayette, IN 47902. 317/463-2581, Telex 209147 ISE UR.

KNOWLEDGE  
man/2<sup>®</sup>  
THE UNIVERSAL KNOWLEDGE MANAGEMENT SYSTEM



## EXPANDABLE MEMORY

video memory also are used for page frames. Furthermore, if any holes exist in the memory below 640KB, then more page frames also are assigned there. In practice, these will be assigned in multiples of four, because memory on the PC and AT is almost always populated with banks of 64KB.

The 64 registers allowed by the AQA specification never can be used all at once, because each register must be associated with a 16KB block of conventional memory that is free of RAM and ROM. Because 64 blocks of 16KB each exist in the conventional memory space, 64 page frames would be possible only if the system were left with no memory. The maximum number of page frames in a practical system (256KB of conventional RAM, color/graphics adapter, no hard disk, and no EGA) is 42.

Both the AQA and LIM specifications call for implementing the frame registers as four I/O ports. In the AQA version, a fifth port, called the map control register, is used to specify which 4 of the 64 registers appear in the I/O space at any given time.

The bank-switching functions themselves are performed by a program called the Expanded Memory Manager (EMM). The basic concept of bank switching is familiar to anyone who has ever installed a memory expansion card in a PC. Before the card is plugged into the system board, switches must be set so that the banks of memory chips appear in the proper places in the PC's address space. Usually, the entire memory on the board is permanently switched immediately above the memory already present in the system.

A bank-switching arrangement extends this concept by allowing only a portion of the memory to be switched into the system address space. A set of switches controls which portion is addressable at any given time. These bank switches (also known as *page registers*) are controlled by a running program. A switch that can be set by software is nothing more than an I/O port.

The total memory addressed at any one time by the microprocessor is no more than 1MB, but a portion of that memory, say 16KB or 64KB, can be used as a window into a much larger memory space. The portion of extra memory visible at one time is called a *page*, and the area within the processor's memory space where it appears is a *page frame*. The page frame may be at any address not otherwise populated by ROM or nonswitched RAM. Inactive pages, those not currently in the page frame, are not addressable by the sys-

**TABLE 1:** *The EMM Functions*

FUNCTION NUMBER	INVOCATION NUMBER	DESCRIPTION
1	40H	Get EMM status.
2	41H	Get the segment address of page frame 0.
3	42H	Get the total number of expanded pages and the number of available (not allocated) pages.
4	43H	Get an "EMM handle" (process ID) and allocate a set of pages to it.
5	44H	Map an expanded memory page into one of the page frames.
6	45H	Close an EMM handle and deallocate pages.
7	46H	Get the EMM version number.
8	47H	Save the current status of the EMM mapping registers (at entrance to a resident routine).
9	48H	Restore the status of the EMM mapping registers (at exit from a resident routine).
10	49H	Reserved. (Get I/O port addresses of the mapping registers.)
11	4AH	Reserved. (Get mapping of a handle's pages to physical page numbers on the EMS board.)
12	4BH	Get the total number of active EMM handles.
13	4CH	Get the number of pages allocated to a specific handle.
14	4DH	Get an array of page counts allocated to each handle.
15	4EH	Save, restore, or swap the EMM status for all handles (operating system task switch).
33	5AH	(AQA EMS only). Get an array of all page frame addresses above the user memory space.

The Expanded Memory Manager for the LIM EMS has 15 functions, which are shown here with their invocation numbers and an explanation of their use. Function 33 is included in the AQA EMS only.

tem, but the board on which they are mounted keeps them powered and refreshed to conserve the contents.

The significant feature of bank switching is that the contents of a memory page need not be copied into the page frame, either by the processor or by a DMA channel. A page appears in the frame as the result of writing a single 8- or 16-bit value to an I/O port. This makes bank switching even more efficient than a RAM disk, because with a RAM disk, data must be physically copied as if they were being input from external storage.

The EMM is installed at system boot time as a DOS character device driver, but it implements only two of a driver's functions: initialization and status reporting. Applications using the EMM request all other functions not through DOS function calls, but through interrupt 67H. Therefore, a requirement for using the EMS is that no other program use this interrupt. Use of this interrupt number is not a good choice, because this series of interrupts

is meant for applications, not utilities performing low-level functions.

The functions performed by the EMM are listed in table 1. One of the problems with the readability of the specification document is that the functions are identified by number as given in the table, but the values that are placed into the AH register to invoke each function are different (40H for function 1, 41H for function 2, etc.). The function numbers are displayed at the top of each page, but the invocation values are buried in fine print.

Some functions are holdovers from the previous version, left to maintain compatibility with applications written for the earlier implementation. For example, the Get Status function is no longer useful, because it tests whether or not the EMM was busy servicing a previous request. The current version is partially reentrant and partially noninterruptible, so it never returns a busy status. This makes it more readily usable by both interrupt service routines and multitasking operating systems.





## MAKE THE CONNECTION . . .

Our **Connection** systems will solve your problem of trying to read and write diskettes or tapes from almost any computer system using your PC.

The **Diskette Connection** is a hardware system that enables the IBM PC or compatible to read and write most 8 inch, 5¼ inch, or 3½ inch diskettes.

With our **File Connection** software programs you can transfer data files between most computer systems, including CP/M, DEC, Honeywell, Univac, IBM 3740, S/1, S/3, S/23, S/32, S/34, S/36, and S/38.

Our **Word and Typesetting Connection** programs use IBM standard Document Content Architecture (DCA-RFT) to transfer document files between most word processing and typesetting systems, including Compugraphic MCS, CPT, Displaywriter, OS/6, Multiset, NBI, Quadex, Xerox, and Wang.

Our **Tape Connection** system will read and write IBM or ANSI standard ½ inch 1600 BPI magnetic tape. A full size 2400 foot tape can store a 45 MByte file and be written in 6 minutes.

Since 1982, we have supplied thousands of systems to customers around the world, including IBM, NASA, AT&T, Kodak, and General Motors.

Our specialty is conversion systems and we can provide a solution to your problem. Call us today to discuss your requirements.

*This ad is one of a series featuring NASA missions. For a free poster, send us your written request.*

**Box 1970 Flagstaff, AZ 86002  
(602) 774-5187 Telex 705609**

CIRCLE NO. 229 ON READER SERVICE CARD

## . . . FLAGSTAFF ENGINEERING



## EXPANDABLE MEMORY

The use of the EMM functions is best illustrated by the following sequence of operations that a nonresident application program would use in order to access expanded memory. These operations do not include the AQA enhancements.

1. Determine if the EMM is installed.  
Two methods for doing so are outlined in the specification: opening the EMM device and inquiring as to its status, or looking for the device name at a fixed offset in the segment pointed to by the INT 67H vector. If the EMM is not available, the program may either terminate with an error message or continue execution in normal memory mode.
2. Function 7 determines the EMM version number to ensure compatibility with the program's requirements.
3. The total and unallocated pages of expanded memory can be determined with function 3.
4. Function 2 determines the base address of the page frames. The returned value is the segment address of page frame 0; the paragraph addresses of page frames 1 through 3 are at base plus 400H, 800H, and C00H, respectively.
5. Function 4 is used to allocate a number of pages to the program. The function returns an EMM *handle*, or identifier, for the set of pages allocated. (This terminology was added by Microsoft to version 3.2. Previously, this was called a *process ID*. The specification recommends that a program call this function once, to obtain as much memory as it needs, but nothing prevents it from calling it repeatedly to obtain more memory as needed. Each invocation returns a new handle number.
6. Function 5 maps an expanded memory page into one of the page frames. This function would be used most often in the course of execution. Pages are referenced by handle and page number within the handle. Memory within each mapped page may then be accessed by an offset from its own frame base (16KB maximum) or from the base of frame 0 (64KB maximum). When a new page is mapped into a frame, the contents of the page previously residing there are inaccessible but not lost.
7. The program must keep track of which page (and which handle, if there is more than one) contains which data. Ordinarily, tables that are in normal memory are used to point to the page locations of data in expanded memory.

8. At termination, function 6 is used to deallocate the pages for each handle obtained by the program. Pages are not freed automatically and remain unavailable to subsequent programs unless specifically deallocated.

The contents of expanded memory are not restricted. Both data and programs may be stored there, and programs may be executed from expanded memory, provided that they are appropriately written to perform the page swapping when references cross page boundaries. However, the DOS loader (which is the EXEC function) will not load a program into a page frame in the ROM space; a customized loader has to be written.

The EMM may be used by resident programs such as DOS device drivers, RAM drives, print buffers, and taskswapping utilities of the TopView type. A resident program could allocate a set of expanded memory pages at installation time, following the procedure outlined in steps 1 through 4 above. It could even load part of its code into expanded memory, so that it does not take up space in normal memory.

**T**he EMM may be used by resident programs such as DOS device drivers, RAM drives, print buffers, and taskswapping utilities of the TopView variety.

Two functions, 8 and 9, are provided especially for use by resident programs. When a resident program is invoked, the portion residing in normal memory saves the EMM state (using function 8) because the invoking program also may be using the EMM. Once the state is saved, the page set of the resident program is mapped into page frames. Data then may be moved to and from expanded memory, or a branch may be taken to code in expanded memory. Before exiting, the resident program restores the state (using function 9) so the invoking program may resume. Thus, the use of the EMM by interrupt-driven utilities is transparent to the programs requesting their services, because the contents of the page frames are the same before and after execution of the interrupt.

The area where the status information is saved is not addressable by programs. The number of save areas per EMM handle—therefore the number of times each process may be reentered—is not stated in the specification.


Function 15 provides a more comprehensive save/restore capability. It saves in program memory the mapping information for all EMM handles, not only for the one that is currently active. This function was added in version 3.2, presumably at Microsoft's request, and is meant to implement task switching in future multitasking operating systems. It can be useful even under current versions of DOS, however. For example, by allocating the save area on a stack, a program using function 15 could be made reentrant.

The two reserved functions 10 and 11 provide lower level access to the mapping hardware. Using them, any expanded memory page can be pulled in, regardless of its allocation to any process, bypassing the memory management functions of the EMM. These two functions were placed on the reserved list in version 3.2 because they are incompatible with the new support for resident programs and multiple tasks, but they are maintained for compatibility with programs adhering to version 3.0 of the specification. Such programs, however, might not coexist with those that take full advantage of the status-switching functions.

Functions 12, 13, and 14 are meant for EMM maintenance and for utilities that report on expanded memory usage. They are useful with boards that allow switching memory between expanded and extended modes, disallowing the switch when expanded memory already has been allocated.

Function 33, available only in the AQA enhanced EMM, fills a memory array with the addresses of all page frames above the 640KB user area. The first entry in the array points to the same address as returned by function 2, and the first four are guaranteed to point to the contiguous block that is the equivalent of the four page frames defined by LIM. The addresses of any page frames in user memory below 640KB are not returned, but they may be determined by manipulating the map control register and reading the various page registers. Because direct access to the hardware is not recommended by the current EMS specification, some manufacturers are developing functions to provide software access to the lower page frames. The significance of allocating page frames in user memory is that,





# Alloy's Streamliner Series. The best protection for your company's past, present, and future.

The best protection for your personal computer data storage needs is available today. From Alloy. Choose tape only. Or combined disk and tape. Either way, the Streamliner Series provides the performance you expect from the leader. At a remarkably affordable price.

Alloy's FT-60 streaming tape back-up subsystem gives you up to 60Mb storage capacity and high-speed data transfer. The SL-60 models give you the same high quality tape unit *plus* integral hard disk. And you can choose 20Mb or 41Mb formatted data capacities.

With Alloy's Streamliner Series, you'll get the best protection for your company's past, present, and future. So call Alloy today at (617) 875-6100.

**ALLOY**  
Computer Products, Inc.

100 Pennsylvania Avenue, Framingham, MA 01701 (617) 875-6100, TWX 710-346-0394  
In Europe: ALLOY Computer Products (Europe) Ltd., Cirencester, Gloucestershire, England. Tel.: 0285 69571 Telex: 43340

CIRCLE NO. 108 ON READER SERVICE CARD



potentially, this memory could be managed by DOS. Therefore, these new functions will be intended for use by the operating system, because applications should not perform bank switching of memory that could be under DOS control.

One potential problem with the AQA specification is the assignment of page frames in segment B, the one reserved for video memory on monochrome and color/graphics adapters. When expanded memory is mapped into these page frames, programs that test for the existence of a particular adapter by writing to this memory will fail, possibly crashing the system, or worse, damaging a monochrome monitor. One example is the DOS MODE command. AST's RAMpage! board (which is reviewed below), however, allows for excluding specified blocks of memory from the page mapping.

The EMS functions are obviously meant primarily for assembly language programming, but expanded memory can be used from a high-level language. The compiler must provide two capabilities: the ability to issue software interrupts (either directly or via an interface to assembly language routines) and the use of far pointers to any address in the 1MB conventional address space. Turbo Pascal and Lattice C provide these services; BASIC could be used with some arcane programming tricks.

### FIRST IMPLEMENTATION

Intel's Above Board was the first hardware implementation of the EMS. It is a full-length board containing memory only (no ports or clock), with sockets for eight banks of chips. When populated with 256KB chips, that adds up to 2MB. It also may be filled with 64KB chips for a total of 512KB.

Two versions of Above Board are available—one for the PC and one for the AT. Above Board PC does not allow mixing of 64KB and 256KB memory chips; a hardware switch must be set to indicate one or the other. Other switches specify the amount of memory on the Above Board and whether any part of this memory is to be used to fill out the normal memory space to 640KB. The system must have at least 256KB already installed before Above Board can be added.

Above Board AT can fill out normal memory to 640KB (provided the system starts out with 512KB) and can provide both expanded and extended memory in a variety of combinations. The combination must be set by switches at the time of installation and may not be

changed by software. The board may be populated with a mixture of chips, but the only valid combination is 64KB chips in the first two banks and 256KB chips in all others—and then only if 128KB of normal memory is being added to the system. For some reason, even if two Above Boards are installed in an AT, the system is limited to 6.5MB of extended memory. Up to 8MB of expanded memory, however, can be added on both the PC and AT.

The AT version of Above Board can accept an optional piggyback board that doubles the memory to 4MB; the PC version does not have this option. The add-on board is, in effect, a second board with its own switches for memory size and port addressing. The advantages are that it saves a slot and is less expensive than a second board; nevertheless, it is a tight fit in the AT's close slot spacing.

With the exceptions of the above-mentioned differences, the boards for the PC and AT are functionally identical,

*One potential problem with the AQA specification is the assignment of page frames in segment B, the one reserved for video memory on both monochrome and color/graphics adapters.*

and all descriptions that follow apply equally to both.

The page registers are implemented as eight I/O ports, but they take up only two port addresses in the PC's I/O space. How this bit of magic is accomplished is explained in an accompanying sidebar. The ports are addressed at 2x8H and 2x9H, where x is any hex digit set by the user on four switches. Some of these 16 possibilities represent addresses already reserved by IBM, and the manual lists seven recommended settings in order of increasing probability of conflict with other devices. If more than one board is used in a system, each must have the page registers at a different address.

The address at which the page frames appear need not be set by switches; this is specified by a parameter on the DEVICE statement in the

CONFIG.SYS file. As described below, this line is added to CONFIG.SYS by the installation program, but it may be changed by the user.

Installation is no more difficult than for a normal memory board, although the documentation could stand some improvement. The program disk that is supplied by Intel contains an installation program, the EMM.SYS device driver, and two versions each of RAM disk and print buffer programs. The 107KB installation program needs to be run immediately after installing the hardware. It is entirely menu driven. It presents a list of most commonly used software (1-2-3, Symphony, Framework, dBASE, WordStar, among others) and suggests recommended memory configurations for several combinations of these applications. In addition, the user may specify exactly how to divide up the available memory between RAM disks, print buffers, and program memory. The end results of the installation process are new CONFIG.SYS and AUTOEXEC.BAT files, with appropriate lines added. The former contents of these files are maintained.

In addition, the installation program determines the location of the page frames in the system's ROM space and checks that the port addresses set on the board's configuration switches are indeed free of other devices. The page frames are placed on a 16KB boundary at the lowest available 64KB block in the range C400H through E000H on the PC, and C000H and D000H on the AT. The installation process must be repeated if new adapter cards containing ROM code or I/O ports are added to the system.

The EMM.SYS device driver provides all the expanded memory functions through interrupt 67H. It occupies a very reasonable 4KB of memory and adds what seems to be an interminable 26 seconds to cold-boot time, but only an insignificant 3 seconds to the keyboard reset time (provided that short diagnostics are requested by the appropriate command line parameter).

Intel's EMM implements one save area per process for the save and restore functions (numbers 8 and 9). A program that uses these functions cannot be reentrant, but with the availability of function 15, this is not necessarily a major problem.

Two bugs were discovered in Intel's implementation of EMM function 14, which fills an array with all active EMM handle numbers and the number of pages allocated to each. These have been confirmed by Intel, which is offer-



# **SIM3278/PC**

## **A MICRO-MAINFRAME CONNECTION IN A CLASS OF ITS OWN**

### **Data Decisions Gives SIM3278/PC High Marks**

*\*Data Decisions reviewed and evaluated SIM3278/PC, giving it high marks for **User Interface, Ease of Use and Systems Interface**. Their conclusion: "Simware has demonstrated an understanding of the user's need to maximize productivity gains possible with computers."*

*Using inexpensive asynchronous or X.25 network communications, SIM/PC provides you with advanced features such as error free file transfer, printer support and an intelligent command processor. "Unlike many communications packages that present primarily a menu-driven user interface, SIM/PC's command language is a very powerful enhancement over simple 3270 emulation."*

*SIM/PC eliminates the need for expensive add-on boards and gives you the most flexible micro-to-mainframe link available.*

*A corporate license entitles you to make multiple copies of SIM/PC without paying any additional per copy price every time another PC is added to your network.*

**CALL TODAY FOR A FREE EVALUATION SYSTEM AND JUDGE FOR YOURSELF.**


## **SIMWARE**

**a practical approach to communications**

14 Concourse Gate, Ste. 100  
Nepean, Ontario K2E 7S6  
(613) 727-1779 Telex: 053-4130  
Toll Free: 1 (800) 267-9991

Distributed in Europe by:  
The European Software Company

\* Source: recent analysis by  
Data Decisions on Product  
Quality Ratings for SIM3278/PC.



SIM3278/PC is a trademark  
(pending) of Simware Inc.



## EXPANDABLE MEMORY

ing a new release to current owners. First, if no processes are using the EMM, then the function returns a non-zero process count (the array is not written to). The true length of the array must be determined by function 12, which returns only the active process count and works reliably. An alternative method of obtaining the correct count is to clear register BX to 0 before invoking the function call.

Second, function 14 does not clear the direction flag before filling the array, so if the flag is set when the function is invoked, the array is filled backwards from the specified starting address, destroying the contents of the preceding memory. Programs must clear the direction flag with the CLD instruction before invoking this function.

The RAM disk program is supplied in two versions, for systems with and without expanded memory. Both are implemented as DOS device drivers. The resident portion is less than 800 bytes, comparable in size to DOS's VDISK. QUIKMEM, as Intel calls it, is not as flexible as VDISK, because the disk parameters are not under the user's control. The sector size is fixed at 512 bytes, and the maximum number of root directory entries is always 128. The number of sectors per cluster (allocation unit) is one for RAM disks up to 1MB, and two thereafter. These values are reasonable for RAM disks of more than a megabyte, but they waste space for smaller sizes. Generally, QUIKMEM works well, but VDISK is preferred for RAM disks in normal memory or on an AT with extended memory.

The print buffer program, QUIKBUF, also comes in different versions for systems with and without expanded memory. Both are resident programs installed by a DOS command or from the AUTOEXEC.BAT file, not from CONFIG.SYS; the resident size in normal memory is a fat 10KB to 11KB. QUIKBUF takes over the print screen interrupt. When Shift-PrtSc is pressed, a printer control menu appears on the bottom two lines of the display. It offers the choice of pausing, resuming, or canceling printing, resetting the printer, ejecting a page, or printing the screen. In the last case, the original contents of the screen are printed, not the menu. However, if printing is in progress when a screen dump is requested, the screen is not queued at the end of the buffer, but printed immediately, set off by blank pages.

On systems with more than one printer, the buffer is not assigned to a printer at installation. It becomes asso-

ciated with the first printer to which output is sent, but screen dumps are always sent to LPT1.

QUIKBUF has several problems. Some are merely annoying inconveniences: the menu requires pressing the Enter key even though the menu choices are single digits; the length of text waiting to be printed cannot be determined; and in BASIC's SCREEN 1, the menu is almost unreadable.

More serious is that in most cases the buffer does not accept output when the printer is off-line; this should be one of the major functions of this type of utility. The only program that succeeded in sending output to a dead printer was IBM's Professional Editor. All other attempts (the DOS COPY command, Lotus spreadsheets, and several word processors) failed with "Printer not ready" errors.

QUIKBUF's worst flaw is that, at installation, the type of display adapter must be specified as a command line

**I***nstallation of Above Board is no more difficult than it would be for a normal memory board; however, the documentation could stand some improvement.*

parameter: monochrome, CGA, EGA, Hercules graphics card, or other. In the last case, the menu is not available. The documentation warns that physical damage to the monitor may result if the wrong type is entered. This is unacceptable, because forgetting the extra parameter is too easy (remember, QUIKBUF may be installed interactively from the DOS command line, not only from a batch file). Many programs present pop-up menus (SideKick, ProKey, Spotlight) without being told the type of monitor and without endangering the hardware. Above Board users would do well to obtain another print buffer program that supports EMS.

The contents of the Above Board documentation indicate that Intel is new at marketing to consumers and does not know its audience. For example, the manual states, "If you aren't familiar with RAM disks, attach a paper clip to this page and turn to Chapter 4. When you finish, turn back to this page." The

manual contains a lot of such chaff, which makes the significant information difficult to locate.

Another slim booklet, *Hacker's Guide to Installing the Above Board*, errs in the other direction: it is terse. It gives the experienced user useful information, such as no-nonsense instructions on setting configuration switches and how to set up the command line parameters without going through the installation menus. These parameters control the location of page frames, whether full or abbreviated diagnostics are performed on a keyboard reset, and the sizes of the RAM disk and print buffer. The information in the two booklets is certainly complete, but locating it is somewhat of a chore.

### ON A RAMPAGE!

Like Above Board, AST's RAMPage! is a full-length, memory-only board carrying up to 2MB of 256KB chips; 64KB chips are not supported. Given the intended use of this board and the fact that 256KB chips are more economical per byte than the 64KB variety, this is a reasonable design choice. Configuration switches may be set to fill out the normal memory to 640KB, regardless of the amount of RAM that has already been installed in the system.

The AT version is also limited to 2MB per board; no piggyback is available. It may be used to fill out normal memory and to add both extended and expanded memory in various combinations. Once set, the combination cannot be changed by software, but AST provides an alternative: a program that simulates extended memory (the memory addressable in the protected mode of the '286) in expanded memory.

Installation is simple, requiring only the setting of the starting memory address (to determine whether or not conventional memory is being added) and the address of the I/O ports. The port addressing is the same as on the Intel board: seven possibilities, each taking up two port addresses in the 1KB I/O space. No installation program is included, so the user must make the changes to CONFIG.SYS and .BAT files by following the instructions in the manuals or using the several examples provided on disk. Moderately experienced users will probably prefer this method because it provides more control over the available options.

The expanded memory driver, called REMM, takes up a whopping 33KB of memory. If installing Intel's driver adds a long time to the cold-start time, installing this one seems to add



Save \$150 to \$200 over Crosstalk Mk 4™ or Microsoft® Access™

# Introducing *BackComm*, the most powerful, easy to use background communication software, for only \$95

*BackComm* has a built-in command language (like dBase III®) for building communication programs. It can store over 34 million\* names and phone numbers that it can call automatically 24 hours a day. It squeezes, encrypts, or copies files—all from within *BackComm*. And, like Borland's SideKick®, it remains resident in background so it's always ready to communicate when you are.

*BackComm* is designed for communication for both the beginning or the most advanced user. The new user can get anywhere simply by selecting menus, while the advanced user can invoke any function with a single command.

## Works in Background

LaSalle Micro's *BackComm*™ background communication program remains resident in your computer's RAM memory. That means that while you are working on other programs, your computer can send or receive files. What's even more convenient, any time you want to use *BackComm*, simply press the "Alt-Break" key and you are ready to communicate in the active mode.

## Calls Automatically

If you're a busy executive, but you need to send or receive calls, you can use *BackComm*'s automatic call menu. *BackComm*, for example, can call Dow Jones News/Retrieval®, log on, get the stock information you're looking for, and log off, all automatically. Furthermore, *BackComm* can do it once a day, once an hour, or every 5 minutes—whenever you want.

If that's not enough, *BackComm*'s powerful command language can give you a warning when your stock goes above or below a certain value. And it will do all this while you're working on Lotus® 123™ or virtually any other program.

## Powerful Command Language

*BackComm* has a built-in command language called *BackTalk*™ that does for communications what dBase III's built-in language does for databases. The flexibility is unlimited. You can write templates that convert *BackComm* into an electronic mail program, or you can go all out and write a complete com-

munication program with *BackTalk*.

Companies can design *BackComm* to fit their specific communication needs with this powerful built-in communication language. And so can VADs and VARs. *BackTalk* will let you simplify the most complex communication procedure—whether it's downloading from a mainframe or sending a Telex.

## Error-Free Protocol

*BackComm* uses the universal standard XMODEM protocol, but it doesn't stop there. We have added the powerful and emerging new standard—X.PC. This new protocol allows you virtually error-free transmission or reception with other software using X.PC, as well as other *BackComm* users.

But X.PC offers more. Its most powerful feature is its ability to let you have multiple communication sessions. That means you can talk to two different stock exchanges at the same time—buying on one and

selling on the other. Imagine—electronic arbitrage! In fact, you can even have up to 8 separate sessions.

## Endless Features

There's not enough room to tell you all the features *BackComm* offers. You can store over 34 million names (DOS permitting) in a tree structured format. You can find any name, phone number, or address with *BackComm*'s built-in search command. You can keep track of the cost of every call on your screen and keep a log of all outgoing and incoming calls. And, without leaving *BackComm*, you can squeeze or unsqueeze files for lower cost transfer or even encrypt them for security.

## Lowest Cost, Best Value

*BackComm* has all of the features you'd expect in a \$250 to \$300 program, plus more. But we think that's too much to charge. So we decided to drop the price and go for volume. You can pay more for Crosstalk or Microsoft Access, but you won't get more.

*BackComm* is not copy protected for a simple reason—we are continuously adding to and improving the program. We'll be adding specialized electronic mail templates for MCI Mail, Easy Link,™ and other programs—all at a low price. (All of these additions will be built from our built-in language *BackTalk*.) For these additions, as well as the basic program enhancements, we believe everyone will want a registered version to keep up to date.

Order your copy now. Simply call  
**1-800-882-5171 Ext. 300**



and give us your VISA, MasterCard, American Express, or Diner's Club number. We'll send you your copy of *BackComm* immediately.

# LA SALLE MICRO

1350 Remington Rd, Suite W  
Schaumburg, Ill 60195

In Illinois, call 1-312-882-5171

## Dealer Inquiries Invited

*BackComm*, *BackTalk* and LaSalle Micro are trademarks of LaSalle Micro, Inc. Crosstalk and Crosstalk Mk 4 are trademarks of Microsoft, Inc. dBase III is a registered trademark of Ashton Tate. Microsoft is a registered trademark and Microsoft Access is a trademark of Microsoft Corp. SideKick is a registered trademark of Borland International Corp. Lotus is a registered trademark and Lotus 123 is a trademark of Lotus Development Corp. IBM is a registered trademark of the International Business Machines Corp. Easy Link is a service mark of Western Union Corp. Dow Jones News/Retrieval is a registered service mark of Dow Jones & Co., Inc.  
Requires IBM® PC, XT, or AT or IBM compatible and DOS 2.1 or higher.  
© LaSalle Micro, Inc. 1985

Screen color customization capability lets you set the color combinations you want.


Copy, encrypt, squeeze, rename, delete, and view files without disconnecting.

Each screen holds 57 names 6 screens deep.

Built-in communication language lets you automate all your communications functions.

Display date, time, time on line, cost of call, or other prompts at bottom of screen.

*BackComm* is menu-driven and command-driven.



CIRCLE NO. 150 ON READER SERVICE CARD

\*Operating system and disk size dependant



## EXPANDABLE MEMORY

an eternity: 1 minute 20 seconds. On a keyboard reset, however, REMM can be installed in less than 2 seconds.

REMM has a process to save multiple contexts with function 8. By default, the nesting limit is 5, but a limit of up to 32 may be specified when the device driver is installed. This allows writing reentrant interrupt service routines, but as explained previously, the availability of function 15 makes this feature less necessary than it was under the previous version of the EMS.

Other installation options may be used to control the starting address of the page frames and to keep page frames out of specified blocks of memory. The user should disallow page frames at segments B000H through BC00H, where presence of memory implies the use of a particular type of video adapter. Additionally, the total number of processes that can concurrently use expanded memory may be limited (the EMS allows up to 256; the default limit for the RAMpage! is 32). The documentation does not explain what advantage, if any, is gained by the user limiting the number of processes.

The implementation of function 33, which fills an array with the addresses of all the page frames above 640KB, has a bug similar to the one in Intel's function 14. If the direction flag is set when the function is invoked, the data are placed in memory backwards from the array's starting address. The user must clear the direction flag with the CLD instruction before every invocation.

The REX device driver program is an extended memory emulator that allows simulating the AT's extended memory in expanded memory. It can even do this on a PC, allowing VDISK to be installed with the /E option. REX is installed as a resident EMM process with a specified number of pages allocated to it. These pages then become unavailable to other EMM processes until the system is rebooted. It provides the INT 15H BIOS services that the AT uses to move data between conventional and extended memory, except that paged expanded memory is used instead of extended memory. REX is the only program supplied by AST that can use the expanded memory manager directly. All other utilities are written to use extended memory, so they need REX to provide the interface to expanded memory.

AST supplies new versions of its venerable SUPERDRV RAM drive and SUPERSPL print buffer programs. These are the AT versions that can use extended memory, so they need the ser-

**TABLE 2: Symphony Capacity Tests**

	CAPACITY RATIO	CAPACITY		NORMAL % FREE	EXPANDED % FREE
		NO EMS	WITH EMS		
		NO. CELLS	NO. CELLS		
Integer constants	0.98	52,824	51,592	0	100
Real constants	2.9	17,608	51,592	0	80
10-character strings	3.9	13,205	51,592	0	70
50-character strings	12.9	3,201	41,125	0	0
Small formula <sup>a</sup>	10.0	5,155	51,592	0	1

<sup>a</sup>A3 = (A1+A2)/2, A1 and A2 constant, A3 copied to the end of the column, then column A copied across the spreadsheet.

The use of an expanded memory board for a spreadsheet application allows larger spreadsheets to be created. System size used in the capacity tests was 495KB available user memory (per CHKDSK) and 2MB expanded memory.

**TABLE 3: Symphony Execution Times**

	NO EMS	WITH EMS
Load 255KB file from hard disk	58	62
Copy 5,000 formulas	42	48
Recalculate 5,000 formulas	38	49

Execution time increases when the expanded memory board is used. The increase in memory is only slightly offset by a reduction in speed. Formulas used in these tests are the same as those used in table 2.

vices of REX to run in expanded memory. Because SUPERDRV emulates a floppy disk, it is limited to 360KB and requires the setting of system board switches to indicate an extra diskette drive. It is not very useful on a system with expanded memory. Fortunately, another RAM drive program, FASTdisk, is implemented as a device driver and can therefore support larger RAM disks. It seems to be a clone of VDISK (the installation parameters are the same) and works in much the same way.

SUPERSPL is not the best print buffer in the world, but its wide distribution indicates that many users are familiar and comfortable with it, and it is preferable to Intel's QUIKBUF. A new SUPERSPL feature allows the user to control output to the printer by the printer interrupt, instead of by the timer. But for this to work, the printer port must be initialized with a reset procedure other than the one performed by DOS. No such program is provided by AST. Another useful addition is that the installation message displays the address where the buffer is allocated. The user interface is essentially unchanged from previous versions.

The documentation for RAMpage! lives up to the high standards set by

previous AST hardware products. The hardware and software instructions are presented in two separate manuals. They manage to provide all pertinent information clearly and concisely without insulting the reader's intelligence. Perhaps the manuals are a little unclear for a user who has never installed a circuit board, but AST wisely assumes that its primary audience is somewhat more experienced.

To test the compatibility of RAMpage! and Above Board with one another, each of the utilities was run on the other manufacturer's board. All of them worked fine, including, surprisingly, REX on Above Board. Each EMM device driver, however, is specific to its own board and will not work with the other. This means that multiple expanded memory boards must come from the same manufacturer or at least be designed for the same device driver. Users who are installing one board now but who are planning to add more in the future will want to consider only those manufacturers that can be expected to remain in business until the additional boards are needed. Intel, which was a codeveloper of the base EMS specification, and AST, one of the leading board makers for the personal



## THE I/O ADDRESS SPACE

The 8088 microprocessor can address two distinct address spaces: 1MB of program/data space and 65,536 I/O ports. But just as IBM limited user memory to less than a megabyte, it also limited the usable I/O space to less than the processor's limit: 1,024 ports. Of these 1,024 ports, the first 256 are reserved for the system board, and the next 256 are not usable. That leaves 512 ports available in the expansion slots for use by adapter boards. Although reserving some memory space for bit-mapped video and ROM is reasonable (it may be argued, however, that IBM took more than necessary), the limitation on the number of ports seems arbitrary. Most adapter boards require a whole block of ports to support each peripheral device, so the lack of adequate I/O address space may begin to loom as large as lack of memory.

Several physical ports may be provided for each address in the 1K of I/O space, however. This possibility arises from the fact that the CPU is still capable of specifying all 64KB of possible I/O addresses; however, most adapter cards recognize only 1,024 of these. The reason is that the cards implement incomplete address decoding, as illustrated in the accompanying figure. The diagram is meant to be a conceptual representation of address decoding; it is not a schematic of the actual hardware components.

The address decoding circuitry samples only the lowest 10 of the 16 address lines. The port responds to any address with the proper bit pattern in those 10 bits regardless of the state of the high-order 6 bits. Thus, for the example given, the port responds to hex addresses


0208, 608, 808, A08, and so on for the 60 other addresses whose low-order 10 bits have the same pattern. In effect, incomplete address decoding makes each port take up 64 I/O addresses, reducing the available ports from 64K to 1K.

Because the address decoding circuitry is on the adapter board, not on the system board, a board may be designed to perform complete, or perhaps "less incomplete," decoding. The EMS boards decode two of the high-order 6 bits, thus providing four ports at each address in the 1KB address space. If the board's port address is set to 208, the four page registers are addressed at 0208, 4208, 8208, and C208.

This method does not magically expand the I/O address space back to 64KB. For example, ports cannot be addressed at F3F0 through F3F7, no matter how complete the decoding, because the block of eight diskette controller ports beginning at 03F0 responds to the same addresses. What this method does provide, however, is the potential for implementing as many as 64 ports for each address that is not already in use by a port that contains standard decoding circuitry. As more and more devices become available for the PC, complete decoding will be increasingly used in order to relieve congestion in the I/O space.

—TM

**FIGURE:** *Incomplete Address Decoding*



The EMS boards decode two of the high-order six bits that are not normally decoded in order to provide four ports at each of 1KB address space.

computer market, both qualify for inclusion in this category.

### EXPANDED BENEFITS

Lotus Symphony 1.1 was used as a test of the benefits provided by expanded memory. It ran equally well on both Above Board and RAMpage!. In order to test the added capacity that is provided by expanded memory, an empty spreadsheet was successively filled with integer constants, real constants, short and long text strings, and a simple formula until the memory was exhausted. The tests were repeated both with and with-

out the addition of expanded memory. The results of these capacity tests are given in table 2.

Notice that a "Memory full" condition can occur even when a significant amount of expanded memory is unfilled. This condition results because pointers to locations in expanded memory are kept in conventional memory; when that is filled, no more can be placed into expanded memory. Judging from the results that are shown in table 2, each expanded memory pointer takes up the same amount of space in conventional memory as does an integer.

Therefore, integers are not placed into expanded memory; they would take up twice as much space.

The capacity of the spreadsheet is reached when the conventional memory is filled. If, however, expanded memory is filled first, additional cells are allocated in the remaining conventional memory. This situation occurs in the case of the long strings: in round numbers, expanded memory is filled with 34,000 cells, but about one-third of conventional memory is free at that point, and an additional 7,000 cells are placed there.



When Symphony starts up, it does not immediately allocate all of the free pages of expanded memory. Allocations are made only as needed, so that add-in applications (including programs executed through DOS.APP) also may use any expanded memory not currently being used by Symphony.

The advantages of expanded memory vary, depending on the makeup of a spreadsheet. Tests with some typical spreadsheets containing a mixture of labels and formulas of various lengths indicate that adding 2MB of expanded memory to 640KB of conventional memory expands the maximum number of cells by a factor of 3 to 4.

Although the EMS specification allows 8MB of expanded memory, the Lotus spreadsheets (Symphony and 1-2-3) support only 4MB. In practice, the typical spreadsheet can use no more than 2MB before filling up conventional memory on a system with 640KB of user memory. Installing more than one EMS board is useful when the spreadsheet holds a database rather than formulas or when using utilities that are coresident with the spreadsheet, such as RAM drives or print buffers.

The best news is that the expanded capacity is obtained at a tolerable cost in execution speed. Table 3 lists the times for loading a large file and for copying and recalculating short formulas (the same ones used for the capacity test), with and without expanded memory. In most cases, the speed penalty is less than 25 percent.

After all of the technical specifications are described and the tests run, the bottom line on expanded memory is, of course, how well it works. The verdict is overwhelmingly positive. The EMS can be immediately useful even to users who do not measure their spreadsheets by the acre. Running a system with 2MB of RAM disk and many resident utilities—with more than 400KB of DOS memory left over—is a joyful experience. The true potential of expanded memory, however, will be realized by systems software that can concurrently load, if not run, several applications. A variety of useful programs that take full advantage of the EMS currently are in various stages of development, and some are already available. Intel, for example, is currently bundling Above Board with Microsoft Windows, while AST is including Quarterdeck's DESKVIEW with RAMpage!. Both of these software packages are the latest versions that make full use of the capabilities that are available with the respective EMS specifications.

## MEMORY EXPANSION BOARDS

In addition to Intel's Above Board and AST's RAMpage! reviewed here, several other boards are available that conform to the Lotus/Intel/Microsoft (LIM) and/or the AST/Quadram/Ashton-Tate (AQA) Expanded Memory Specification. Some of these boards are listed below. Their performances have not been evaluated by *PC Tech Journal*.

*Companion Card*: \$295 with 0KB; \$395 with 256KB; \$495 with 512KB; \$595 with 768KB; \$695 with 1MB; \$1,090 with 2MB

*Supports LIM spec only*  
Mega Omega Systems, Inc.  
5217 Ross Avenue  
Dallas, TX 75206  
214/828-0960  
CIRCLE 303 ON READER SERVICE CARD

*JRAM-3*: \$269 with 0KB; \$309 with 256KB; \$589 with 2MB

*JRAM-AT-3*: \$349 with 0KB  
*Supports LIM spec only*  
Tall Tree Systems  
1121 San Antonio Road  
Palo Alto, CA 94303  
415/964-1980  
CIRCLE 304 ON READER SERVICE CARD

EMS is in a unique position to bridge the gap between the past and future of the IBM PC: on a basic PC, it can provide several additional years of useful life for a system that otherwise might be fast approaching antique status. In addition, it provides an AT with some of the functionality that so far has been untapped in that machine.

In comparing the Lotus/Intel/Microsoft and AST/Quadram/Ashton-Tate specifications, the latter appears to provide more flexibility by hedging the user's bets. It works with currently available applications written for the LIM standard and is ready for the applications that can make full use of all the enhancements—when and if those become widely available. As a matter of fact, Lotus, the arbiter of EMS compatibility, has certified RAMpage! as fully compatible with the EMS specification.

With Microsoft as one of the partners in the LIM specification, the possibility exists that future versions of the operating system will render the AST superset of functions unusable.

In comparing the two hardware offerings, the AST RAMpage! board is preferred not only because of its underlying design specifications, but also

*Liberty*: \$395 with 64KB; \$595 with 512KB; \$895 with 1MB; \$1,295 with 2MB

*QuadMEG-AT*: \$445 with 128KB; \$595 with 512KB; \$1,295 with 2MB; \$2,685 with 4MB  
*Supports both LIM and AQA specs*  
Quadram Corporation  
4355 International Blvd.  
Norcross, GA 30093  
404/923-6666


CIRCLE 305 ON READER SERVICE CARD

*Memory Companion/PC*: \$395 with 256KB; \$699 with 2MB

*Supports LIM spec only*  
STB Systems, Inc.  
601 N. Glenville, Suite 125  
Richardson, TX 75081  
214/234-8750  
CIRCLE 306 ON READER SERVICE CARD

*TOP BOARD*: \$495 with 256KB; \$695 with 512KB; \$1,095 with 1MB; \$1,895 with 2MB

*Supports both LIM and AQA specs*  
Seattle Telecom Data, Inc.  
2637 151st Place, N.E.  
Redmond, WA 98052  
206/883-8440  
CIRCLE 308 ON READER SERVICE CARD

because the superior documentation and utilities make this a better package overall. This is not to say that Intel's Above Board is inherently flawed. Except for the print buffer utility, it is a good product in its own right. 

*Above Board AT*: \$795 with 512KB; \$1,495 with 2MB; \$2,690 with 4MB  
*Above Board PC*: \$495 with 256KB; \$1,395 with 2MB

Intel Corporation  
5200 N.E. Elam Young Parkway  
Mail Stop TOC-03  
Hillsboro, OR 97123  
503/629-7369  
CIRCLE 301 ON READER SERVICE CARD

*RAMpage!*: \$595 with 256KB  
*RAMpage AT!*: \$745 with 512KB; \$1,045 with 1MB; \$1,495 with 2MB

AST Research, Inc.  
2121 Alton Avenue  
Irvine, CA 92714  
714/863-1333  
CIRCLE 302 ON READER SERVICE CARD

*Ted Mirecki is a corporate planner who is responsible for developing decision support systems on a variety of hardware. He has a master's degree in computer science.*




# CXI doesn't answers, just



PCOX/STANDARD links a PC direct to the mainframe. PCOX/PLUS (not shown) can "window" a PC session, host session and two notepads on the same screen.



PCOX/3270 PC turns the PCs you have into the 3270 PCs you need. We also offer an upgrade to 3270 PC for other PCOX products and even for IRMA.



PCOX/GRAPHICS gives you easy access to mainframe data and mainframe graphics like SAS-Graph™, GDDM™ and DISSPLA™.

## PCOX micro-to-mainframe connections are designed with your IBM 3270 network in mind.

At CXI, we've come up with hardware and software solutions that solve problems at both ends of the micro-to-mainframe connection.

Be it coaxial or remote.


Together we call them the PCOX™ 3270 Series (pronounced "peacocks").

To start with, there's our PCOX/STANDARD and PLUS emulator boards. They link your PCs to the mainframe. And provide file transfers to and from the host.

Our PCOX/3270 PC upgrades your PC to multiple host sessions for a fraction of the price of an IBM 3270 PC. While PCOX/GRAPHICS lets you do true S3G graphics terminal emulation right on a PC.

Looking for micro-to-mainframe connections for your LAN?

Our PCOX/GATEWAY products come in coaxial and remote versions and serve host sessions to your IBM PC Network or NETBIOS-compatible LAN.



We designed this proprietary gate array chip (on your left) to let us fit a lot more capability in a lot less space. With more reliability. It was also the first chip designed exclusively for 3270 terminal emulation.



# have all the more of them.

Or snap on one of our smart accessories. Like **KEYBOARD MATE**. A compact addition to your PC keyboard that gives you single keystroke access to 3278/79 and 3270 PC functions.

## We've thought our answers through.

All PCOX products work with IBM® PCs, XT's, AT's and compatibles. They're easy to install. And easy to upgrade. It's as simple as changing a diskette.

But more important, since we design and manufacture everything we sell, we can track and respond to changes in the industry.

So the investment you make now will be safe. And supported. How?

With training, technical assistance, and even a toll-free customer hotline.

Of course, when you go with

CXI, you'll be in the company of other good companies like General Motors, Citicorp, TWA, British Petroleum and more.



## PCOX works with all major micro-to-mainframe software.

Whether it's Cincom, Cullinet, Informatics, MSA, Micro Tempus or Performance Software, PCOX runs it. This is due in part to the three application program interfaces we provide. Namely, IBM's, IRMA's and our own PCOX API.

CIRCLE NO. 162 ON READER SERVICE CARD

So for the name of your nearest CXI distributor, call **800-225-PCOX**. In California, call (415) 424-0700.

Or send us the coupon. And we'll have an answer to you quicker than you can say PCOX.

For a copy of our brochure, "More Micro-to-Mainframe Answers," fill in this coupon or attach your business card and mail it to CXI, Inc., 3606 West Bayshore Road, Palo Alto, CA 94303. TELEX: 821945.

Name, Title \_\_\_\_\_

Company \_\_\_\_\_

Address \_\_\_\_\_

City, State, Zip \_\_\_\_\_

Phone (      ) \_\_\_\_\_

**More  
micro-to-mainframe  
answers.**

**CXI**

PCOX and all PCOX products are trademarks of CXI, Inc. Other computer and software names identified by "®" or "™" are tradenames and/or trademarks of their respective manufacturers. © 1985, CXI, Inc.

*We offer a choice of connections:  
either coaxial to a controller or remote via a modem.*





# PC BRAND: SPECIALIZING IN TOOLS FOR PROGRAMMERS

## PADLOCK

Protect Any Program Using Anyone's Diskettes

You are a program developer seeking a low-cost way to protect your program from piracy? You are with a prominent company fearful of embarrassing lawsuits should employees copy programs illegally?

We have a devilishly clever solution for the two of you we call PadLock™. It gives you the keys to lock up any program you want—yours or someone else's—without buying a stockpile of expensive fingerprinted disks.

PadLock is software. One of its programs formats any manufacturer's disk, embedding your secret code in sectors the operating system will ignore. Another program installs this code in any program files you name, whether YourProg or WordStar®, or any .COM or .EXE files. From then on there's no picking the lock without the combination: the coded software together with a coded disk.

So it's not despised copy prevention. Protected programs can be copied anywhere, to hard disks, to backup diskettes. It's a lock and key scheme. A protected program will just lock up at load time without a keyed diskette (possibly its own) in one of the drives. The key disk may then be removed to free the drive.

PadLock is economical. You buy software that fingerprints disks for as little as \$2.50 each, not \$8.00 laser-drilled disks you may never use. Tell you what. PadLock keeps track of how many disks it has formatted. Try it out. Format up to 5 test disks. If PadLock doesn't suit you, return it within 30 days for full refund.

Incidentally, don't look elsewhere. PadLock is available only from PC Brand.

## CURSES Unix Style Screen Management

Curses is a Lattice® creation which manages the screen of the IBM PC in the same fashion as the curses utility of Unix. This C library has all the same functions of Unix curses with matching parameter lists. So your Unix program will be content when you move it to the PC, and programs created on the PC will be Unix compatible.

Curses is a library of eighty-four functions and macros which can keep any number of screen images in memory. A screen may be full or partial size, and any can be summoned to the physical screen at your programs's command.

The product supports color, and all four memory models. In keeping with the terminal orientation of Unix curses, the physical screen is re-painted (at high speed) only when your program calls a refresh function. Within a screen, Curses employs a vast function set to get characters, wrap lines, scroll, blank lines, highlight—virtually any tool needed to update the screen.

Ask for:	List:	PC Brand:
L0850	\$125	\$100
L0860 with Source	\$250	\$200

## FIRSTIME C Programmer for Hire. Real Cheap.

Not interested in interpreters? Then explore the other fast lane to coding: language-specific editors. FirstTime™ is the strongest C editor we have seen, with many more commands and utilities.

FirstTime asks what program structure you want and sets up its skeleton for you: "main", or "function", or "if-else" or "while" or any component of C, with all semi-colons and curly braces tended to.

It puts placeholders into these structures to prompt you to enter code—the conditionals and counters which complete an "if", for example. FirstTime can even transform one type of structure into another, such as "for" into "while" or

NEW LOW COST VERSION

Ask for:  
M0030 Formats 30 disks  
M0100 Formats 100 disks

Prices:  
\$99  
\$250

## PROSPERO'S PRO PASCAL

ISO Validated Pascal for Serious Users

BORLAND USERS SPECIAL OFFER!

Turbo Pascal™ was irresistible at the price but its limitations loom larger as your Pascal expertise expands. Might it be time to look into a truly professional Pascal compiler?

Prospero Software's Pro Pascal™ was awarded a Class A certificate for its faithful implementation of the International Standard for Pascal (ISO 7185) conquering a suite of 740 tests, the only validated Pascal compiler for the PC and 8086 family of machines. Its UK creator has sold several thousand in a worldwide market where standards are a priority.

Turbo cannot compile programs utilizing standard Pascal features that Borland unaccountably sloughed off (e.g., get, put, page, function name passing). That's probably led to wordy equivalents in your programs at penalty of expanded size and run time. Bluntly, "there is a Pascal standard. [Borland] is definitely not standard Pascal" (Cortesi, Dr. Dobbs's Journal, 7/85).

Pro Pascal corrects such deviance to make your work acceptable in any circles. Perhaps more enticing, it breaks free of Borland (and MT+™ and IBM®) 64k boundaries. Large memory model programs of 10,000+ lines and 1,000+ identifiers are now possible.

Pascal as defined is austere as an Alp, but Pro Pascal has sturdy outcroppings to hang onto: dynamic strings, random file record access, long integers, single and

## BRIEF

Is Anything But. A Whopper of an Editor

Dvorak in Infoworld said it for us: "the word is getting around... that Brief, The Programmer's Editor is simply the

OUTSTANDING FOR ANY LANGUAGE

best text editor you can buy." With a name that belies its thoroughness, Brief™ has every feature you've ever contemplated for your editor-in-chief. Here goes:

Text, from keyboard or files, is housed in multiple buffers, and scrolled through one or more windows you open, close, resize. A text buffer may be called to different windows to view two areas at once. A change in one changes both. Text may be marked for printing, writing to files, movement to scrap buffers for cut and paste into other buffers, or deletion, with as many "undo" levels as you want.

To find and fix, Brief has text search abilities rivaling "grep", with wildcards for matching, indifference to intervening characters, acceptance of character ranges, even multiple choice of patterns and their replacements.

If you use Lattice, C86™, or Wizard, and have 320k, you can compile your C program without ever leaving Brief. It finds the lines with errors, and marches you through the text for repairs.

Parts of Brief were written with its own Lisp-like macro language. It has structure, 32-character variable names, conditional execution, loops, and you can actually read it! Nothing like the hieroglyphs we've seen elsewhere.

A macro compiler comes with your copy, and pre-written macros in source to give you the flavor. One even turns Brief into a word processor, with margin setting and wraparound. There's even a bulletin board and public domain disks with macros contributed by a mushrooming cult of macromaniacs. A disk full of contest-winning macros comes free with your purchase! (Needs 192k.)

Ask for: U0590	PC Brand:
List: \$195	\$CALL

Ask for:	List:	PC Brand:
P0100 <	\$390	\$345
P010X <	Borland Trade-In*	\$299
*Upon receipt of original Borland disks		

## The TOOLSHED™ Trusted Favorites for a Well-Appointed Workbench

Interested but need to know more? Ask for literature about these products.

### C-SPRITE Lattice's Own Debugger

This versatile companion to Lattice C™ displays function and variable names, data types, source code line numbers, and source itself. At any breakpoint disassemble object code and see source and assembler on screen.

Optionally offers machine addresses. Differentiates between C's data types to treat addresses as strings, long integers, etc., even pointers. At breakpoints set by symbols or addresses, C-Sprite™ will execute clusters of commands or commands that execute until a condition is met.

Debug through a COM port with a second terminal to leave a program's display screen undisturbed. Link with Plink86™, and C-Sprite can even tackle overlays.

Ask for: L2300	PC Brand:
List: \$175	\$145

### PRO FORTRAN With Source Debugger

Prospero also offers a polished Fortran which satisfies completely ANSI X3.9-1966 (known as Fortran 66) and adds an abundance of Fortran 77 extensions (which may be blocked as a compile option). Its strict standards mean mainframe to micro compatibility.

Pro Fortran™ supports both small and large memory models, optionally uses the 8087, is equal to Microsoft in speed, but produces extraordinarily compact code—as little as 1/5 and an average of 1/2 the size of Microsoft's in tests we've seen! It comes with a linker, a librarian, and the same source debugger as Pascal above.

Ask for: F0100, List: \$390, PC Brand: \$345.

### LMK Unix-like "Make" Builds Systems Easily

Working on a large program (in any language)? Tell Lattice's LMK™ what source files to compile using which options, which modules to assemble into what libraries, what libraries to search, what to link into the final product.

LMK keeps track of the last time every action was performed, and all the steps in your program system which depend on them. Over and over as you write and test, LMK rebuilds your program faultlessly, however intricate the assembly, and saves time doing only what's needed.

Ask for: L2100, List: \$195, PC Brand: \$159.

### CODE SIFTER Profiler at Bargain Price

Several expensive programs will now find the sluggish spots in your program; our Code Sifter saves you plenty. It divides .COM or .EXE files into partitions on its own (or you can specify boundaries), then

samples your program at precise intervals, counting how many times it finds the instruction pointer in each partition. Between each run Code Sifter can discard less active ranges and re-partition the hot spots, so that you zoom in literally byte tight! You'll see unmistakably where to optimize.

Ask for: N3100, List: \$119, PC Brand: \$99.

### TEXT TOOLBOX Tames Text Files

Lattice has assembled a cluster of the most useful Unix text management tools into a single package. The Toolbox™ has:

"Grep": Rapid searching of any number of files to spot text patterns. Powerful expression syntax that goes far beyond your text editor's search command.

"Splat" substitutes new text for matches found using grep's syntax. "Files" can copy or erase files down paths to the point of eliminating full directory structures.

"Diff" compares text files line for line. "Ed" is similar to the well-known Unix editor.

Ask for: L2220, List: \$120, PC Brand: \$100.

### CVUE Customizable Text Editor

CVUE™ is Lattice's text editor which has undelete, full path name support, and features important to programmers: recognition of non-display characters, pattern searching, indenting and unindenting.

Supports text files as big as RAM. Compact and fast. Runs in only 64k with no tedious overlays. The real value: Even the binary version offers full customization of keyboard commands. Plus, opt for source code and make this editor truly your own.

Ask for: L2240, List: \$75, PC Brand: \$69. For Source Code as well, Ask for: L2245, List: \$250, PC Brand: \$195.



# AND GETTING THEM TO YOU AT REDUCED PRICES, FAST. TRY US!

## C-TREE

### B-Tree File Manager, Source Code, No Royalties!

C-tree™ has been around since 1979. (It became Digital Research's Access Manager™.) That means seasoned, sturdy code which hasn't cracked under the weight of prolonged and widespread use. C-tree comes in C source code, revealing all you've ever wanted to know about how b-trees are written. Provided you bind it into your binary application, you can re-distribute C-tree without royalties.

C-tree's design splits nodes to allow any number of users to access an index file simultaneously even during updates. So multi-user configurations and adaptation to networks are possible. You must write record-locking routines, as they are compiler and operating system dependent, but the documentation shows how.

The latest version has new features: support of variable record length files; multiple key indexes in a single physical file. Thanks to source code which does not deviate from the K&R standard, C-tree can travel. Tests in many environments prove that C-tree gives your application a ticket to anywhere.

C-tree permits any number of keys for a data file, supports duplicate keys, alphanumeric or numeric, etc., etc.—it's a comprehensive product with everything you'd expect. Intellegently designed, too, comprising both high level ISAM routines which minimize coding by handling all details of an activity, as well as decomposed step-by-step functions you can access directly. Either way C-tree maintains optimal index structures which will find a record amongst a million ten-byte keys in no more than five disk seeks.

Ask for: F0660 < PC Brand: **\$329**  
List: **\$395**

PC BRAND, Craftsman, PadLock, Toolshed, and Toolbox TMs of PC BRAND / Unix TM Bell Laboratories / Lattice registered TM; and Lattice C, LMK, C-Sprite, CVUE and dBC TMs of Lattice Inc. / dBASE TM Ashton-Tate / c-tree TM FairCom / Pre-C, Plink88 TMs Phoenix Computer Products / MS TM of Microsoft / IBM registered TM of Int'l Business Machines / Brief TM UnderWare, Inc. / FirstTime TM Spruce Technology Corp. Inc. / WordStar registered TM Micropro / C86 TM Computer Innovations Inc. / Access Manager, CP/M, MT+, TMs Digital Research / Toolworks TM Software Toolworks / Pro Pascal and Pro Fortran TMs Prospero Software / Turbo Pascal TM Borland Int'l

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

standard to guarantee maximum portability anywhere in the C world. There are then plentiful command line options to relax such rigor during early coding when work is incomplete. Use purchased binary libraries? Profile them for Pre-C and it will thereafter insure that function calls from any C program are letter perfect. A miracle worker in speeding large system development. Needs 128k minimum; 192k recommended.

Ask for: P0590 PC Brand: **\$295**  
List: **\$395**

## TOOLWORKS C COMPILER

NEW!

### Benchmarks Embarrass Biggies at Giveaway Price!

Borderline move over. If you are looking for minimum cost tools for learning C or for getting straightforward jobs done, we are happy to end your search.

Take a peek at the prices below, then look at the benchmarks. We have here a bargain C compiler with some very respectable clockings against not only low price compilers, but even against big-leaguers like Lattice. The timings will surprise you (will you look at floating point?).

Lattice it's not. Our Toolworks™ C doesn't have the full repertoire of features. But maybe you don't need them just yet. If the small memory model (64k for program and data each) will keep you busy for now, and you haven't yet found a reason for double precision math; if what you really need is to create C code and get it compiled, and you don't mind doing it for several hundred dollars less, then Toolworks C will be happy to generate remarkably fast and efficient compiled code for you.

To save the most, get the essential compiler—restricted to integer math values not exceeding  $\pm 32k$ . Or order the Mathpak as well and receive a library capable of single precision floating point and long integers, as well as trigonometric, hyperbolic, logarithmic and powers.

Toolworks C has a configuration program to change the compiler's default option settings, and a runtime profiler to uncork bottlenecks. It can generate either object code or assembler compatible with Microsoft's MASM, and gives you source code of its complete standard library, which includes access to DOS and BIOS interrupts.

Our compiler doesn't care what generation of DOS you are creating for. Toolworks C supports register variables, can use the 8087 math chip, even has an exec() function which will branch to another program or a DOS transient and return.

It's simply packaged. Nothing fancy. But our evaluators tell us that it is easier to use than most compilers, and no bugs were found. Not surprising. This compiler is not new. It started life under CP/M™. Thousands of keybangers shaped the original to perfection's mold. We're so confident of reliability that if you are the first to document a bug, you can keep the compiler, and we'll refund your money.

Prices:  
TC001 Compiler & Runtime Library **\$49.95**  
TM001 Mathpak for Floats & Longs **\$29.95**

### BENCHMARK RESULTS Each test's best score indexed to 100.

	#1a	#1b	#2	#3	#4	#5	#6	#7	Compile Time Size
Toolworks	180	100	100	213	139	146/200	181/218	61k	162 135
Lattice		240	140	100	100	103/100	105/100	58k	205 121
DeSmet	670		113	107	100	100/130	100/113	60k	100 117
Ecosoft		160	115	116	110	101/130	105/143	fail	171 100
Test Key:									
#1a: Floating point.									
#1b: Same, using 8087 if capable.									
#2: Function calls.									
#3: Character counting.									
#4: String copy using pointers.									
#5: File copy using getc, putc; floppy/harddisk.									
#6: File creation, floppy/harddisk.									
#7: Max. memory allocated using malloc().									
Benchmark by DrasTech.									

## dBC Lattice Library Maintains dBASE Compatible Files With the Power and Speed of C

dBC links C to dBASE. It creates and maintains files and their indexes which exactly replicate dBASE™ file design. So dBASE can read and update them. And the reverse. dBC™ can use any files created by dBASE. Now C and dBASE can operate on the same data bases interchangeably.

That opens up the widespread culture of dBASE installations to exploitation by C programmers, and there are a lot of dBASE users out there. You can tap that market, avoid the resident dBASE lan-






IMAGE • HERBERT WAGNER COMPUTER GRAPH



# Three-Dimensional Modeling

*When combined with a 2-D drafting system, MEGA CADD's Design Board Professional provides a complete CAD toolkit.*

VICTOR E. WRIGHT

**M**icrocomputers are not (yet) equal to the task of hosting a three-dimensional CAD (computer-aided drafting) system with all the features of a production drafting system—one that automates the tasks required to produce finished drawings, ready for the contractor, machinist, tool-

maker, etc. Minicomputers and mainframes are needed to host these CADD (computer-aided drafting and design) systems. CADD is basically a CAD system with additional software that automates portions of the drafting and design process. The distinction between CAD and CADD is somewhat artificial,

but a CADD system generally presents a user interface customized for a particular field of design, whereas a CAD system is a general drafting system with no discipline-specific features.

Microcomputers, however, do very well at hosting either two-dimensional production drafting systems or three-





## 3-D MODELING

dimensional modeling systems. MEGA CADD's Design Board Professional for the IBM PC family is a worthy example of the latter. The latest version, 2.04, was released in October 1985.

Design Board Professional provides the capability of creating 3-D models and displaying them in perspective views, with hidden lines shown or removed at the user's option. It is aimed at the designer—the person who creates and develops concepts—as opposed to the production draftsman. The program supports all the functions that a designer would reasonably expect, from interactive creation of 3-D models to storage on disk to plotted hard copy. MEGA CADD does not pretend that its product is a production drafting system, but instead has designed the system so that it can be used in conjunction with other production drafting packages.

### DRAWING DATABASE

A CAD program is a database management system at heart. As each drawing entity is entered, it is recorded in a drawing database file (entities may be entered in a buffer in RAM and only periodically written to disk). A record is devoted to each entity, and the contents of the various fields in the record contain the data necessary to depict the entity graphically.


Each CAD system designer chooses a different format for the system's database, just as word processor designers and spreadsheet designers choose different storage formats. The differing formats account for the fact that one CAD program cannot read the drawing files created with another one, as well as for the different capabilities of one program in relation to another.

Design Board Professional maintains its entire drawing database in memory, as opposed to some CAD programs that maintain buffers and automatically write the information to disk when the buffers are full.

MEGA CADD does not describe its database structure in the manual; nor does it provide a data interchange format. However, a utility is available to translate drawing files to the interchange formats that are readable by other CAD programs.

Modeling programs, such as Design Board Professional, fall into two categories: wire frame modelers and solid modelers. Solid modelers know about solids and the surfaces that separate the solids from the surrounding space, and wire frame modelers know about the lines that form the edges of surfaces, but not about the surfaces themselves. A

**FIGURE 1: Line Removal**



Hidden line removal applied to intersecting objects created by a wire frame modeler produces a line disappearing into a surface.

solid model is opaque, whereas a wire frame model is transparent unless it has been processed to remove hidden lines. Most microcomputer programs that model 3-D objects are wire frame modelers, as is Design Board Professional.

A limitation of a wire frame modeler is that the program does not detect when one object is placed in the space occupied by another existing object. A wire frame modeler does not store a representation of a solid object or the surfaces that define the solid object. (Solid modelers known as Constructive Solid Geometry modelers and Boundary Representation modelers represent solid objects using those respective methods.) Therefore, the program cannot detect the intersection of two objects. This characteristic is revealed when two intersecting objects are displayed with hidden lines removed (see figure 1). When an edge of one object penetrates another object, the edge disappears, as it should, but no line appears where the planes of the two objects intersect.

### HARDWARE REQUIREMENTS

Design Board Professional is fairly demanding of computing resources, as indicated by the following list of requirements: two floppy-disk drives or one floppy- and one hard-disk drive; 512KB of RAM; mouse or digitizer pointing device; 8087 numeric data processor; graphics card; DOS 2.0 or later. For hard-copy output, a graphics printer or pen plotter is required.

For this review Design Board Professional was tested primarily on an IBM PC with 640KB of RAM, an 8087, two floppy-disk drives, 15MB Winchester hard disk, Hitachi Tiger digitizer tablet, (also with a Mouse Systems

mouse), the Houston Instrument DMP-42 plotter, and standard IBM Color Display and Roland DG MB-142. Several different graphics cards were tried.

The program also was run on a PC/AT during its evaluation. The power and speed of the AT make it the preferred machine, primarily because displays are generated more quickly, but the PC does a respectable job with the program, which is a large one written in FORTRAN.

The key to effective use of CAD is a good graphics display. A high-performance CAD system needs a high-performance display. Although detailed drawings may be created with a low-resolution display, the process is slower because the designer must change viewpoints more often.

High resolution generally is considered to begin at 640 pixels wide by 400 pixels high. (As a point of comparison, large CADD systems provide resolution of 1,024 by 1,024, some as high as 4,096 by 4,096, on screens ranging from 19 to 25 inches.) The standard IBM Color Graphics Adapter can achieve a resolution of 640 by 200—and that only in monochrome; for color, resolution is only 320 by 200. Design Board Professional supports several color/graphics adapters that offer higher resolution, however. Various configurations were tested for this review.

Tecmar's Graphics Master board provides a resolution of 640 by 400, operating in an interlaced mode, with a palette of 16 colors—although Design Board Professional makes use only of white, violet, and cyan. The Tecmar card should be used with a long-persistence monitor, because a standard monitor flickers when driven in the interlaced mode. Flickering was quite annoying when the Graphics Master was installed on a PC with the standard IBM Color Display attached, but barely noticeable on an AT with the Tecmar LP color monitor. The Tecmar monitor produced a slight smearing effect in noninterlaced displays.

The Tecmar Graphics Master also was tested driving monochrome monitors at a resolution of 720 by 704. The difference between the 720-by-704 and 720-by-352 displays is readily apparent, but not as dramatic as the difference between the 640-by-200 monochrome display of the IBM CGA and the 640-by-400 color display of the Tecmar card/IBM Color Display combination.

An AST Prevue card was tested with a Roland DG MB-142 monochrome display (white type on black background; the display can be reversed with the



push of a front panel button to produce black lines on a white background, which is very effective for CAD displays). To use Prevue, the Design Board program must be configured for the Hercules Graphics Card, which Prevue emulates. Both the Prevue and Hercules cards provide a resolution of 720 by 352, which is acceptable for CAD work.

One problem with the Prevue/MB-142 configuration was that the display could not be adjusted to show the border on all four sides of the Design Board Professional screens. When another monochrome monitor was substituted, the problem cleared up.

The IBM Enhanced Graphics Adapter and Hercules Graphics Card also were tested with Design Board Professional. The EGA display is impressive. The magenta highlights of the Tecmar Graphics Master are replaced with a bright red in the EGA, while the grid remains an unobtrusive cyan. The Hercules card produces a sharp monochrome white on black. These two cards were added to version 2.04, along with the Control Systems Artist I card and the Sigma Designs Color 400 card. Beta test documentation mentions that several cards supported under previous versions now are supported in additional configurations, but the production manual does not elaborate.

Design Board Professional also supports the Amdek MAI adapter, the Number Nine Resolution card, and the Conographics Cono-Color/Model 40. This last card has 256KB of RAM and drives an analog RGB monitor. Conographics recommends monitors by Electrohome and Aydin Controls, but Princeton Graphic Systems has announced its SR-12P analog RGB monitor, and the IBM Professional Graphics Adapter is an analog RGB monitor.

Because many users do not have high-resolution monitors and graphics boards but do have color displays, MEGA CADD designed its CAD system to produce a good display using the medium-resolution mode of the Color Graphics Adapter. The menus are not standard 40-by-25 mode characters, but a graphically produced font that resembles drafting text lettering.

## INPUT DEVICES

Design Board Professional supports three types of input devices: keyboard, mouse, and digitizer tablet. Keyboard input is limited to numeric data for selected commands. Either a mouse or a digitizer tablet can be used as the interactive pointing device that controls the location of the screen cursor, a set

of cross-hairs that extends across the screen vertically and horizontally.

The program supports both versions of the Microsoft Mouse, serial and bus, and the Mouse Systems mouse. Mice are easily installed, requiring only the installation of a device driver, which is furnished with the mouse, via the CONFIG.SYS file or a .COM file.

Several digitizer tablets are supported: Summagraphics MM1201, Summagraphics SummaSketch, Hitachi Tiger, and Kurta Series One. (Version 2.04 has added CalComp 2000 and 2100, Houston Instrument DT 114 HIPAD, Kurta Series 1, GTCO DP-5, and Summagraphics MM 961 and Bit Pad One to its list of supported digitizers). A digitizer tablet has no significant advantage over a mouse, because Design

*The plotting program has been modified so the pen is lifted at the end of a stroke. If the plotter waits for data from the computer with the pen down, blots can occur.*

Board Professional does not provide a means of calibrating the tablet to digitize existing drawings. Installation of a digitizer tablet also is more complex than for a mouse.

In keeping with MEGA CADD's philosophy of running Design Board Professional in conjunction with a separate production drafting system, the two Summagraphics tablets can be configured to work with VersaCAD and AutoCAD as well as Design Board Professional. The manual advises that these tablets must be factory configured for packed binary format, 9600 baud, and odd parity. The Kurta Series One tablet can be configured by the user to work with Design Board Professional, AutoCAD, CADVANCE, and VersaCAD.

The Hitachi Tiger II tablet can be configured to work with Design Board Professional and only one of the three programs, AutoCAD, CADVANCE, and VersaCAD. The tablet has three switch blocks to set, and the three programs use different switch settings. Design Board Professional provides a device driver that works with any of the settings, but not all three. Another setting has been optimized for use with Design

Board Professional only. Installing the Hitachi Tiger II requires a special cable, the wiring diagram of which is shown in the manual. Although the manual does not mention it, a Smart Cable can be used to connect the Hitachi Tiger II to the computer, thereby eliminating the need for a special cable.

## HARD-COPY OUTPUT DEVICES

Design Board Professional supports a limited selection of dot-matrix graphics printers and pen plotters. Among graphics printers, only the Epson FX-100 printer and others that emulate it are supported. A plot produced on this printer is of lower resolution than that produced on a pen plotter, but printer plots are useful nonetheless. They can be plotted quickly and do not require refilling pens with ink. The scale can be specified for printer plots, and the plots are properly proportioned (round circles and square squares) even though screen displays are not always so.

The selection of pen plotters is also limited: Hewlett-Packard models 7470, 7475, 7585, and 7586, and Houston Instrument models DMP-29, DMP-40, DMP-41/42, DMP-51/52, PC-595, and PC-695. The HP 758x series handles drawings up to E-size (47-by-36 inches), and the Houston Instrument DMP-41/42 and DMP-51/52 plotters handle drawings up to D-size (36-by-24 inches). Version 2.04 has added a few more plotters to the list supported by the previous version. Among them are the CalComp 1043 plotter, the Western Graphtec MP 1000, and Roland 880. The plotting program in version 2.04 also has been modified so that the pen is lifted at the end of a stroke. If the plotter were to wait for data from the computer with the pen down, blots could occur.

The manual provides all the information needed to make up the correct cable and configure a plotter. As with digitizer tablets, MEGA CADD has chosen cable configurations and communications protocols that are compatible with three other popular CAD systems—AutoCAD, CADVANCE, and VersaCAD. If a plotter is connected properly for operation with Design Board Professional, then it should work with any one of those three programs.

Installing Design Board Professional consists of configuring the hardware and creating working copies of the program to suit the hardware devices. The program is not copy protected, which greatly simplifies installation on a hard disk.

Once the hardware is connected and DIP switches positioned correctly,






Not long ago, *PC Magazine* called MDBS III "The most complete and flexible data base management system available for microcomputers." That's a powerful statement. But then, MDBS III is an amazingly powerful software package. So powerful, in fact, that it lets you build mainframe-quality application systems on your micro or mini. MDBS III is not for beginners. It's for application developers with large data bases or complex data interrelationships who want to define data base structures in the most natural way—without resorting to redundancy or artificial constructs. It's for professionals who can appreciate its extensive data security and integrity features, transaction logging, ad hoc query and report writing capability and its ability to serve multiple simultaneous users. And if you want the power and the glory that only the world's most advanced data management system can provide, MDBS III is for you. For information on MDBS III and our professional consulting services, write or call Micro Data Base Systems, Inc., MDBS/Application Development Products, 85 West Algonquin Road, Suite 400, Arlington Heights, IL 60005. (800) 323-3629, or (312) 981-9200. **MDBS III. ABSOLUTE POWER.**


# WE'LL GIVE YOU THE POWER.

# YOU TAKE THE GLORY.



**PHOTO 1: CREATE Screen**

Design elements are created in plan view and are developed automatically as a three-dimensional perspective model.

**PHOTO 2: MODIFY Screen**

Four different views can be displayed simultaneously. Changes in any one view will be shown in all four.

the Design Board Professional program must be configured to recognize the hardware. This is done using a separate CONFIG.EXE program, which requests the type of graphics printer, graphics card, and plotter being used. It does not read previous configuration files for use as default values, so every question must be answered each time the program is reconfigured, even if only a single parameter is changed.

Device drivers must be installed prior to running Design Board Professional. If a driver is not installed, or if the wrong driver is installed, the program signs on and freezes up, waiting for word from an input device. The only way out is to reboot, because the program does not accept keyboard input for commands, even to exit.

The manual presents an example AUTOEXEC.BAT file and explains its contents for those who wish to automate the loading process, which consists of configuring the ports, installing operating system device drivers, and issuing the DBPRO command that actually invokes the program.

The Design Board Professional program operates in a loop. It waits for a command. When a command is entered, it requests the graphics data (or text) required to carry out the command. Then, it executes the command, updating the contents of the drawing database and the screen display. Finally, it returns to the top of the loop, and waits for another command.

Design Board Professional is an interactive program. It displays a screen cursor, which consists of a set of cross-hairs, at all times. The screen cursor can be positioned with a mouse or digitizer. In the case of a mouse, the

screen cursor moves whenever the mouse is moved, but it does not reflect the absolute position of the mouse with respect to a certain frame of reference. With a digitizer, however, the position of the screen cursor does reflect the position of the digitizer cursor or stylus relative to the digitizer pad.

This is a menu-driven system. In three of the four screen display modes, a menu area is displayed. On the right-hand side of the screen is a menu block that varies with the mode. Across the bottom of the screen is a menu bar that lists those commands always available—QUIT, CREATE, MODIFY, VIEW, HIDE, FILE, HRD-CPY, CANCEL, and REDRAW.

Commands are executed by moving the screen cursor to the desired block and pressing the appropriate button. Some commands execute immediately; others require numeric data, in which case the program displays a numeric keypad on the screen, so that numbers can be entered in the same manner. The current version also accepts numeric data from the keyboard.

### MODELING CONCEPTS

Design Board Professional provides the designer with a world of wire frame blocks, in which he or she can create models of complex objects. In the mode that is used to create models, these blocks are prisms, or extrusions of plane figures.

The names given to the basic prisms are the names of the cross-sections: *square*, *rectangle*, *N-sided*, *circle*, and *free-form*. Three-dimensional objects that are not blocks or extrusions of plane figures are called *dome* and *surface*. Complex models are created by combining these primitive 3-D objects.

A Cartesian coordinate system represents the models. The X and Y axes correspond to length and width of a plan view; the Z axis corresponds to the height above and below the X-Y plane.

Design Board Professional operates in four different modes, each of which displays the model in a different manner. Each mode provides separate facilities for manipulating the model.

The process of creating a model begins in the CREATE mode. The initial display provides a status area, a menu, and two windows (see photo 1). One window, occupying about two-thirds of the screen, is the creation space. It displays a plan view of a design space, 100 drawing units in each direction, centered on the origin of the drawing universe. The second window displays a perspective view of the objects drawn in the creation space.

As objects are defined in the creation space window, they are displayed in perspective in the perspective window. To ease the task of maintaining orientation, the perspective window also displays a diagram of the three axes, called the *perspective orientation diagram*. The creation space window includes axis labels, again to aid in maintaining orientation. A status area displays the current plan view coordinates of the screen cursor, the distance between successive data points, and a compass bearing when entering objects.

Version 2.04 allows configuration parameters, such as grid size and creation space dimensions, to be saved so the program starts with the proper configuration. The previous version always started with the same set-up.


Once the basic shapes have been entered from the CREATE mode, the



# TEXT PLUS GRAPHICS, MINUS SCISSORS AND PASTE: THE \$2195 PC SOLUTION!

Now you can produce full-function text-and-graphics for reports, manuals, color overheads and slides right on your PC XT/AT. All you'll cut out is the scissors and paste! The CONCEPT 100 System lets you create text on a Wang-like word processor, complete with 90,000-word dictionary and list processing. You can easily create charts and drawings. Or import text or graphics from other systems. Then, use electronic cut-and-paste to combine them on-screen just as you'll see them in hard copy.

CONCEPT 100™ is based on the ANSI GKS\* standard



using the Virtual Device Interface. It offers Tektronix terminal emulation and output options like the ConceptWriter™ or Lasergrafix laser printers. In short, it's a personal publishing system at an unprecedented low price. Now available from your local distributor.


**Call 1-800-631-2692 for more information.**



CONCEPT TECHNOLOGIES, INC.  
A QMS Company

P.O. Box 5277, Portland, OR 97208

## THE DOCUMENT PROCESSORS®



\*Concept Technologies VDI is an implementation of the GKS Virtual Device Interface (VDI) standard.

IBM PC, XT and AT are registered trademarks of IBM Corporation. Lasergrafix is a trademark of QMS, Inc. Tektronix is a registered trademark of Tektronix, Inc.

CIRCLE NO. 117 ON READER SERVICE CARD



model can be edited in the MODIFY mode (see photo 2). Four views of the model are displayed—top, front, right, and perspective. New objects cannot be defined in the MODIFY mode, but the basic shapes defined in the CREATE mode can be rotated, scaled, moved, deleted, and duplicated. The basic shapes also can be stretched, compressed, and distorted to transform them into shapes that are not merely simple extrusions of plane figures.

The VIEW mode reverses the windows of the CREATE mode. The perspective view is displayed in the larger window, and a plan view is displayed in the smaller window. Again, new objects cannot be defined. Existing objects can be rotated, scaled, moved, and deleted, but not duplicated.

The fourth mode of Design Board Professional allows the user to view the model with hidden lines removed. The HIDE command displays a perspective view with hidden lines removed and without the clutter of screen menus.

#### CREATING BASIC OBJECTS

Creating an object, or drawing entity, requires the selection of a shape from the shapes menu—SQUARE, RECTangle, CIRCLE, N-SIDED, FREe-FORM, SURFACE, and DOME—and the entry of the shape's dimensions along all three axes. The three dimensions—length, width, and height—can be entered in three different ways: interactively from the creation space window with the pointing device, from the keyboard, or a combination of the two.

With the exception of the SURFACE command, which creates a plane surface with four edges and vertices, and the DOME command, which creates a hollow spherical dome, the creation of an object begins with the complete specification of the plan view of the object. A cube or a prism of a square cross-section is selected with the SQUARE command, which prompts the user for two points to define the length of an edge and a third point to determine the side of the first edge on which the square will be drawn. When those three points have been entered, the program prompts the user for the elevations of the top and bottom surfaces. A prism of a rectangular cross-section can be created in a similar manner, except that the third point is used to determine the location of the side that is opposite the first edge, and therefore the second dimension, not just the orientation of the rectangle.

The CIRCLE, N-SIDED, and FRE-FRM commands all produce right

cylinders of the specified cross-section. That is, the top and bottom surfaces are superimposed in plan view, and are perpendicular to the Z-axis.

The SURFACE command operates in a slightly different manner. A surface is defined by entering four X-Y coordinates in a circular pattern, but following each coordinate entry with the elevation of the corner. Surfaces need not be square in plan view, or in the true view, and they can be inclined with respect to any or all of the axes. When the surface has been defined, it is displayed as a network of 22 lines dividing the surface into 100 four-sided areas. The 10-by-10 net is the default setting; the MISC option of the STATUS command can be used to set the number of lines in each direction in the range of 2 to 17. The 2-line setting causes only the outline of a surface patch to be displayed, and the 17-line setting causes a surface patch to be displayed as a 16-by-16 net.

A dome is a portion of a sphere—a hemisphere or less—with a plane, circular base. The DOME command prompts first for the angle subtended by the base of the dome. An entry of 180 degrees, the largest entry possible, specifies a hemisphere. Then the program prompts for the center and radius of the base of the dome, and the orien-

*The coordinate display is limited to five digits, providing a universe that stretches from -99,999 to 99,999 drawing units in each of three directions—adequate for any design task.*

tation, allowing the creation of both convex and concave domes. The display of a 180-degree dome resembles a globe cut in half through the north and south poles, rather than at the equator, with the surface defined by the net of latitude and longitude lines (parallels and meridians). A dome of less than 180 degrees is defined by the same number of lines, but distorted in order to produce the flatter shape.

Version 2.04 has added a WALL command to the shapes menu that allows buildings to be drawn more easily. With the earlier version, walls had to be

entered as FRE-FRM shapes, which required entering inside and outside faces separately—beginning at a corner and working around the outside and inside faces to return to the starting point. The WALL command allows the designer to specify a beginning point, an end point, and intermediate vertices (or corners), followed by the elevation of the top and bottom of the wall. The beginning point is displayed as a target; if a vertex is entered within the target, the program closes the figure and ends the command. If a closed wall is not desired, the user can end the sequence with the END command.

The initial creation space display of Design Board Professional is 100 units square—hardly large enough to model skyscrapers—however, the space available for design is much larger. The STATUS-UNITS command allows specification of English (feet and inches) or metric (meters) units, with fractional units displayed either in fractions ranging from  $\frac{1}{64}$  inch to  $\frac{1}{2}$  inch or in decimal fractions.

The display also may be varied to show a larger or smaller portion of the drawing universe. ZOOM displays a smaller volume, ZM-OUT displays a larger volume, and PAN changes the location of the volume in the universe without changing the size. Although the manual does not mention the size of the drawing units, a little experimentation with the ZM-OUT command reveals that the coordinate display is limited to five digits, providing a universe that stretches from -99,999 to 99,999 drawing units in each of three directions—adequate for any design task.

GRID, SET GRD, SNAP, LATCH, and EL-MRK fall into the class of drawing aids, or alignment commands. GRID toggles the grid on and off. The grid is a network of dotted lines that facilitates maintaining orientation in the drawing. The SNAP command is also a toggle. When SNAP is on, data points can be selected only at the interval to which the grid has been set with the SET GRD command. Both the GRID and SNAP command blocks are displayed in reverse video when the modes are on.


The grid has two settings: the working grid size, which determines the snap interval, and the visible grid multiplier, which determines the size of the grid displayed. One of Design Board Professional's weak points is its handling of the grid. By zooming out without changing the grid size, or turning off the grid, the designer may end up with a display that is all grid dots—after an extremely long delay. Fortu-




# Carbon Copy<sup>TM</sup>

## The ultimate remote solution!

Finally, an acceptable way to run personal computers remotely. Carbon Copy is a powerful software tool which allows you to instantly connect your PC with any other PC. Once connected, run any program you wish. Application programs, hardware or software diagnostics, utilities, or any other PC program of your choice can be used remotely with Carbon Copy.



TELEPHONE  
LINES



ORIGINATE MODEM

LOCAL PC

- Carbon Copy<sup>TM</sup> has many uses. Originally, it was developed for use in major corporation support departments, where it has saved thousands of hours in needless telephone calls. Now, the support personnel can *SEE* what the problems are, *INSTANTLY*. No more wasting valuable, productive time in unnecessary endless conversations with an inexperienced user trying to describe a highly technical problem.

- Many major corporations use Carbon Copy as a training tool. They simply call up their remote user (a client, a customer, or perhaps a branch office) and proceed to demonstrate how to use the custom software package developed in-house by their programming staff. The remote user is able to ask and answer questions, working with the training staff in real time, without any staff having to leave their own office.

- When Carbon Copy links the two computers, their screens and keyboards are linked as one. Any keystroke entered on either PC is displayed, in its proper position, on both systems. Anything you could do sitting in front of your computer, you can do on the remote computer, except change a floppy disk!

**Meridian  
Technology**

1101 Dove Street, Suite 120  
Newport Beach, CA 92660  
(714) 476-2224



nately, Ctrl-Break or Ctrl-X terminates a zoom and redraw sequence. Even at reasonable grid settings, the program takes as long to redraw the grid as it does to redraw a simple model, so working with the grid turned off most of the time is advisable.

The LATCH and EL-MRK commands define relations between objects. Specifically, these two commands allow two objects to share a common point, line, or face. LATCH links objects along the X and Y axes, and EL-MRK links objects along the Z axis. LATCH is particularly useful in modeling large, complex curved surfaces. In the latch mode, the vertices of new surfaces snap to the vertices of existing surfaces in elevation if the two vertices are within the current snap resolution. When a vertex of one surface is latched to a vertex of another, the elevation is not specified. Surfaces can be latched only at the vertices. A vertex of a surface cannot be latched to the midpoint of an edge—the elevation must be specified. (Surfaces will latch to the control points of other surfaces.)

As noted above, objects are created by defining both a plan view and top and bottom elevations. That would be a limitation without the AXES command, which allows the user to specify which plane is displayed in plan view. Stated more correctly, objects can be defined either from a plan view or from elevation, or side, views.

The EDIT command replaces the shapes menu with an editing menu. This menu provides five basic commands—ROTATE, MOVE, SCALE, REPEAT, and DELETE—and various qualifiers—LAST, SAME, NEXT, KEEP, and RETRY. In addition, a SHAPES selection returns the user to the shapes menu. Switching between the shapes and editing menus does not disturb the display and alignment menu selections. The EDIT and SHAPES boxes are in the same location on the screen.

The ROTATE command deserves special mention. Although objects generally must be created so that they are aligned with the three axes, they can be arbitrarily rotated with respect to any or all of the axes.

One last command on the CREATE screen is the STATUS command, which displays a menu of three choices—MISC, PERSP, and CREATION. These commands display and allow specification of various system parameters, such as the dimensions of the creation space, the location of the window in the creation space, and whether or not distances between data points are displayed along with absolute coordinates.

The STATUS-MISC selection includes CURSOR, which is a toggle that switches the cursor from full-screen cross-hairs to a small tracking cross. The smaller cursor seems to flicker less than the larger one. (Incidentally, the full-screen cursor on the EGA configuration does not actually stretch the complete dimensions of the screen.)

One selection in the CREATION submenu that deserves mention is a command that allows the specification of two *clipping planes*. If the X-Y plane is displayed in plan view, the command is ZCLIP; if the X-Z plane is displayed, the command is YCLIP; and if the Z-Y

*Several of the editing commands are more powerful in the MODIFY mode than in any of the other modes.*

plane is displayed, it is XCLIP. The clipping planes ease the task of working with a model that has many objects at different elevations, which overlap in plan view. The clipping planes define a slice of the model for display. The top of the slice is defined by the near clipping plane, and the bottom is defined by the far clipping plane.

#### MODIFYING MODELS

The commands of the CREATE mode permit the construction of detailed models from standard shapes. Unfortunately, these standard shapes do not adequately fit the needs of most of the designers who would want to use Design Board Professional. The MODIFY mode provides the commands that customize the standard shapes into shapes of arbitrary complexity. Right circular cylinders can be transformed into cones, square cylinders into pyramids. A prism created with the top and bottom surfaces can be modified so that either the top or bottom, or both, are inclined with respect to the original plane or so that the axis is inclined.

The MODIFY screen provides four views of the model—top, front, right side, and perspective (see photo 2). Almost half the screen is devoted to menus. The upper half of the menu area contains a key diagram, or axis icon area, and the modify menu. In the lower half of the menu area is the edit menu, which provides the five editing commands and the same qualifiers as

does the edit menu in the CREATE mode. However, the MODIFY mode has an additional command, TO-PNT, that can be used to collapse a group of points, perhaps an entire face, to a single point to produce pyramids, cones, and other arbitrary shapes.

Several of the editing commands are more powerful than they are in the other modes. The SCALE ALL command does not scale the model as it is defined in the drawing database, but affects only the perspective view. If the designer defines the model in the CREATE mode, invokes SCALE ALL in the MODIFY mode, returns to the CREATE mode, and then returns to the MODIFY mode once more, the model will be the same in the top, front, and right side views, but the perspective view will be changed.

All the editing commands require selecting the objects to which the command applies. This is done by placing the screen cursor on one of the object's vertices and clicking the pointer button or by drawing a box around the item. When an item has been selected, it is highlighted, and the KEEP qualifier executes the command. Most commands can apply to several objects. Selecting several objects that are superimposed in one or more views can be frustrating, but practice does improve performance.

The MODIFY mode provides the facilities to create curved surfaces of arbitrary complexity. As noted above, the CREATE mode allows the creation of plane surfaces, and it displays those surfaces as 10-by-10 grids. The program actually defines a surface as a set of 16 control points that divide the surface into nine areas. In the MODIFY mode, the program displays only the 16 control points and a grid of 16 lines.


The control points control the shape of the surface, according to the Bezier Theory of Surfaces. If the control points are arranged in a plane, the resulting surface is a plane. Surfaces are planes when originally created, with the exception of domes.

Displacing one or more control points from the original plane distorts the plane into a curved surface. The surface remains coincident with the 12 points on the periphery of the surface, but all points can be moved from the original plane, allowing surfaces to curve in one or two directions.

A net of 16 control points is hardly sufficient to create surfaces of arbitrary complexity, but many surface patches can be LATCHed together to create large surfaces with many control points. A complex surface can be modeled with



# They live together. They might as well talk to each other.



Your PC and IBM System 34/36/38 spend a whole workweek under the same roof. But if they're not communicating, they're not as productive as they could be.

That's why Tecmar created the 5251/11 Emulator. With it, your IBM PC, XT, AT, or compatible can communicate with your System 3X by emulating an IBM 5251-11, 5291, or 5292-1 terminal.

In addition to emulation, the 5251/11 will let you use the Tecmar QIC-60™, a sixty megabyte tape system to back up data on your System 3X.

Compatibility isn't a worry. The 5251/11 supports all IBM System 3X and file transfer software. The printer you have now will work as a host-addressable printer. And it'll be able to run at full speed — up to 600 lines per minute.

What won't the half-sized board 5251/11 do? It won't slow down a DOS application or host session while you're printing. And it won't cost nearly as much as a System 3X terminal and printer.

To find out how the 5251/11 Emulator can help in your office, visit your Tecmar dealer. Or call us at (216) 349-1009.

And start a productive friendship.


## **TECMAR**

6225 Cochran Road, Solon, Ohio 44139-3377


Telephone: (216) 349-1009; Telex: 466692

CIRCLE NO. 225 ON READER SERVICE CARD



**PHOTO 3: VIEW Screen**

The VIEW screen shows the perspective view as the main view. It can be rotated by alterations made to either the eye, the target, or the height variables.

**PHOTO 4: Perspective View**

The perspective view of the three-dimensional model can be processed to remove hidden lines by the HIDE command. The display does not have any menu areas.

many small surface patches, whereas a simple surface can be modeled with a few large surface patches.

The surface patch does not appear contoured in the MODIFY screen, but rather appears as a faceted surface through the control points. In both the VIEW mode and the perspective view of the CREATE screen, however, the surface does appear contoured.

The number of lines to be shown in the contoured display can be set by selecting MISC from the STATUS menu. The default value of 11 lines in each direction can be changed to 2-17 lines.

The MODIFY screen includes a PROJECT command that eases the task of creating shapes with inclined surfaces. The basic shape menu still creates right cylinders with both the top and bottom surfaces parallel to the X-Y plane (or X-Z or Y-Z). Modifying these surfaces under the previous version meant moving edges or points until the surface was in the desired plane. PROJECT allows specification of the surface to be projected and of the plane onto which it is to be projected, after which the cylinder is extended or truncated so that the specified surface is coincident with the projection plane.

The ruler display is available in the MODIFY mode, as well as in the CREATE mode. This is an important enhancement for the latest release, because it greatly eases the task of editing in this screen. Earlier versions required an iterative procedure.

**VIEWING MODELS**

The VIEW mode provides the ability to see the three-dimensional model in perspective, and at a larger size than

that of the perspective view of the CREATE screen. The VIEW mode shows the perspective view in the large window on the left half of the screen and the plan view in the smaller window over the menu area (see photo 3). This is the opposite of the CREATE screen.

The menu changes when the VIEW screen is displayed. The menu bar displays an additional command, HIDE, and the shapes menu is replaced with the editing menu.

The display controls—ZOOM, ZM-OUT, FIT, and PAN—apply to both windows; the editing commands apply only in the perspective window. While in the VIEW mode, the perspective view can be edited—individual objects, or the entire model, can be rotated, moved, scaled, and deleted. Editing the entire perspective—for example, rotating the entire model—does not affect the drawing database, but only the perspective view of it. The model remains in the orientation in which it was created, relative to the axes.

The EL-MRK command, which displays the top and bottom elevations of shapes, is available in both the VIEW and the CREATE screens. This command is useful for selecting an object to be edited from the perspective view of the VIEW screen, because it highlights the object. The object can be selected from either the large perspective view or the smaller plan view.

All parts of the current model are continuously displayed in perspective. Each time an object is added, deleted, or modified, the perspective view is updated. A perspective view is determined by several parameters. The first is the location of the viewer in relation to the

model, often called the *viewpoint*, but referred to simply as the *eye* by Design Board Professional. The next parameter is the direction in which the viewer looks in relation to the model, called the *target*. The viewer is at location eye, and looks toward location target.



The eye-target line is the axis of a portion of the universe or creation space called the *cone of vision*, which encloses the model or portion of the model that is visible. Actually, the cone of vision is a four-sided pyramid, because the view of the model is rectangular. The apex is at the eye, and the target is inside the pyramid, halfway between two clipping planes. The viewer sees only the objects or parts of objects inside the cone of vision and between the clipping planes. Objects in front of the near clipping plane and behind the far clipping plane are not displayed. The cone of vision cannot include an angle that is larger than 180 degrees, meaning that both the near and far clipping planes must be in front of the eye location.

Another point also affects the perspective view: the *center*. This point initially coincides with the target at the location on the axis of the cone of vision and halfway between the clipping planes. However, the target always remains directly in front of the eye, and the center always remains on the axis of the cone of vision, which can be skewed by certain commands. For example, the PAN command moves the eye and the target in a direction parallel to the clipping planes, but leaves the center unaffected. Thus, the perspective of a model is not changed by PAN. It does not produce the effect of moving



# PROUD.

To build a workstation good enough to put your name on, use the modular building blocks we put our name on. ACS, a company dedicated to the support of OEM's in pursuit of excellence.



**ACS-1000**

**THE POWER . . .** a single board SuperComputer that is **100% IBM XT compatible** from its mounting holes to its memory mapping, but with more speed: **4.7 and 8 MHz**. Floppy controllers and network communications are built right onto the motherboard along with a SASI hard disk interface and as much as **1 Meg** of memory.

**GraphAx**

**THE GLORY . . .** a graphics card (one card) with more than **20,000,000 pixels** of video memory powerfully arrayed in 5 planes (**32 Colors**). Driven by an on board graphics processor, this **2K x 2K** color card is compatible with most of the popular CAD/CAM packages . . . like AUTOCAD, PC Draft, GKS, and Tektronics Emulators . . . packages that run up to 5 times faster and virtually eliminate redraw by **zooming and panning** in memory instead of constantly recalculating.

**Peacock**

**AN IMPRESSIVE DISPLAY**  
The Peacock high resolution monitor will put all this technology up front where it counts. With a horizontal scanning frequency of **33.5 KHz** and a bandwidth of **40 MHz**, this RGB monitor gives you a **1K x 1K** window on the world with profitable OEM pricing.

If you're going to build a workstation, you might as well build the best. The people at ACS are ready to help. For more information, call or write:

ACS International  
2105 Luna Rd. Suite 330  
Carrollton, Texas 75006  
**214-247-5151**  
**TLX 709748 ACS UD**

In Canada:  
Soltech Industries  
9274 194th St.  
Surrey, B.C. V2T4W2  
**604-888-2606**

CIRCLE NO. 110 ON READER SERVICE CARD



IBM XT, Autocad, PC Draft, & Tektronics are trademarks of IBM, Autodesk, PCT and Tektronics respectively. ACS-1000, GraphAx & Peacock are trademarks of ACS.



### 3-D MODELING

in a three-dimensional world—that is, a constant change in perspective view. Instead, the effect is that of walking past a perspective drawing, or projection of a 3-D drawing on a plane.

Like PAN, the commands ZOOM and ZM-OUT also leave the locations of eye, target, and center unmoved in relation to the model. They enlarge or reduce only the portion of the model that is displayed in the window. Again, the effect is that of moving toward or away from a perspective drawing, rather than of moving through a landscape along the line of sight.

In the VIEW mode, the ROTATE, MOVE, SCALE, and DELETE commands affect the perspective view of the model in that they change the relationships between the objects in the model. The eye, target, and center points remain fixed in relation to the space in which the model was created. Rotating, moving, scaling, and deleting objects requires that the perspective view be updated to reflect the changes.

The perspective view may be altered without changing the model. SETVIEW allows the specification of the eye and target points in all three dimensions. When both points have been located, a new perspective view is generated, with the target and center points again coincident.

The PERSP option of the STATUS command provides another mechanism to refine perspective views. Invoking PERSP first displays the key statistics about the perspective view. Specifically, the program displays the coordinates of the eye, target, and center points in three dimensions, the distance of the near and far clipping planes from the eye, the front width, and the spread.

Of the values displayed, the eye, front width, near distance, and far distance can be changed directly by choosing the name of the value and typing in new values or choosing the new values from the calculator keyboard displayed on the screen. The remaining values cannot be set directly; they are calculated from the values that can be set.

The SETVIEW and PERSP commands provide similar, though not identical, facilities. SETVIEW allows the location of the eye and target points to be set directly. The ZOOM and PAN commands can be used in conjunction with SETVIEW in order to vary the spread of the cone of vision. The PERSP command provides control of the eye point, clipping planes, and the cone of vision, but not of the target point. The SETVIEW command is available to the user only in the VIEW mode, but the

PERSP command can be used in both the CREATE and VIEW modes.

All these view management facilities taken together provide a means of moving around and through the model for a limitless number of presentations. The value of the continuous perspective generation facility should be obvious to any designer who relies on perspective views to portray design concepts.

While Design Board Professional is not a production drafting system, it does provide all the facilities necessary for the preparation of schematic plans. As the designer develops the schematic plan, the perspective view is updated continuously. Therefore, the designer has the perspective view available as a feedback device at all times.

After the model is complete, the perspective generation facility allows the designer to select the view that best portrays the design. This option is a vast improvement over the selection of stan-

**T***he value of the continuous perspective generation facility should be obvious to any designer who relies on perspective views to best portray design concepts.*

dard views by rote or producing several views manually and then selecting the one that seems best for development into a full color rendering. The HIDE command processes the drawing and removes the hidden lines. The display does not have any menus visible at this point allowing a full perspective view of the drawing (see photo 4).

#### PLOTTING DRAWINGS

Plotting is initiated with the DRAW command from the main menu bar. DRAW displays a menu that includes the selections, PLOT, PRINT, and SCREEN. If the program has been configured for both a plotter and printer, it asks whether to print or plot the drawing. After that selection is entered, the program asks whether the drawing is to be scaled if a plan view is being plotted. If so, it suggests a scale and requests confirmation before the plotting/printing operation begins. If the suggested scale is not accepted, the numeric keypad is displayed, and a scale factor is requested.

It must be specified as the fraction of an inch that represents a foot.

If a perspective view is being plotted, the program does not request a scale factor. For a printer plot, it fits the view to an 8½-by-11-inch sheet of paper; for a pen plotter, it requests the media size from a list of choices.

The last question asked is whether to erase hidden lines before plotting. Hidden line erasure takes longer than the plot itself, but is often essential. As the hidden lines are removed, the drawing is displayed on the screen. When the screen display is complete, plotting begins. Version 2.04 includes a revised hidden line removal algorithm that speeds the process slightly.

The SCREEN selection in the DRAW menu displays the current main display, with the view of the model in the left window without the clutter of menus and auxiliary views. If the program is properly configured (to be used in conjunction with the Design Board Illustrator), these views can be saved as picture files by typing Ctrl-G.

File handling is accomplished with the FILE command on the main menu bar. Invoking FILE displays a file menu that includes the commands RECALL, SAVE, MERGE, APPEND, CONTINUE, LIST, MORE, ENTER, and CLEAR, and a block for file name entry, NAM=. The commands must be selected with the pointing device, but file names can be typed in from the keyboard, or called up with the LIST command and selected with the pointing device.

Files are not saved automatically at the end of a session, nor are they written to disk periodically during a session. The user has to save the model, and saving it does not clear the model from the machine's memory. Both the SAVE and RECALL commands automatically append the file extension .DB3, and both commands can be used with LIST in order to produce a list of existing files on the screen.

MERGE and APPEND allow models stored on disk to be inserted into the current model. The MERGE command places the model in the merged file at the coordinates at which it was created. APPEND allows the location of the inserted model to be specified. Therefore, MERGE permits segmentation of a model in order to speed response, and APPEND allows the use of standard components, or symbol libraries, so that these standard components can be inserted arbitrarily. The symbol library capability is a feature that is essential to any system claiming to approach the level of a CADD system.



### ADVANCED MODELING

The Design Board Professional manual includes a section entitled "Advanced Modeling," which illustrates several techniques for creating complex models and sophisticated presentations. The first technique presented is one for creating four-view plots—the standard three-view orthographic drawing plus perspective view—on the same sheet of paper. The technique relies on the MODIFY mode to position the object in each of the views in a different quadrant of its respective window. After the views are set up, each view can be plotted in turn, without removing the media from the plotter.

One of Design Board Professional's drawbacks is that it does not use the disk as a virtual storage device; it writes to disk only when the SAVE command is issued. Thus, the size of the model that can reside in memory at any given time is limited. (Some production drafting systems update the disk file periodically, so the absolute limit on drawing file size is imposed by the operating system limits on file size (the deterioration in response time redrawing large models may impose a lower, practical limit on drawing size.)

However, several models can be plotted on the same sheet of media, to produce a hard-copy model that is larger than the largest model that can be held in memory. The technique is essentially the same as that used to create four-view plots—running several plots in succession without removing the media from the plotter. The individual models used to create the composite model must be constructed in the proper locations in the creation space, all using the same coordinate system. The individual models must be set up so that the perspective view parameters, such as eye and target, are identical. This technique is equally suited for large plans and perspectives. The manual presents an example in which a composite city planning model is plotted from individual models, each consisting of a single block.

The "Advanced Modeling" section of the manual also presents a technique for creating a hollow object—not a trivial matter in a wire frame modeler, because it does not represent solid objects or their surfaces, only the lines defined by the intersection of surfaces.

A feature that large system CADD manufacturers never fail to mention when trying to sell a system is walk-through viewing. In fact, most of them extend the concept to "fly-around-and-in-and-through" viewing. Design Board

Professional provides the same capability with the SETVIEW command. The manual illustrates a walk-through tour of the PROHOUSE model, included on the disk of models provided with the system. Creating a walk-through tour is somewhat time-consuming with Design Board—just as it is on even the largest and most powerful systems.

Another advanced modeling technique covered in the manual is the use of clipping planes as a means to simplify the task of detailing models, especially those that require detailing at various elevations—such as a multistory building. The clipping plane feature allows the designer to work in a slice of the model, suppressing the display of

**O**ne of Design Board Professional's drawbacks is that it does not use the disk as a virtual storage device; it writes to disk only when the SAVE command is issued.

lines above and below the slice. The program also limits the selection of items for modification. Only visible features can be selected.

Another example of an advanced modeling technique is the creation of a complex curved model—a pitcher. This stresses the importance of the Bezier technique and the LATCH command.

### USE WITH OTHER PROGRAMS

Design Board Professional is primarily a conceptual modeling tool. It lacks many features of production drafting programs—features such as automatic dimensioning, automatic cross-hatching, polylines, layers, and creation of blocks. MEGA CADD does not pretend that this product should be the only CAD tool in the designer's toolkit. Instead, the company suggests that it should be used in conjunction with a production drafting program. MEGA CADD has gone to some length to ensure that its hardware configurations are common to three supported production drafting programs: AutoCAD (versions 1.4 and 2.x), CADVANCE, and VersaCAD.

MEGA CADD also provides a translator program, called Design Board Link, that can extract two-dimensional views from Design Board Professional models

and produce drawing exchange files for use with the three 2-D programs that were just mentioned.

DBLINK is not an interactive program. It requests the type of exchange file it is to create, the source file name (a Design Board Professional file with the extension .DB3), and the type of information to extract.

The program allows the extraction of orthographic, isometric, or saved views. If an orthographic view is selected, an additional six choices are available—front, back, left, right, top, and bottom. The isometric selection produces eight additional choices, depending upon the views to be displayed on the faces of the isometric cube.

The saved view selection provides only two choices: perspective or axonometric. Axonometric views are similar to isometric views in that lines and planes do not converge to vanishing points. However, an isometric view is constructed at standard angles (the eye-target line in a true isometric view would make an angle of 35 degrees 16 minutes with the X-Y plane and a 45-degree angle with both the X and Y axes), whereas the viewpoint of an axonometric view can be specified. Both perspective and axonometric views extracted from Design Board Professional files are dependent upon the perspective view saved in the drawing file. All views can be transferred with hidden lines displayed or removed.

DBLINK was tested with AutoCAD 2.1, transferring the several views of the PROHOUSE model from Design Board Professional to AutoCAD. The process went smoothly, with only one surprise. The resulting AutoCAD drawing had an origin at 0,0 in one case, and in the third quadrant (both coordinates negative) in another. This is not a serious problem, but most users would reposition the entire model to the first quadrant (both coordinates positive).

DBLINK is a one-way program. It extracts information from Design Board files and produces drawing files for 2-D programs, but it does not process 2-D CAD files to produce Design Board files. Although the combination of Design Board Professional and a 2-D program allows the preparation of working drawings from a 3-D model, it does not allow the type of 3-D production drafting that large systems provide, where orthographic views, perspectives, and isometric views can be displayed simultaneously and used as creation spaces interchangeably.

MEGA CADD and VersaCAD have announced a joint distribution agree-



ment to afford users the benefits of having a single source for the complete 2-D/3-D CAD software system. The arrangement does not involve any special products—both Design Board Professional and VersaCAD are the same product whether purchased from separate sources or a single source.

### 3-D MODELING LEADER

Design Board Professional is an excellent conceptual modeling tool. The availability of perspective views at the stroke of a key enhances the modeling process by making it more interactive. For some designers, this may be the only CAD tool required. For others, the program will be one component in a system, handling the conceptual modeling task, while another program handles the production drafting. Given this philosophy, the only omission from the package is a color shading facility. The automatic saving of a file when the program is exited also would be a simple but valuable addition to the package. The risk of losing unsaved data is too great in the product's present form.

Although Design Board Professional's wire frame modeling facility does not provide the appealing images associated with solid modelers, it allows the construction of complex wire frame models that are easily converted to working drawings or plotted in a variety of views. Drawing files are limited in size because the drawing is in RAM. However, the limits are adequate for the conceptual or schematic modeling of most large projects. With the use of techniques described in the manual, complex models can be created in modules and plotted on the same sheet for simultaneous presentation.

In addition, Design Board Professional is ideal for the creation and presentation of details as a supplement to working drawings created with the production drafting system. Wire frame drawings can be used to illustrate assemblies of parts in see-through form and with exploded views. Such illustrations are difficult to produce with a 2-D package, but are relatively straightforward using Design Board.


A Design Board Professional 3-D modeling system based on a PC, XT, or AT can be assembled for less than \$10,000. A complete system—large plotter, digitizer, and a production drafting program—should not exceed \$20,000.

Creating simple models is a snap; creating complex models, especially those that require substantial use of the MODIFY screen, is not so simple. Like any powerful program, Design Board

Professional demands considerable effort and regular use before achieving its full potential.

The product is obviously aimed at architects, consulting engineers, and planners—judging from the models furnished with the package—but the syntax of commands and terminology used in the manual is general enough to be applicable to designers in any field.

MEGA CADD seems intent on being the leader in the 3-D modeling field. Design Board Professional 2.04 is a significant improvement over its predecessor,

and all indications are that more improvements are yet to come. 

*Design Board Professional: \$1,750*  
*MEGA CADD, Inc.*

*The Court in the Square*  
*410 Second Avenue South*  
*Seattle, WA 98104*  
*206/623-6245*  
**CIRCLE 317 ON READER SERVICE CARD**

*Victor E. Wright is the manager of process engineering at Luckett & Farley, located in Louisville, Kentucky. He has written two books that deal with CAD and software.*

## DISCOVER THE LANGUAGE OF ARTIFICIAL INTELLIGENCE

### PROLOG V

*Interpreter for MS-DOS/PC-DOS*

At last! A Prolog with enough muscle to handle real-world applications for UNDER \$100! Discover why Japan has chosen Prolog as the vehicle for their "Fifth Generation Machine" project to design intelligent computers.

**CHOOSE FROM TWO GREAT VERSIONS:**

**PROLOG V-Plus**  
**\$9995**

- ☐ More Than 100 Predefined Predicates
- ☐ Large Memory Model (to 640K)
- ☐ Floating Point Arithmetic
- ☐ 150-Page User's Manual and Tutorial plus Advanced Programming Documentation
- ☐ Co-Resident Program Editor
- ☐ Calls to Co-Resident Programs
- ☐ Text and Graphic Screen Manipulation

**PROLOG V**  
**\$6995**

- ☐ 70 Predefined Predicates
- ☐ Small Memory Model
- ☐ Integer Arithmetic
- ☐ 122-Page User's Manual and Tutorial

**FREE FREE FREE FREE FREE FREE**  
*Programming in Prolog by Clocksin & Mellish, \$17.95 value Available with purchase of PROLOG V-Plus only. Offer valid through March 31, 1986.*

#### STANDARD FEATURES ON BOTH:

- ☐ Clocksin & Mellish-Standard Edinburgh Syntax.
- ☐ Extensive Interactive Debugging Facilities
- ☐ Dynamic Memory Management (garbage collection)
- ☐ Custom-Designed Binder and Slipcase

#### THE CHOICE OF UNIVERSITIES

Generous university site licenses and an excellent teaching tutorial and reference guide have made PROLOG V the choice of universities nationwide. Call for details.

**PHONE ORDERS: 1-800-621-0852 EXT 468**

☐ **PAYMENT ENCLOSED \$**

CA residents add 6% sales tax

☐ **CHARGE MY:** ☐ MasterCard ☐ Visa

Card No. \_\_\_\_\_ Exp. Date \_\_\_\_\_

Signature \_\_\_\_\_

Mr./Mrs./Ms. \_\_\_\_\_  
(please print full name)

Address \_\_\_\_\_

City/State/Zip \_\_\_\_\_

**PROLOG V-Plus \$99.95**  
**PROLOG V 69.95**  
**UPGRADE ONLY 40.00**  
Return factory diskette and \$30 plus \$10 Handling

**SHIPPING:**  
\$ 5.00 U.S.  
7.50 Canada  
10.00 Caribbean,  
Hawaii Air  
20.00 Overseas Air

**COD Orders Not Accepted**  
**15 day check clearance**



**CHALCEDONY SOFTWARE**

5580 LA JOLLA BLVD.  
SUITE 126  
LA JOLLA, CA  
92037  
(619) 483-8513

*Upgrade to PROLOG V-Plus for only the difference in price plus a handling charge.*

**NO RISK OFFER**  
*Examine the documentation at our risk for 30 days. If not fully satisfied, return with disk still sealed for full refund.*

**CIRCLE NO. 122 ON READER SERVICE CARD**



# The personal computer that raised high performance to new heights.

If you work with high volumes of information,  
you need answers fast.

You need a personal computer that's up to the task.

Which is why IBM created the Personal Computer AT® system. It's changed a lot of ideas about business computing.

The idea of "fast" has become much faster. The idea of "data capacity" has become far greater.

There are new definitions of "power" in a stand-alone PC. While phrases like "sharing files" and "multi-user systems" are being heard more often.

And surprisingly, words like "affordable" and "state-of-the-art" are being used *together*.

Clearly, the Personal Computer AT is different from anything that came before. And what sets it apart can be neatly summed up in two words.

Advanced Technology.

If you've ever used a personal computer before, you'll notice the advances right away.

To begin with, the Personal Computer AT is extraordinarily fast. That's something you'll appreciate every time you recalculate a spreadsheet. Or search through a data base.

It can store mountains of information — literally thousands of pages' worth — with a single "hard file" (fixed disk). And now you can customize your system to store up to

30,000 pages with the addition of a *second* hard file.

The Personal Computer AT runs many of the thousands of programs written for the IBM PC family. Like IBM's TopView, the program that lets you run and "window" several other programs at once.

Perhaps best of all, it works well with both the IBM PC and PC/XT. Which is welcome news if you've already made an investment in computers.

You can connect a Personal Computer AT to the IBM PC Network, to share files, printers and other peripherals with other IBM PCs.

You can also use a Personal Computer AT as the centerpiece of a three-user system, with your existing IBM PCs as workstations.

Most important, only the Personal Computer AT offers these capabilities *and* IBM's commitment to quality, service and support. (A combination that can't be cloned.)

If you'd like to learn more about the IBM Personal Computer AT, see your Authorized IBM PC Dealer, IBM Product Center or IBM marketing representative. For a store near you, call 1-800-447-4700 (in Alaska, call 1-800-447-0890).

## The IBM Personal Computer AT, for Advanced Technology.





IBM®



**MOUNTAIN'S NEW  
PC DRIVECARD IS  
THE HARD CARD  
TO BEAT! 10 OR  
20MB.**





Hardly a day goes by without PC users demanding more storage and speed in less space at an affordable price.

Enter Mountain's new DriveCard.™

A self-contained 3½" hard disk drive with controller on a single plug-in card that fits neatly inside an IBM,® AT&T,™ COMPAQ® or compatible computer.

**10MB...\$1,095. 20MB...\$1,195.**

Unlike the other plug-in card on the market today, DriveCard gives you a choice of 10 or 20 megabytes of fast, reliable hard disk storage in a single slot. Without sacrificing one of your existing floppy disks.


Installation couldn't be easier. Simply plug DriveCard into an expansion slot inside the PC and you're ready to run. It requires no wires, leads, cables, switches or extra power supply.

DriveCard provides the same software compatibility as the factory original built-in drives, while actually improving your system's overall performance.

What's more, DriveCard is 100% compatible with DOS 2.1 and higher, PC IX, UNIX,™ and XENIX.™ And comes ready to support the 3COM Ether Series, Novell, IBM's PC/LAN, NESTAR, STARLAN™ and other networks.

#### **ONE YEAR WARRANTY.**

DriveCard is backed by a 12-month warranty featuring "Ready Replacement" within the



first six months. If anything goes wrong, simply take it to your nearest Mountain dealer for service or

return it to Mountain for replacement.


#### **WIDEST RANGE OF STORAGE OPTIONS.**

Mountain offers the industry's widest range of high-performance storage upgrades. Our field-proven FileSafe™ internal and external disk, tape, Mini Mountain and combo systems are known worldwide for their outstanding value.

#### **A ROCK-SOLID REPUTATION.**

Mountain's hard-earned reputation among business users over the last eight years for responsiveness, innovation and reliability means we'll be there when you need us.

Find out today why Mountain's new PC DriveCard is the hard card to beat. Call for more information and the name of your nearest Mountain dealer.



# Mountain®

**THE PEAK OF PERFORMANCE**

**1-800-458-0300** (in Calif., 1-800-821-6066)

CIRCLE NO. 194 ON READER SERVICE CARD

Mountain Computer, Inc., 360 El Pueblo Road, Scotts Valley, CA 95066, (408) 438-6650.  
TWX 910-598-4504. Mountain products are distributed and sold worldwide. Call or write for the name of the dealer or distributor nearest you.


\*registered trademarks and \*trademarks of Mountain Computer, Inc., American Telephone and Telegraph Co., International Business Machines Corp., COMPAQ Computer Corp., Microsoft Corp., and AT&T Bell Labs.  
©1985 Mountain Computer, Inc.



# Set Implementation

TOM SWAN

*Made popular in Pascal, sets also can be used in assembly language programs to help the user simplify many applications.*



The use of sets in assembly language programming holds some pleasant surprises. When sets are added to an 8086/88 subroutine library, for example, they reduce the size and increase the running speed of the programs. The added value of sets and set operators is illustrated in the following simple example: A programmer needs to input a character from the keyboard and test if the character typed is a digit 0 to 9 or a capital letter A to Z. If any other character is entered, an error routine should be called, otherwise the program should continue. One method often used for this operation in 8086/88 programs is shown in figure 1.

Although the program works correctly, continuing only if a legal character is typed, this approach should be avoided for several reasons. First, the logic may be difficult to follow. Unless the code is studied thoroughly, the purpose of, say, the third jump may not be clear. Second, a knowledge of the underlying character set is assumed. In ASCII, the binary values for the characters 0 to 9 are less than those for A to Z. With another character set, this might not be true, and the program would fail. Third, tests for additional character ranges would increase the length of the program, making the code more difficult to understand and more prone to catching a bug.

All of these problems can be avoided with the use of sets. By declaring a set of the legal characters ex-

pected by the program, the example can be rewritten as in figure 2.


Besides improving the clarity of the program, additional characters can be tested without increasing the size of the test or slowing it down. With sets, not a single byte is added. (The size of a set in memory, as will be shown, does not depend on the number of elements it contains.) Also, the improved program assumes nothing about the underlying binary character values.

This article deals with the construction of sets in assembly language, how they are represented in memory, and how to include them in programs. SETS.EXT and SETS.ASM (listings 1 and 2, respectively) are in IBM's MASM format, and after assembling, form a stand-alone module that can be linked to host programs with DOS LINK. The linking process is explained with a test program, SETTEST.ASM (listing 3), also written in MASM format.

## COMPARING SETS

A set can be thought of as a box or sphere that can contain objects of a certain *base type*. For example, a set of colors might exist with a base type equal to the 16 colors available on a PC equipped with IBM's Color Graphics Adapter. Figure 3 shows a set of three of those colors—green, red, and yellow—represented by a circle. Elements in the set are located inside the circle; elements not contained in the set are outside the circle. All available colors







**FIGURE 1:** Sample Test Code

```

begin:
    call input          ;get character into dl register
    cmp dl,'0'          ;is it less than 0-9, A-Z?
    jb  begin           ;if yes, repeat
    cmp dl,'9'          ;is it in 0-9 range?
    jbe continue        ;if yes, jump to continue
    cmp dl,'A'          ;is it less than A?
    jb  begin           ;if yes, repeat
    cmp dl,'Z'          ;is it in A-Z range?
    ja  begin           ;if no, repeat, else continue
continue:

```

Code such as this, written in 8086/88 assembly language, is often used to test if a character falls within a certain range.

**FIGURE 2:** Improved Test Code

```

begin:
    call input          ;get character into dl
    lea di,legal_chars  ;address set of legal characters
    mov ah,0            ;prepare for set membership test
    call sets           ;test if dl is in set
    jne begin           ;if no, repeat, else continue
continue:

```

The code in figure 1 is made smaller and faster by the use of sets, as shown above (also in assembly language).

could be inside the set, or the set could be empty. Several sets could exist, each containing a different combination of colors. The only restriction is that no color can be both inside and outside a set at the same time. The programs in this article manipulate enumerated sets. Such sets are finite in principle and small in practice.

In mathematics, parentheses or braces are used to indicate sets; in programming, brackets are more common. The null set is represented by empty brackets: []. The set of colors in figure 3 can be shown this way: [GREEN, RED, YELLOW]. The set of all colors can be shown with ellipses between the first and last possible elements: [BLACK...HI-WHITE]. This is the same as listing every element of the set's base type inside the brackets.

Two sets can be compared in much the same way as two simple numbers. Using the color set from figure 3, the comparisons in figure 4 are all true. Equality (=) and inequality (<>) tests work as might be expected—two sets are mathematically equal only if they have the exact same members. The tests for inclusion (<= and >=) may not be so obvious. A set is less than or equal to another set if all of its members are contained in the other set: A <= B is true only if the members of A are also members of B—if A is a subset of B. Notice in figure 4 that any set is always greater than or equal to the null set []. Although it contains nothing, the null set is valid and can be used in all comparisons and operations.

Another set comparison is the membership test. In this test, a set is examined for a particular element; the operator is the word IN. The two membership tests in figure 4 determine if RED is or is not in a set of colors. Both statements are true.

Sets not only can be compared mathematically, but combined mathematically as well. Again, familiar mathe-

matical symbols are used (see figure 5). Some of the results may surprise users unfamiliar with sets and set operators. The operators are union (+), difference (−), and intersection (\*). They work as follows (assume two sets, A and B, are to be combined into a new set C):

- Set union (C = A + B). The set of elements C equals all the elements in set A plus all the elements in set B.
- Set difference (C = A − B). The set of elements C equals the elements in set A, that are not also in set B.
- Set intersection (C = A \* B). The set of elements C equals those elements found in both sets A and B.

Figure 5 shows sample expressions using the set of colors from figure 3. Each statement is correct.

### SETS IN MEMORY

Because one element is either in a set or *not* in a set, it can be stored in a single bit, which is equal only to 0 or 1. Elements are either present (1) or absent (0). A set of elements, then, is easily represented in memory as an array of bits, with each bit reserved by the computer for one potential set element.

Figure 6 shows how the set in figure 3 might be represented. In this example, a maximum of 16 bits (and therefore 16 elements) is possible. This is adequate for a limited set, such as the foreground colors on the PC, but would not do for the 128 symbols of the ASCII character set, for example. For larger sets, simply increase the number of bits. Any size set may be constructed.

The number of elements in a set has nothing to do with the size of the set in memory. In figure 6, if all of the colors are in the set, then all 16 bits in the set variable would be 1. If the set contains no colors, then all of the bits would be 0. The saturated set [BLACK...HI-WHITE] and the null set [] take the same amount of memory.

However, the number of *possible* elements does affect the size of a set;

this is calculated in bytes with a simple formula for *n* elements:

$$\text{bytes} = ((n - 1) \text{div } 8) + 1$$

Applying this formula, a set of any combination of 256 elements, numbered from 0 to 255, would take 32 bytes of memory. Similarly, 512 elements (0 to 511) would occupy 64 bytes. Remember that *n*, called the *cardinality* of the set's base type, represents the maximum number of possible elements, not the actual number of elements contained in one set variable.

### SETS IN PROGRAMS

Suppose a programmer were writing a custom program for a motel manager who has 190 units to rent. Some of the units are doubles, some are singles, and a few are luxury rooms with kitchens and sitting areas. Occasionally, a unit must be taken out of service for repairs and cannot be rented.

The manager wants a quick way to indicate which units are occupied and which are available, and further, which of those are singles, doubles, or luxury apartments. Because the motel is divided into wings, the manager also should be able to show this information for the north, south, east, or west divisions. This example will assume that the motel rooms are numbered from 0 to 189. (A real situation might involve room numbers such as A-15N and C-99S. These numbers first would have to be converted, or mapped, to the numbers 0 to 189 by the program.)

This is a database problem that could have several solutions. Each room, for example, could have a record with fields for indicating if the room is a single or double, whether it is occupied, if it is being repaired, and so forth. This is certainly a reasonable approach, but displaying the status of all rooms in a certain category—for example, all unoccupied south wing singles—would probably require a



sequential search of the database. With sets the data are available instantly, and the programming is greatly simplified.

Set variables are needed for each category. Figure 7 shows how this might be programmed in assembly language. A set data type is defined as a 32-byte variable using the assembler's **STRUCT** operator. Then variables for NORTH, SOUTH, EAST, WEST, SINGLES, DOUBLES, LUXURY, and OCCUPIED are defined and included as part of the program's data segment.

If the manager enters a command to display all unoccupied singles in the south wing, the Pascal fragment in figure 8 shows how the request could be satisfied. (It is sometimes helpful to express ideas in a structured language, such as Pascal, before writing an assembly language program—a welcome change to flow charts.)

Yet, an even easier and faster way to satisfy this request calls on the set intersection and difference operations. A new set can be formed that satisfies the search argument "in the south wing, single, and unoccupied." The expression is written in this way:


```
TEMP = (SOUTH * SINGLES) -
        OCCUPIED
```

That is, TEMP is the set of room numbers whose members are in both sets SOUTH and SINGLES, but are not in the set of OCCUPIED rooms. This expression, coded in an assembly language fragment, is listed in figure 9. Considering the conventional database programming required to produce the same results—opening a file, reading each record, and testing various fields stored in the record—the use of sets reduces the amount of writing necessary.

## LIMITATIONS

Some other searches may not be as easily accomplished with sets. For example, the motel manager undoubtedly would want to keep a list of the reservations for certain types of units, listing starting and ending dates, along with the names of the persons who made the reservations. While sets are useful for recording a variety of limited attributes, they are not as good for recording names and addresses, telephone numbers, and dates. (Even if it were possible, constructing the set of all persons in the country or world, and then assigning a reservation bit to each in a set variable would hardly be practical.) The point is that, while all data can be represented as belonging to a set of a certain class, some are more practically dealt with using sets than others.

**FIGURE 3:** *A Set of Colors*



A set of three colors, green, red, and yellow, is represented above by location within a circle. Other colors not in the set are located outside the circle.

**FIGURE 4:** *Testing Sets*

### EQUALITY

```
[BROWN, LIGHT RED] = [BROWN, LIGHT RED]
[BROWN, LIGHT RED] <> [WHITE, LIGHT RED]
```

### SUBSETS

```
[BLACK, GREEN] <= [BLACK, BLUE, GREEN]
[BLACK, BLUE, GREEN] >= [ ]
```

### MEMBERSHIP

```
(RED IN [RED, WHITE, BLUE])
NOT (RED IN [BLUE, GREEN])
```

Above are six true statements about sets of colors using the elements available in figure 3.  $A \leq B$  means that A is a subset of B and  $A \geq B$  means that B is a subset of A. The  $[]$  represents a set with no members (the null set).

**FIGURE 5:** *Operations on Sets*

### SET UNION ( $C = A + B$ )

```
[RED, WHITE, BLUE] = [RED, WHITE] + [RED, BLUE]
```

### SET DIFFERENCE ( $C = A - B$ )

```
[WHITE] = [RED, WHITE, BLUE] - [RED, BLUE]
```

### SET INTERSECTION ( $C = A * B$ )

```
[RED, BLUE] = [RED, WHITE, BLUE] * [RED, GREEN, BLUE]
```

The SETS.OBJ module provides these operations, the set comparisons of figure 4, and three others as well: create a set, copy a set, and add an element to a set.

For example, if a set could contain 32,768 elements, it would take 4KB of memory (4,096 bytes by the formula presented earlier) even if the set contained only one element. Such a representation might be economical in some applications (a specialized database, for example) but practically speaking, sets of those dimensions are seldom useful. Keeping in mind the goals of reducing memory and increasing speed, a more reasonable limit for sets must be found.

(Arbitrary limits can be set on the maximum number of bytes. Sets that are limited to 32 bytes would have a maximum of 256 elements—a practical amount. It is also common to see maximums of 512 and 128 elements, 64 and 16 bytes, respectively.)

Decreasing the 32-byte set size is easy. For example, if no values greater than 127 are inserted, a 16-byte set variable could be used; values no greater than 31 will fit into 4 bytes and so on.



Increasing set size, however, is more difficult. Because SETS.ASM uses byte arithmetic and 8-bit registers to hold set values, going beyond 32 bytes requires major surgery. Still, this is not as restrictive as it may seem. If more than 255 elements are to be stored in a set, a simple solution is to use two set variables, A and B for example. Set A could represent values from 0 to 255, set B values 256 to 511. This approach could be extended to represent an arbitrarily large set of values.

Finally, a more fundamental limitation is imposed on the sets described here: they must be finite. Each element, while represented in the set by a single bit, must have a corresponding integer value for use as an index into the set. For example, the color MAGENTA might be given the value 4 in an equate statement, with other colors given other values (refer to figure 6). Another suitable base type is the ASCII character set, numbered from 0 to 127 (extended to 255). However, the set of all positive integers, numbered from 0 to infinity, would be unsuitable. Clearly this is out of the finite memory range of the computer (even those with extra RAM cards installed). A subset of integers from 0 to 31, for example, could be programmed. The user will find it helpful to keep such limitations in mind when designing programs that use sets.

### ASSEMBLING SETS.ASM

The SETS module in listings 1 and 2 contains procedures for adding sets to assembly language programs. First type in SETS.EXT and SETS.ASM with a text editor (or download the files from PCTECHline). The command MASM SETS; will assemble both into the SETS.OBJ module. This module is a set of subroutines that cannot be run directly—do not link it yet. In order to use the procedures in the module, a host program must be written and assembled; the resulting code is then linked to SETS.OBJ.

Although this may seem like a lot of trouble, the advantage to this approach is that SETS.ASM never has to be assembled again. Any number of host programs can be written and linked to the SETS.OBJ file. Furthermore, because the programming in the module does not have to be reassembled, host programs will assemble faster than they would if the sets procedures were included directly in the assembly language text. If a change is made to the sets module, however, the programs will have to be reassembled and a new SETS.OBJ file created.

**FIGURE 6:** Sets in Memory

15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
0	0	1	0	0	0	0	0	0	0	0	0	1	0	1	0
B	H	Y	L	L	L	L	L	G	W	B	M	R	C	G	B
L	I	E	T	T	T	T	T	R	H	R	A	E	Y	R	L
A	.	L	.	.	.	.	.	A	I	O	G	D	A	E	U
C	W	L	M	R	C	G	B	Y	T	W	E		N	E	E
K	H	O	A	E	Y	R	L		E	N	N			N	
	I	W	G	D	A	E	U				T				
	T		E		N	E	E				A				
	E		N			N									
			T												
			A												

The set of colors from figure 3 is represented as a 16-bit word in memory. Each bit stands for one possible set element. Elements in the set [GREEN, RED, YELLOW] have bits equal to 1. Other elements not in the set have bits equal to 0.

SETTEST.ASM is a sample host program that demonstrates how to use the sets module procedures. Check to see that SETS.EXT and SETS.OBJ are in the same directory and assemble SETTEST. Before running the test, link the resulting SETTEST.OBJ file with the sets module as follows with the command LINK SETTEST+SETS;. (This program *cannot* be converted to a .COM file.)

To run the test, enter SETTEST.

The program will provide three strings of characters, one string at a time. Type all the letters and digits displayed for each string. If any extra characters (that are not shown) are typed accidentally, that test will have to be repeated. In addition, the upper- and lowercasing of letters is significant, but characters may be entered in any order. The characters typed must correspond exactly with the characters that appeared on the screen before the program will continue. After three tests have been performed, the example program ends.

This somewhat contrived example uses nearly all of the programming in the sets module. The first part of the program, and the main body beginning at SETTEST, are standard for 8086/88 programs, and should be easy to follow. The PRINT procedure displays a string addressed by register SI. PRINT contains an internal subroutine, NEWLINE, that is called separately to display blank lines.

Procedures TEST and REPORT both make good use of sets. In TEST, the two set variables CHSET and DONESET are declared using the set<> structured data type (declared in the SETS.EXT include file). The only input to TEST is register SI, which must address the string of characters to be used in this typing test. Only when all characters in that string are entered—in any order—

will the test end. The string must begin with a byte that indicates its length.

After displaying the string addressed by SI, TEST uses set function 4 to create DONESET, which contains a set of all the characters in the string. Next, CHSET is nulled with a call to set function 10. The main loop of the TEST procedure begins at the label TEST1:. DOS function 1 is called to get and echo a character from the keyboard. With set function 8, this character is inserted into CHSET. As the loop repeats, the set of all characters entered by the user is collected in CHSET.

The test ends when all characters entered are found in DONESET (when DONESET is found to be a subset of CHSET), ignoring any extra characters typed. Notice how registers SI and DI are reversed before set function 6, the inclusion test, is called (just after the label TEST1:). If CHSET were tested as a subset of DONESET, the test would either end immediately (after a single correct character) or continue forever (if the first character were incorrect). A check can be performed by removing the two `xchg si,di` instructions.

The REPORT procedure also uses sets to display the accuracy of keyboard typing. It assumes that DONESET equals the set of expected characters for the test, and CHSET contains those characters plus any extra characters typed. The extra characters are easily extracted from CHSET by finding the difference of CHSET – DONESET using set function 2. Printing these characters is accomplished with a simple loop beginning at label REP1: with the set membership test. An ERROR flag indicates the presence of extra characters in CHSET. If none is present, *Done* is displayed. REPORT passes the zero flag ZF



# Turbo, who?

Do you have to give up power and advanced potential to get ease of use and affordability? Not anymore. Because now, you can have *UCSD Pascal* for only \$79.95!

If you're making your move into programming, there's no better way to go than Pascal. And starting now, you *don't* have to settle for a stripped-down version of Pascal in order to get a price that's right. Instead, you can choose UCSD Pascal—the recognized Pascal programming standard in colleges and universities throughout the country—at the incredibly low introductory price of \$79.95 for your PC-DOS, MS-DOS, or other popular computer.

## Start with the standard

With an entry-level system, you spend a lot of valuable time learning a non-standard form of Pascal. And you don't get all the capabilities a true Pascal system is supposed to deliver—unless you buy a lot of add-on utilities—which can send the cost of your system sky-high! Worst of all, when you're ready to tackle anything more than short, simple programs—you have no choice but to move up to a more sophisticated system (like UCSD Pascal). And at that point, you also have to *relearn* standard Pascal.

## UCSD Pascal has everything you need

With UCSD Pascal, you get a

full-featured, professional programming tool that's being used right now in the development of major scientific and business applications. The system comes with an outstanding text editor, a complete on-line tutorial, 8087 math coprocessor support and BCD (decimal arithmetic) included in the package at no extra cost. In fact, UCSD Pascal contains virtually everything you need—as standard equipment—for developing the simplest to the most

sophisticated programs.

UCSD Pascal is available for MS-DOS, PC-DOS, UNIX, VMS, MSX and many other operating systems. You can use UCSD Pascal to write programs of any size on virtually any computer, and port them to any other computer. And if speed is what you're after, the latest native code version of UCSD Pascal actually benchmarks favorably with Turbo Pascal® in execution time!

## Programming that's easy ...and fun!

At Pecan Software Systems, we strongly believe programming should be as easy as possible. UCSD Pascal was originally designed for teaching programming skills, so it's extremely easy to learn and to use. With UCSD Pascal, you'll be developing programs right from the start that are easy to write, easy to understand, and easy to maintain. We also believe that programming should be fun. So we've made UCSD Pascal as enjoyable to use as it is powerful.

## The right tool at the right price

When the fun gets serious, you'll have a comprehensive programming system right at your fingertips with UCSD Pascal—a system that will help you develop those big-league programs you may eventually want to write—at a price you can readily afford.

Put UCSD Pascal programming power on your PC now for only \$79.95! Order by mail today or phone now 1-800-63-PECAN. UCSD Pascal—the original standard of Pascal programming excellence. The new leader in Pascal price/performance.

# PECAN

The UCSD Pascal Company  
Pecan Software Systems, Inc.  
1410 39th Street, Brooklyn, NY 11218  
718-851-3100

# UCSD Pascal

UCSD Pascal \$79.95 (for PC-DOS, MS-DOS, AMIGA, APPLE, ATARI 520, MACINTOSH, RAINBOW, TANDY, as well as most popular 8/16/32-bit systems).

Price includes 8087 support and BCD.

Please send me \_\_\_\_\_ copies of UCSD Pascal for my \_\_\_\_\_ (Operating system) which runs under \_\_\_\_\_.

(Name and model of computer) \_\_\_\_\_  
My disk size is 3 1/2" \_\_\_\_\_ 5 1/4" \_\_\_\_\_ 8" \_\_\_\_\_.

Total amount (NYS add appropriate tax) \_\_\_\_\_  
Payment by ☐ VISA ☐ MC ☐ US Bank Check ☐ Bank Draft

Card Number: \_\_\_\_\_

Credit Card Expiration Date: \_\_\_\_\_

Mail to: Pecan Software Systems, Inc.  
1410 39th Street  
Brooklyn, NY 11218  
ITT Telex No. 494 8910  
CompuServe Code 76703, 500

Name \_\_\_\_\_  
Shipping Address \_\_\_\_\_  
City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_  
Telephone \_\_\_\_\_

Call or write for UNIX, VAX or other UCSD Pascal versions—and ask about our powerful Pascal add-ons, too. **SCHOOLS:** Contact us for our special educational discounts!  
Call toll-free or enclose a check with this coupon to place an order. Please add \$2.50 for shipping within the US. Foreign orders add \$10 and make payment by bank draft payable in US dollars on US bank. New York State residents add appropriate sales tax.

**UCSD Pascal**  
**Not copy protected**  
**60-day money-back guarantee**

**CREDIT CARD ORDERS**  
**CALL TOLL-FREE**  
**1-800-63-PECAN**  
**(NYS) 1-800-45-PECAN**

AMIGA is a trademark of Commodore Electronics LTD.  
APPLE & MACINTOSH are trademarks of Apple Computer.  
ATARI 520 is a trademark of Atari Corporation.  
RAINBOW is a trademark of Digital Equipment Corporation.  
TANDY is a trademark of Radio Shack.  
Turbo Pascal is a registered trademark of Borland International.

UCSD Pascal is a registered trademark of The Regents of University of California



**FIGURE 7:** *Creating Set Variables*

```

SETLEN EQU 32
SET     STRUC
        DB SETLEN DUP(0)
SET     ENDS

DSEG    SEGMENT PARA PUBLIC 'DATA'

NORTH   SET<->
SOUTH   SET<->
EAST     SET<->
WEST     SET<->
SINGLES  SET<->
DOUBLES  SET<->
LUXURY   SET<->
OCCUPIED SET<->

DSEG     ENDS

```

One way to create set variables in assembly language is to use the assembler's STRUC operator to create a 32-byte data type named SET, and then declare labeled variables of that type in the program's data segment.

**FIGURE 8:** *Sample Pascal Code*

```

for UNIT := 0 to 189 do
begin
    if ( UNIT in SOUTH ) and
       ( UNIT in SINGLES ) and
       ( not ( UNIT in OCCUPIED ) ) then DISPLAY_UNIT_NUMBER
end;

```

This Pascal fragment is used to visualize the operations that are necessary to performing a search in assembly language.

**FIGURE 9:** *A Set Expression in Code*

```

LEA SI,SOUTH      ;ADDRESS SOUTH SET WITH SI
LEA DI,SINGLES     ;ADDRESS SINGLES SET WITH DI
MOV AH,3           ;SELECT SET INTERSECTION
CALL SETS          ;SINGLES <- (SOUTH*SINGLES)
LEA SI,SINGLES     ;ADDRESS SINGLES SET WITH SI
LEA DI,OCCUPIED    ;ADDRESS OCCUPIED SET WITH DI
MOV AH,2           ;SELECT SET DIFFERENCE
CALL SETS          ;OCCUPIED <- (SINGLES-OCCUPIED)

```

(SOUTH\*SINGLES)–OCCUPIED is coded above in assembly language, using procedures 2 and 3 from SETS.OBJ.

back to the TEST procedure, which repeats the last test until only the expected characters are entered.

This test could be used as a shell for user-written programs—just remove procedures PRINT, TEST, and REPORT. Two macros simplify calls to DOS and to the sets module. To call a DOS function, use DOSFN *n* where *n* is any DOS function number. To call a set function, use SETFN *n*, where *n* is a set function number, 0 to 9.

### SETS MODULE PROCEDURES

Each procedure of the SETS module is listed below with its necessary parameters (refer to listing 1) and other information. To call a procedure, place a selection code in register AH, set the appropriate parameters, and call SETS. A macro can be used, as shown in SETTEST.ASM. After calling SETS, the results of the operation can be tested. All registers are preserved by the sets module. (The := symbol indicates assignment to the variable on the left from the expression on the right.)

**(AH)=0 Set membership.** (V IN SET) Set ES:DI to the address of a set variable, and place an 8-bit test value in DL. On return, if ZF=1 (use jz), then the value in DL was not found in the set. If ZF=0 (use jnz), then the value was found.

Membership is easily determined by isolating the position of the bit in the set for the value being tested. This is done with a call to local procedure SETCALC, which returns AL with the byte containing that bit, AH with the bit in its relative position in that byte, and BX as an offset into the set where that byte is located. After that, membership

is determined by TESTING the bit in AL with the byte in AH, setting flag ZF if the bit is equal to 1.

**(AH)=1 Set union.** (SET2 := SET1 + SET2) Set DS:SI to the address of SET1, and ES:DI to the address of SET2. Call SETS to form the union of the two, with the results replacing SET2. Set union is the logical OR of all bytes in the sets from which the union is formed. By ORing all bytes, all bits equal to 1 in both sets are transferred to SET2.

**(AH)=2 Set difference.** (SET2 := SET1 – SET2) Set DS:SI to the address of SET1, and ES:DI to the address of SET2. Call SETS to form the difference of the two sets, with the results replacing SET2.

Set difference is the logical AND of the complement of all bytes in the set being subtracted from SET1. The programming of set difference can be described this way: for each byte in SET2, complement one byte, AND the result with the same byte in SET1, and store the result back in SET2. Complements are formed by the exclusive ORing of bytes with FFH.

**(AH)=3 Set intersection.** (SET2 := SET1 \* SET2) Set DS:SI to the address of SET1, and ES:DI to the address of SET2. Call SETS to form the intersection of the two, with the results replacing SET2.

Set intersection is simply the logical AND of all bytes in both sets from which the intersection is formed. By ANDing all bytes, only bits equal to 1 in both sets are transferred to the result.

**(AH)=4 Make set from string.** (SET := [S(1),S(2),...,S(n)]) Set DS:SI to the address of the first byte of a string of any 8-bit values. The first byte of the string must be the length of the string,

followed by that many characters (or other values). Set ES:DI to the address of a destination set. This function creates a new set equal to the set of all characters in the string. Any values previously in SET are lost. Values are inserted into the set by ORing the appropriate bits into the destination set.

**(AH)=5 Make set alternate.** (SET := SET + [S(1),S(2),...,S(n)]) Use the same parameters as in function 4. Each value in the string is inserted into SET, but values already in SET are not removed. This is equivalent to the union of a set with the set of characters in the string.

**(AH)=6 Set inclusion.** (SET1 <= SET2) Set ES:DI to the address of SET1, and DS:SI to the address of SET2; this is the reverse sense of many operations. Use this function to determine if SET1 is a subset of SET2. Be careful to assign SI and DI in the correct order.

Set inclusion is found by forming the logical AND of all bytes in both SET1 and SET2, then checking if the result is unchanged from the original values in SET1. The logical AND of the bits in SET1(n) with SET2(n) will equal the bits in SET1(n) only if all bits also are found in SET2(n). That is, for SET1 to be a subset of SET2, all elements of SET1 also must be present in SET2.

**(AH)=7 Set comparison.** (SET1 = SET2) Set DS:SI to the address of SET1, and ES:DI to the address of SET2. Call SETS to compare the two set variables. No changes are made to SET1 or SET2. The sets module returns the ZF flag which can be tested as follows:

```

(ZF = 1) (SET1 = SET2) (use JE)
(ZF = 0) (SET1 <> SET2) (use JNE)

```



**NEW !!****TURBO****NEW !!**

# MASTER DEVELOPMENT SYSTEM

Give your application a Turbo Boost with the Most Advanced Turbo Pascal Environment Available. Have Turbo Master generate your screen, file handling and menu Programs automatically.

## TURBO ISAM MASTER

**GENERATES 'Ready to Run' Turbo Programs Using BORLAND'S Turbo Pascals Database TOOLBOX.**

With a few key strokes you can generate the following Pascal programs/Includes files. Automatically interfaces to Turbo Screen Master.

**A. MASTER DATABASE PROGRAM** - Generates Pascal Program Code for the following functions.

**1. Add a Record** - Allows both duplicate & unique only keys. Change the up to 6 fields comprising the primary key and the up to 3 secondary keys at any time during input, and the validity of the keys are checked and the ISAM key files are automatically adjusted.

**2. Delete a Record** - Shows the record to be deleted on the screen and allows you to change your mind about deleting, and then adjusts the keys files automatically for the up to 4 keys. The disk space is reused automatically by the programs.

**3. Edit a Record** - with a key change allowed.

**4. Search Database by Key** - Up to 4 keys-and has a 1 key lookup to find next key in alphabetic order.

**5. For Each Key** - The ability to display the keys on the screen or printer in sorted order.

**B. DATA BASE RECOVERY PROGRAM.** This program recovers your data base if it is corrupted by a power outage or certain hardware failures.

**C. MULTIPLE ISAM FILES** - Can be used at the same time in a single program. The generator also produces context sensitive instructions on how to integrate the generated program into your main program.

**D. DOCUMENTATION** - Print screens and ISAM specifications. Also inline program documentation is generated.

## TURBO MENU MASTER

**GENERATES 'Ready to Run' Turbo Programs with Dedicated Screens or Windows.**

**FEATURES:** Has Menu Data Base so its easy to modify menus. **PROVIDES SELECTION BY:** (1) Press of a number (2) Press of a function key - (3) Press the high lighted letter - (4) Use the arrow keys. **ADAPTIVE SCREEN COLORS** - Different screen colors are automatically used for color or monochrome display. This allows you to provide a better interface for the user.

**INTERACTIVE MENU BUILDER:** (1) Allows for the automatic entry and reorder of selections. (2) Offers easy color selection. (3) Allows for choice of procedure, chain, execute or comment code generation for each selection. (4) Has startup Menu that YOU design. (5) Provides for the intergerated Display and control of the Key Lock Status.

**SCREEN SCULPTURE USERS** - Easily move up to these advance features ... we provide routines to use Your Screen Sculpture Created Screens.

## RISK FREE TRIAL

Try the demo package included for 30 days. If not pleased return for a full refund.

Credit card orders call:

**1-800-821-9503**

CIRCLE NO. 135 ON READER SERVICE CARD  
In Florida (800) 342-0137

**NO ROYALTIES**  
on Generated  
Programs

**HAWAIIAN VILLAGE COMPUTER SOFTWARE**  
1109 Pennsylvania Ave. St. Cloud, Florida 32769

## TURBO SCREEN MASTER

**GENERATES 'Ready to Run' Multi-screen programs with advanced field definition.**

- **USER SPECIFIED PROCEDURES** can be called before and after data entry for each field. This allows **SCREEN GENERATION THAT IS INDEPENDANT OF USER INSERTED PROGRAM STATEMENTS.**
- **YOU CAN CUSTOM PROGRAM** special field edits and processes which Screen Master automatically includes into the screen program. This allows for "On the Fly" **FUNCTION KEY AND WINDOW ROUTINES.**
- **RECORD FORMATS** and initialization routines for Structures and Arrays are automatically generated.
- **CAN SPECIFY** a Protected Field to be automatically redisplayed if its' value changes.
- **TYPES INCLUDE** Strings, Yes/No, Time, Male/Female and Numbers.
- **FIELDS CAN BE STORED** (declared) as Boolean, Integer, Real, Character, or String.

## AND MUCH MUCH MORE ...

COMPARISON WITH OTHER PRODUCTS	TURBO SCREEN MASTER	TURBO SCREEN VER. 1.10	SCREEN SCULPTURE Ver. 1.01
Full Support for Structures, Arrays and Declarations specifications	YES	NO	NO
Full Support for user written procedures Function Keys & Help Screens	YES	NO	NO
Etch-A-Sketch Border Drawings	YES	NO	NO
Point and Paint color interaction	YES	NO	YES
Border Color Control	YES	NO	NO
User defined Valid Character Sets	YES	NO	NO
Display of Caps/Num Lock Status	YES	NO	NO
Optional Realtime Initialization of Date/Time	YES	NO	NO

**FREE MASTER TOOLS \$44.95**

WITH ORDER OF A MASTER PRODUCT

VALUE

YES, Enclosed is \_\_\_\_\_

### INTRODUCTORY OFFER

<input type="checkbox"/> Turbo Master Tools	FREE
<input type="checkbox"/> Turbo Menu Master	\$59.95 \$54.95
<input type="checkbox"/> Turbo Screen Master	\$124.95 89.95
<input type="checkbox"/> Turbo ISAM Master	\$149.95 \$124.95
<input type="checkbox"/> ALL 4 for \$249.95	\$249.95

Systems Requires: IBM PC,XT,AT or 100% Compatible -16K. MS DOS 2.0 or Higher - 80 column screen. Turbo Pascal 3.0 - 2 DD/D5 Disk Drives. ISAM Program Generator Requires Turbo Database Toolbox.

\*These prices include shipping to all U.S. Cities. All foreign orders add \$10 per product ordered

**For Other Inquires Call (305) 892-5686**

Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Shipping Address: \_\_\_\_\_


City: \_\_\_\_\_ State: \_\_\_\_\_ Zip: \_\_\_\_\_

VISA or MC #: \_\_\_\_\_ Exp. Date: \_\_\_\_\_

C.O.D.'s will be accepted. Outside USA; make payment by bank draft, payable in US dollars drawn on a US bank.

©Turbo Pascal & Turbo Database Toolbox are trademarks of Borland International. IBM is a trademark of International Business Machines. MS-DOS is a trademark of Microsoft. Turbo Screen is a copyright of Pascom Computing. Screen Sculpture is a trademark of the Software Bottling Co. of New York. ©1985 Hawaiian Village Computer Software.





## Why Send Anything But Your Best Software Into Final Production?

You don't have to with Pfinish™! You'll find all the inefficient parts of any MS-DOS® or PC DOS program. Assembler. C. PASCAL. FORTRAN. BASIC. Get comprehensive reports that show you the number of times various sections of code in a program are executed. Down to the instruction level. Displayed. Stored on disk. Or printed out. In tabular form or histograms.

Unlike other analyzers which use arbitrary address ranges, Pfinish can generate reports which reflect the structure of your program.

Using symbol table information provided by either our Plink™86 linkage editor or Microsoft's LINK, Pfinish divides your program into functional subroutines so you can check the number of times each subroutine is entered, as well as the number of instructions executed while within the subroutine. In addition, Pfinish can monitor any address range or interrupt inside or outside your program.

You can do a dynamic program scan. Pick out the most frequently executed subroutines. Track inter-

rupts. Handle overlays. Find a programming error that costs your program valuable time. Rank program subroutines from the most to the least frequently executed. And, you can analyze any memory-resident program in your system since Pfinish can be set up to stay permanently resident.

This Pfinish report shows, for each routine, the number and percentage of its calls, the number and percentage of its instructions, and the


clock time it consumed:

HIT COUNT	HIT %	RUN COUNT	RUN %	TICK COUNT	ADDRESS
79280	96	396400	91	92	CXA38
2570	2	10280	7	5	CXC33
2540	1	7620	1	25	_SBRK
84390		414300		122	

Pfinish is priced at \$395 and is available for 8086-based micros running MS-DOS.

Find out more about Pfinish today! Call (800) 344-7200. In Massachusetts (617) 762-5030. Or, write.

Phoenix Computer Products Corp., 320 Norwood Park South, Norwood, MA 02062



**PROGRAMMERS' PFANTASIES™**  
BY

*Phoenix*

CIRCLE NO. 205 ON READER SERVICE CARD

Pfinish and Programmers' Pfantasies are trademarks of Phoenix Computer Products Corporation.

Plink86 is a trademark of Phoenix Software Associates Ltd. MS-DOS and Microsoft are registered trademarks of Microsoft Corporation.

## SETS

Set comparison is easily accomplished by comparing all bytes in both sets. Because SI and DI are used to address the set variables, this can be done quickly in 8086/88 assembly language using the CMPSB (compare string byte) instruction with a repeat prefix, REPZ. A word comparison (CMPSW) was not used on the chance that a future version of SETS would not have an even number of bytes in set variables. The comparison would be twice as fast, however, if CMPSW were used. In that case, CX would have to be set to half the byte length of a set variable.

**(AH)=8 Add element.** (SET := SET + [ELEMENT]) Set ES:DI to the address of a SET variable. Place any 8-bit value in DL and call SETS to add that value to the SET. No existing members of the set are disturbed. If the element is already in the SET, then this function has no effect. This operation is equivalent to the union of one set with a set that contains only one element.


Adding an element to a set is similar to testing for membership (function 0), except that the logical OR of the appropriate bit is stored directly in the result instead of setting the ZF flag.

**(AH)=9 Copy set.** (SET1 := SET2) Set DS:SI to the address of the source set (SET2), and ES:DI to the address of the destination set (SET1). Call SETS to copy the source to the destination set.

A very fast copy is possible using the 8086/88 MOVSB instruction to move the byte addressed by DI directly to the byte addressed by SI, without going through an intermediate register. Also, a repeat prefix REP makes it possible to copy the entire set with a single, although repeated, instruction.


**(AH)=10 Make null set.** (SET := []) Set ES:DI to the address of a set variable. Call SETS in order to make that set equal to the null set.

Nulling a set is accomplished by setting all bytes in the set equal to 0. This is done as quickly as possible with the use of a repeat prefix in front of the STOSB (store string byte) instruction as shown in the listing.

These procedures enable programmers to add sets to assembly language programs and to make use of features normally found only in higher-level languages. Judicious use of set comparisons, set operators, and set membership tests can reduce program size while increasing running speed. 

*Tom Swan runs Swan Software, a consulting business. He has written four books published by the Hayden Book Company, most recently, Pascal for Data Base Management.*





# The Best C Book A Powerful C Compiler One Great C Value \$39.95

A good C book just isn't complete without a good C compiler to go with it. That's why we give you both. You get a comprehensive 450 page book and a full feature standard K&R C compiler with the Unix V7 Extensions. The Book is loaded with examples that teach you how to program in C. And our fast one pass C compiler comes with an equally fast

linker so you don't waste a lot of time watching your disk drives spin. You also get a Unix compatible function library that contains more than 150 functions (C source code included). And if all that isn't enough, we offer you a 30 day money back guarantee. So what are you waiting for? The exciting world of C is just one free phone call away.

## Language Features

- Data Types: char, short, int, unsigned, long, float, double
- Data Classes: auto, extern, static, register
- Typedef, Struct, Union, Bit Fields, Enumerations
- Structure Assignment, Passing/Returning Structures

abs	conbuf	feof
asm	conc	ferorr
asmx	cos	fflush
atan	cpyst	fgets
atof	creat	fileno
atoi	curtblk	filetrap
atol	curslin	find
bdos	curscol	floor
bdosx	curscrow	fopen
bios	cursoff	fprintf
biosx	curson	fputs
calloc	delete	freed
ceil	drand	free
cfree	exec	freopen
chain	execl	fscanf
character	execv	fseek
chdir	exit	ftell
chmod	exitmsg	fwrite
clearerr	exp	getc
close	fabs	getch
clrcrn	fclose	putch
cmpstr	fdopen	getchar

## Functions

getcseg	isascii	movmem	replace	strcat
getdseg	isctrl	open	repmem	strcmp
getd	isdigit	outp	rewind	strcpy
putd	islower	peek	right\$	strlen
getdate	isprint	perorr	rindex	strncat
gettime	ispunct	poke	rmdir	strncpy
geti	isspace	poscurs	scanf	strsave
puti	isupper	pow	setbuf	system
getkey	itoa	printf	setbufsiz	tolower
getmode	keypress	putc	setcolor	toupper
setmode	left\$	putchar	setdate	ungetc
gets	len	puts	settime	ungetch
getw	log	putw	setjmp	unlink
heapsize	log10	rand	setmem	write
heaptrap	longjmp	read	sin	writes
hypot	lseek	readattr	sound	xmembeg
index	malloc	reach	sprintf	xmemend
inp	alloc	writetech	sqr	xmemget
insert	mathtrap	wreaddot	srand	xmempur
iofilter	mid\$	wrealloc	sscanf	xmovmem
isalnum	mkdir	rename	stacksiz	_exit
isalpha	modf		str\$	

## MIX Editor \$29.95

When you're programming in a high level language you need a high powered editor. That's why we created a programmable full/split screen text processor. It lets you split the screen horizontally or vertically and edit two files at once. You can move text back and forth between two windows. You can also create your own macro commands from an assortment of over

100 predefined commands. The editor comes configured so that it works just like Wordstar but you can change it if you prefer a different keyboard layout. The editor is a great companion to our C compiler. Because they work so well together we want you to have both. To make sure you do, we're offering the editor for just \$15 when purchased with the C compiler.

## ASM Utility \$10

The ASM utility disk allows you to link object files created by Microsoft's MASM or M80 assemblers. Lots of useful assembly language functions are included as examples.

**ORDERS ONLY**  
**1-800-523-9520**  
IN TEXAS  
**1-800-622-4070**

Canadian Distributor  
Saraguay Software: 416-923-1500

CIRCLE NO. 125 ON READER SERVICE CARD

### NOT COPY PROTECTED

Editor \$ \_\_\_\_\_ (29.95)  
C \$ \_\_\_\_\_ (39.95)  
C & Editor \$ \_\_\_\_\_ (54.95)  
ASM Utility \$ \_\_\_\_\_ (10.00)  
TX Residents \$ \_\_\_\_\_ (6.125% sales tax)  
Shipping \$ \_\_\_\_\_ (see below)  
Total \$ \_\_\_\_\_  
☐ Check ☐ Money Order  
☐ MC/Visa# \_\_\_\_\_ Exp \_\_\_\_\_  
Shipping Charges: (No charge for ASM Utility)  
USA: \$5/Order  
Canada: \$10/Order  
Overseas: \$10/Editor • \$20/C • \$30/C & Editor

☐ PC DOS/MSDOS (2.0 or later)  
☐ IBM PC Single Side  
☐ IBM PC Double Side  
☐ Tandy 2000  
☐ 8 Inch  
☐ Other \_\_\_\_\_  
☐ CPM 80 (2.2 or later)  
☐ 8 Inch  
☐ Kaypro II  
☐ Kaypro 4  
☐ Apple (Z80)  
☐ Osborne I SD  
☐ Osborne I DD  
☐ Morrow MD II  
☐ Other \_\_\_\_\_

Name \_\_\_\_\_  
Street \_\_\_\_\_  
City \_\_\_\_\_  
State \_\_\_\_\_  
Zip \_\_\_\_\_  
Country \_\_\_\_\_  
Phone \_\_\_\_\_

**MIX** 2116 E. Arapaho  
software Suite 363  
Richardson, TX 75081  
(214) 783-6001

Ask about our volume discounts.



# Powerful MS-DOS<sup>TM</sup> Software.

For the IBM® - PC, XT, AT & others with generic MS-DOS/PC-DOS 2.0 or higher.

Not copy  
protected!

Only **\$39.95** Each!

UTAH

## COBOL<sup>TM</sup>

Whether student, teacher or professional programmer, this is the one you've heard so much about.

- ☐ It's easy to use. Compiles 5000 statements on a 128K machine.
- ☐ 170 clear error messages, i.e. DATA-NAME IS MISSING OR MISPELLED.
- ☐ Distribute your object code programs royalty free.
- ☐ Small object code programs conserve disk space.
- ☐ Fast compile times to increase programmer productivity. Over 25 times faster than one compiler costing \$995!
- ☐ You get a diskette and 213-page manual with lots of examples and 16 complete COBOL source code programs. **\$39.95.**

Also available: COBOL Application Packages, Book 1 **\$9.95.**

UTAH

## PASCAL<sup>TM</sup>

- ☐ 14-digit precision, BCD math, no round-off errors with decimal arithmetic for business and floating point + 63 - 64 for scientific.
- ☐ A very nice TRACE style debugging.
- ☐ Arrays up to 8 dimensions and 64K strings.
- ☐ External procedures and functions with dynamic auto-loading.
- ☐ One-step compile, no assembly or link required.
- ☐ You get a 132-page manual and diskette. **\$39.95**

UTAH

## PILOT<sup>TM</sup>

- ☐ Perfect for industrial training, office training, drill and testing, virtually all programmed instruction, word puzzle games, and data entry facilitated by prompts.
- ☐ John Starkweather, Ph.D., the inventor of the PILOT language, has added a built-in full-screen text editor, and much more.
- ☐ Meets all PILOT-73 standards for full compatibility with older versions.
- ☐ You get a diskette, 125-page manual and ten useful sample programs. **\$39.95.**

Also still available for 8-bit machines with CP/M® is our world famous Nevada Software Series used by 50,000 customers in 40 countries. These include Nevada COBOL, Nevada FORTRAN, Nevada PASCAL, Nevada PILOT, Nevada BASIC and Nevada EDIT. **\$39.95** each.

Satisfaction guaranteed. If for any reason you're not completely satisfied, just return the package within 15 days in good condition, and we'll refund your money.

IBM is a registered trademark of International Business Machines Corp. CP/M is a registered trademark of Digital Research. MS is a trademark of Microsoft Corp. © 1985 Ellis Computing, Inc.

UTAH

## FORTTRAN<sup>TM</sup>

- ☐ FORTRAN IV based upon ANSI-66 standards.
- ☐ Very fast compile times and easy to use.
- ☐ IF . . THEN . . ELSE constructs.
- ☐ Chaining with blank and named common.
- ☐ Copy statement.
- ☐ ENCODE and DECODE.
- ☐ Free-format input and output.
- ☐ A very nice TRACE style debugging.
- ☐ 150 English language error messages.
- ☐ You get a diskette, and 223-page manual. **\$39.95**

UTAH

## EDIT<sup>TM</sup>

- ☐ A character-oriented full-screen video display text editor designed specifically to create COBOL, FORTRAN and PASCAL programs.
- ☐ Only requires 15K disk space so it can fit on the same disk as your compilers.
- ☐ Completely customizable tab stops, default file type, keyboard control key layout and CRT by menu selection.
- ☐ Diskette comes with easy to read 58-page manual. **\$39.95.**

UTAH

## BASIC<sup>TM</sup>

- ☐ This interpreter has a built-in full-screen editor.
- ☐ Single- and Multi-line user definable functions.
- ☐ BCD Math- no round-off errors.
- ☐ Full Matrix operations.
- ☐ You get 220-page manual and diskette. **\$39.95.**

Handling/Shipping: No shipping charge within US. Overseas add \$10 for first package, \$5 each additional. Checks must be in US Dollars, drawn on a US bank.

Utah Software requires 128K RAM and PC-DOS or MS-DOS 2.0 or higher.

HOW TO ORDER. Send check or money order to Ellis Computing, Inc. with VISA or MASTERCARD order by phone. Sorry no COD's.



Ellis Computing, Inc.  
5655 Riggins Court, Suite 10  
Reno, Nevada 89502  
Phone (702) 827-3030

SINCE 1977



**ELLIS COMPUTING<sup>TM</sup>**



**LISTING 1: SETS.EXT**

```
;SETS.EXT
;External declarations

;-----
;      Equates
;-----
setlen equ    32                ;bytes in one set

;-----
;      Type declarations
;-----
set      struc                ;all new sets are empty
        db      setlen dup(0)
set      ends

;-----
;      External declarations
;-----
if host
        extrn  sets:near
endif
```

**LISTING 2: SETS.ASM**

```
page 60,132
title  Sets 1.01

;-----
; Program      : Sets (Set handling package)
; Version      : 1.01
; System       : IBM PC DOS 2.00+
; Language     : IBM 8088/86 Macro Assembler
; Author       : (C) 1984 by Tom Swan
; Address      : Swan Software P.O. Box 206 Lititz PA 17543
;-----
true equ      -1
false equ     0
host equ      false                ;true for host program only
maxfn equ     10                  ;maximum function number
```

```
;-----
;
; * All sets are composed of 32 bytes.  each bit represents
;   one of 256 values in the set.  If the bit = 1, that value
;   is in the set, else that value is absent.
;
; * Except for flags, all registers are preserved.
;
; * Set routines are called by placing a selection value in ah and
;   calling "sets".  See individual routines for exact parameters.
;
; example: mov  di,value          ;value to test
;           lea  di,anyset        ;address first byte in set
;           mov  ah,0             ;select set membership test
;           call sets            ;call set routine
;           jnz  success          ;found value in set
;
; * Procedures in the module include:
;
; (ah) = 0  set membership
; (ah) = 1  set union
; (ah) = 2  set difference
; (ah) = 3  set intersection
; (ah) = 4  make set from string
; (ah) = 5  make set alternate entry
; (ah) = 6  set inclusion
; (ah) = 7  set comparison
; (ah) = 8  add single element to set
; (ah) = 9  copy set to set
; (ah) = 10 make null set
;
;-----
page
dgroup group  dseg
cgroup group  cseg
        assume cs:cgroup, ds:dgroup, es:dgroup, ss:nothing
;
;      Code Segment
;-----
```

*Frustrated With the Tyranny of PASCAL? Tired of the Drudgery of BASIC?*

## Free Yourself With CCSM, the Database Language...only \$59.95

*Compare This Routine to Your Present Language, and See the Difference*

```
RD  READ "NAME: ",NAM,! QUIT:NAM=""
IF NAM'?2.A1","1A.E WRITE "PLEASE ENTER AS LAST, FIRST MI",! GO RD
TEL READ "TEL # ",TEL,! IF TEL'?3N1"--4N WRITE "NNN-NNNN PLEASE",! GO TEL
SET ^DATA(NAM)=TEL GO RD
PRT WRITE "    NAME",?20,"TELEPHONE #",! SET NAME=""
LP  SET NAM=$ORDER(^DATA(NAM)) QUIT:NAM="" WRITE NAM,?20,^DATA(NAM),! GO LP
```

This simple program accepts, screens and saves names and phone numbers... sorts and prints them. These six lines of code are an example of the extremely compact, and familiar nature of COMP Computing Standard **MUMPS**, the Database Language. In lines 1 and 2, READ, IF, WRITE and GO should be easy to follow. The pattern match operator "?" filters for the correct input of alpha characters to make a name. In line 4, SET ^DATA creates a permanent global file, with NAM as a subscript. The data node is SET to the telephone number. In line 6, the \$ORDER command gets the next subscript in order, from the ^DATA file, thereby SETting NAM to the next name in the file.

CCSM, the Database Language, frees you from the tyranny of typed and restrictive languages...NO declarations of variables or data files. Look at these Features:

- Full Screen Editor
- Virtual Memory (routines and variables may be as large as a disk)
- Multi-User available...up to 15
- B-Tree File Structure
- 8087 and BCD Support
- Exceeds 1984 ANSI Standard MUMPS
- Transportable from Micro to Mini to Mainframe

CCSM, the Database Language, is a fast, modern version of ANSI Standard **MUMPS**, developed by COMP Computing. It comes with a 20 year history of development, solving database applications. CCSM improves programmer productivity, and efficiency...typical programs are written in 1/3 the code of BASIC or PASCAL. CCSM is an easy to learn language and comes with a 250 page manual.

AMEX, VISA and  
MASTERCARD  
accepted by phone.

### 1-800-257-8052

In Texas 713-529-2576

CCSM, the Database Language, sells for \$59.95, and comes with full documentation. Until March 31, 1986, for an additional \$15.95, we'll send along the "Cookbook of MUMPS", and its disk, (reg. \$24.95) containing useful routines and utilities. For charts and graphs, order the Graphics disk for \$49.95. Multi-user version, \$450. Disks are non-copy-protected. Requires IBM PC or compatible with 128K. (Macintosh version available...\$89.95)

Order by phone, or clip and mail:

**1-800-257-8052**  
in Texas, 713-529-2576

**Guidance Software**  
P.O. Box 5362  
Kingwood, TX 77325

AMEX	_____	card no. _____	exp. date _____
VISA	_____		
MC	_____	CCSM, Cookbook, and disks special package	<b>\$75.90</b>
		CCSM, the Database Language	<b>\$59.95</b>
		Graphics disk	<b>\$49.95</b>
Please add \$3.00 for shipping and handling. Texas residents add 6 1/8% sales tax.			
name _____			
street _____			
city _____ st _____ zip _____			

IBM PC and Macintosh are trademarks of International Business Machines, and Apple Computer.

CIRCLE NO. 153 ON READER SERVICE CARD



```

cseg segment byte public 'code'
include sets.ext ;include global equates
public sets
sets proc near
cld ;clear df (set auto-increment mode)
push ax ;save all registers
push bx
push cx
push dx
push di
push si

```

; Use function number in ah as an offset into a jumtable containing  
; the addresses of the various set functions. Jump to selected function.

```

cmp ah,maxfn ;test for illegal selector
ja setexit ;exit if ah > 6
mov bx,offset jumtable ;bx=base addr (in cseg)
mov al,ah ;place function number in al
xor ah,ah ;zero ah to make word in ax
shl ax,1 ;ax<-ax*2 (16-bit word offset)
add bx,ax ;bx<-bx+ax forming table address
jmp word ptr cs:[bx] ;jump to routine at cs:[bx]

```

; All routines jump to here when done. Restore all destroyed  
; registers and return to caller.

```

setexit:
pop si ;restore all registers
pop di
pop dx
pop cx
pop bx
pop ax
ret ;return to caller

```

```

sets endp
page

```

```

; SETCALC

```

```

; Purpose -- calculate word address and bit position
; for a set value.

```

```

;
; Called by -- functions 0,4,5,8
;
; Arguments -- (es:di) = address of set (first word)
;            (dl) = value (8-bits) to test
;
; Returns -- (al) = byte from set for value in dl
;           (ah) = bit in relative position for value
;           (bx) = offset of word (i.e. at ds:[di+bx])
;

```

```

dseg segment byte public 'data'
bittab db 01h,02h,04h,08h,10h,20h,40h,80h ;bits 0..7 set = 1

```

```

dseg ends

```

```

setcalc proc near
; byte offset = value div 8
; bit offset = value mod 8

```

```

push di ;save di register
xor ax,ax ;zero ax so that ah=0
mov al,dl ;set ax=value dl (16-bits)
mov bh,8 ;set bh=divisor
div bh ;al<- ax div bh ;ah<- ax mod bh
xor bx,bx ;zero bx so that bh=0
mov bl,ah ;bx<- value mod 8 (bittab offset)
lea di,bittab ;address 8-byte bit table
mov ah,byte ptr [di+bx] ;ah<- bit in relative position
pop di ;restore register (address of set)
mov bl,al ;bx<- value div 8 (set offset)
mov al,byte ptr [di+bx] ;al<- byte from set for value dl
ret ;return to caller
setcalc endp ;end procedure

```

```

page

```

```

; SET0 (ah=0) set membership (v in set)

```

```

; Purpose -- test for presence of value (v) in set

```

```



; Called by -- set jump table

```

```

; Calls -- setcalc

```



## ARE YOU TRYING TO COMMUNICATE ?

C programs can communicate with the world now through the power of **The Greenleaf Comm Library**. Now from the people who brought you **The Greenleaf Functions** General Library for C, comes this rich interrupt driven, ring-buffered asynchronous communications capability.

Over 100 functions in C and assembler to facilitate communications at up to 9600 baud. Up to eight ports at a time: ASCII or XMODEM. X-On/X-Off too. Hayes compatible modems controlled here. Safe too, bet you can't exit your application with interrupts hot. Major applications around the world base their communicating applications on **The Greenleaf Comm Library**. Stop just trying and start really communicating. Get your copy of **The Greenleaf Comm Library** today. For all major C compilers, all models, all versions. For the IBM PC and just about any machine with MSDOS and an 8086. Comes with source code, extensive examples, demo programs, featuring **C-Terminal**, reference card and newsletter. No royalty. \$185

**Other Products:** **The Greenleaf Functions** General Library, over 220 functions for total control of the IBM PC, with source. \$185 for the compilers listed below. (See ordering instructions below).

**Specify compiler** when ordering: Lattice, Microsoft, Computer Innovations, Mark Williams, or DeSmet. Add \$7.00 for UPS Second Day Air (or \$5.00 for ground). Texas residents add sales tax. Mastercard, VISA, check, or P.O. In stock, shipped same day.

**The  
GREENLEAF  
COMM  
LIBRARY™**

- ☐ General Libraries \$185
- ☐ Comm Library \$185
- ☐ C186 Compiler \$349
- ☐ Lattice C \$395
- ☐ Mark Williams \$475

PRICES ARE SUBJECT TO  
CHANGE WITHOUT NOTICE.



2101 HICKORY DR.  
CARROLLTON, TX  
75006

For Information:  
214/446-8641







## SETS

```

mov     cx,setlen           ;cx=number bytes in set
set3_1:
  lodsb                     ;al<-[si]; si:=si+1
  and    byte ptr [di],al   ;[di]<- logical and of [di],al
  inc    di                 ;advance destination set pointer
  loop   set3_1             ;loop on cx
  jmp    setexit            ;end set3
set3    endp
page
;-----
; SET4 (ah=4) make set from string set <- [s(1),s(2),...,s(n)]
;-----
; Purpose      -- insert 8-bit elements from string (s)
;               into the set. Assumes first byte of string
;               indicates length.
;
; Called by    -- main jump table
;
; Calls        -- set5 (via fall-through)
;
; Arguments    -- (ds:si) = address first byte of string (s[0])
;               (es:di) = address of destination set
;
; Registers    -- none
;-----
set4    proc    near
  mov     cx,setlen         ;set cx=number bytes in set
  xor     al,al             ;set al=0 (value to store in set)
  push    di                ;save di (set address) on stack

;----- make existing set null

rep     stosb               ;store al at [di] until cx=0
  pop     di                ;restore di
  fall through to set5 procedure

set4    endp
page
;-----
; SET5 (ah=5) make set alternate set <- set + [s(1),s(2),...,s(n)]
;-----

```

```

; Purpose      -- add 8-bit elements from string s into
;               an existing set
;
; Called by    -- main jump table
;               set4 (via fall-through)
;
; Calls        -- setcalc
;
; Arguments    -- (ds:si) = address first byte of string (s[0])
;               (es:di) = address of destination set
;
; Registers    -- none
;-----
set5    proc    near
  xor     cx,cx             ;zero cx so that ch=0
  lodsb                     ;get length al<-[si]; si<-si+1
  mov     cl,al             ;set cx=count of chars in string
  jcxz    set5_2            ;exit on null string

set5_1:
  lodsb                     ;get byte al<-[si]; si<-si+1
  mov     dl,al             ;move value in al to dl for setcalc
  call    setcalc           ;calculate byte offset bx; bit ah
  or      byte ptr [di+bx],ah ;or bit in ah into set byte
  loop    set5_1            ;cx<-cx-1; if cx<>0 then loop


set5_2:
  jmp     setexit           ;end set5
set5    endp
page
;-----
; SET6 (ah=6) set inclusion set1 <= set2
;-----
; Purpose      -- test if set1 is a subset of set2
;
; Called by    -- main jump table
;
; Calls        -- none
;
; Arguments    -- (es:di) = address of set1
;               (ds:si) = address of set2
;
;

```


## FLOPPY DISK SERVICES INC.

39 Everett Dr., Bldg. D  
Lawrenceville, N.J. 08648


Floppy Disk Services, inc. has been serving the computer community for 6 years now. We offer the best in products and service for the professional and hobbyist alike. Organizations like NASA, RCA, AT&T and IBM who demand quality are among our valued customers. Our techs can custom assemble virtually any special cabling or enclosure set-up you may need. We offer an enclosure line that has sold thousands over the years and our replacement warranty policy puts us out front. . . We are among the first to offer 8 inch double sided drive systems that run on the IBM-PC/XT for interchangeability standards from mainframe to micro.




Mitsubishi 4851 DS/DD 48 tpi. ....	\$139.
Mitsubishi 4854 1.6mb AT drive ....	\$185.
10 megabyte system .....	\$495.
20 megabyte system .....	\$595.
40 megabyte system .....	\$995.
130 watt pc supplies .....	\$ 95.
XT motherboards.....	Call
Western Digital controllers .....	\$165.
Taxan 415 RGB monitors .....	\$299.
Teac 55F 80 track drives .....	Call



Taxan monitors (built for ACORN) \$299.



All our connectors and adaptors are crimped on AMP certified equipment!



AST, Quadram and Western digital boards available!

We offer many more products than space allows. Please call for FREE catalog or let one of our expert staff help you make the right choice, and the call is on us!

"... (Floppy Disk Services) is one of the few mail order houses that enthusiastically does custom work; the technicians there can assemble virtually any desired floppy or hard disk system to order. . ."

Jeff Duntemann  
Technical Editor, PC Tech Journal

VISA

Toll Free Order Line: 1 (800) 223-0306

MasterCard


CIRCLE NO. 163 ON READER SERVICE CARD

PC TECH JOURNAL









If you're still paying for multiple copies of dBASE or RunTime<sup>†</sup> at hundreds of dollars a pop, you can stop.

And use a WordTech compiler instead.

With a WordTech compiler, you only need a single copy of dBASE II<sup>†</sup> or dBASE III<sup>†</sup> for every programmer, not every user.

Then you can distribute as many copies of your compiled (and protected) programs as you want with no site licenses, no runtime fees and no strings attached.

Our MS-DOS compilers typically run your dBASE applications 3 to 10 times faster and use just 128K of free memory on any MS-DOS computer, not only the IBM PC.

You don't pay any penalties because WordTech compilers use the same language and syntax as dBASE and the same index, memory and data files (up to 10 data files open simultaneously, each with up to 7 indexes).

# Still using dBASE?

And you don't pay the usual high price because WordTech compilers are just \$750. Once.

With a WordTech compiler, you can also run your programs on multi-user and networked systems. Our multi-user compiler runs your existing dBASE programs under AT&T's UNIX System V or CROMIX. And our networking compiler runs your present code on

DOS 3.1 local area networks (LAN's). The compiler will take care of file and record locking for you, or you can take full control using dBASE III networking commands.

We can help you extend your applications as well as your budgets. You can do windows with dBFrame<sup>™</sup>, business graphics with dBChart<sup>™</sup> and even replace dBASE itself for just \$169 with dB-XL<sup>™</sup>, an interpreter with an extended superset of the dBASE III language.

And we back everything with free support, one year of maintenance and a money-back guarantee.

For details and the name of your nearest dealer, contact WordTech Systems, Inc., P.O. Box 1747, Orinda, CA 94563. (415) 254-0900. TELEX 503599.

You owe it to your wallet to call now.

## WORDTECH SYSTEMS





```
; Arguments  -- (es:di) = address of set
;             (dl) = 8-bit value (v)
;
; Registers  -- zf=1 = value not present    (use jz)
;             zf=0 = value present         (use jnz)
;
;-----
```

```
set0 proc near
call setcalc ;ax=value; bx=address; cx=bit
test al,ah ;test bit in ah against set val
jmp setexit ;end function 0
set0 endp
page
```

```
; SET1 (ah=1) set union (set2 <- set1 + set2)
```

```
; Purpose -- make set2 equal to all elements in set1
;          plus elements already in set2.
```

```
; Called by -- main jump table
```

```
; Calls -- none
```

```
; Arguments -- (ds:si) = address of set1
;            (es:di) = address of set2
```

```
; Registers -- none
```

```
set1 proc near
mov cx,setlen ;cx=number bytes in set
set1_1:
lodsb ;al<-[si]; si<-si+1
or byte ptr [di],al ;[di]<-logical or of [di],al
inc di ;advance destination set pointer
loop set1_1 ;loop on cx
jmp setexit ;end set1
set1 endp
page
```

```
; SET2 (ah=2) set difference (set2 <- set1 - set2)
```

```
; Purpose -- make set2 equal to the set of elements of set1
;          which are not also members of the original set2
```

```
; Called by -- main jump table
```

```
; Calls -- none
```

```
; Arguments -- (ds:si) = address of set1
;            (es:di) = address of set2
```

```
; Registers -- none
```

```
set2 proc near
mov cx,setlen ;cx=number bytes in set
set2_1:
xor byte ptr [di],0ffh ;complement byte at [di]
lodsb ;al<-[si]; si<-si+1
and byte ptr [di],al ;[di]<- logical and of [di],al
inc di ;advance destination set pointer
loop set2_1 ;loop on cx
jmp setexit ;end function 2
set2 endp
page
```

```
; SET3 (ah=3) set intersection (set2 <- set1 * set2)
```

```
; Purpose -- make set2 equal to the set of elements in
;          both set1 and the original set2
```

```
; Called by -- main jump table
```

```
; Calls -- none
```

```
; Arguments -- (ds:si) = address of set1
;            (es:di) = address of set2
```

```
; Registers -- none
```

```
set3 proc near
```

Source  
Code  
Included

# Personal Operating Systems for your IBM-PC.

## PCVMS \$99.00

### WHAT IS PCVMS?

PCVMS is similar to VAX/VMS, the popular operating system developed by Digital Equipment Corporation for their line of mainframe computers. Everyone thought such a sophisticated and elegant operating system could never work on a microcomputer.

### A MAINFRAME OPERATING SYSTEM ON A PC.

That's when Wendin put PCVMS on IBM-PC, XT, and AT personal computers. And now, for the first time in history, you can get mainframe performance from your personal computer — at a fraction of the cost. PCVMS has the same powerful features you're used to, like MULTIPLE PROCESSES, MULTIPLE USERS, NETWORKING SOFTWARE, a RICH COMMAND SET, and a complete SET OF SYSTEM SERVICES.

## PCUNIX \$99.00

### AFFORDABLE UNIX FOR PERSONAL COMPUTERS.

PCUNIX is Wendin's implementation of the super-hit UNIX operating system developed at Bell Laboratories for PDP-11 minicomputers. Designed by systems programmers for systems programmers, a UNIX-like environment is ideal for developing system software.

### A MAINFRAME OPERATING SYSTEM ON A PC.

Just when you thought UNIX was going to need an IBM-AT computer, 20 megabytes of disk space, and thousands of dollars for an AT&T license, Wendin put PCUNIX on the PC for a fraction of the cost. PCUNIX has the same powerful features you're used to, like MULTIPLE PROCESSES, MULTIPLE USERS, POWERFUL SYSTEM SERVICES, and the set of tools called the PROGRAMMER'S WORKBENCH.

Ask us about our new Operating System Toolbox™, only \$99.



ORDER HOTLINE  
**509/235-8088**  
CREDIT CARDS WELCOME!

Foreign orders inquire about shipping.  
Domestic orders add \$3.50/1st item, \$1.00 each additional  
item for shipping, handling and insurance.  
Washington residents add 7.8% sales tax.

Unix is a registered trademark of AT&T  
VAX/VMS is a registered trademark of Digital Equipment Corporation  
MS-DOS is a registered trademark of Microsoft, Inc.  
PC-DOS is a registered trademark of IBM  
Wendin and XTC are Registered Trademarks of Wendin, Inc.  
PCVMS, PCUNIX, and Operating System Toolbox are Trademarks of Wendin, Inc.

**WENDIN**®

BOX 266  
CHENEY, WA 99004

The people who make quality  
software tools affordable.



```

mov     cx,setlen           ;cx=number bytes in set
set3_1:
lodsb   ;al<-[si]; si:=si+1
and     byte ptr [di],al    ;[di]<- logical and of [di],al
inc     di                  ;advance destination set pointer
loop    set3_1              ;loop on cx
jmp     setexit             ;end set3

set3    endp
page
;-----
; SET4 (ah=4) make set from string  set <- [s(1),s(2),...,s(n)]
;-----
; Purpose      -- insert 8-bit elements from string (s)
;               into the set. Assumes first byte of string
;               indicates length.
;
; Called by    -- main jump table
;
; Calls        -- set5 (via fall-through)
;
; Arguments    -- (ds:si) = address first byte of string (s[0])
;               (es:di) = address of destination set
;
; Registers    -- none
;-----
set4    proc    near
mov     cx,setlen           ;set cx=number bytes in set
xor     al,al              ;set al=0 (value to store in set)
push    di                 ;save di (set address) on stack

;----- make existing set null

rep     stosb               ;store al at [di] until cx=0
pop     di                 ;restore di
;fall through to set5 procedure

set4    endp
page
;-----
; SET5 (ah=5) make set alternate  set <- set + [s(1),s(2),...,s(n)]
;-----

```

```

; Purpose      -- add 8-bit elements from string s into
;               an existing set
;
; Called by    -- main jump table
;               set4 (via fall-through)
;
; Calls        -- setcalc
;
; Arguments    -- (ds:si) = address first byte of string (s[0])
;               (es:di) = address of destination set
;
; Registers    -- none
;-----
set5    proc    near
xor     cx,cx               ;zero cx so that ch=0
lodsb   ;get length al<-[si]; si:=si+1
mov     cl,al               ;set cx=count of chars in string
jcxz    set5_2              ;exit on null string

set5_1:
lodsb   ;get byte al<-[si]; si:=si+1
mov     dl,al               ;move value in al to dl for setcalc
call    setcalc             ;calculate byte offset bx; bit ah
or      byte ptr [di+bx],ah ;or bit in ah into set byte
loop    set5_1              ;cx<-cx-1; if cx>0 then loop

set5_2:
jmp     setexit             ;end set5


set5    endp
page
;-----
; SET6 (ah=6) set inclusion      set1 <- set2
;-----
; Purpose      -- test if set1 is a subset of set2
;
; Called by    -- main jump table
;
; Calls        -- none
;
; Arguments    -- (es:di) = address of set1
;               (ds:si) = address of set2
;
;

```


## FLOPPY DISK SERVICES INC.

39 Everett Dr., Bldg. D  
Lawrenceville, N.J. 08648


Floppy Disk Services, Inc. has been serving the computer community for 6 years now. We offer the best in products and service for the professional and hobbyist alike. Organizations like NASA, RCA, AT&T and IBM who demand quality are among our valued customers. Our techs can custom assemble virtually any special cabling or enclosure set-up you may need. We offer an enclosure line that has sold thousands over the years and our replacement warranty policy puts us out front. . . We are among the first to offer 8 inch double sided drive systems that run on the IBM-PC/XT for interchangeability standards from mainframe to micro.




Mitsubishi 4851 DS/DD 48 tpi. .... \$139.  
Mitsubishi 4854 1.6mb AT drive ..... \$185.  
10 megabyte system ..... \$495.  
20 megabyte system ..... \$595.  
40 megabyte system ..... \$995.  
130 watt pc supplies ..... \$ 95.  
XT motherboards ..... Call  
Western Digital controllers ..... \$165.  
Taxan 415 RGB monitors ..... \$299.  
Teac 55F 80 track drives ..... Call



Taxan monitors (built for ACORN) \$299.



All our connectors and adaptors are crimped on AMP certified equipment!



AST, Quadram and Western digital boards available!

We offer many more products than space allows. Please call for FREE catalog or let one of our expert staff help you make the right choice, and the call is on us!

"... (Floppy Disk Services) is one of the few mail order houses that enthusiastically does custom work; the technicians there can assemble virtually any desired floppy or hard disk system to order..."

Jeff Duntemann  
Technical Editor, PC Tech Journal

VISA



Toll Free Order Line: 1 (800) 223-0306

MasterCard

CIRCLE NO. 163 ON READER SERVICE CARD



# SHIFT YOUR HARD DISK BACK INTO HIGH GEAR



with  
**disk optimizer**

ONLY  
**\$49.95\***

Special Introductory Price

## Tunes Your Disk Files For Highest Performance

The Disk Optimizer organizes your disk to make your PC run faster. You'll discover faster program loading, faster file loading and sorting, faster file creation, faster backups to diskette. And the disk Optimizer reduces the chances of error during your disk I/O.

### BEFORE DISK OPTIMIZING

A	CC	AA	DDD	D	E	BB	F	FF	GG	AAA	H	BB	JJ	JJJ	AAA	BBBB
A	CC	AA	DDD	D	E	BB	F	FF	GG	AAA	H	BB	JJ	JJJ	AAA	BBBB

### AFTER DISK OPTIMIZING

AAAAA	AAAAA	BBBBB	BBBBB	CC	DDDD	E	FFF	GG	H	JJJJ	JJJJ
AAAAA	AAAAA	BBBBB	BBBBB	CC	DDDD	E	FFF	GG	H	JJJJ	JJJJ

### DOS IS SLOWING YOU DOWN!

Whether you realize it or not, the more you use your hard disk, the slower it is likely to react. This is because the operating system (PC-DOS/MS-DOS) stores things (programs, overlays, batches, etc.) randomly, wherever unused disk space is available. Your operating system doesn't keep pieces of the same file together. This means slower access time. Lost speed. Lost productivity.

### TURN THE THROTTLE BACK UP!

Now, the Disk Optimizer puts the zip back into your hard disk! The Disk Optimizer collects all the scattered pieces of your files and re-stores them together in neat, well-organized areas on your disk. The result: immediate performance improvement . . . faster loading programs (and their overlays) . . . faster sorting . . . faster loading and storing spreadsheets or document files.

### BONUS EXTRAS — at no extra cost

- ✓ **DISK ANALYZER**  
Displays a visual performance analysis . . . shown in percentages . . . for any disk or diskette.
- ✓ **PERSONAL FILE SECURITY**  
Password protect any file or program.
- ✓ **FILE PEEKER**  
Now you can visually examine any file on your system.

**\$49.95\***

\*Plus \$5.00 Shipping & Handling

**Order Toll-Free:**  
**1-800-272-9900**



CIRCLE NO. 178 ON READER SERVICE CARD

**SOFTLOGIC  
SOLUTIONS**

*Creators of DoubleDOS*

530 Chestnut Street, Manchester, NH 03101

1-800-272-9900. In NH, call 627-9900

Disk Optimizer works with IBM PC's and true compatibles.



# How To:

1. Write Less Documentation
2. Create Bug Free Code
3. Program Faster

**STERLING CASTLE**  
Reader Inquiry

**HELP**  
PUT IT ANYWHERE,  
CALL IT ANYTIME,  
DISPLAY WHATEVER  
INFORMATION YOU CHOOSE

**STERLING CASTLE**

Name : John D. Pritchard  
Title : General Manager  
Company : GTL Products International  
Address : 117 South Upliftment Lane  
City : New York State : NY Zip : 10016  
Phone : (213) 1001  
Publication : 100  
Comments :

Tech Jnl  
Byte  
Comp Lang  
Prog Jnl  
PC World  
Infoworld  
PC Week  
Dr Dobbs

**EZ POP UP WINDOWS**

1001

10-01-85

**MULTIPLE WINDOWING CAPABILITY**

**1**

## HELP MESSAGE SYSTEM

Minimize documentation! Create and edit, context sensitive, interactive help and/or tutorial functions. Turns your text information into callable libraries. Overhead to your programs is insignificant.

**2**

## B-PLUS TREE SUB-SYSTEM

Write your program without worrying about sorting or handling of index files. Direct and sequential accessing, variable length keys, multiple non unique keys and multiple keys per record. Get first, Next, Last or Prior key in sequence. Can access a key field in less than one second. Complete source code included!

## EZ SCREEN (pop up windows)

An Assembler language routine embedded in a basic subroutine to perform screen handling and windowing functions when called from a Basic program.

**3**

## SCREEN BUILDER SYSTEM

Using either the built in editor or your word processor, create and edit fields of any length anywhere on the screen with full screen editing within each field and full screen movement from field to field. The generated code is ready to insert in your program. Does not use BLOAD or BSAVE. Makes no calls to BIOS.

**4**

\*Requires PC or MS Dos, BASICA or Microsoft Basic \*Runs under interpretive and compiled basic \*Compatible under IBM, Microsoft, or Quick Basic Compiler

**30 Day Money Back Guarantee Not Copy-protected Pay No Royalty**

Any 1 Program \$ 49  
Any 2 Programs \$ 69  
Any 3 Programs \$ 89  
All 4 Programs \$ 99

30 day  
special  
all 4

**\$69**

**STERLING  
CASTLE**

Helping You to Solve Problems

CREDIT CARDS WELCOME!

Shipping Included  
No Extra Charges  
CA residents add 6% sales tax

**Order Hotline: (213) 306-3020**

702 Washington Street  
Suite 174  
Marina del Rey, CA 90292

CIRCLE NO. 183 ON READER SERVICE CARD



```

; Registers -- zf = 1 if set1 <= set2 (use je)
;           zf = 0 if not (set1 <= set2) (use jne)
;
;-----
set6 proc near
mov cx, setlen ;cx=number bytes in set
set6_1:
lodsb ;al <- [si]; si := si + 1
and al, byte ptr [di] ;al <- [si] & [di]
cmp al, byte ptr [di] ;compare with original byte
jne set6_2 ;jump on difference found
stosb ;advances di (value [di] unchanged)
loop set6_1 ;loop on cx (flags preserved)
set6_2:
jmp setexit ;end set6
set6 endp
page
;-----
; SET7 (ah=7) set comparison set1 = set2
;-----
; Purpose -- test if set1 equals set2
;
; Called by -- main jump table
;
; Calls -- none
;
; Arguments -- (ds:si) = address of set1
;            (es:di) = address of set2
;
; Registers -- zf = 1 if set1 = set2 (use je)
;            zf = 0 if set1 <> set2 (use jne)
;-----
set7 proc near
mov cx, setlen ;cx=number bytes in set
repz cmpsb ;compare [si],[di]
;loop on cx if equal
jmp setexit ;end set7
set7 endp
page
;-----
; SET8 (ah=8) add element set1 := set1 + [element]

```

```

;-----
; Purpose -- add one element to members of a set
;
; Called by -- main jump table
;
; Calls -- setcalc
;
; Arguments -- (es:di) = address of destination set
;            (dl) = 8-bit element to add
; Registers -- none
;-----
set8 proc near
call setcalc ;calculate byte offset bx; bit ah
or byte ptr [di+bx], ah ;or bit in ah into set byte
jmp setexit ;end set8
set8 endp
page
;-----
; SET9 (ah=9) copy set set1 := set2
;-----
; Purpose -- copy one set variable to another
;
; Called by -- main jump table
;
; Calls -- none
;
; Arguments -- (ds:si) = address of set2 (source)
;            (es:di) = address of set1 (destination)
; Registers -- none
;-----
set9 proc near
mov cx, setlen ;cx=number bytes in set
rep movsb ;copy [di]<-[si] until cx=0
jmp setexit ;end set9
set9 endp
page
;-----
; SET10 (ah=10) make null set set1 := []

```

## MEX 'n' Match

**MEX-PC** — Full-featured modem software for your IBM-PC (Versions also available for Tandy 2000 and most CP/M machines). Now can be menu driven • Fully programmable function keys • Simple built-in programming language for custom applications development • Choice of 8 background/foreground colors • All popular protocols (KERMIT available Dec. 85) • Automatic & repeat dialing • Runs DOS commands and programs while on-line • "Clones" customized versions.

**\$59.95**

**NightOwl Connection** — A multi-user on-line service that provides you with round-the-clock access to MEX support, plus all the latest and best in public domain and user-supported software. The **Connection** features 36 megabytes of free software — some of it exclusive to **Connection** subscribers — including 18 megabytes worth of programs for the IBM-PC and compatibles. MEX-PC owners can download all updates to their communications program free of charge!

**\$100/yr.**

(\$50/yr. renewal)

**TEM** — Intelligent terminal emulation add-on module for MEX-PC. As shipped, MEX emulates an ADM-3A equivalent terminal. **TEM** expands MEX to emulate either a Televideo 925 or DEC VT52/VT100.

**TEM** is full-function emulation, allowing you to use remote text processors and spreadsheet programs running on mainframes that require a specific terminal interface. Simple installation. Fully documented.

**\$29.95**

**REO** — REmote Operation module with password security. This inexpensive add-on module adds remote access capability to your MEX program. It allows you to call up your office computer from home — or your home computer from your office — and swap data or text files, even programs. Download a spreadsheet, rework it at home, then send it back, updated, to your office. Password security keeps unauthorized persons from gaining access to sensitive files.

**\$29.95**

FEATURE	MEX-PC <sup>®</sup>	Cross-talk <sup>®</sup>	PC-Talk <sup>®</sup>	Symphony <sup>®</sup>
"CLONE" customized versions	YES	NO	NO	NO
Run DOS commands & programs	YES	YES	NO	NO
Repeat dialing	YES	YES	NO	NO
List dialing	YES	NO	NO	NO
Maximum baud rate	57,600	9,600	1,200	9,600
"Interactive" script files	YES	YES	NO	YES
Programmable keys	40	10	10	***
Modem-7 batch transfers	YES	NO	NO	NO
CompuServe transfer protocol	YES	NO	NO	NO
Price (suggested retail)	\$60	\$195	\$35	\$695

\*\*\* Symphony supports keyboard "macros."

MEX and MEX-PC are trademarks of NightOwl Software, Inc. • CROSSTALK is a registered trademark of Micro Stuf • SYMPHONY is a trademark of Lotus Corporation • PC-TALK is a trademark of Headlands Press, Inc.

### MEX PACK..... \$99.95

As a special introduction to our remote operating module and terminal emulation system, we're offering an all-in-one package for a limited time only. **MEX-PACK** is a complete communications package that includes: **MEX-PC** (version 1.50); **REO** remote operating module; **TEM** intelligent terminal emulation module; and a six-month subscription to the **NightOwl Connection**. Purchased individually, the items in this package would cost you \$144.85 — a savings of almost \$45!

**Give us a toll-free call at  
1-800-NITEOWL**

**In Wisconsin, 1-414-563-4013**

MasterCard, VISA welcome

NightOwl Software, Rt.1 Box 7, Ft. Atkinson, WI 53538





```

;
; Purpose      -- make a set variable equal to the null set
;
; Called by    -- main jump table
;
; Calls        -- none
;
;
; Arguments    -- (es:di) = address of set1
;
; Registers    -- none
;-----
set10  proc    near
        mov     cx,setlen          ;cx=number bytes in set
        xor     al,al              ;al <- 0
rep     stosb          ;store al at [di] until cx=0
        jmp     setexit           ;end set10
set10  endp
page
;-----
;
;      Jump Table (in code segment)
;-----
; following are the addresses of the individual routines in the set
; package. the list of addresses forms a table for selecting a
; function based on the value in ah.
jumpable:
        dw      set0              ;fn0-set membership
        dw      set1              ;fn1-set union
        dw      set2              ;fn2-set difference
        dw      set3              ;fn3-set intersection
        dw      set4              ;fn4-make set
        dw      set5              ;fn5-add to set
        dw      set6              ;fn6-set inclusion
        dw      set7              ;fn7-set comparison
        dw      set8              ;fn8-add single element
        dw      set9              ;fn9-copy set to set
        dw      set10             ;fn10-make null set
cseg   ends
end
;end of code segment
;end of text

```

### LISTING 3: SETTEST.ASM

```

page 60,132
title SETTEST.ASM 1.00
;-----
; Program      : Sets module test program
; Version      : 1.00
; System       : IBM PC-DOS 2.00+
; Language     : IBM 8088 Macro Assembler
; Author       : (C) 1985 by Tom Swan
; Address      : Swan Software P.O. Box 206 Lititz PA 17543
;-----
true equ -1
false equ 0
host equ true

;-----
;      Code, data, stack groups
;-----
dgroup group dseg
cgroup group cseg
sgroup group sseg
assume cs:cgroup, ds:dgroup, es:dgroup, ss:sgroup

;-----
;      Equates
;-----
cr equ 13 ;ASCII carriage return
lf equ 10 ;ASCII line feed

;-----
;      Macro definitions
;-----

; Call dos function p1

dosfn macro p1 ;;"dosfn 2" calls dos function #2
mov ah,p1 ;;pass function number in ah
int 21h ;;call dos via interrupt 21 hex
endm

```

```

; Call sets function

setfn macro n ;;"setfn 8" calls sets function #8
mov ah,n ;;select function n
call sets ;;call sets package (near)
endm

;-----
; Data segment
;-----
dseg segment byte public 'data'
progid db 'Set Test Program 1.00',cr,lf
db '(C) 1985 by Tom Swan',cr,lf
crlf db cr,lf,'$'
donemsg db cr,lf,'Test completed',cr,lf,'$'

;----- Test strings. First byte = length.

s1 db 36,'1234567890abcdefghijklmnopqrstuvwxyz'
s2 db 13,'ACEGIKMOQSUYW'
s3 db 13,'BDFHJLNPRTVXZ'

dseg ends

;-----
; Stack segment
;-----
sseg segment para stack 'stack'
db 8 dup('**Stack**')
sseg ends

;-----
; Code segment
;-----
cseg segment byte public 'code'

include sets.ext ;include global declarations

settest proc far
push ds ;set up far return address on stack
xor ax,ax ; equal to ds:0000.
push ax
push ds ;save value of segment
; registers ds,es


push es
mov ax,dseg ;prepare to load ds,es via ax
mov ds,ax ;set ds=data segment address
mov es,ax ;set es=data segment address
lea dx,progid ;dx=address program id message
dosfn 9 ;print string
lea si,s1 ;test string 1
call test
lea si,s2 ;test string 2
call test
lea si,s3 ;test string 3
call test
lea dx,donemsg ;dx=address done message
dosfn 9 ;print string
pop es ;restore segment registers es,ds
pop ds
ret ;execute far return to dos

settest endp
page
;-----
; PRINT / NEWLINE
;-----
; Purpose -- display test string
;
; Called by -- test
;
; Calls -- none
;
; Arguments -- (ds:si) = address of string at len byte
;
; Registers -- ax,cx,dx destroyed, si preserved
;-----
print proc near
push si
cld ;clear df for auto increments
lodsb ;al <- [ds:si]: si <- si + 1

```



# Why your next generation of products should use our 5th generation tools.



Arity's integrated family of programming tools allows you to combine software written in Arity/Prolog, the best of the fifth generation languages, with Arity SQL, the best of the fourth generation languages, and with conventional third generation languages such as C or assembly language to build your smarter application.

You can use Arity/Prolog to build expert systems using the Arity Expert Systems Development Package. Or to build natural language frontends. Or to build intelligent information management systems. Arity/Prolog lets you build advanced technology into your vertical applications package.

## And more...

That's not the whole story. Arity's products are all designed to be fast, powerful, serious. Each of our products contains unexpected bonuses. Such as a one gigabyte virtual database integrated into Arity/Prolog. The most powerful of its kind on a PC.

## Quality first. Then price.

In order to be the best, we had to prove it to our customers. Our tradition of quality software design is reflected in every product we sell. Quality first. Then price. And we always provide the best in customer support.

Our products are not copy protected. We do not charge royalties. We offer generous educational and quantity discounts. And we have a 30 day money back guarantee.

Try us to know that we keep our promise on commitment to quality and reliability. Try us by using our electronic bulletin board at 617-369-5622 or call us by telephone—you can reach us at 617-371-2422.

Or fill in this coupon. Whether you order today or not, let us send you full descriptions of our integrated family of Arity products.

CIRCLE NO. 136 ON READER SERVICE CARD

**arity**

We design and distribute high quality, serious application software for the IBM PC, XT, AT and all MS-DOS compatibles.

Please complete this form to place your order and/or request detailed information.

		Quantity	Info only
Arity/Prolog Compiler and Interpreter V4	\$795.00	_____	_____
Arity/Prolog Interpreter V4	\$350.00	_____	_____
Arity Standard Prolog	\$ 95.00	_____	_____
Arity SQL Development Package	\$295.00	_____	_____
Arity Expert System Development Package	\$295.00	_____	_____
Arity Screen Design Toolkit	\$ 49.95	_____	_____
Arity File Interchange Toolkit	\$ 49.95	_____	_____
TOTAL AMOUNT (MA residents add 5% sales tax) (These prices include shipping to all U.S. cities)		\$ _____	_____

NAME \_\_\_\_\_

SHIPPING ADDRESS \_\_\_\_\_

CITY/STATE/ZIP \_\_\_\_\_

TELEPHONE \_\_\_\_\_

Payment: ☐ Check ☐ PO ☐ AMEX ☐ VISA ☐ MC

Card # \_\_\_\_\_ Exp. date \_\_\_\_\_

Signature \_\_\_\_\_

ARITY CORPORATION • 358 BAKER AVENUE • CONCORD, MA 01742

**arity**



```

xor     cx,cx           ;zero cx
mov     cl,al           ;cx = string length 0 .. 255
jcxz    print2          ;exit if length = 0

print1:
  lodsb                ;al <- next character from string
  mov     dl,al         ;transfer al to dl
  dosfn   2             ;print char in dl
  loop    print1        ;loop on cx

print2:
  pop     si            ;restore si register

;----- Print crlf and return. Can be called as separate subroutine.
newline:
  lea     dx,crlf       ;dx = address of ASCII$ string
  dosfn   9             ;print string
  ret                      ;return to caller

print    endp
page
;-----
; TEST
;-----
; Purpose      -- perform test -- enter characters until
;               set of characters typed equals expected
;               set of characters. Repeat test if any
;               extra characters are accidentally typed.
;
; Called by    -- main program
;
; Calls        -- sets
;               print
;               report
;
; Arguments    -- (ds:si) = address of test string
;
; Registers    -- ax,cx,dx,di destroyed
;-----
dseg    segment byte public 'data'
chset   set<>           ;set of characters entered
doneset set<>           ;set of characters expected
dseg    ends

```

```

test    proc    near
  push    si            ;save si in case test repeats
  call    print         ;print test string
  lea     di,doneset    ;di = address of doneset variable
  setfn   4             ;doneset <- set of chars in string
  lea     di,chset       ;di = address of chset variable
  setfn   10            ;make chset = null set []
  lea     si,doneset     ;preset si = address of doneset

test1:
  dosfn   1             ;get and echo char (ch in al)
  mov     dl,al         ;transfer char to dl
  setfn   8             ;insert dl into chset at (di)
  xchg    si,di         ;si=chset, di=doneset
  setfn   6             ;test for doneset <= chset
  xchg    si,di         ;si=doneset, di=chset
  jne     test1         ;jump if doneset
                          ; not a subset of chset

;----- Report results of test, and repeat same test on any errors
  call    report        ;check and report results
  pop     si            ;restore si register
  jz      test          ;repeat test on any errors
  ret                      ;else end test

test    endp
page
;-----
; REPORT
;-----
; Purpose      -- report results of test.
;
; Called by    -- test
;
; Calls        -- newline
;               sets
;
; Arguments    -- doneset (in test dseg) = expected char set
;               chset (in test dseg) = chars entered
;
; Registers    -- ax,dx,di,si destroyed
;               zf = 1 if extra chars entered (use jz)
;               zf = 0 if entry was perfect (use jnz)
;-----
dseg    segment byte public 'data'
repmsg  db    'Extra chars = ','$'
noerr   db    'none',cr,lf,'$'
error   db    ?
dseg    ends

report   proc    near
  mov     error,false   ;error flag = false
  call    newline       ;write a blank line
  lea     dx,repmsg      ;prepare to print report message
  dosfn   9             ;print string
  lea     di,doneset     ;di = address of doneset
  lea     si,chset       ;si = address of chset
  setfn   2             ;doneset <- chset - doneset
  mov     dl,32          ;dl = ASCII first char to check

rep1:
  setfn   0             ;set membership for value in dl
  jz      rep2          ;jump if dl not a member of doneset
  mov     error,true     ;else flag the error
  dosfn   2             ;and print the extra character

rep2:
  inc     dl            ;next char to test
  cmp     dl,128         ;loop while dl < 128
  jb      rep1

  lea     dx,noerr       ;prepare to print "none" message
  cmp     error,true     ;check error flag
  jne     rep3          ;jump if no errors detected
  lea     dx,crlf        ;print crlf if errors found

rep3:
  dosfn   9             ;print ASCII$ string at dx
  call    newline       ;write two blank lines
  call    newline
  cmp     error,true     ;set flags before returning
  ret                      ;end test / report

report   endp
cseg    ends
end      settest        ;end of segment
                          ;end program

```

## Does your disk look like THIS?



Let **HD TUNEUP** cleanup your act!  
**HD Tuneup** reallocates all files on a disk into adjacent clusters, speeding up your file and program loads.

**HD Tuneup** leaves all of the free space on your disk in one area so that your new files may be allocated contiguously.

**HD Tuneup** speeds directory searches by placing all directories adjacent to each other and eliminating deleted entries. Files in the same sub-directory are moved adjacent to each other, minimizing head movement between files during disk intensive applications.

**HD Tuneup** requires PC compatibility, DOS 2.x/3.x and 196k. Hard drives up to 32mb may be tuned, along with any diskette.

### AVAILABLE NOW

for \$39.95 + \$3.00 s/h


**SofCap Inc.**

P.O. Box 131

Cedar Knolls, NJ 07927

Visa (201) 267-0848 M/C

N.J. residents add 6% sales tax.





# Microsoft languages speak for themselves.





## Loud and clear.

Microsoft has been the language leader from day one. From the world's favorite BASIC to the systems languages software developers prefer. No one else has put so much programming power on so many micros.

Microsoft offers a complete set of languages. Whether you favor the elegance of C, or the power of assembly language. From data munching in COBOL to number crunching in FORTRAN, we've got the power you need.

### The advantages of leadership.

Microsoft languages have developed quite a following. They're backed by the largest collection of support libraries you've ever seen. Packages for advanced mathematics and data management. From graphics support to context-sensitive editors. All available today. So you can spend your time solving real problems, not reinventing the wheel.

Microsoft's languages—like C, FORTRAN, Pascal and Macro Assembler—have become the favorites of commercial software developers. It's not surprising. Interlanguage calling allows libraries written in one language to be

used with others. Which means your existing routines can be an investment in future projects, not lost time and effort.

Our interactive debuggers are another Microsoft edge. Now you can debug the object code using the source language. Easier debugging lets you spend more time creating.

### Pipelines to the future.

Microsoft wrote the book when it comes to operating systems. Nobody knows MS-DOS® or XENIX® better. And our languages show it. We put the latest advances within your grasp. From networking and pipes to multi-tasking, Microsoft languages have the edge you need.

### Complete support.

Only Microsoft offers language support this comprehensive. Our clear, thorough documentation, and regular product enhancements are setting new standards in the industry. Add our technical "hotline" and our highly-trained support staff, and you'll reach the same conclusion the industry has: Microsoft languages always lead from strength.





# Microsoft C

First with the pros.

*"Microsoft C is the cornerstone of all our future development projects. Not only is the code more efficient, we can really exploit the PC's architecture with Microsoft C's NEAR and FAR pointer types."*

Ray Ozzie, President of IRIS Associates and key Symphony developer.

*"The code optimization is impressive—especially the register declarations."*

Jim Bean, Peachtree Software.

When you need code that's small and fast, Microsoft® C is the language.

Our optimizing compiler lets you squeeze the maximum out of your machine with minimum effort. Tighter code runs faster. And virtually every program will run faster with Microsoft's C Compiler than with any other MS-DOS compiler.

Our advanced memory models give you unmatched flexibility. No arbitrary limits on code and data. Use large or small memory models as the application demands. Exclusive features like our NEAR and FAR pointers let you combine different models without sacrificing performance.

Our extensive math libraries are another plus. The floating point package supports 8087 operation when speed is the key. There's also floating point emulation for unendowed PCs. And the almath package gives you an extra burst of speed when you really need it.

A bundle of other features can save you programming time. There's inter-language calling support. So you can use existing library routines. Unsurpassed XENIX compatibility. And documentation that reviewers have praised for its clarity and thoroughness.

If Microsoft C amazes you, don't be surprised. After all, our C is the choice of the leaders. Companies like Lotus® Ashton-Tate. And IBM®.

## Microsoft C Compiler Version 3.0 for MS-DOS

### Microsoft C Compiler

- Produces compact code and fast executables.
- Implements register variables.
- Small, medium and large memory model libraries.
- Can mix models with NEAR and FAR pointers.
- Transport source and object code between MS-DOS and XENIX 286 operating systems.
- Library routines implement most of UNIX™ System V C library.
- Choose from three math libraries and generate in-line 8087/80287 instructions or floating point calls:
  - Floating Point Emulator (utilizes 8087/80287 if installed).
  - 8087/80287 coprocessor support.
  - Alternate math package provides extra speed without an 8087/80287.
- Link your C routines with Microsoft FORTRAN (version 3.3 or higher), Microsoft Pascal (version 3.3 or higher) or Microsoft Macro Assembler.
- Supports MS-DOS pathnames and input/output redirection.
- File sharing, record locking and file locking are supported.
- Do source level debugging with the Symbolic Debug Utility, available separately with Microsoft Macro Assembler.

### Library Manager

- Create, organize and maintain your object module libraries created with Microsoft languages.

### Object Code Linker



- Simple overlay linker combines relocatable object modules created using Microsoft languages into a single program.
- Link very large programs (over 1 megabyte) using overlays.

### Microsoft EXE File Compression Utility

- A new utility to compress sequences of identical characters from an executable file and optimizes the relocation table.

### Microsoft EXE File Header Utility

- Display and modify EXE file header, allowing you to tune the stack size and initial memory allocation.





# Macro Assembler

The quickest. Bar none.

Our Macro Assembler has long been the most complete package on the market. Now it's also the fastest. Three times faster than before. And faster than anyone else. Period.

Of course, it's still the most powerful assembler on the market. It supports the standard 8086/8087 opcodes. And the new 186/286/287 instruction set. So you can make the most of the new machines.

Debugging is quicker, too. Thanks to our interactive symbolic debugger, SYMDEB. Now you can refer to variables and source code instead of getting lost in hex dumps. And this debugger also works with Microsoft languages like C, FORTRAN and Pascal. So now you can set breakpoints and trace execution—using source code for reference.


SYMDEB is just part of our complete set of utilities. Tools that make programming as fast as it should be. There are the linker and library managers you'd expect. Plus a new version of MAKE, our maintenance utility, with improvements like macro expansions and inference rules.

We've also revised the manuals. Our new Macro Assembler has a lot to offer, so we added more examples. Now our manuals are not only thorough, they're clearer than ever before.

For quick development and assembly, the choice is obvious. Microsoft. There's nobody faster.



*The Macro Assembler's symbolic debugger lets you debug Microsoft FORTRAN programs at either the source or object code level. Set break points, observe the contents of variables and expressions, and examine the contents of the stack.*



## Microsoft Macro Assembler Version 4.0 for MS-DOS

### Macro Assembler

- Fastest macro assembler for MS-DOS computers.
- Supports the 8086/8087/8088 and the 186/286/287.
- Define macros.
- Conditional assembly.
- Optional case sensitivity for symbols.
- 100% upward compatibility from earlier versions of both the Microsoft and IBM Macro Assemblers.

### Interactive Symbolic Debug Utility

- Source level debugger for programs written in Microsoft Macro Assembler, C Compiler, FORTRAN, and Pascal.
- Screen swapping helps debug highly visual applications.
- Set breakpoints on line numbers and symbols.
- Single step to follow program execution.
- Disassemble object code.
- Display and modify values.
- Full I/O redirection.

### Program Maintenance Utility

- Rebuilds your applications after your source files have changed.
- Similar to UNIX MAKE utility.
- Supports macro definitions and inference rules.

### Library Manager

- Create, organize and maintain your object module libraries created with Microsoft languages.
- Set page size from 16 to 32678, to create compact and granular libraries.

### Object Code Linker

- Simple overlaying linker combines relocatable object modules created using Microsoft languages into a single program.
- Load Map generation.
- Specify from 1 to 1024 segments.

### Cross-Reference Utility

- Creates a cross-reference listing of the definitions and locations of all symbols used in an assembly language program, which makes debugging programs easier.

### Microsoft EXE File Compression Utility

- Packs EXE files for smaller size on disk and faster loading at execution time.


### Microsoft EXE File Header Utility

- Display and modify EXE file header, allowing you to tune the stack size and initial memory allocation.



# FORTRAN

The overwhelming favorite.



*View the FORTRAN source code. Set a break point at line #14. Run the program (g) and use the expression evaluator (?) to examine the contents of a variable. Then use the trace command (t) to observe the program flow.*

## Microsoft FORTRAN Compiler Version 3.3 for MS-DOS and XENIX 286

### Microsoft FORTRAN Compiler

- Implements most ANSI 77 standard features, plus extensions.
- Easily port mainframe/minicomputer programs with little or no modification.
- Overlay support in the compiler and linker.
- Common blocks and arrays greater than 64K.
- Supported by the largest number of third party libraries.
- Includes a full set of math libraries to select from:
  - 8087/80287 emulation.
  - 8087/80287 coprocessor support.
  - Floating Point without 8087/80287.
  - BCD Floating Point.
- Conditional compilation.
- Link your FORTRAN routines with Microsoft C Compiler (version 3.0 or higher), Microsoft Pascal (version 3.3 or higher), and Microsoft Macro Assembler.
- MS-DOS 3.1 network support and IBM local area network support.
- Source code compatible between MS-DOS and XENIX 286.
- Do source level debugging with the Symbolic Debug Utility, available separately with Microsoft Macro Assembler.

### Object Code Overlay

- Simple overlay linker combines relocatable object modules created using Microsoft languages into a single program.
- Link very large programs (over 1 megabyte) using overlays.

### Library Manager

- Create, organize and maintain your object module libraries created with Microsoft languages.

### Microsoft EXE File Compression Utility (MS-DOS only)

- A utility to pack EXE files for smaller size on disk and faster loading at execution time.

### Microsoft EXE File Header Utility (MS-DOS only)

- A utility that allows you to display and modify the fields in EXE file headers.

How did Microsoft FORTRAN get so popular?

It could be the mainframe compatibility. Our compiler makes porting applications a cinch with overlays and the ANSI features you need.

It could be our support for arrays and COMMON blocks larger than 64K. So you can tackle mainframe-size problems.

It might be the shelves and shelves of third party support libraries. No other FORTRAN comes close.

It could be the extensive math support. Our collection of math libraries is simply the largest available. Tackle real problems with direct 8087 support or emulation. Use IEEE floating point or—for extra speed—the altmath package.


It could be the comprehensive set of utilities. A powerful linker and library manager combination. Plus tools like EXEMOD and EXEPACK. Standard.

It could be the XENIX and MS-DOS source-level compatibility. Or the direct interlanguage calling to Microsoft C, Pascal, and Assembler. Or the ability to work with our Macro Assembler's symbolic debugger.

It could be the value. Nobody offers a FORTRAN package this complete at this low a price.

Why is Microsoft FORTRAN the most popular FORTRAN?

All the above.





# COBOL

The interactive edge.

```
1 79      close transaction-file.
80
81 *      p110-read-and-process.
82      read transaction-file into work-trans-rec
83      at end move on-value to end-of-file-sw.
84
85      if transaction-status = "00"
86 *      display p110-read-and-process-rcount
87      else if transaction-status > "10"
88      move on-value to error-sw, end-of-file-sw.
89
90 TRANSACTION-STATUS (01) 00000000
91 WORK-TRANS-REC (0) 00000000
92 TOTAL-RECORD-COUNT (000000) 000000
93
94 Breakpoint 1 Step Count 0 on Entry of P110-READ-AND-PROCESS
95 Breakpoint 2 Step Count 0 on line number 86
96
97 COMMAND: Breakpoint Display Find Help Options
98          Quit Transfer User View Window
99 Breakpoint 1 Step Count 0 on Entry of P110-READ-AND-PROCESS
100 Current line: 81 Status: Breakpoint 1 ViewCob: latest
```

Microsoft COBOL gives programs a new look. With dazzling support for interactive programs, and more. Our new COBOL Compiler brings applications to life in several ways.

Our extended screen section lets you create programs that you'd never thought could be written in COBOL. Quickly, easily.

Performance is top notch as well. Our ISAM lets your applications blaze through files. After all, our ISAM is the fastest on the micro market.

Of course, Microsoft COBOL complies with the ANSI standard. Amazing performance, without runtime license fees. No wonder our COBOL is the choice of manufacturers like IBM, AT&T, DEC, HP and Wang.

## Another breakthrough: Microsoft COBOL Tools.

Only Microsoft makes debugging this easy.

Our COBOL Tools is the perfect companion to our COBOL Compiler. A complete set of utilities. Tools that make debugging and maintenance easier than you'd thought possible.

The star of the show is ViewCOB, our

advanced interactive debugger. ViewCOB lets you control and examine programs easily. Open windows on variables and procedures while watching the source code execute. ViewCOB is simply the most advanced COBOL debugger you can get.

Microsoft COBOL and COBOL Tools. An unbeatable team.

### Microsoft COBOL Compiler Version 2.1 for MS-DOS and XENIX 286

#### Interactive extended screen section

- Cursor positioning, auto skip, and automatic data field formatting.
- ACCEPT or DISPLAY a screenful of data with a single statement.

#### Fast multi-key ISAM

- Split keys, alternate keys, duplicate keys.
- Benchmark results of 2500 reads, writes and rewrites to an ISAM file.


	Microsoft COBOL	Micro Focus native code	Ryand McFarland COBOL 2.0
Seconds	846	4073	1177
Source code compatible between MS-DOS and XENIX 286.			

### Microsoft COBOL Tools for MS-DOS and XENIX 286

- Cross reference utility speeds program development.
- Menu generator allows you to use Microsoft Word style menus in your program.
- Mouse interface allows you to create programs that use the mouse (MS-DOS only).

#### Advanced interactive debugger

- Use trace, single step, and execution history to follow the program flow.
- Observe the contents of variables and memory while the program is executing.
- Set breakpoints and change the contents of variables.
- Trap fatal runtime errors.
- Use the menu driven windowing user interface with on-line help.





# Pascal

When you've outgrown the others.

Only Microsoft Pascal is powerful enough to push the outer limits of your PC. With more features than any other Pascal compiler.

Microsoft Pascal handles large programs with ease. No 64K boundaries — use multiple code and data segments up to a megabyte. Create your own libraries of pre-compiled Pascal modules. Separately-compiled modules can be overlayed or linked together into one file.

Our Pascal comes complete with the BCD and 8087 math libraries you'd expect. Including an IEEE floating point emulator. And Microsoft Pascal is completely compatible with IBM's Local Area Network and MS-DOS Networking. Added features without added costs.

Microsoft Pascal also supports direct interlanguage calling to modules written in Microsoft C, or Microsoft FORTRAN or assembly language. And it's compatible with our Macro Assembler's symbolic debugger. So you can track down those subtle logic errors with breakpoints instead of guesswork.

Microsoft Pascal. Nobody does it better.

## Microsoft Pascal Compiler Version 3.3 for MS-DOS and XENIX 286

### Microsoft Pascal Compiler

- Separate module compilation.
- Large program support; up to 1 megabyte code and multiple data segments.
- Overlay support.
- Contains four math libraries to choose from:
  - 8087/80287 coprocessor support.
  - Fast IEEE floating point.
  - 8087/80287 floating point emulation.
  - BCD decimal math.
- Link in your routines or third party software routines written in Microsoft FORTRAN (version 3.3 or higher), Microsoft C Compiler (version 3.0 or higher) or Microsoft Pascal (version 3.3 or higher), or Microsoft Macro Assembler.
- Source code compatible between MS-DOS and XENIX 286.
- Supports file sharing and record and file locking.
- Supports MS-DOS pathnames and input/output redirection.
- Do source level debugging with the Symbolic Debug Utility, available with the Microsoft Macro Assembler.

### Library Manager

- Create, organize and maintain object module libraries created with Microsoft languages.

### Object Code Linker

- Simple overlay linker combines relocatable object modules created using Microsoft languages into a single program.
- Link very large programs (over 1 megabyte) using overlays.

### Microsoft EXE File Compression and File Header Utility (MS-DOS only)

- Compress, modify and examine executable files and their headers.

# Microsoft QuickBASIC

BASIC just got faster.

Microsoft's new QuickBASIC Compiler gives your programs an extra burst of speed. Without sacrificing BASICA compatibility. Your compiled programs will run just like before, only faster. Three to ten times faster. With little or no modification.

QuickBASIC makes structured programming a snap. New extensions like alphanumeric labels make programming easier too. And separately compiled subprograms let you test and compile individual routines one at a time.

Microsoft QuickBASIC. All the features of a compiler, with BASICA compatibility to boot.

## Microsoft QuickBASIC Compiler Version 1.0 for IBM PC and Compatible Computers

### BASICA compatibility

- Sound statements including SOUND and PLAY.
- Graphics statements including WINDOW, VIEW, DRAW, GET, PUT, LINE, CIRCLE, LOCATE and SCREEN.

Results of the Sieve benchmark	BASICA	QuickBASIC
seconds per iteration	71	0.5

### Structured programming support

- Subprograms can be called by name and passed parameters. Both local and global variables are supported.
- Multi-line functions can be called by name and return a value.
- BASICA structures are supported including WHILE/WEND, IF/THEN/ELSE, FOR/NEXT, GOSUB/RETURN, and event handling.

### Alphanumeric labels

- Can be used to make your programs more readable. Line numbers are not required but are supported for BASICA compatibility.

### Modular programming support

- Separate compilation allows you to create compiled BASIC libraries to use and reuse in your programs.
- Named common gives you control of data flow between individual modules.

### Large program support

- Code can use up to available memory.
- Data can use up to 64K RAM.



# LISP

## The language of Artificial Intelligence.

What's Microsoft LISP got going for you? It runs significantly faster than the competition. And this new version adds several advanced libraries. Over 400 Common LISP functions, macros and special forms. Most implemented in machine code.

If you're putting AI on your PC, Microsoft LISP is your language.

# muMATH

## Mainframe math on your PC.

From solving equations to high precision calculations, muMATH is the ticket.

Microsoft muMATH handles tasks from algebra to calculus and vector analysis. Now your PC can do numeric analysis based on symbolic expressions. And give you exact answers.

If you crunch numbers—or equations—muMATH is just what the CPU ordered.

# Sort

## Versatility without compromise.

Microsoft Sort makes fast sorting easy.

A powerful, programmable interpreter lets you choose ASCII, EBCDIC or custom sequences. Sort handles files from any Microsoft language. Without limiting the size of your file, the number of search keys, or your record length.

Microsoft Sort. The speed and power you need. Easily.

## The leadership edge.

No other languages are backed by as massive a collection of third-party software. Here are just a few of the companies that speak our languages: **Blaise Computing, Graphic Software Systems, Greenleaf Software, Inc., IMSL, Media Cybernetics, Microrim, Numerical Analyst Group, Phoenix Software, Solution Systems, Spruce Technology, Trio Systems, and Virtual Microsystems.**

This is just a sample. For a complete list, call Microsoft at the number below.

## An added value for our readers.

We're proud of the way our family works together, so we're offering a \$25 rebate on our Macro Assembler when you purchase Microsoft C, Pascal or FORTRAN.\*

For more details, upgrade information or the name of your nearest Microsoft dealer, call toll free (800) 426-9400. In Washington State and Alaska, call (206) 828-8088. In Canada, (800) 387-6616.

Microsoft Corporation  
Bellevue, Washington USA

Microsoft GmbH  
München DEUTSCHLAND

Microsoft Canada Inc.  
Toronto CANADA

Microsoft AB  
Stockholm SWEDEN

Microsoft Pty  
Sydney NSW AUSTRALIA

Microsoft Ltd.  
Reading ENGLAND

Microsoft SARL  
Paris FRANCE


QNIX Microsoft  
Seoul KOREA

Microsoft Far East  
Tokyo JAPAN

Microsoft SpA  
Milano ITALIA

\*Rebate offer valid only in the United States.


Microsoft, MS-DOS, and XENIX are registered trademarks and The High Performance Software is a trademark of Microsoft Corporation. Microsoft Lisp and muMATH were developed by Soft Warehouse, Inc.



# Microsoft<sup>®</sup> Languages

The High Performance Software™





*The Hardcard, with its combination of a 10MB Winchester disk and controller on an expansion card, is fast, reliable, and easily installed by the user.*

# Storage on a Card

Most users are accustomed to the idea of inexpensive hard-disk systems for the PC. *PC Tech Journal* reviewed ten internally mounted 10MB systems in November 1984 (see "Ten by Ten," Thomas V. Hoffmann, p. 52). Each system included a full-length adapter card and a 5¼-inch disk drive that mounted in a diskette slot on the system unit. Seven used half-height drives, three used full-height drives like those in the PC/XT.

The Hardcard from Plus Development Corporation integrates a 10MB 3½-inch Winchester disk and controller on a single expansion card. Installation involves just one screw that secures the card to the rear panel—no cables or connectors are needed. The drive is four inches high and only one inch thick, and the controller, which occupies about half of the card's length, uses high-density, surface-mounted custom LSI chips. Table 1 lists the Hardcard's technical specifications.

The disk and controller are newly designed by Plus. The disk contains a single platter that spins at the standard rate of 3,600 RPM; it has two read/write heads, one for each surface. The standard XT disk has two platters and four surfaces, each with 306 tracks of 17 sectors. The Hardcard has 612 tracks per surface, yielding the same 10MB capacity. Its fixed-disk BIOS presents a logical disk with 306 cylinders and four heads for compatibility with existing systems and applications. Table 2 shows the Hardcard space allocation under DOS.

The product claims a high degree of reliability, with an MTBF (mean time between failures) of 25,000 power-on hours. This is about double that for most other 10MB Winchester drives. In addition, the drive automatically retracts the heads to a safe landing zone when power is removed. This feature is helpful for a PC that is moved about because it averts the need to execute a special "shipper" or "head parking"

THOMAS V. HOFFMANN



# Fortran Support for IBM PC/XT/AT & Compatibles

## Versions Available For:

Microsoft, Supersoft, RyanMcFarland, IBM Professional, Lahev, & IBM Fortran.

### Forlib-Plus

**\$69.95**

Supports graphics, interrupt driven communication, program chaining, and file handling/ disk support. A Fortran coded subroutine is included which will plot data on the screen either in linear/linear, log/linear, linear/log, or log/log on the appropriate grid.

### Strings & Things

**\$69.95**

Supports string manipulations, command line usage, DOS call capabilities, SHELL generation and data transmission, BATCH file control, music generation, PEEKS and POKES, PORT access, and general register manipulations.

### For-Winds

**\$89.95**

Gives the Fortran programmer the capability of generating up to 255 windows on the screen. Each window can be individually scrolled, moved, sized, generated, and removed. Both color and monochrome type displays are supported. Full source code is supplied for customization.

### ACS Time Series

**\$495.00**

This is a COMPLETE time series analysis package which contains VERY HIGH SPEED FFTs, Filter generations, convolutions, transfer function calculations, auto and cross spectra calculations, Cepstrum, curve fitting algorithms, coherence calculations, and many other associated routines. The price includes FULL source code.

### Fortran Scientific Subroutine Package

**\$295.00**

There are approximately 100 Fortran subroutines included which fall under the following 12 categories:

1) Matrix storage and Operations 2) Correlation and Regression, 3) Design Analysis (ANOVA), 4) Discriminant Analysis, 5) Factor Analysis, 6) Eigen Analysis, 7) Time Series, 8) Nonparametric Statistics, 9) Distribution Functions, 10) Linear Analysis, 11) Polynomial Solutions, 12) Data Screening. Full source code is included.



**Alpha Computer Service**  
P.O. Box 2517  
Cypress, California 90630  
(714) 894-6808

California Residents  
Include 6% Sales Tax

There are NO license fees

## HARDCARD

**TABLE 1: Hardcard Technical Specifications**

<b>DRIVE</b>	
Manufacturer	Plus Development Corporation
Height	1 inch (less than one-third of full height)
Media	Oxide
<b>CONTROLLER</b>	
Manufacturer	Plus Development Corporation
IBM-compatible	Yes
Extra functions	No
<b>FIXED-DISK BIOS</b>	
	On controller
<b>INTERLEAVE FACTOR</b>	
User choice	3 No
<b>SOFTWARE</b>	
Hardware formatter	No
DOS device driver	No (not required)
Diagnostics	No
Shipper	No (not required)
Other	Installation, menu-based directory manager
<b>POWER CONSUMED (amperes)</b>	
+5-volt DC	0.47 (0.54 running maximum, 0.54 startup)
+12-volt DC	0.67 (0.70 running maximum, 1.27 startup)
<b>AUXILIARY POWER</b>	
	Not required
<b>PERFORMANCE</b>	
Capacity	10.56MB (minimum)
Transfer rate	5.00 MBits/second
Access times	15 ms track to track
(includes setting)	65 ms average 105 ms full stroke

The Hardcard draws very little power and should not require auxiliary help, even in a standard PC that has a full complement of memory and adapters. The board's thinness permits other expansion boards to be placed in adjacent slots.

**TABLE 2: Hardcard Space Allocation under DOS**

ITEM (unit)	QUANTITY
Total cylinders used	305
Sectors per track	17
Sector size (bytes)	12
Logical surfaces (heads)	4
Total sectors	20,740
Hidden sectors (defect table)	17
Reserved sectors (boot, dir, FAT)	50
Available sectors	20,673
Cluster size (sectors)	8
Clusters	2,584
Wasted sectors	1
Total space available (bytes)	10,584,064

The Hardcard has two physical surfaces with 612 tracks each. The controller and BIOS make these appear as four logical surfaces with 306 tracks each. All but one are used; the last is reserved for diagnostic tests and is a safe landing zone.

program before each power down. The unit comes with a registration card for a one year warranty.

Plus's Hardcard fits in any full-length expansion slot in the IBM PC or XT, Compaq Portable or Plus, or AT&T PC 6300. It is thin enough to take only one slot, even in the narrow spacing of the XT, and not interfere with adjacent boards. Its physical installation is sim-

ple: turn off the PC, open it up, insert the card edge guide, put the Hardcard in the expansion slot, tighten the hold-down screw, and close up. The unit draws little power (0.54 amp maximum from the 5-volt DC supply, 0.67 amp maximum from the 12-volt DC supply) and should not require auxiliary help, even in a PC with a full complement of memory and adapters.



**TABLE 3: Benchmark Results for 10MB Disks**

	HARDCARD	PC/XT	AVERAGE <sup>a</sup>
<b>SEQUENTIAL READ</b>			
1 sector	19	22	20
8 sectors	48	71	50
16 sectors	77	126	86
24 sectors	110	187	125
<b>RANDOM READ<sup>b</sup></b>			
1 sector			
0.10	52	70	73
0.33	75	120	113
0.50	85	160	143
0.90	102	240	212
8 sectors			
0.10	84	120	105
0.33	101	160	144
0.50	110	210	178
0.90	129	300	246
<b>INTERLEAVE FACTOR</b>	3	6	3

*All times are in milliseconds per read.*

<sup>a</sup>These figures are the average of results for the DDS StoragePlus and the Qubie PC10, two 10MB internally-mounted 10MB systems. They were chosen for comparison because they each have an interleave factor of 3.

<sup>b</sup>Seek distance is the distance the heads travel as a fraction of the width of the disk platter.

The controller has two sector buffers, which may give the system an advantage in multiple-sector sequential transfers. However, these results show the Hardcard is much faster in random seeks. Short, random accesses, such as database lookups, should display the system to its best advantage.

The installation manual does not mention any machines other than those listed above, but the card should work in any IBM PC compatible that can use a Zebec model 1410A disk controller (which the Hardcard emulates). The IBM Portable PC is an interesting example. It has only two full-length slots. The first, next to the built-in monitor, is shipped with the display adapter card inserted. Slot 2 is generally available, but it is very close to the brightness and contrast controls that protrude into the card cage area, and Hardcard simply will not go into it. For this review, Hardcard was installed by moving the display adapter to slot 2, then carefully forcing the Hardcard into slot 1. Great pressure and perseverance are necessary to get the drive portion past the metal support that keeps cards in slot 1 from touching the CRT housing, but the plastic covering on the drive protects against accidental shorts.

While this procedure cannot be recommended, it did work. The card sticks up a little in the back, but everything is tight and the unit reviewed survived several trips in the trunk of a car. The resulting system is about as full as any PC can be: 10MB fixed disk, two half-height diskette drives, 640KB memory, clock/calendar, parallel port, internal modem, and a second serial port.

#### HARDCARD SOFTWARE

The Hardcard comes preformatted for DOS, and it has several programs already on disk. One of these is an automatic installation program that copies the files to a diskette (creating a backup for which a preprinted label is included), then formats the disk, partitions it, and installs DOS and other utilities from whatever system diskette the user supplies. Its reinstallation program repeats the procedure automatically from the backup diskette.

Because the Hardcard is hidden inside the PC, its activity is not indicated by a red light. Instead, two programs called SOUND and LIGHT provide optional audible or visible feedback when the Hardcard is accessed. SOUND ON causes a click from the PC's speaker and LIGHT ON displays a plus sign in the upper right corner. These features can be turned off if desired.

A menu-based shell program called HCD (Hardcard directory) lets the user set up 16 different applications to be invoked from a menu screen. A file called PROGHELP prints (on paper, not on the screen, with no option) instructions for installing many popular applications programs on the hard disk. The instructions are clear and useful.

Using any of this software is optional, although the manual does not

# C

## POWER

## FREE!

### UNIX for the PC!

(WITH ANY PURCHASE OF \$250 OR MORE BEFORE 2/26/86)

**LIBRARY:** 325 fully tested functions screen handling/graphic, cursor/keyboard/data entry, string handling, status and control, utility/DOS/BIOS/time/date, printer control.

4 disks, 400 page manual \$129.95

**WINDOWS:** The most powerful windowing package available, overlays, borders, pop-up menus/help windows, zap instantly on/off screen, status lines, horizontal/vertical scrolling, color control/highlighting, word-wrap, files to windows, keyboard to windows

3 disks, 225 page manual \$129.95

**SUPERFONTS FOR C:** Dramatic, high impact screens. Use our character & image libraries and functions, or create your own.

Font & Function Library \$49.95

**B-TREE LIBRARY:** Fast indexing B-tree. 16 million each: keys and records, unlimited keys per file, variable length records.

PC-DOS, UNIX, XENIX, CP/M. \$79.95

**ISAM DRIVER:** \$49.95

**COMPATIBILITY:** PC/XT/AT; Full K&R, CI-C86/De Smet/Lattice/Microsoft 3.0/Aztec/others.

**VALUE:** All source code, No royalties, on packages above.

**C-TERP:** Simply the best C interpreter available. See C Journal Summer 1985

C-TERP (specify compiler) \$299.95

**PC-UNIX:** Multi-tasking, networking multi-user. With source code \$99.95

**PC LOCATE:** Create ROM-able .exe files \$199.95

#### COMBINE AND SAVE!

C LIBRARY plus C WINDOWS

BOTH for only \$179.95

+ SUPERFONTS FOR C \$199.95

+ B-TREE and ISAM \$299.95

(A \$440 VALUE)

C LIBRARY plus C WINDOWS

+ SUPERFONTS

+ C-TERP (a \$610 value) \$459.95

All (a \$740 value) \$549.95


# Entelekon

12118 Kimberley, Houston, TX 77024  
713-468-4412

VISA MASTERCARD CHECK COD

CIRCLE NO. 158 ON READER SERVICE CARD





# How we improved Structured Query Language.

Actually, we didn't change a thing.

We just combined it with the best relational database management system.

Introducing INFORMIX®-SQL.

It runs on either MS™-DOS or UNIX™ operating systems. And now with IBM's SQL as part of the program, you can ask more of your database. Using the emerging industry-standard query language.

To make your job easier, INFORMIX-SQL comes with the most complete set of application building tools. Including a full report writer and screen generator. Plus a family of companion products that all work together.

Like our embedded SQLs for C and COBOL. So you can easily link your programs with ours. File-it!™, our easy-to-use file manager. And C-ISAM™, the de facto standard ISAM for the UNIX operating

system. It's built into all our products, but you can buy it separately.

And when you choose RDS, you'll be in the company of some other good companies. Computer manufacturers including AT&T, Northern

Telecom, Altos and over 60 others. And major corporations like Anheuser Busch and The First National Bank of Chicago.

Which makes sense. After all, only RDS offers a family of products that work so well together. As well as with so many industry standards.

So call us for a demo, a manual and a copy of our Independent Software Vendor Catalog. Software vendors be sure to ask about our new "Hooks" software integration program. Our number: 415/322-4100.

Or write RDS, 4100 Bohannon Drive, Menlo Park, CA 94025.

And we'll show you how we took a good idea and made it better.



**RELATIONAL DATABASE SYSTEMS, INC.**

INFORMIX is a registered trademark and RDS, C-ISAM and File-it! are trademarks of Relational Database Systems, Inc. IBM, UNIX and MS are trademarks of International Business Machines Corporation, AT&T and Microsoft, respectively. © 1985, Relational Database Systems, Inc.



## HARDCARD

emphasize this point. However, users who prefer not to use menus should be careful. During the review, the HCD was deleted for this reason (it was assumed that the data were backed up). Later, an attempt was made to load it back to check some information, but the backup disk had become unreadable. This was no one's fault, it simply happens sometimes. (It would have been safer to make two backups before deleting the files.) Plus Corporation sent a replacement diskette.

### IMPORTANT FACTORS


The Hardcard has a very fast seek time, which accounts for its exceptional performance in *PC Tech Journal's* fixed-disk benchmarks (see "Fixed-disk Benchmarks," William J. Hunt, November 1984, p. 64); the results are shown in table 3. Its interleave factor of 3:1 also is a contributing factor (the XT is interleaved 6:1). Table 3 shows times for the Hardcard, the XT, and the average of the two 10MB systems reviewed in "Ten by Ten" that came formatted with 3:1 interleaving.

The benchmarks demonstrate that the Hardcard is marginally better in sequential transfers, but it is considerably faster for longer random seeks. The controller has two sector buffers that may give the system an advantage in multiple-sector sequential transfers. Its overall performance with a real application (loading Lotus spreadsheet files, for example) will not reflect exactly the same relative speed superiority because applications generally do some processing for each segment of a file that is loaded; speeding up the disk transfer impacts only part of the process. Short, random accesses, such as database look-ups, should help display the system to its best advantage.

The Hardcard comes formatted with a standard 17 sectors per track, but physically it has 18 on each. The extra one is used in case of a bad sector. The defect mapping and sector allocation is done during the hardware formatting process at the factory. No hardware formatter is shipped with the Hardcard. The formatter included with IBM's Advanced Diagnostics should *not* be used because it will overwrite the bad block table stored on the disk and defeat the spare block feature. (The space allocation for the Hardcard under DOS is shown in table 2.) To reformat the hardware to Plus Development's standard, the unit must be returned.

The Hardcard can be the only hard disk in a system or the second drive. Alone, it is recognized by DOS as drive

### PHOTO 1: Internal View of Hardcard Hard Disk



Above is a cutaway of the Hardcard. The head position is controlled by a pivot arm system located in the upper right area with the drive motor below.

C:. According to Plus, the controller is compatible with the IBM Fixed-Disk Adapter, and supports the IBM Diagnostics and Advanced Diagnostics.

If the Hardcard is used as a second hard disk, a jumper on the card that is normally in the PC position must be moved to the XT position. (All XTs al-

ready have a hard disk; many PCs do not.) This changes the hardware addresses of the controller's I/O registers from 320-323H to 324-327H, and moves its ROM fixed-disk BIOS from C8000H to CA000H. This allows the Hardcard to coexist on the same bus with another standard IBM controller.

## COPY II PC OPTION BOARD

**At last,** an almost foolproof method of making archival backups of protected software! The Copy II PC Option Board is an add-in board that will give your PC the same disk duplication technology used by most disk duplication firms (who put the copy protection on software in the first place!).

### DUPLICATES NEARLY ALL\* PROTECTED DISKETTES!

The Option Board can easily backup almost all protected diskettes for the IBM PC, including ones software-only backup programs can't touch! It even includes a track editor that will allow the more technically inclined to look at protection schemes and edit any data on a diskette.

The Option Board uses a full size slot in an IBM PC, XT, or AT (with at least 1 360KB floppy disk drive), Compaq Deskpro. Compaq Portable requires an extra \$15 cable.

**CENTRAL POINT  
Software, Inc.**

9700 SW Capitol Hwy., #100  
Portland, OR 97219

**503/244-5782**

M-F, 8-5:30, W. Coast Time



CHECK, COD WELCOME  
(Prepayment Required)

**\$95.00**

plus \$3 s/h (\$12 outside U.S.)

\*Except those "protected" by physical disk damage.

**Now Available!** Put all the most popular **disk utilities (even undelete!)** together with a powerful DOS interface. Then make them **resident** and what do you have?? **PC TOOLS!** PC Tools lets you run nearly any DOS command *within any other running program.*

**JUST \$39.95** plus s/h.



Requests for drive D: are handled by the Hardcard BIOS, which knows to use the relocated I/O addresses. The BIOS also handles requests for drive C:—it assumes that the other controller is at the normal I/O addresses. If the other controller is not exactly what the Hardcard BIOS expects, trouble may ensue. Plus Development says that some third-party disk controllers can cause problems. Users who plan to use the Hardcard as D: with a non-IBM controller for C: should call Plus for the latest compatibility information. Even then, an

ironclad agreement with the dealer to take one or the other back if the combination does not work is a good idea.

The Hardcard cannot be used as a second disk (as drive D:) with operating systems or applications that avoid the BIOS and go directly after the hard-disk controller because they will not find the Hardcard in its alternate I/O configuration. Systems that would cause such problems include Microsoft XENIX, Unisource VENIX/86, and IBM PC-IX.

Plus Development Corporation plans to market the Hardcard through

retail computer dealers at a suggested price of \$1,095. The company's market research indicates that most hardware sales to corporate users take place through the retail channel (though software is increasingly purchased by mail), and that 10MB disk upgrades were going for \$1,000 to \$1,500. The Hardcard is priced near the low end of that range and offers several advantages over the standard 5¼-inch Winchester such as those reviewed in "Ten by Ten."

Its advantages include a simpler installation, faster operating speed, no need for auxiliary power, and no need to convert from full- to half-height diskette drives to make room for the new hardware. The theory is that people will be willing to pay the same or a bit more for a better product.

Some considerations come to mind. First, users may not be paying as much for 10MB disks as Plus assumes. Some mail-order houses advertise 10MB internal systems for as little as \$395, complete with controller and mounting hardware. Retailers charge about \$900, including installation. Large corporate purchasers probably get a slightly better deal. Further, *PC Tech Journal* surveys show that its readers *do* buy hard disks through the mail and apparently are satisfied with the results.

The Hardcard is ideally suited to mail-order sales. It is functional, reliable, and incredibly easy to install (unless it must be forced into a Portable PC—but that is not the fault of the Hardcard). Given that it does not require the user to buy a new power supply and that he does not have to throw out his old diskette drives to make room for it, the product is worth a premium. At \$600 the Hardcard probably would be a runaway bestseller; as it is, an additional \$500 is hard to justify.


The user will find much to like about the Hardcard, and it should be around for some time. It is technically and technologically sound, and an ideal add-on for any portable system. Plus should try to get the price in line with the rest of the disk market so it can be enjoyed by more users.

**Hardcard: \$1,095**  
**Plus Development Corporation**  
 1778 McCarthy Blvd.  
 Milpitas, CA 95035  
 408/946-3700  
 CIRCLE 318 ON READER SERVICE CARD

*Thomas V. Hoffmann is director of advanced systems development for General Instrument Corporation in Hunt Valley, Maryland. He is consulting editor to this magazine.*

## C-terp

The C  
 Interpreter  
 You Won't  
 Outgrow



C-terp will grow with you as you progress from novice through professional to guru. Unbelievable, but true, the easiest-to-use C interpreter will provide you with the most advanced programming features for upward growth. Our exclusive **object module support** enables you to add libraries (like HALO, PANEL, Windows for C, etc., or your own homebrew libraries) to C-terp as you add them to your computing repertoire. Use C-terp as a microscope on your libraries! Flip a bit and allow our **software paging** (NEW) to handle those big jobs! There are no fixed-size tables to overflow, and C-terp can be configured for different screens and screen adapters (NEW). With multiple modules and **full K&R support**, we offer a dream C environment.

- Our new improved **configurable editor** competes with anything going.
- Speed -- Linking and semi-compilation are breathtakingly fast.
- Convenience -- Errors direct you back to the editor with the cursor set to the trouble spot.
- Symbolic Debugging -- Set breakpoints, single-step, and directly execute C expressions.
- Compatibility guaranteed -- batch file to link in your compiler's entire library. Supported compilers include: **Computer Innovations C86, Lattice C, Microsoft C 3.0, Mark Williams C86, and Aztec C.**
- Many more features including batch mode and 8087 support.

### What Our Users/ Reviewers Are Saying

- "... easy to use, powerful, and a timesaver."
- "... we absolutely LOVE C-terp."
- "... has restored my faith in interpreters."
- "... a programmer's dream."
- "... wonderful technical assistance."
- "... increased our productivity by a factor of 40."
- "... the best C product ever, in any category."

- **Price: \$300.00 (Demo \$45.00)**  
 MC, VISA


Prices include documentation and shipping within U.S. PA residents add 6% sales tax. Specify compiler.

- C-terp runs on the IBM PC (or any BIOS compatible machine) under DOS 2.x and up with a suggested minimum of 256 Kb of memory. It can use all the memory available.
- C-terp is a trademark of Gimpel Software.

**GIMPEL SOFTWARE**

3207 Hogarth Lane • Collegeville, PA 19426  
 (215) 584-4261





# AT™ Pfantasies for your PC or XT.™

Want better speed and memory on your PC or XT without buying an AT?

You've got it!

Phoenix's new Pfaster™286 co-processor board turns your PC or XT into a high-speed engine 60 percent faster than an AT. Three times faster than an XT. It even supports PCs with third-party hard disks. But that's only the beginning.

You can handle spreadsheets and programs you never thought possible. Set up RAM disks in both 8088 and 80286 memory for linkage editor overlays or super-high-speed disk caching. All with Pfaster286's 1mb of standard RAM, expandable to 2mb, and dual-mode design.

You can develop 8086/186/286 software on your XT faster. Execute 95 percent of the application packages that run on the AT, excluding those that require fancy I/O capabilities your PC or XT hardware just isn't designed to handle. Queue multi-copy, multi-format print jobs for spooling. Or, switch to native 8088 mode to handle



hardware-dependent programs and back again without rebooting. All with Pfaster286's compatible ROM software. And, Pfaster286 does the job unintrusively! No motherboard to exchange. No wires to solder. No chips to pull. Just plug it into a standard card slot, and type the magic word, "PFAST."

If you really didn't want an AT in the first place, just what it could do for you, call or write: Phoenix Computer Products Corp., 320 Norwood Park South, Norwood, MA 02062; (800) 344-7200. In Massachusetts, 617-762-5030.

Programmers' Pfantasies™  
by

*Phoenix*

XT and AT are trademarks of International Business Machines Corporation. Pfaster286 and Programmers' Pfantasies are trademarks of Phoenix Computer Products Corporation. For the Ferrari aficionado: yes, we know this is a rear engine car. We are showing the addition of a second engine to symbolize how Pfaster can be added to your PC or XT to increase performance.

CIRCLE NO. 169 ON READER SERVICE CARD





# THE GREAT ESCAPE!

FROM IVORY TOWERS AND  
COLD COMPUTER ROOMS TO  
THE WARMTH OF YOUR OFFICE.

Artificial intelligence for business  
has arrived in a revolutionary new  
product . . . Guru.

At last, artificial intelligence designed especially for business! Guru brings together expert system capabilities of artificial intelligence, the productivity of familiar business computing tools and the ease of communicating with your computer using menus, commands or plain English. All available in a single, integrated program.

Guru works like human experts, considering uncertainties, reasoning through forward and backward chaining, asking for more information when needed, and explaining its recommendations.

Guru's expert system works hand-in-hand with all the familiar business computing tools like spreadsheets, statistical analysis, business graphics and a programming language, always available for both expert consultation and your everyday business computing needs.


Best of all, you won't need to learn LISP or PROLOG or buy fancy computers . . . Guru runs on your PC and communicates in plain English! Guru is artificial intelligence that means business.

For more information, call or write Micro Data Base Systems, Inc./Marketing & Sales, P.O. Box 248, Lafayette, IN, 47902, 317/463-2581, Telex 209147 ISE UR.

# GURU<sup>TM</sup>

ARTIFICIAL INTELLIGENCE THAT MEANS BUSINESS.





*While it is not revolutionary, IBM's new fixed-disk drive for the PC/AT model 239 provides the user with an easy-to-install mass storage option.*

# Storage Expansion for the AT

IBM's new 30MB fixed disk for the PC/AT is as noteworthy for the questions it provokes as it is for the answers it provides. The disk debuted with the model 239 AT, a system that offers not only this larger fixed disk, but also a new keyboard and ROM. The model 239 system board uses industry-standard 256KB dynamic RAM chips instead of the 128KB piggyback modules built from two 64KB chips that were used in the original AT. The new ROM supports the 14 standard types of fixed disks and the new 30MB drive, as well as several others (see table 1).

The 30MB disk is available as an upgrade kit that can be installed as either drive C: or drive D: in the original AT, or as drive D: in the model 239. Thus, it is now possible to have an

all-IBM AT with 0-, 20-, 30-, 40-, 50-, or 60MB of fixed-disk storage built from various combinations of the two available disk capacities.

The list price for the model 239 AT is \$5,995, only \$200 more than that for the 20MB model 099. The 30MB upgrade kit is \$1,795, again only \$200 more than its 20MB counterpart. This \$200 price difference should widen, however, because IBM will have been offering lower dealer prices on the 20MB model 099 ATs throughout the fourth quarter of 1985. A decrease in the consumer price of the model 099 should follow early in 1986.


Both the 20MB and the 30MB IBM disks have retractable heads that move to a safe landing zone when power is shut off. A *park* utility is not necessary.

THOMAS V. HOFFMANN



# The PC Bus:


## Cost-Effective, Board-Level Solution To System Integration



Get your dedicated system to market *months* sooner with the PC Bus. Full board-level implementation by I-Bus lets you plug together system components from hundreds of PC Bus board manufacturers, and directly execute software developed on and for the IBM® PC.

I-Bus has board-level CPU's with 8088 or 80188 processors, full disk or diskless operation and up to 160K of EPROM, 256K of RAM on board. We have the most complete line of system packaging for the PC Bus, too.

Start cutting your schedule today—give us a call today at (800) 382-4229. In California, call (619) 569-0646.



# I-BUS

SYSTEMS

9235 Chesapeake Drive  
San Diego, CA 92123

## DISK DRIVE

**TABLE 1: Disk Types Supported by AT BIOS**

DISK TYPE	CYLINDERS	HEADS	WRITE PRECOMP	LANDING ZONE	CAPACITY (MB)
1	306	4	128	305	10,653,696
2	615	4	300	615	21,411,840
3	615	6	300	615	32,117,760
4	940	8	512	940	65,454,080
5	940	6	512	940	49,090,560
6	615	4	none	615	21,411,840
7	462	8	256	511	32,169,984
8	733	5	none	733	31,900,160
9	900	15	none	901	117,504,000
10	820	3	none	820	21,411,840
11	855	5	none	855	37,209,600
12	855	7	none	855	52,093,440
13	306	8	128	319	21,307,392
14	733	7	none	733	44,660,224
15	0	0	0	0	0
16	612	4	0	663	21,307,392
17	977	5	300	977	42,519,040
18	977	7	none	977	59,526,656
19	1,024	7	512	1,023	62,390,272
20	733	5	300	732	31,900,160
21	733	7	300	732	44,660,224
22	733	5	300	733	31,900,160
23	306	4	0	336	10,653,696

The disk table in the ROM BIOS of the model 239 AT defines the hard disk types that are shown here. The new types are numbered from 16 through 23.

For testing, the 30MB upgrade kit was installed in a model 099 AT with a 20MB fixed disk and two diskette drives. The 30MB disk, a full-height drive, bore a striking resemblance to the 20MB drive already installed, which also was manufactured by IBM. IBM uses several sources for its PC components, and, as a result, the drives installed in a particular system actually may have been manufactured by some other company.

In addition to the drive, the upgrade kit contains a new set of ROM BIOS modules, a data cable to connect the drive to the fixed-disk adapter, a keeper bar that holds the drive in place, installation instructions, a diagnostic disk (version 2.0), and updated pages for the "Testing Your System" section of the *Guide to Operations*.

### READY TO INSTALL

The installation instructions begin with a warning that the IBM limited warranty (which is good for one year, just as with the AT) applies only to properly installed options and recommend that the user allow IBM or an authorized dealer to install the system. Most customers probably would prefer that the dealer install the disk; the operation is

not difficult, but oversights (such as forgetting to remove the terminating resistor pack from drive D:) are always a danger. However, the instructions are detailed and illustrated, and most users should find them quite helpful.

If a system's ROM BIOS is dated earlier than June 10, 1985, it must be replaced prior to installation of the new drive. However, the kit provided with the drive contains no tools for removing or inserting ROM modules.

Installing the disk itself is a straightforward operation that requires only a screwdriver and the proper cables. Because the 30MB drive is full height, the second diskette drive in the system used for testing had to be removed to make room for the installation of the new drive.

After everything has been connected properly, the SETUP program on the diagnostic disk must be run to record the new system configuration. The instructions suggest using the SETUP program provided on the advanced diagnostic disk that comes with the *Hardware Maintenance and Service Manual*. However, for this review, the SETUP on the diagnostic disk included with the new drive was used because it is a more recent version.



**TABLE 2: Benchmark Results**

MACHINE	IBM 20MB FIXED DISK	IBM 30MB FIXED DISK	IBM PC/XT FIXED DISK
<b>SEQUENTIAL READ</b>			
1 sector	4	4	22
8 sectors	26	26	71
16 sectors	51	49	126
24 sectors	77	76	187
<b>RANDOM READ</b>			
1 sector			
0.10 <sup>a</sup>	36	34	70
0.33	43	51	120
0.50	57	60	160
0.90	66	59	240
8 sectors			
0.10	58	63	120
0.33	66	71	160
0.50	77	81	210
0.90	90	80	300
<b>INTERLEAVE FACTOR</b>	2	2	6

<sup>a</sup>Results for IBM 20MB and 30MB fixed disks were obtained on a 6 mHz PC/AT.

Benchmark results for the 20MB and the 30MB hard disk drives are shown here in comparison with those for the PC/XT hard disk. The 30MB disk performed well.

The label on the front of the disk drive showed eight bad spots (the 20MB disk used for testing had no bad spots) and a type code of 20. The old SETUP program allowed type codes only from 1 through 15; the new one prompted for codes from 1 through 47. After SETUP, FDISK and FORMAT were run (which took 4 minutes, 15 seconds) and the system was ready.

A 30MB disk has a capacity of at least 30,000,000 bytes, usually more. The type 20 disk has 733 cylinders and 5 heads. Each track of 512 bytes is formatted with 17 sectors; thus, the maximum number of bytes available is 31,900,160. The amount of usable space, which does not include boot blocks, bad track tables, the root directory, FATs, and other overhead, is 31,768,576 bytes, minus the bytes that are in the eight bad spots on the test disk.

The 30MB disk drive performed well in the *PC Tech Journal* disk-drive benchmarks (see "Fixed-Disk Benchmarks," William J. Hunt, November 1984, p. 64); it produced times that were slightly faster than those for the 20MB drive. (See table 2.)

#### NEW ROM VERSUS OLD

When IBM introduces a new ROM BIOS for a member of the PC family, questions arise: Why now? What has been changed? What bugs have been fixed? What hidden features have been added? IBM's listings, which usually help to provide the answers to some of these

questions, have not yet been published for this new ROM. However, some information is available.


The ROM in the AT provides 64KB of memory, 32KB of which is used to contain the Cassette BASIC interpreter. Both the old and the new AT ROMs use BASIC version C1.10—no change there.

The uppermost 8KB of the AT ROM BIOS, from F000:E000 to F000:FFFF, is made up primarily of error message text, tables, and entry points that provide compatibility with the original PC ROM. The number of existing programs that presume the locations of various ROM routines and interrupt service routines has prompted IBM to preserve those entry points, if only to serve as jumps to new locations where the work actually is performed.

Differences between the top 8KB of the old and the new ROMs indicate that the new version is the product of source changes, not simply a few patches. For example, the text of the error messages has been rearranged and is now stored in order by error code number. Many jump tables and interrupt vector tables point to routines in the lower 24KB that have been moved to new locations. Some routines have been changed slightly, some have been reordered. The ASCII-encoded identification numbers, the copyright notice, and the date code have been updated (the new date code is 6/10/85).

The only functional difference announced by IBM is the support for the

## FORTRAN PROGRAMMERS



### EVER FEEL LIKE YOUR PROGRAM WILL NEVER FINISH COMPILING?

Your valuable time is spent waiting endlessly for your programs to compile. As your waiting increases you fall further and further behind on your PC FORTRAN project.

If pride in your work and meeting deadlines are important to you then you can't afford to be without **F77L** any longer. With **F77L** we have not only developed an unbelievably fast compiler but we did it without sacrificing features, diagnostics, or the speed of execution. This uncompromising attitude is evident in the quality and performance of **F77L**. Whether you are downloading from mainframes or developing on the personal computer, you can appreciate the importance of compiler speed.

**PHONE FOR DETAILS about  
VERSION 2.00 and our NEW MANUAL**

**F77L**

**"THE PROGRAMMER'S FORTRAN"**

**\$477.00**

Requires: PC/MS-DOS, 256K, 8087

**TO ORDER OR FOR MORE INFORMATION**

**(213) 541-1200**

**Lahey Computer Systems, Inc.**  
31244 Palos Verdes Drive West  
Suite #243  
Rancho Palos Verdes, CA 90274  
Serving the FORTRAN community since 1969  
**NUMBER TWO IN A SERIES OF ADS**



# Brand New From Peter Norton A PROGRAMMER'S EDITOR

only  
**\$50**

that's *lightning fast* with the *hot*  
features programmers need


Direct from the  
man who gave you  
*The Norton Utilities*,  
*Inside the IBM PC*,  
and the *Peter Norton  
Programmer's Guide*.

## THE NORTON EDITOR



"This is the program-  
mer's editor that I wished  
I'd had when I wrote my  
*Norton Utilities*. You can  
*program your way to  
glory with The Norton  
Editor.*"

*Peter Norton*



*Easily customized, and saved*  
*Split-screen editing*  
*A wonderful condensed/outline display*  
*Great for assembler, Pascal and C*

Peter Norton, 2210 Wilshire Blvd., #186  
Santa Monica, CA 90403, 213-826-8032  
Visa, MasterCard and phone orders welcome

CIRCLE NO. 138 ON READER SERVICE CARD



## DISnDATA, The Only Disassembler That Tracks Down DATA!!!

- Fully disassembles both .EXE and .COM files!
- Performs recursive flow- and Segment Register data-trace to determine SEGMENT, PROC & Data Areas (even within 'CODE' segments)!
- Outputs appropriate SEGMENT and PROC pseudo-ops at proper places within the assembly-language output!
- Outputs data areas using most appropriate form of DB or DW (ASCII printable text as a character string, others as their hex value).
- Chooses data lengths (DB or DW) to match byte or word data references in code, allowing most memory references to be free of BYTE or WORD length operators.
- Outputs large, all-zero areas with "DB/DW nn DUP (?)" to prevent excessive output from large buffers, uninitialized arrays, etc.
- Fully labels both code and data. Labels are of the form 'Hxxxx', where 'xxxx' is the hex offset of labelled item from the beginning of the program.
- Outputs code, data & pseudo-ops in IBM\* ASM or MASM assembler format. (Output may be directed to display, printer, and/or disk.)
- For IBM\* PC\*/XT\* & compatibles, 128K+ RAM, 1 or more disks, DOS 2.x.

#8634-20 PC-DISnDATA 1.0 (SSDD 5-1/4" diskette) and manual ..... \$145

U.S. Funds Only. Add \$3 shipping (U.S. & Canada), \$10 (overseas air) per item. Ohio residents please add 6% sales tax. \*Registered trademark, IBM Corporation



To order, phone (513) 435-4480 (M-F, 9 A.M.-5 P.M. EST), or send check, money order, or VISA/MasterCard information (name, street address (no P.O. Box please), card number, expiration date, and your telephone number) to:

**PRO/AM SOFTWARE**  
220 Cardigan Road  
Centerville, OH 45459

Professional Software for  
both Novice and Expert

CIRCLE NO. 198 ON READER SERVICE CARD

## DISK DRIVE

new 30MB disk drive. The original ROM BIOS supported four nominal 30MB drives (see table 1), but none of these has the same parameters as the type 20 drive in the upgrade kit (although type 8 differs only in its write precompensation value). The original ROM defined disk types 1 through 14 and reserved type 15. The ROM can support a total of 47 disk types. Version 2.0 of the diagnostic disk accepts disk types 1 through 47; the new ROM defines only types 1 through 23 (as with the original ROM, type 15 is reserved).

Because the new ROM supports more than 15 fixed-disk types, changes in the configuration set-up code are required. The original ROM used only four bits to store a type code; it packed the types for drives C: and D: into a single byte. Other routines show signs of minor improvement, also. The timer interrupt routine now disables interrupts before it issues the EOI (end of interrupt) command to the 8259A interrupt controller; the original version left interrupts enabled. The print screen routine (software interrupt 5) sends a carriage return followed by a line feed to the printer after each line of text; the old version sent the line feed first, followed by a carriage return.

Of greater concern, particularly to those who have replaced the original crystals in their ATs with faster ones to boost performance, is the news that the new ROM fixes the clock speed at 6 MHz. The IBM technical documentation states, "Note: Installation of the 30MB Fixed Disk Upgrade Kit will fix the microprocessor clock speed at 6 MHz." This indicates some code in the new ROM will not work at speeds greater than 6 MHz, possibly a side effect of a change to improve the reliability of some device control code (such as adding a software time-out).

The new 30MB fixed disk and model 239 AT are not revolutionary. They are, however, small improvements to IBM's PC family that give users increased versatility.

239 AT: \$5,995  
30MB upgrade kit: \$1,795  
IBM Corporation  
5201 S. Congress Avenue  
Boca Raton, FL 33432  
Contact the local IBM dealer;  
800/426-2468  
CIRCLE 356 ON READER SERVICE CARD

*Thomas V. Hoffmann is the director of advanced systems development for General Instrument Corporation. He is consulting editor for this magazine.*



The logo features the word "DATA" in blue and "FLEX" in a multi-colored, striped font. Below the text is a large, funnel-shaped graphic composed of vertical bands of color: blue, orange, green, and purple. The funnel tapers from top to bottom.

# DATA FLEX<sup>®</sup>

*The World's  
Best Selling  
Multi-User  
Database  
For Five Years  
Running.*

A smaller version of the DataFlex logo, featuring the word "DATA" in blue and "FLEX" in a multi-colored, striped font.

## DATA FLEX<sup>®</sup>

DataFlex versions are available  
for all popular single-user  
and multi-user operating systems,  
including Xenix.

For a free copy of this poster  
(minus ad copy), write Data  
Access Corp. or leave a message  
on our Bulletin Board System:  
(305) 238-0640.

DATA ACCESS CORPORATION  
8525 S.W. 129th Terrace, Miami, FL 33156-6565 (305) 238-0012, Telex 469021 DATA ACCESS CI


CIRCLE NO. 118 ON READER SERVICE CARD



# "Blessed are the Pessimists; for they hath made backups."

— Exasperated 1:16

Introducing **COREtape™** Model CT60i.  
For your IBM PC, XT, AT and just about everyone else.



*Put 4,000 pages of text  
in your back pocket in less than 2 minutes.*

## **TAPE SOFTWARE WORTH WRITING HOME ABOUT.**

We gave COREtape™ all the features of the best tape systems, and more. You can BACKUP the average 10 MB system in less than three minutes. COREtape's FILE-BY-FILE mode saves you even more time by optionally backing up only the files that have changed. And unlike other tape backup systems, COREtape™ allows SELECTIVE RESTORE from an IMAGE backup, saving much time and tedium.

## **IT'S ALL ON THE MENU.**

COREtape™ was designed by folks well aware of the user-hostile software common to other backup systems. So we made the COREtape™ system software 100% MENU driven. Just a few keystrokes and...Zaaaap! Your data is on its way. With COREtape™, even a novice can make a successful backup.

In fact, our extensive documentation is unnecessary. If you need help, even *that's* on line. We feature the most comprehensive MENU driven HELP FACILITY that covers every aspect of COREtape MENU operations. Hit a key, get an answer.

COREtape™ also works with batch file commands you create, allowing your custom programs to *automatically* control operations. Our WAIT/TIME feature allows operations in your BATCH file to be initiated *at a time you specify!*

## **YOU CAN TAKE IT WITH YOU.**

Roughly the size of a paperback book, each COREtape™ cartridge holds 60 MB of data. Larger files automatically record on next cartridge. It's fast, transportable, easy to use and incredibly reliable.

## **DO IT YOURSELF.**

COREtape™ is complete; the drive, controller, cable and easier-than-pie software are all in the kit. COREtape™ works with IBM PCs, XTs, ATs, and anyone else using the standard IBM PC bus running PC/MS DOS or XENIX. If you can read, you can install COREtape™. If you'd rather not, your dealer will be glad to.

In either case, COREtape is a tape you can live with, because *we* live with it everyday.

So see your local dealer, or call us directly. You have nothing to lose. And *everything* to save.



**7171 North Federal Highway Boca Raton, Florida 33431**

**305/997-6055 Telex: 315 809 CORE INTL DEBE**



V

# ENIX: Setting UNIX Standards

AUGIE HANSEN

*AT&T's System V specification begins to establish a standard UNIX base; VENIX brings the new standard to the PC.*

VenturCom has brought to market the first UNIX System-V compatible operating system that runs on the PC/XT and PC/AT. VENIX is a port of AT&T sources to the PC family and to several other microcomputer and mini-computer products. Along the way, some features have been added to permit access to DOS programs and data files; a sprinkling of specialty programs has been included as well. Other System V release 2 products from the Santa Cruz Operation and IBM (via Microsoft and Interactive Systems) have been announced or will be shortly.

So why all the interest in System V? Mostly this is a matter of setting standards to avert long-term disarray in the UNIX community. Viewed from a distance, UNIX has taken on a Hydra-like appearance because of efforts by third parties and AT&T itself to make UNIX do things its designers never intended.

Offshoots of the seventh edition (called version 7), with many Berkeley extensions, are hot in scientific and CAD/CAM circles because of additions made in graphics support, among other things. Other UNIX vendors have added helpful realtime features, usually at the expense of multitasking performance. Still others have emphasized modifications to the file system to facilitate database applications. (See "Reflections of UNIX," Augie Hansen, *PC Tech Journal*, May, 1985, p. 54, for an overview of several PC UNIX systems.)

The AT&T System V Interface Definition (which is discussed in the sidebar that accompanies this article) is the intended rallying point for present and future UNIX systems development. Already Sun Microsystems and Microsoft have entered into agreements with AT&T regarding the convergence of their respective systems into one that is



common at the core. However, some differences among operating system and application extensions are welcome and to be expected, in order to distinguish various products and to accommodate real market demands for specialized features and functions.

AT&T's 3B2 supermicrocomputer and 7300 UNIX PC are substantially impacting the perception of System V as a standard for UNIX, VENIX, XENIX, and other systems based on UNIX. The promise of source code compatibility across a wide range of machines is an important consideration to a company preparing an applications product for market. Because these machines run AT&T's System V release 2 operating system, it is possible to recompile the programs without changing the source code. Of course, if a program depends on nonstandard extensions, such as bit-mapped display features and the user agent, then porting will require additional work to revise the interface.

Object code compatibility across machines that use compatible processors, such as those in the Intel family, is an added bonus. The System V standard specifies source code compatibility, but it took some ingenuity to achieve object code compatibility. To illustrate, a program written and compiled on a VENIX/86 system (PC/XT) can be moved unchanged to a VENIX/286 engine (PC/AT) and run in protected mode—no need to recompile or patch. A defective program that could render an XT useless will cause only a memory protection violation and a debugging core dump when run on the AT.

VENIX is available for two broad classes of machines: the Intel microprocessors (8086/88, 80186/88, 80286) used in the IBM PC, XT, AT, and many compatibles, and the DEC processors used in the Pro 350/380, PDP-11-series, and LSI-11 computers.

The VENIX System V product is large (because System V is large). The PC versions consume approximately 9MB of disk storage if all of the operating system features and optional programs are installed. On a PC or XT equipped with a 10MB hard disk, this leaves little room for user applications and data files. A system administrator may reserve more disk space for users by eliminating unnecessary files. VenturCom offers guidance regarding disk space conservation in the notes that accompany release 2.

The company recommends a minimum of 256KB RAM and 10MB on a hard disk, but systems with more than one user will require at least 512KB of

## TABLE 1: Upgrading 2.0

### CHANGED COMMANDS

cu  
echo  
login  
ls  
nroff  
ps  
stty  
sum  
(ratfor compiler is omitted)

### CHANGED SYSTEM CALLS

access  
alarm  
ioctl  
signal  
(sema mechanism has been dropped in favor of "counting")

### CHANGED SUBROUTINES<sup>a</sup>

curses  
fopen  
printf  
realloc  
string

<sup>a</sup> In the C language and standard I/O libraries.

**VENIX 2.0 programs will run under VENIX System V release 2 without major revisions. However, some version 2.0 commands behave differently under System V. These upward compatibility snags are listed above.**

main memory and 20MB on the hard disk to accommodate any serious work.

The VENIX documentation is complete and well written. Much of it is reproduced from the original AT&T distribution, although some portions, especially those that are related to system administration, were rewritten or heavily revised by the VenturCom staff. Four very full 6½-inch-by-9-inch ring binders hold the information, most of which has been typeset.

The software is distributed on a set of 21 diskettes. One contains the transfer programs that begin the installation process; diskettes A through F hold the system files; and diskettes 1 through 13 contain the user files. One floppy disk contains machine-dependent programs. Except for the last, the diskettes are identical for the XT and AT installations. It takes about an hour to prepare the hard disk and to install the entire VENIX system on an AT. A much slower disk on an XT-compatible machine can add 10 to 15 minutes to that time.

Owners of older VENIX versions should note that mountable file systems

and dump-format diskettes are not transportable between old versions and VENIX System V. VenturCom recommends saving source and data files using tar before installing the new system. Table 1 is a summary of command changes from VENIX version 2.0 to VENIX System V release 2 that could cause upward compatibility problems. System V enhancements that pose no such problems are listed in table 2. The changes include enhancements to commands, many entirely new commands and function calls, and enhancements to system calls and device drivers.

The VENIX quadscreen feature uses display memory buffers on the color graphics adapter. The feature is not available on monochrome-only systems, however, because monochrome adapters provide no additional memory for paging. This approach differs from the multiscreen virtual console feature of SCO's XENIX, which uses buffers in main memory for each virtual console. Although the latter method consumes 4KB per console, it makes the feature available on any display system.

## CONNECTIONS

VENIX provides a means of exchanging data with DOS, but the interface is only marginally useful. Table 3 lists and describes the DOS interface commands. This add-on capability is not well designed (from the user's perspective), nor has it been fully debugged. However, VenturCom has been responsive to problems reported during this review and some of the bugs that were discovered have been fixed.

One problem with the DOS interface is that it is cumbersome. Except in rare cases, the user must indicate DOS files to VENIX by prefixing path names with dos! and VENIX path names by prefixing specified paths with venix!. This seems unnecessary because in most situations the command context renders this information redundant. The respective DOS interfaces of PC/IX and XENIX are superior overall.

The DOS interface also has problems performing file copies that use wild-card specifications. A bug in the interface involving diskette volume labels and recursion along a directory path name has been fixed, but VENIX still has problems copying a set of files out of a subdirectory on a floppy disk.

The uucp (UNIX-to-UNIX copy) and cu (call UNIX) programs provide the primary connections to other computer systems and networks. The setline, modem, and ttystate commands are used to allocate, enable and disable,



**TABLE 2: VENIX System V Enhancements**

<b>NEW COMMANDS</b>		
asa	id	pcat, unpack
batch (at)	ipcrm	red (ed)
cflow	ipcs	regcmp
cpio	killall	rsh (sh)
crontab	labelit (volcopy)	SCCS <sup>a</sup>
csplit	line	setline
ctags	logname	tic
ctrace	mkstr	tput
cut	mm	ttysate
cxref	mmchek	uname
dirname (basename)	modem	volcopy
env	newform	whodo
fsplit	news	xargs
getopt	nl	xstr
head	pack	
<b>COMMAND ENHANCEMENTS</b>		
The following commands have new or changed options and added features:		
cat	lint	sort
cc	lp	vi
cu	pr	who
ld	sh	
<b>NEW SYSTEM CALLS</b>		
In addition to named pipes (FIFOs), VENIX adds the following:		
fnctl	msgget	uname
getpgrp (getpid)	msgop	ustat
lockf	setpgrp	
msgctl	ulimit	
<b>SYSTEM CALL ENHANCEMENTS</b>		
These calls now conform with the System V interface definition:		
chown		
signal		
<b>DRIVER ENHANCEMENTS</b>		
<ul style="list-style-type: none"> <li>• Improved bad-track remapping for hard disks</li> <li>• ANSI control sequences for the console drivers</li> <li>• OS kernel reconfiguration is permitted using config</li> </ul>		
<sup>a</sup> SCCS is the source control system composed of the following commands:		
admin	get	sccsdiff
cdc	help	unget
comb	rmdel	val
delta	sact	what

These System V enhancements cause no upward compatibility problems.

and initialize PC ports for uuucp/cu usage. The programs worked fine for setting up and running dial-out connections. An external Hayes-compatible modem worked correctly with no modification of the /usr/lib/uuucp/L-modems modem definition file entry.

Additional ports may be used, such as those provided on quad-port and eight-port boards. The maximum number of licensed users specified in the purchase agreement is enforced in the software; the enforcement algorithm allows for the use of dial-in and dial-out ports for machine-to-machine communications, which do not count against the licensed user limit.

## PERFORMANCE

VENIX is a good performer in the compiler benchmarks (see table 4). The AT system used had a 20MB hard disk (37-millisecond average access time) and 1.64MB of RAM. The XT system had a 10MB hard disk (85-millisecond average access time) and 576KB of memory. VENIX recognizes the presence of the additional RAM and uses it effectively. These simple tests highlight some important aspects of operating system performance. (Note that these results can be compared with those for XENIX in "XENIX for the XT," Augie Hansen, June 1985, p. 129 and for PC/IX in "PC/IX," Augie Hansen, July 1985, p. 80.)

# Instant-C™ The Fastest Interpreter for C

**Runs your programs 50 to 500 times faster than any other C language interpreter.**

Any C interpreter can save you compile and link time when developing your programs. But only **Instant-C** saves your time by running your program at compiled-code speed.

**Fastest Development.** A program that runs in one second when compiled with an optimizing compiler runs in two or three seconds with **Instant-C**. Other interpreters will run the same program in two minutes. Or even ten minutes. Don't trade slow compiling and linking for slow testing and debugging. Only **Instant-C** will let you edit, test, and debug at the fastest possible speeds.

**Fastest Testing.** **Instant-C** immediately executes any C expression, statement, or function call, and display the results. Learn C, or test your programs faster than ever before.

**Fastest Debugging.** **Instant-C** gives you the best source-level debugger for C. Single-step by source statement, or set any number of conditional break-points throughout your program. Errors always show the source statements involved. Once you find the problem, test the correction in seconds.

**Fastest Programming.** **Instant-C** can directly generate executable files, supports full K & R standard C, comes with complete library source, and works under PC-DOS, MS-DOS, or CP/M-86. **Instant-C** gives you working, well-tested programs faster than any other programming tool. Satisfaction guaranteed, or your money back in first 31 days. **Instant-C** is \$495.

**Rational**  
Systems, Inc.

P.O. Box 480  
Natick, MA 01760  
(617) 653-6194



Because VENIX apparently uses identical names for temporary files in the /tmp directory during compiles, it had problems with the multitasking tests. When one compile job clears its temporary files, it also deletes those of other compiles spawned by the same parent shell, making it impossible to run concurrent background or foreground/background compiles. Dissimilar jobs running concurrently (background printing or compile with foreground editing, for example) do not interfere with each other in this way.

VENIX's implementation of the vi editor contains a few bugs that VenturCom is working to eliminate: a time-out problem on the Esc key used to terminate insert-mode operation, and a lock-up condition when **showmatch** is set and a matching opening brace, parenthesis, or bracket is highlighted. However, the editor loads quickly and seemed well behaved in all other respects. Further, unlike the editors with other UNIX-based systems, this vi editor implements auxiliary keypad arrows and PgUp/PgDn keys.

### SYSTEM DIFFERENCES

The VENIX designers tried to follow the interface definition of UNIX System V; they succeeded in all but three areas. These intentional departures from the standard should be noted:

- First, the alarm functions, **sleep()** and **alarm()**, use unsigned arguments in System V release 2, but are signed under VENIX to permit the use of negative numbers to specify clock-tick durations. This permits finer grained alarm and sleep settings (to one-sixtieth

**TABLE 3: DOS Interface Commands**

COMMAND NAME	DESCRIPTION
dos	Invoke a DOS shell. Prompts with <b>dos:</b> and accepts the commands shown below. ^C (the equivalent of BREAK) returns control to the VENIX shell.
dosdel	Delete named files from the DOS diskette.
dosdir	Displays information about files and directories on the DOS diskette.
doscopy	Copies files between DOS diskettes and the VENIX file systems. The <b>-a</b> option is required to correctly handle ASCII files that require conversion of the DOS CR/NL pair to the VENIX NL convention and the reverse.
dosren	Rename a DOS file.
dostype	Display the contents of a DOS file or a list of files. This command does not support I/O redirection.

The VENIX/DOS interface is not well designed, nor has it been fully debugged. Except in rare cases, the user must indicate DOS files to VENIX by prefixing path names with **dos!** and VENIX path names by prefixing specified paths with **venix!**.

of a second) than the whole seconds of the UNIX specification, and is useful in realtime applications. VENIX supports realtime via the **nice** command, which allows only the super user (root) to specify negative increments to obtain higher priorities for some processes.

- Second, VENIX does not accept the use of control characters in path names. Instead, it replaces each such character it encounters with a sharp sign (#). Because using control characters in file and directory names is usually accidental (and a poor practice if done intentionally), this is probably a good idea.
- Third, in the area of shared memory, VENIX uses what VenturCom calls a


"functionally superior" method. Primarily, this method permits a compatible interface to share memory across Intel and DEC architectures, but it is not source-code compatible with the System V release 2 interface definition. The superiority of this method lies in its ability to access shared data segments that exceed the allotted 64KB address space.

AT&T's **curses** and **terminfo** are the heart of the virtual terminal interface used by VENIX. This version of **curses**, originally developed at the University of California at Berkeley has been rewritten by AT&T to work with a greater range of terminals and capabilities and to use a compiled terminal database for greater speed of loading and execution.

## ATTENTION TURBO PASCAL PROGRAMMERS

"Excellent product... best screen manager I've ever seen in any language."

Don A. Williams  
Finance & Administration  
Honeywell



Computer Language Magazine

TURBO PROFESSIONAL's easy to use routines let you...

- write safe, "sidekickable" routines that can use DOS
- execute DOS commands from Turbo
- create super-fast windowed displays
- service interrupts without assembler
- make your own keyboard enhancers
- allocate memory from DOS
- print concurrently with DOS 3.x.

Complete with 109 + routines, manual, source code to Super Macs keyboard enhancer, and many example programs.

Only \$49.95 + \$5.00 shipping & handling

Visa, MasterCard OK

**Order now!**

**(206) 367-0650**



Sunny Hill Software  
13732 Midvale North Suite 206  
Seattle, Washington 98133


Get the tools that have no competition.

Requires Turbo for compatibles. Turbo Pascal & Sidekick Trademark Borland Intl.



**Kimtron**

# MULTI-USER SOLUTION for IBM PC, XT, AT



## Compare the Solution!

The Multi-User Solution of the future is now available.

Convert your IBM PC, XT, AT or Compatibles to a true multi-user system while maintaining display, keyboard and software compatibility.

Since the KT-7/PC display is the same as your PC monochrome monitor, with its look-alike keyboard, operators will feel they're using an IBM PC and can also use the same software manual. Kimtron's multi-user solution includes file and record locking, shared data access, and communication between users. It is **the** intelligent alternative.

The KT-7/PC supports Time Sharing, Enhanced Time Sharing

and Multi-Processor implementation under PC DOS, MS DOS, UNIX, XENIX, CPM 86, Multilink, Concurrent PC DOS, and other compatible multi-user operating systems.

Kimtron's multi-user solution may be tailored for cost effectiveness; as low as \$1095 for an additional user, and for speeds more than ten times faster than LAN. You can add one or as many as 31 additional users per PC. Kimtron delivers the future now by allowing an ever-widening network of multi-user PC's.

The KT-7/PC may be complemented with one (or more) I/O Card, Memory Card, 8086 Speed

Enhancer Card, 80286 AT Card, 8088 Multi-Processor Card, 80186 Speed Enhancer Card, 68000 Card, and related software.

For more information about Kimtron's Multi-User Solution, or general video data terminals for other mini or micro multi-user systems, call your local computer dealers, distributors or Kimtron Corporation Today!

**(408) 286-8790**

**TWX: 910-338-0237**

NOTE: IBM PC, XT, AT, PC DOS, MS DOS, UNIX, XENIX, CPM 86, Multi-Link, Concurrent PC DOS are registered trademarks of IBM Corporation, Microsoft Corp., Bell Labs., Digital Research Inc., Software Link Inc. respectively.


CIRCLE NO. 188 ON READER SERVICE CARD



1705 Junction Court  
Building #160  
San Jose, CA 95112

**Kimtron**





## HATS OFF TO AN ASSEMBLY LANGUAGE TEACHING SYSTEM THAT WORKS.

Assembly language programming isn't easy, but you don't have to be a genius to learn it. Let your PC teach it to you.

The Visible Computer: 8088 is a skillful blend of text and software for mastering the elusive skills of assembly language.

It's an animated simulation of the 8088 microprocessor that lets you see with your own eyes how the 8088 works. You'll be using it as a debugging tool for years to come.

It's a tutorial. The 350 page manual is more than instructions on running the simulator—it may just be the best book on assembly language ever written.

It's 45 demonstration programs you'll work through with the 8088 simulator, from simple register loads to advanced interrupt driven tone generators and file utilities.

The Visible Computer: 8088 for the IBM PC and compatibles: **\$69.95**. If your dealer doesn't have it, order direct: Software Masters, P.O. Box 3638, Bryan, TX 77805. (409) 822-9490. Please include \$3.00 shipping. Bank cards accepted.

**Software  
Masters™**



TVC: 8088 lets  
you see into an 8088  
as it executes programs.

## VENIX

**TABLE 4:** Performance Summary

C COMPILER <sup>a</sup>	PC/AT			PC/XT		
Program size (bytes)	SOURCE	OBJECT <sup>b</sup>	EXECUT.	SOURCE	OBJECT <sup>b</sup>	EXECUT.
empty	11	60	116	11	60	116
sieve	663	314	212	663	314	212
hello	77	133	8,616	77	133	8,490 <sup>c</sup>
Compile time (seconds)	REAL			REAL		
empty	0:05	—	—	0:21	—	—
sieve	0:07	—	—	0:30	—	—
hello	0:09	—	—	0:30	—	—
Timings (seconds)	REAL	USER	SYSTEM	REAL	USER	SYSTEM
empty	0.1	0.0	0.0	0.3	0.0	0.1
sieve	2.3	2.3	0.0	6.9	6.6	0.1
hello	0.1	0.0	0.1	0.3	0.0	0.3
MULTIPROCESSING TESTS (minutes:seconds)						
Foreground sequential	REAL			REAL		
make sortdemo	0:30			1:30		
make xsort	0:16			0:58		
Total time	0:46			2:28		
Background/foreground <sup>c</sup>						
(make sortdemo; echo "\07 1") &	—			2:18		
make xsort	—			1:51		
Total time	—			2:18		
Background simultaneous <sup>c</sup>						
(make sortdemo; echo "\07 1") &	—			2:18		
(make xsort; echo "\07 2") &	—			1:53		
Total time	—			2:18		

<sup>a</sup> Programs were compiled with the `-s` option to strip the symbol table from the resulting object and the `-O` option to produce optimized code.

<sup>b</sup> The `cc` command removes the `.o` file after the link step is completed so the size of `.o` files was obtained separately using the command line `cc -O -s -c file.c` after the full compile job was run using `cc -O -s -o file.c`.

<sup>c</sup> The simultaneous tasks could not complete on the AT because of an apparent problem with the naming of temporary files. This problem has been fixed as can be seen in the results for the XT version of VENIX, which is a more recent release of the product.

The Venix system performance tests were conducted with a user logged onto the console as root and another user logged on via a direct serial connection.

For downward compatibility with programs that make calls to the old **curses** support package, VENIX retains the older library routines and the **termcap** database. A special library called **libbcurses** is linked to programs of the older vintage with this command:

```
cc [options] [files] -lbcurses
```

The source files should include the header file `<bcurses.h>`.

VENIX System V is a full-featured package that offers fast operation. Presently it is flawed by several minor bugs and a few major ones. However, VenturCom's track record of support for earlier VENIX versions gives encouragement that these bugs will be found and fixed. Updates will be made available to licensed owners as the improvements are made; the prices for updates have not been established.

The DOS interface is the area most in need of significant improvement in this system. A developer of custom ap-

plications, for example, depends on a flexible and reliable connection between UNIX and DOS. The VENIX/DOS interface is neither flexible, nor reliable at this point. Nevertheless, this is a complete package that, when the bugs are fixed, will be a good value in a multi-user, multitasking operating system for IBM XT and AT class machines. In the meantime, this is a positive step toward a common UNIX.

VENIX 2.0: \$1,195  
VenturCom, Inc.  
215 First Street  
Cambridge, MA 02142  
617/661-1230  
CIRCLE 357 ON READER SERVICE CARD

Augie Hansen is the owner of Omniware, a software development and training firm that specializes in UNIX and DOS systems and applications. He has written several UNIX-related articles for PC Tech Journal. The author's UNIX net address is {allegra,amd,attunix,cbosgd,ucbvax}!nbires!bdaemon!arh.



## CONSIDER IT STANDARD

This is how AT&T would like everyone to think about System V. It is also the wish of numerous others in the UNIX community who recognize that the long-term viability of this operating system is seriously threatened by the proliferation of specialized versions. One predominant flavor of UNIX most likely will never rise to the top of the heap and match the extensive market penetration of single-user MS-DOS/PC-DOS. However, considering the many users of multiuser UNIX, not just the number of licensed sites, a standard UNIX could, over time, build a very large user population.

The standards committee of /usr/group, an independent organization, has worked for years to define a standard UNIX operating system. AT&T has included many, but not all, of the organization's recommendations in the *System V Interface Definition*, a document that specifies at several levels "...an operating environment where applications software can be written that is independent of any particular computer hardware." Already UNIX is running in various forms on everything from microcomputers to the latest Cray supercomputers—this range of environments is unmatched by any other operating system. AT&T also has taken into account recommendations of the proposed ANSI standard for the C language and standard libraries. Some of the ANSI and /usr/group proposals are in conflict. AT&T has some tough choices to make.

In defining System V, AT&T specified components made available to applications programs and to users, but did not specify implementations. The system interface is defined in terms of a base requirement plus optional extensions. If extensions are available in a given implementation, they must conform to the specification. In addition, vendors of System V-compatible systems are free to add their own extensions as long as the validity of items covered by the definition is maintained.

The substance of the interface definition is organized as shown in the table that accompanies this sidebar. Vendors who wish to have their System V products verified (tested for conformance with the interface definition) must pass the UNIX regression test suite (URTS). Several

**TABLE: System V Levels**

<b>BASE</b>
Operating system services
Error conditions
Signals
Other library routines
Header files
Utilities
Environmental variables
System-resident data files
Directory tree structure
Special device files
<b>K_EXT</b>
Kernel extensions
<b>EXT (extensions for:)</b>
Basic utilities
Advanced utilities
Software development
Network services
Large machine
Graphics
Basic text processing
User interface services
Database manager

**The evolution of the UNIX standard will be controlled by *commitment levels* assigned to each component of the definition. These commitment levels indicate the degree of permanency of the specific component.**

vendors, including VenturCom, are using prerelease copies of URTS to fine tune their System Vs. They plan to submit the software to AT&T for formal verification when the test suite is officially released.

UniSoft, a Berkeley, California company that has done numerous UNIX ports, has been tapped by AT&T to provide the verification suite that will be used to test vendors' systems for conformance to the new standard. VenturCom, the Santa Cruz Operation, and Microsoft are among the guinea pigs who have agreed to help debug the test set.

Both the United States government and IBM have effectively endorsed UNIX System V as the multiuser operating system of choice for many applications. The Pentagon insists that computer system vendors offer UNIX software before they will be considered in its bidding process. IBM is looking out for its own interest, a large part of which involves giving its customers what they want.

Many of them want, even demand, UNIX. Other large computer companies, Amdahl and Cray for example, have announced plans to go the System V route as well.

IBM is now committed to moving its UNIX OS software to the System V standard—a shift that would involve everything from PC/IX on the PC/XT to VM/IX, a mainframe version of UNIX that runs as a guest OS under IBM's virtual machine (VM) OS. IBM would, of course, prefer to sell its own systems and not plug the competition, but it apparently sees UNIX as a path to moving a lot of equipment in the future.

The *System V Interface Definition* is a living document that will require modifications over time in order to track continuing evolution of the system as AT&T UNIX is merged with features from XENIX, Berkeley UNIX, and other branches of the family tree. AT&T will try to keep any one edition of the standard in effect for a reasonable period of time so that most vendors will be inclined to get in step with the rest of the industry rather than to set their own cadences. Those who would "walk to the beat of a different drum" will do so at their own peril given the apparent overall gravitation to the new standard.

The evolution of the standard will be controlled by *commitment levels* that are assigned to each component of the definition. A component tagged as a level 1 commitment will remain in the definition and be migrated into future editions in an upwardly compatible way. Items given a level 2 commitment initially and those moved to level 2 from level 1 will remain in the definition for a period of no less than three years, after which they may be dropped from the definition. Also, components of extensions may migrate into the base system definition (the converse is not true) and new extensions may be added in future editions of the definition.

—AH


*System V Interface Definition: \$27 (Select Code 307-127)*  
 AT&T Consumer Information Center  
 2833 N. Franklin Road  
 Indianapolis, IN 46219  
 800/432-6600 (operator 77)  
 CIRCLE 358 ON READER SERVICE CARD





A Data Manager Designed for

# Complex Applications





*Based on the minicomputer PICK operating system,  
Revelation is a complex product, but not complicated.  
To use this data manager to its fullest  
involves a commitment to explore, experiment, and  
study a powerful, complex system.*

KENT PHELPS

**T**he trickle-down theory of economics may or may not work, but the trickle-down theory of computer software and hardware certainly appears to be alive and well. Today, operating systems, utilities, and most importantly, concepts from minicomputers are being applied to desktop microcomputers.

Revelation by Cosmos is an example of this trickle-down effect. It is a derivative of the PICK operating system, available for many years on a variety of minicomputers. Revelation features not only compatibility with many PICK-based minicomputers and their software and file structures, but an applications development environment that lets the programmer worry about the logic of the problem while the operating system worries about its mechanics. Revelation is flexible, easy to modify, self-documenting, and usable by a novice once the system is set up. Its price of \$950 is somewhat more than the average data manager, but its development environment is filled with powerful tools.

The designers of Revelation perceived the need for a development environment that would function more like the real world than like a computer lab, an environment where the requirements change as the application progresses, where the cost of software maintenance exceeds the initial cost of the software within a year, where the application must be able to provide answers to one-time questions.

The basic specifications indicate Revelation's scope: an unlimited number of files open at one time, a limit of 65,000 characters per record, with 65,000 fields per record, 65,000 characters per field, relatively unrestricted data types, and an internal calculation range of  $\pm 10^{4.932}$ . Precision for data

output is 14 digits to the left of the decimal point plus 4 digits to the right; input is allowed to 18 decimal places. Exponential notation is supported as well. Total disk space is the only limit on number of records per file or number of files in a database. Revelation was designed from the start to use the 8087 numeric coprocessor, but will run with a software emulator automatically if no 8087 is detected.

While Revelation can be used in a floppy-disk configuration, it is really at home on a large memory system with hard disk(s). The programs, which are easily installed, are not copy protected and can be readily copied to a hard disk. Because it uses a demand-paged virtual memory manager with 65KB buffers, Revelation needs at least 320KB to run; any memory beyond that simply means less disk access, the traditional bottleneck on complex database systems. If Revelation must be run on a floppy-disk system, a RAM disk might be beneficial to hold the system files that the user does not often need to access. However, a RAM disk should not be created at the expense of sufficient free memory to run the application.

#### **MINICOMPUTER INTERFACING**

Revelation has facilities to transfer a file or a record between a PICK operating system minicomputer and the Revelation environment. In order to combine the established installed base of PICK minicomputers with independent workstations, such as PCs running Revelation, Cosmos devised an offshoot of the Alternative Filing System, a generalized file system and device interface that is hardware independent.

One part of this scheme is an additional product from Cosmos called R/COMM, which allows Revelation to at-

tach the resources of an entire minicomputer as just another logical drive and to retrieve files without special actions on the part of the operator. If the need is to store large amounts of data and have direct access to any record, more than one disk can be used. For example, 600MB of data can be spread across ten 60MB disks on a network, each disk holding portions of the same large file. If a network of PCs and file servers is required, Revelation's RLAN interface can be configured for any one of several LAN protocols.

Because Revelation is very close to the PICK operating system, which is used worldwide, thousands of programs could be moved over to Revelation with a little bit of work. Cosmos publishes a listing, updated every three months, of applications written specifically for Revelation. Cosmos has runtime modules available for \$200; the company will negotiate limited site licenses and will work with developers closely on unusual applications.

Revelation includes minicomputer communications ability and a terminal emulator (TERMINAL and PORT commands) as part of the basic package. An applications generator (R/DESIGN) and report processor (R/LIST) speed database definition and ad hoc reporting. The programming language (R/BASIC) includes external subroutines with parameter passing, named COMMON areas, structured coding features, and a full interactive symbolic debugger.

#### **REVELATION AND DOS**

Revelation is an application running on top of DOS, not an operating system itself like PICK. The PICK operating system is available on IBM PCs and ATs, but when it is running, no DOS functions are available. Revelation, on the



other hand, depends on DOS for its elementary functions. Compromises are made within this interface, but it allows both systems to lend the best they have to the task at hand.

Several interfaces exist between Revelation and DOS. The simplest is the command, PC, which executes the remaining command line as a DOS command within the limits of memory, returning to the Revelation command processor when finished. Therefore, all DOS utilities (and programs) are available to the operator at the command

level. Within R/BASIC, the statement PCPERFORM accomplishes the same objective and is the only language interface available. This allows an R/BASIC program to run any DOS program no matter what the language. When doing so, the DOS file system in general is seen as a file from within Revelation, and DOS files are treated as records in that file.

These DOS interface commands allow the user to select any DOS program editor or word processor that produces ASCII files, but Revelation

supplies two editors itself: R/EDIT, a line editor supplied mostly for ex-mini-computer programmers, and R/TEXT, a full-screen text editor that contains most word processing functions. R/TEXT also is available within R/DESIGN in places where free-form text entry is required.

Memory-resident programs such as SideKick work with Revelation, and most of SuperKey coexists.

Full path-name support of DOS files is available, although clear instructions on this topic are lacking in the documentation, especially with respect to creating subdirectories under Revelation and accessing them as logical disks. Each user may have his or her own set of files in a separate subdirectory while sharing common system files from the default drive. The ATTACH command is used to locate a group of files and make them accessible to the current user. Revelation keeps the correspondence between DOS files and the Revelation internal name, so the 11-character limit on DOS file-name length does not apply, and files can be assigned meaningful names.

Revelation is based on the relational model of database design; the relation is established by the presence of a common identifier in the two files, such as a department code in an employee master file. Data redundancy is minimized, therefore, by keeping the department description in only one place; all references to the employee master file requiring the printing of the department description do an automatic temporary JOIN to the department file to retrieve the description. (The retrieval language, R/LIST, does automatic JOINS on a record-by-record basis without the need to create a third file.) Because the department description is located in one place, all reports print that information identically, and a change of the department name from "Personnel" to "Human Resources" is immediately effective everywhere.

The use of this facility is not always desirable, because it forces additional disk reads and file OPENS. For small data items, it may be faster to accept the redundancy and keep the raw data in the record itself, so that all the data necessary for the typical query come into memory at one time.

Revelation's demand-paged memory manager feature means that once a file is read into memory, it remains there unless it falls to the bottom of the most recently used queue. In that case it is written back to disk if it was changed, or thrown away if it was not changed. In any case, if no activity has

## Tools for the Programmer from Blaise Computing

Save Up To \$130 On These Special Offers!

### TOOLS & TOOLS 2

For C or Pascal

For a limited time, pick up both packages and save \$50 off our regular list price. The C version comes with libraries for the Lattice, Computer Innovations and Microsoft (version 2.03 and

3.00) compilers. The Pascal version supports IBM and Microsoft Pascal. **\$175.**

### VIEW MANAGER With Source

All libraries are included. Please specify C or Pascal. Regular \$425. Save \$130. **\$295**

Blaise Computing provides a broad range of fine programming tools for Pascal and C programmers, with libraries designed and engineered for the serious software developer. You get clearly written code that's fully commented so that it can serve both as a model and also be easily modified to grow with your changing needs. Our packages are shipped to you complete with comprehensive manuals, sample programs and source code. None of the programs are copy-protected.

#### FOR C AND PASCAL PROGRAMMERS:

##### TOOLS ♦ \$125

Extensive string and screen handling, graphics interface and easy creation of program interfaces. Includes all source code.

##### TOOLS 2 ♦ \$100

Memory management, general program control and DOS file support. Interrupt service routine support. Includes all source code.

##### VIEW MANAGER ♦ \$275

General screen management. Create data entry screens that can be easily manipulated from your application program. Block mode data entry and retrieval with fast screen access.

##### VIEW LIBRARY Source ♦ \$150

Source code to the VIEW MANAGER library functions.

##### ASYNCH MANAGER ♦ \$175

Powerful asynchronous communications library providing interrupt driven support for the COM ports. All source code included.

#### FOR THE TURBO PASCAL PROGRAMMER:

##### Turbo POWER TOOLS ♦ \$99.95

Extensive string support, extended screen and window management, interrupt service routines, program control and memory management, interrupt filters. All source code included.

##### Turbo ASYNCH ♦ \$99.95

Interrupt driven asynchronous communication support callable from Turbo Pascal. ASYNCH is written in assembler and Turbo Pascal with all source code included.

#### PACKAGES FOR ALL PROGRAMMERS:

##### EXEC ♦ \$95

Program chaining executive. Chain one program from another even if the programs are in different languages. Common data area can be specified. Source code included if you're a registered C TOOLS and C TOOLS 2 user.

##### SPARKY ♦ \$75

Run-time resident (or stand-alone) scientific, fully programmable, reverse polish notation calculator. No limit on stack size, variables or tape. Includes all standard scientific functions and different base arithmetic.

**TO ORDER, call Blaise Computing Inc. at (415) 540-5441**

♦ 2034 Blake Street ♦ Berkeley, CA 94704 ♦ (415) 540-5441 ♦

**BLAISE** *watch us!*  
BLAISE COMPUTING INC.



occurred in 30 seconds or so, the memory manager checks for changes and copies the file to disk automatically if changes have been made. For many applications, therefore, the memory manager takes the place of both a cache memory subsystem and a RAM drive, without any intervention by the user or special instructions by the programmer.

### FILE STRUCTURE

Revelation files consist of variable length records containing variable length fields. The package offers two types of file structures, ROS and LINK, both of which are written to disk as normal DOS files. With files under 200KB in size, the ROS file structure should be selected; records are stored as sequential strings in groups of DOS files, each up to 65KB in length. Once the correct DOS file is determined (by the record key), as much of the file as necessary is read in until the desired

**W**ith files that are more than 200KB, the LINK file structure, which allows sharing of files in a network, should be selected.

record is found or end of file is reached, which indicates to the user that the record is not present. ROS files cannot be shared in a network.

With files that are more than 200KB, the LINK file structure, which allows sharing of files in a network, should be selected; LINK files are stored in one DOS file as a series of 1KB frames. Each frame has a pointer to the next frame in the chain. LINK files are a variation of the Alternative Filing System. The physical location of data is separated from the logical access to it.

Record retrieval is accomplished by a direct access method based on modulo arithmetic and a hashing algorithm. When a ROS file is created, a modulo is specified, which is the number of distinct DOS files created to hold this file's records. To find a record, the system takes the user-defined ID or key, applies the hashing algorithm, and comes up with a number. This number is combined with the modulo to find the group in which that record is located. If the modulo is sufficiently large for the number of records and the statistical

distribution of the record keys is uniform, then finding one record should not take longer than any other—no matter how large the file. Ideally, a record is found in one disk access.


A ROS frame can be as large as 65KB, and normally each group has one frame. If more space is needed because of an unexpectedly large number of records written into the file, the system expands automatically by attaching another frame to the group. However, doing this will increase the disk-access overhead. The system command RECREATE-FILE can be used to restructure the file system as desired.

Each record is stored with a byte count field followed by the record ID and the record. Adding fields to the database later has no impact on the fields previously defined, because all records and fields are variable length. Everything shifts as necessary to accommodate new data.

With variable length records, if Revelation reads the first record of a group and decides that it is not the one it is seeking, it can skip  $n$  bytes directly and read the next ID and so on until the ID is located or the program determines that the record does not exist. If for some reason the system reads ahead the specified number of bytes and does not find another byte count field and record ID, the file is considered to be corrupted, and a "FRAME FORMAT ERROR" message is returned. Memory changed by static, hardware failure, or writing to a full diskette are usually responsible for this. The situation can be remedied either by editing the file in question and resetting the byte count fields or by using the instructions provided by Cosmos. Recovery of every damaged file may not be possible, so backups of the file system are highly recommended. No other recovery techniques are available, and transaction logging is not a part of the system.

Because the Revelation file system is variable length, and records are hash-encoded into the appropriate DOS file, file compression techniques are not needed. Operating as a virtual memory system, Revelation updates files in memory; if a record is deleted, the Revelation file group (a whole file to DOS) is restructured and written out to disk if needed. Within R/BASIC, the programmer can force a FLUSH to rewrite buffers to disk and do a GARBAGE-COLLECT, which releases unused string space in order to ensure maximum free memory is available.

In the spirit of a high-level language, and at some sacrifice of disk




## Number One In Performance

## Hard Disk Intelligent VCR Backup for AT/XT/PC

### FEATURES

- High speed microprocessor controlled backup (68000)
- Two channel interface
- Built in LAN channel
- Software control of most VCR functions including Fast Forward, Rewind, and auto backup using VCR timer capabilities
- Economical VHS or Beta formats



West: 4704 W. Jennifer, Suite 105, Fresno, CA 93711, 209/276-2345  
East: 67 Grandview, Pleasantville, NY 10570, 914/747-1450  
Distributor: Telemarketing Services, Inc.  
1897 Garden Ave., Eugene, OR 97403, 1 800/874-2288

CIRCLE NO. 237 ON READER SERVICE CARD



# DeSmet C

**8086/8088  
Development  
Package**

**\$109**

## **FULL DEVELOPMENT PACKAGE**

- Full K&R C Compiler
- Assembler, Linker & Librarian
- Full-Screen Editor
- Execution Profiler
- Complete **STDIO** Library (>120 Func)

## **Automatic DOS 1.X/2.X SUPPORT**

## **BOTH 8087 AND S/W FLOATING POINT OVERLAYS**

## **OUTSTANDING PERFORMANCE**

- First and Second in AUG '83 BYTE benchmarks

## **SYMBOLIC DEBUGGER**

**\$50**

- Examine & change variables by name using C expressions
- Flip between debug and display screen
- Display C source during execution
- Set multiple breakpoints by function or line number

## **DOS LINK SUPPORT**

**\$35**

- Uses DOS .OBJ Format
- LINKs with DOS ASM
- Uses Lattice® naming conventions

Check: ☐ Dev. Pkg (109)  
☐ Debugger (50)  
☐ DOS Link Supt (35)

SHIP TO: \_\_\_\_\_

\_\_\_\_\_ ZIP \_\_\_\_\_

**CWARE**  
CORPORATION

**P.O. BOX C  
Sunnyvale, CA 94087  
(408) 720-9696**

All orders shipped UPS surface on IBM format disks. Shipping included in price. California residents add sales tax. Canada shipping add \$5, elsewhere add \$15. Checks must be on US Bank and in US Dollars. Call 9 a.m. - 1 p.m. to CHARGE by VISA/MC/AMEX.

## REVELATION

space, Revelation stores all types of data as ASCII strings in the file system. This helps insulate the programmer from how a task gets done and lets him or her concentrate on the conceptual aspect of the problem. The programmer does not have to be concerned with REALS, INTEGERS, DATES, etc. This means that the system will let a programmer make mistakes. If the system returns the correct answer without complaining, it does not necessarily indicate that the programmer has written maintainable and efficient code.

The data dictionary is the focus of the Revelation system; it not only defines the data files to the outside world, but also manipulates the data. Three primary features distinguish Revelation's dictionary from most others: output conversions, integral R/BASIC code, and in-context documentation.

Dictionaries are responsible for I/O transformation of the data. When a programmer specifies a conversion code or pattern match, the data transformed as input and output occur on a record-by-record basis. This means that special synonym dictionary entries can be created for special purposes—for example, when a field should be displayed with a leading minus sign on a data entry screen, but shown with a CR suffix on a financial statement. Pattern matching and checking input for ranges of values, table look-ups, and default values all can be specified.

Revelation dictionaries also allow the insertion of R/BASIC code to perform special functions. A fragment of code is written into a dictionary as if it were an R/BASIC program. Special variables are available that are known both to R/BASIC and to the R/LIST processor, such as the current record ID, the file variable of the dictionary file, and the string array that is the current record. In addition, Revelation has five user variables that remain set throughout a session (LOGON to LOGOFF) unless explicitly changed and five recursive variables that are saved during certain functions. The result of all this R/BASIC computation is returned in a special variable called @ANS.

In effect, a piece of code can be written in dictionaries within the context of a fully developed reporting system, and as long as certain rules of conduct are followed, the user can manipulate the data desired without having to write the whole program. This process does not replace R/BASIC, but it considerably expands the usefulness of the dictionaries beyond simply displaying data. As the dictionary item con-

struction is completed with the aid of the applications generator, the relevant instructions are compiled and the compiled code is stored in the dictionary, so that the report processor can jump directly to executable code as it processes the report. No interpretation is necessary at runtime. Table 1 shows the dictionary information for the Total Payment field in the ARTICLE file of the sample application used to evaluate Revelation for this article (see below). Total Payment is a computed field created by adding together the Payment and Bonus fields.

## **R/LIST AND R/BASIC**

Revelation's R/LIST query language is a nonprocedural, somewhat natural, command-driven language. It expects a verb to be the first word (LIST, SORT, SELECT) and a file name to follow. Next in any order may be a series of WITH, WITHOUT, OR, and AND clauses that determine the selection criteria, some BY clauses if a sort is requested (SORT AUTHOR BY LAST.NAME), and option specifications (BREAK-ON, AVERAGE, TOTAL, SUM, HEADING, FOOTING).

The command processor parses the sentence, reads the file, builds lists of records that qualify, consults the dictionary for how to display the data, and formats the report to printer or screen. Any data in any file can be accessed if the appropriate dictionary entry is made specifying how to find the data if they are not stored in the current file. Data that are not in any file but that are computed on the run may be LISTed and SORTed as though that data actually were in the file. Multiple sort keys on multiple files can be used at one time.

The command SELECT is used to index a file, which speeds processing time. The system collects and holds a list of the records meeting the selection criteria sorted in the requested order. This list then may be fed to a report request for display or an R/BASIC program for record-by-record processing. Alternatively, the command SAVE-LIST {listname} stores the record IDs that fit the selection criteria in a system file called LISTS. Later, the command GET-LIST {listname} is invoked to prepare the list for processing or display. In certain situations, a select statement may not be easy or even possible due to the nature of the data. The programmer may just write a list of the record IDs of interest, and the command FORM-LIST {filename} {recordname} will read this list to form a select list.

The language supplied with Revelation, called R/BASIC, has a name that is



**TABLE 1: Dictionary Definition**

ITEM #	ITEM	VALUE
01	File Name	ARTICLE
02	Field Name	TOTAL PAYMENT
03	Single/Multivalued	S
04	Field Type (F, S, G)	S
05	Field Number	
06	Which Part of Key	0
07	Output Conversion	MD2,
08	R/BASIC Formula	@ANS = {PAYMENT} + {BONUS}
09	Justification	R
10	List Display Length	8
11	Edit Patterns	(MD2)
12	Bottom Screen Prompt	TOTAL AMOUNT PAID FOR THIS ARTICLE
13	LIST Column Heading	TOTAL PAYMENT
14	Source of Information	
15	Description	THIS IS THE PAYMENT PLUS THE BONUS

Three primary features distinguish the Revelation dictionary from most other data dictionaries: output conversions, integral R/BASIC code, and in-context documentation. The Total Payment field in the ARTICLE file of the sample application is created by adding together the Payment and Bonus fields.

quite misleading. R/BASIC is much more powerful in database manipulation than any other BASIC language. With its wide variety of constructs and functions, R/BASIC is a generic language; FORTRAN programmers tend to write R/BASIC programs that look like FORTRAN, and COBOL programmers write R/BASIC programs that resemble COBOL. R/BASIC is not a strongly data-typed language, so with some discipline, programmers can write the programs they want. Creating a production-quality program that can be maintained by someone else may require extensive initialization and adherence to local programming standards, but to write a quick and dirty utility program does not require a preamble rivaling the Declaration of Independence.

Some combinations of data or processing features are not possible with R/LIST, and an R/BASIC program must be used. This is the case when data cannot be displayed sequentially, or some special processing must take place. R/BASIC has some speed advantages over R/LIST, but the development time is orders of magnitude greater, and programs are more difficult to maintain. The moral of this story is: if ad hoc reporting is important, design the layout of the files and the types of data that are stored in them with R/LIST in mind. R/BASIC can handle anything, but a wise designer will let the Revelation processors do most of the work.


R/BASIC can be used for special tasks, such as sending data to a variety of printers. Using a configuration table

for the appropriate printers, R/BASIC can send control codes to each printer under complete program control. For a particular field, a dictionary entry could be made to prefix data with printer codes that call for a special feature, send the data, and turn off the special feature while running an R/LIST report.

Within R/BASIC, virtually all standard programming constructs are available, including FOR/NEXT, LOOP/REPEAT (and LOOP WHILE, LOOP UNTIL), CASE, IF/THEN/ELSE, GOTO, and GOSUB. COMMON declarations, both labeled and unlabeled, are available. These can be a very powerful tool in coordinating development of groups of programs, in passing parameters, and in ensuring all programs within the functional module use the same parameters. Statement labels may be numeric or alphanumeric. The BLIST command from the terminal produces a formatted, structured output of the source code to the printer to clarify logic flow.

Among special features, the \$INSERT statement is useful because it tells the compiler to merge source code into the program during the compile. This allows the use of standard COMMONs for parameters; a change to the COMMON area is automatically included in a source file. \$INSERT can be used to insert common internal subroutines, EQUATE statements, or whatever needs to be standardized among a group of programs.

Internal and external subroutines are available and may be recursive. Parameters may be passed either in COM-



## Number One in Performance

# Z80H BLUESTREAK™

### IBM/AT/XT/PC- 8mz No Wait States

#### FEATURES

- 64K-256K RAM
- 2K-8K EPROM/Static Ram
- 2 Serial Ports
- Async/Sync/Bisync Communications
- Real Time Clock
- Memory-mapped Dual-port BUS
- On-board/Remote Reset NMI capability
- Up To 32 Boards Per AT/XT/PC
- Can Operate As Standalone Processor
- Less Than Full Size Board  
(will fit other compatibles.)

#### SOFTWARE

- ZP/M™ CP/M Emulation Software  
(Supports Most CP/M Software)
- Multiuser Capability if Used As A  
Slave Processor

IBM is a registered trademark of International Business Machines Corporation.  
CPM-80 is a registered trademark of Digital Research Corp.


West: 4704 W. Jennifer, Suite 105, Fresno, CA 93711, 209/276-2345  
East: 67 Grandview, Pleasantville, NY 10570, 914/747-1450  
Distributor: Telemarketing Services, Inc.  
1897 Garden Ave., Eugene, OR 97403, 1 800/874-2288

CIRCLE NO. 236 ON READER SERVICE CARD



# Learn and Use AI Technology In Your First Evening With TransPROLOG

A complete *Prolog Interpreter, Tutorial, and set of Sample Programs:*

☐ **Modify and write Expert Systems.**

Use the simple "Guess the animal" example on the Tutorial or use the sophisticated system for Section 318 of the US Tax Code written by one of the TransPROLOG authors and published in the March, 1985 issue of Dr. Dobb's Journal.

☐ **Understand Natural Language**

Use the sample program that produces a dBase DISPLAY command as output.

☐ **Write Symbolic Math or Abstract Problem Solving Applications**

This is a complete Prolog program to convert from Fahrenheit to Centigrade:  $f\_to\_c(C,F) :- C is (F-32) * 5/9$ . Planning programs and games are included to help you learn.

☐ **BECOME FAMILIAR WITH PROLOG IN ONE EVENING.**

**Programming experience is not required**, but a logical mind is. Serious development of experimental systems is practical with TransPROLOG. 1 or 2 pages in Prolog is often equivalent to 10 or 15 in C.

**RECENT IMPROVEMENTS:** MSDOS commands, on-line help, load Editor.

**AVAILABILITY:** All MSDOS, PCDOS systems.

**ONLY**

**\$125**

Full refund if not  
satisfied during  
first 30 days.

**Solution  
Systems™**

335-P Washington St.  
Norwell, Mass. 02061  
617-659-1571  
800-821-2492

CIRCLE NO. 126 ON READER SERVICE CARD

## LEARN LISP

### Interactively and Write "Realistic" Programs with TransLISP for Only \$75

A "COMMON LISP" compatible Tutorial, Interpreter, Debugging, and Pretty Printer plus a Fast, Full Screen Editor, Samples and Help

☐ **Start Easily and Quickly:**

A complete, modular tutorial helps you learn LISP at your own pace. An integrated, interactive environment provides all of the elements needed to enter, modify, analyze and debug programs.

☐ **Natural Language, Expert Systems and Mailing List:**

Natural Language concepts are illustrated by a phone number retrieval program. Choose the best word processing program for you with the Expert System. File handling and typical data processing work are demonstrated by a Mailing List program.

☐ **Write Realistic Programs:**

Short examples and substantial programs of about 10 pages in length help you learn by modifying, studying and using the key concepts needed to write programs of 1000 lines or more.

☐ **The "COMMON LISP" Standard:**

TransLISP includes a 230+ function subset of the "COMMON LISP" Standard. Use extras like the MSDOS interface and graphics. Or use "strict compatibility" to make programs written in TransLISP, with no changes, work with other COMMON LISP systems like VAX LISP, GC/LISP or LISP Machine LISP.

Use and Modify the Mailing List program  
to learn how to handle "normal" programming in LISP.

**Runs on any MSDOS or PCDOS Systems:** Not copy-protected, TransLISP is available in just about any 3", 5" or 8" format. PC compatibles can run TransLISP with no installation procedure. 192K memory and 1 floppy drive are the minimums required.

**ONLY**

**\$75**

Full refund if not  
satisfied during  
first 30 days.

**Solution  
Systems™**

335-P Washington St.  
Norwell, Mass. 02061  
617-659-1571  
800-821-2492

CIRCLE NO. 129 ON READER SERVICE CARD

## REVELATION

MON areas or explicitly in the subroutine call. All labels and other variables not passed are local to the subroutine.

Because of the unique way in which Revelation handles them, arrays are of particular interest. Two-dimensional arrays are supported, with commands such as MATREAD, which both reads the item and assigns values to the elements of the matrix. These elements are addressable in the normal fashion—ARRAY(1,2). Element 0 (ARRAY(0,0)) contains the number of elements filled with data if this number is less than the dimensioned size of the array. This is useful for keeping loops to the minimum number of iterations that are necessary.

In addition to dimensioned arrays, Revelation supports dynamic string arrays, and typically these are used more than are dimensioned arrays. The

**D**ebugging an R/BASIC program is handled in two ways: through a smart compiler or an interactive symbolic debugger.

array is stored as a variable length string (up to the 65,000 limit) with system delimiters separating the elements. Fields of a record are separated by field marks (ASCII 254); within fields may be substrings called *values* separated by value marks (ASCII 253). They, in turn, may contain a series of subvalues separated by subvalue marks (ASCII 252). In effect, Revelation is a relational system with a hierarchical subsystem.

The choice between dynamic or dimensioned arrays is a compromise. Dynamic arrays are long strings, so the search for <ITEM100,34,22> requires reading the entire string and counting delimiters along the way until the correct piece of data is found. A dimensioned array is resolved by the compiler as an address into the data space. Thus, accessing ITEM(1354) is no more difficult than ITEM(2), but data space for the entire array must be reserved even if all elements have not been assigned a value. This is an example of how a programmer with a good grasp of the software/hardware interface can write efficient programs.

String processing is very flexible, because it is the basis for dynamic array



manipulation. Concatenations, substring extractions and insertions, and string compares are available. Therefore, interfacing with fixed-length-field systems, blocking the data from the variable-length source files into a format suitable for the outside world, is quite easy. The dynamic array system includes the ability to build a sorted array, using the LOCATE statement. Instead of creating a file of data, then sorting it in a particular order for some purpose, the user can invoke LOCATE to find the position of an element in a dynamic array. If the element exists, the array position is returned. If the element does not exist, the array position where it should be inserted, based on ascending or descending sequencing, is returned, and the INSERT function places it in the proper location. Elements can be retrieved from a variable with the EXTRACT function and removed from the array with the DELETE function.

Revelation can store all numbers and dates in what is called *internal format*. Dates are numbered sequentially from December 31, 1968, which is day 0. All subsequent days are positive numbers, and all previous days are negative. Date arithmetic then is a direct subtraction or addition. The date is converted by a dictionary instruction for output in any of several formats. For example, December 25, 1973, is stored as 2186. Different reports or programs, operating on the same data, could display that date as 25 DEC 1973, 12/25/73, 25 12 73, or five other choices.

An additional benefit is that the date consumes only four characters in the database. Other numeric fields are stored with only the digits required for the task, and formatting rules are applied when the data record is retrieved. \$12,345.20 is stored as 1234520 in the database, and if a check were to be printed for this amount, the command PRINT OCONV(1234520,"MD2\$,12\*"), where MD stands for a masked decimal conversion, would print \$\*\*12,345.20. All the common formats for numbers in business, including debit and credit indicators, trailing minus signs, truncation or rounding, are available through the conversion process.

#### USING THE LANGUAGE

R/BASIC is a compiled language. Even the query language R/LIST parses the command line and writes an R/BASIC program to perform its task, resulting in a six-second delay or so while it compiles. Although it adds to the time an ad hoc query takes to execute, this R/BASIC intermediate step allows some


clever solutions to be applied when trying to get a report just right. An option on the command line for an R/LIST report causes it to save its R/BASIC program to disk, where it can be examined and modified if necessary.

Debugging an R/BASIC program is handled in two ways: through a smart compiler or an interactive symbolic debugger. The compiler is fast and will report most errors of syntax and construct, but it is not as smart as minicomputer versions of PICK BASIC. Some fairly obvious errors may be caught only at runtime. The debugger can be invoked by inserting a DEBUG statement in the source code or by pressing Ctrl-Break. (The R/BASIC command BREAK KEY OFF or ON will disable and then reenables the ability of Ctrl-Break to invoke the debugger.) The program stops at that point and traps to the debugger. This allows the user to set breakpoints, examine or change the value of any variable in the symbol table by name, set the multistep line counter, and set up trace tables.

Most of the techniques applicable to Revelation apply to other computers running the PICK system, so the database design, file layouts, data, and most R/BASIC program code can be moved to a PICK minicomputer. Revelation incorporates many features specific to its implementation on the PC that are not found on a minicomputer; therefore, portability problems may arise. Generally, transporting software written for a PICK-based minicomputer to Revelation is the easier direction to follow, unless the programmer has a target machine in mind and structures the design around the features on that machine.

A knowledge of R/BASIC is the key to using Revelation's applications generator, R/DESIGN, to its fullest. R/LIST is very flexible for retrieving data; most of R/DESIGN's work is in setting up the database and entering data. R/DESIGN works well in this capacity. If special forms are needed, R/FORM, an output forms utility, allows the building of the form with the full-screen text editor. The dictionary name of the item desired is entered at the location on the screen where the information is to be displayed, and R/FORM combines the form layout with the record information as designated by the dictionary. This is a great feature for statements, checks, and other format-specific documents.

R/DESIGN programs ask for but do not require information about the dictionary items being defined; the system uses this information to provide context-sensitive help in data-entry



## Number One in Performance 68010/68000 Coprocessor for IBM/AT/XT/PC- 8/10/12.5mz No Wait States \$1295<sup>00</sup> Qty. 1

#### FEATURES

- 1-2 MB RAM (1MB Standard)
- 16K-64K EPROM
- 2-8 Serial Ports
- Async/Sync/Bisync Communications
- Battery-backed Real Time Clock
- Battery-backed 2K-8K RAM
- 2 Parallel Ports
- 68881 Math Coprocessor
- Memory-mapped Dual-port BUS
- 3-9 Users Per Board (3 Standard)
- Up To 16 Boards Per AT/XT/PC
- Can Operate As Standalone Processor

#### SOFTWARE

- OS9 (Powerful UNIX-like Multi-user OS)
- CPM/68K
- Software selectable OS including concurrent PC DOS/OS-9 or CPM/68K operation
- Support Module for IBM Graphics
- High-speed Local/Global Disk Caching
- Basic, Pascal, Fortran, C, and COBOL

IBM is a registered trademark of International Business Machines Corporation. OS-9 is a registered trademark of Microware Systems Corp. CPM/68K is a registered trademark of Digital Research Corp. MATH800/MATH801 are registered trademarks of Motorola. (Pick is a registered trademark of AT&T)


West: 4704 W. Jennifer, Suite 105, Fresno, CA 93711, 209/276-2345  
East: 67 Grandview, Pleasantville, NY 10570, 914/747-1450  
Distributor: Telemarketing Services, Inc.  
1897 Garden Ave., Eugene, OR 97403, 1 800/874-2288

CIRCLE NO. 238 ON READER SERVICE CARD



## REVELATION

screens and to create a complete document describing the function of the R/DESIGN program and files handled. The documentation describes the file layout, shows the comments entered for each field, and generally consolidates the essential information about a file and/or a program in one maintainable place. With planning from the applications developer in designing comments, this system could be sufficient for an end-user manual. A sampling of the documentation generated by R/DESIGN for the AUTHOR file maintenance

program of the sample application is shown in figure 1.

Revelation's SORT and SELECT processor operates through the data dictionaries. In normal use the Revelation system does not use prepared indexes, although indexes are available as needed through R/BASIC. All system processors except R/BASIC require the dictionary to find where the data are stored, and R/BASIC may use the dictionary if desired. The user need only know the name of the file and the dictionary name of the information

requested, and the system will find, compare, sort, and display it as specified by the dictionary.

A sentence that is typed at the terminal is parsed by the command processor in a nonprocedural fashion, the specified file or files are opened, the requested pieces of the database are retrieved in the order specified, with the records themselves sorted if necessary during the retrieval process. Because Revelation's dictionary system allows for the creation of symbolic or computed fields, a dictionary reference may be created for data that do not really exist in the data file. Even symbolic data may be used in order to perform a JOIN to another file on a record-by-record basis; this is done either to link files together dynamically for a particular request or to produce a computed field for R/FORM to display on a report.

### SYSTEM SECURITY

As on a minicomputer, a Revelation user logs into an *account*. This is part of the inherent multiuser nature of Revelation's design. The only files that can be accessed are those recognized by that account. The master dictionary for an account, or VOCabulary, is a VERBS file of commands and file references that define which functions are available to that user. If a particular command is not present in the master dictionary or the VERBS file, it cannot be executed unless the user inserts it with the editor. However, if the EDIT command is removed, that is not possible either. Common files can be shared among several Revelation accounts by defining them in each account as an actual location (account) within the Revelation system. A file belonging to another account can be accessed temporarily by setting a file pointer; that file then can be accessed just as if it belonged to the current account.

Each account may have a password that must be entered by the user at log-on time. Data-entry screens created with R/DESIGN may have a protected attribute set for any field to make it display only. No file encryption exists in the Revelation system proper—nor on PICK minicomputers. An encryption program may be written in R/BASIC, however. A dictionary entry could be set up to decrypt a field by calling an R/BASIC decryption subroutine, which is provided on the system only in object code. The decryption would be possible only if the appropriate account name were requesting the report.

The application used to test Revelation for this review has three files:

## Programmer Essentials

**"Offers many capabilities for a reasonable price"**

W. Hunt, PC Tech Journal

**"I highly recommend the  UTILITY LIBRARY"**

D. Deloria, The C Journal

### ESSENTIALS

**\$100**

200 functions: video, strings, keyboard, directories, files, time/date and more. Source code is 95% C. Comprehensive manual with plenty of examples. Demo programs on diskette. Upgrade to THE C UTILITY LIBRARY for \$95.

### THE UTILITY LIBRARY

**\$185**


Thousands in use world wide. 300 functions for serious software developers. The C ESSENTIALS plus "pop-up" windows, business graphics, data entry, DOS command and program execution, polled async communications, sound and more.

### ESSENTIAL GRAPHICS

**\$250**

Fast, powerful, and easy to use. Draw a pie or bar chart with one function. Animation (GET and PUT), filling (PAINT) and user definable patterns. IBM color, IBM EGA and Hercules supported (more soon). NO ROYALTIES. Save \$50 when purchased with above libraries. Available February, 1986.

**Compatible** with Microsoft Ver. 3, Lattice, Aztec, Mark Williams, CI-C86, DeSmet, and Wizard C Compilers. IBM PC/XT/AT and true compatibles.

 **Compiler Packages:** Microsoft C - 319, Lattice or CI-C86 compilers - \$329. Save \$40 - \$50 when purchasing compiler and library combinations. Specify C compiler and version number when ordering. Add \$4 for UPS or \$7 for UPS 2-day. NJ residents add 6% sales tax. Visa, MC, Checks, PO's.



ESSENTIAL SOFTWARE, INC

P.O. Box 1003 Maplewood, NJ 07040 914/762-6605

CIRCLE NO. 140 ON READER SERVICE CARD



**FIGURE 1:** *Sample Documentation*

DOCUMENTATION for AUTHORS Generated 00:13:15 12 NOV 1985				Patterns : %LC%			
Program name : AUTHORS (Enter/Retrieve information from the AUTHOR file.) Type : ENTRY Language : BASIC Inscreen : N				Prompt : 03 MI Middle initial of the author if needed. May actually be a middle name or several initials (i.e. J.D. ) if needed. Patterns: 0A			
This is the program that maintains the AUTHOR file. The file is keyed on author number, and if entering a new author, a carriage return at the 'AUTHOR NUMBER ' prompt will assign the next sequential number available. When finished with entry or update, a <CR> or 'FILE' at the change prompt will file the record. 'END' will abandon the changes.				Prompt : 04 Last name Last name of the author contained in this record is stored here. Any length is acceptable. Patterns : %LC%			
The following are the prompts for program AUTHORS				Prompt : 05 Address Address field of Author's mailing address			
DICTIONARY FMC SM CONV PATRN R/O FRMT DFLT VFILE MV.NO MV.SZ DEPTH KEY ----- AUTHOR.NUM 0 S ON R L#6 %S% KR FIRST.NAME 2 S %LC% O L#12 MI 11 S 0A O L#3 LAST.NAME 1 S %LC% R L#18 ADDRESS 3 S R L#20 CITY 4 S %LC% R L#16 STATE 5 S CO ... R L#2 ZIP 6 S 5N ... O L#5 W.PHONE 7 10N ... O L#12 0 0 H.PHONE 8 7N ... O L#10 SSAN 9 O L#10 BIO 10 S %LC% O T#78 8 CHANGE 0 ON ... O L#60				Prompt : 06 City City of residence Patterns : %LC%			
COLUMN EXPLANATIONS				Prompt : 07 State State of residence Patterns : CO,WY,NB			
FMC=Field number, SM= Single or Multi-valued, CONV=Date, time, or decimals PATRN=Editing patterns, R/O=Required or Optional, FRMT=Display format DFLT=Null Defaults, VFILE=Files verified against, MV.NO=Multi-value window #, MV.SZ=Multi-value window size, DEPTH=Depth of multi-lined prompt, KEY=The Key				Prompt : 08 Zip Code Zip code for mailing Patterns : 5N,5N'-'4N			
Descriptions of prompts for program AUTHORS				Prompt : 09 Work phone Phone number(s) at work..enter just the numbers, either with area code or without. Patterns : 10N,7N			
Prompt : 01 Author # This is a sequential number assigned to the author for future reference throughout the system. If a null is entered ( a 'CR' ) the next next available sequential number will be assigned. Patterns : 0N				Prompt : 10 Home Phone Phone number at home. One entry allowed. Patterns : 7N,10N			
Prompt : 02 First name Author's first name is contained here. This allows searches on a first name field rather than having to do a substring extraction on a combined lastname/first name field. No additional space required				Prompt : 11 SSN Social security number. Used to withhold needed money from young starving authors to support old starving authors			
				Prompt : 12 Biography A (hopefully) succinct description of the life and times of this particular author. Patterns : %LC%			
				Prompt : CHANGE "CHANGE" Prompt. Allows the user to enter Ctrl-T or "TOP" to clear the screen, Ctrl-E or "END" to exit the screen with no update, Ctrl-D or "DELETE" to delete the record, "FILE" or press <E> to file a record on disk. Patterns : 0N,"FILE","DELETE"			

The documentation generated by R/DESIGN describes the AUTHOR file layout of the sample application, shows the comments entered and the conversion patterns for the display of each field, and provides other essential information as well. It is system-maintained, on-line, and a giant step ahead of a system that does not work with a documentation processor.

AUTHOR, ISSUE, and ARTICLE. (For a complete explanation of the sample application, see "Sample Application Specifications," August 1985, p. 48, or download it from PCTECHline.) The AUTHOR file consists of information on each author: name, address, phone, etc. The ISSUE file contains the deadline date for the issue in question, and the record keys are the volume concatenated with an asterisk concatenated with the number of the issue within the volume; thus, volume 4, issue 1 is 4\*1. The ARTICLE file, which is the main file, contains data fields such as titles, date received, payment, author codes, article

size in pages, and the category into which the article fits. This file also contains information linking it to the ISSUE (volume and number) and AUTHOR files (author number).

For the sample application, several ad hoc reports were to be generated. In addition, some specialized reports were to be programmed in order to summarize the articles by issue, to print mailing labels for authors in an issue, and to prepare a summary report by author and year, which lists titles, issue references, and payment data. Different aspects of Revelation were used to accomplish each of these tasks.

To obtain a list of names and phone numbers of authors who have missed the deadline for their articles, sorted by issue, zip code and last name, the following sentence was typed:

```
SORT ARTICLE WITH DEADLINE.MISSED
BY ISSUE BY AUTHOR.ZIP BY LAST.NAME
BREAK-ON ISSUE
LAST.NAME AUTHOR.PHONE
AUTHOR.ADDRESS
HEADING "List of authors missing
deadline Page 'PL'"
LPTR
```

This sentence uses a field nonexistent in the database (issue = volume + \* +



## REVELATION

number) to sort the file, followed by the author's zip code and last name; it qualifies the records by referring to the ARTICLE file for date received and comparing it to the deadline date from the ISSUE file (this is what the symbolic field DEADLINE.MISSED does, producing a Boolean result). Finally, the corresponding contents of the AUTHOR file (last name, phone, and address) are listed to the printer for each of the articles selected.

The symbolic (computed) field DEADLINE.MISSED uses the symbolic

datum ISSUE to translate to the ISSUE file in order to get the deadline date field. Translating from one file to another requires that the key to the second file be compatible with the first.

Additional capabilities of the RLIST processor, beyond the retrieval and conversion functions already discussed, were used to accomplish the second part of the sample application. These capabilities include HEADING and FOOTING, insertion of time, date, file names, line feeds, and page counters in the heading/footing, and the ability to

place the value of the field being subtotaled in the heading when a break occurs in the report.

For the sample application a report was requested listing the average fee paid to authors. This sentence produced that report for a particular issue:

```
LIST ARTICLE WITH ISSUE EQ "?ISSUE?"  
PAYMENT AVERAGE PAYMENT  
BREAK-ON ISSUE "Average For 'BV' "  
HEADING "Listing of Average Fee For  
Issue 'BT' page 'PL'"
```

The word ISSUE surrounded by question marks causes RLIST to prompt the operator for that value. The dictionary entry for PAYMENT is one that totals the amounts for normal payment and bonus. RLIST notices the key word AVERAGE and keeps counters going until the break-value changes, at which time the record count is known and the average can be computed. The BREAK-ON statement specifies that each time the issue changes, the string "Average For" and the issue value will be displayed. Heading options B causes the break value (issue) to be displayed, T displays time and date, P is a page counter, and L causes a line feed.

Similar to this report was one that requested a listing of the ARTICLE file sorted by author and displaying article titles, booking information, and fee plus bonus paid per author per year. The problem here was splitting the amount paid among all the authors, because in some cases multiple authors were responsible for one story. These split fees require an R/BASIC program. To get all authors in the list in order when some of the articles had more than one author requires an *exploding sort* on the multivalued author field. RLIST creates a temporary workspace, "explodes" the records to all unique combinations of article and author, sorts the work file, and feeds it to the R/BASIC program. The program then could read the records in order, find out how many authors were part of each article, and split the fee accordingly.

If the BREAK-ON phrase is combined with a P option at the break subtotal, a separate page is issued for each different group of subtotals. For example, if an invoice file was sorted by vendor, and the above options were used to ask for total invoices by vendor, the result would be a report with a new page for each vendor, totaling that vendor's invoices and with the vendor name in the heading; these pages could be used as separate reports.

Other options/key words that are available with the RLIST processor in-

# Lattice® Works

## NEW PROGRAMMER'S SCREEN EDITOR INTRODUCED

Designed specifically for programmers, the Lattice Screen Editor (LSE) is a fast and flexible, multi-window editor that is also easy to learn and use.

LSE runs under MS-DOS or PC-DOS on most popular machines with 128Kb memory. It provides standard editor functions such as block moves, pattern searches, and "cut and paste." In addition, LSE offers special features for programmers such as an error tracking mode and three assembly language input modes.

A complete installation program is included to remap any of LSE's 48 keyboard functions. Menus, prompts, help messages and default file extensions can also be customized for individual user preferences. \$125.00.

## LATTICE TOPVIEW TOOLBASKET NOW AVAILABLE

Providing more than seventy functions, the Lattice TopView Toolbasket is designed for software developers writing applications for IBM's TopView multi-tasking, multi-window environment.



## Lattice

Phone (312) 858-7950 TWX 910-291-2190

INTERNATIONAL SALES OFFICES:

Benelux: De Vooght. Phone (32)-2-720-91-28. England: Roundhill. Phone (0672) 54675

Japan: Lifeboat Inc. Phone (03) 293-4711 France: SFDL. Phone (1) 666 1155

The Toolbasket functions eliminate the need for extensive use of assembly language when interfacing with TopView. The Toolbasket's library includes functions to control window, cursor, pointer, and printer operations. It also provides access to TopView's cut-and-paste facilities and offers debugging services.

The Toolbasket runs on the IBM PC, XT, AT, and compatible systems with 256Kb memory. \$250.00. Binary and source code is available for \$500.00.

## LATTICE CREATES C COMPILER FOR COMMODORE AMIGA

Amiga C, produced by Lattice for the Commodore Amiga, supports the Amiga's 68000 microprocessor and offers the same high speed and extensive capabilities of the MS-DOS Lattice C compiler currently used by more than 30,000 software developers worldwide. Available from both Commodore and Lattice. \$300.00.

In addition, Lattice also offers cross compilers that allow you to develop Amiga programs on MS-DOS or UNIX systems.

Contact Lattice, to discuss your programming needs. Lattice provides C compilers and cross compilers for many environments including Tandy, Sony, Hewlett-Packard, Tandem, and IBM Mainframe. Corporate license agreements available.

CIRCLE NO. 160 ON READER SERVICE CARD



# Back up 10 megabytes in 8 minutes! (or less)

## with Fastback\*

If you've ever lost valuable data, you know backing up your hard disk is a *MUST*. For your business, this necessity can become an expensive nightmare. Until now. Fastback (Version 5.0) is the hard disk backup (and restore) software utility that eliminates the need for expensive and time consuming tape backup systems. It's so fast you can back up a full 10-megabyte hard disk on standard 5¼" floppies in less than 8 minutes or 10 megabytes of data on the IBM™ PC-AT in less than 4 minutes! This can mean a 95% savings of time and money.

Fastback is fully self-contained and functions with any make or size hard disk. It works with PC-DOS™, or MS-DOS™ version 2.0 or higher and requires no additional hardware to take up valuable expansion slots in your IBM PC/XT/AT or compatible. **FASTBACK USES ADVANCED ERROR CORRECTION TECHNIQUES TO RECOVER DATA FROM DAMAGED DISKETTES.** So if your disk is

damaged after the backup procedure, Fastback (Version 5.0) will still be able to recover the data.

Fastback can automatically format your floppy disk as it saves your data; both drives will be used on a dual drive system to eliminate the disk change time. Fastback cataloging feature provides rapid lookup of archived data and prevents accidental overwriting.

You control what files you want because Fastback is completely file oriented, not an image mode backup. All this for the suggested retail price of:


**\$179.**

With Fastback, backing up is fast and easy. Remember, among those who backup regularly, there are only two types—those who use Fastback and those who will!

For further information, call or write to:



Marketing and Sales: 909 Electric Avenue • Suite 202 • Seal Beach • CA • 90740 • Manufacturing: 7942 Picardy Avenue • Baton Rouge • LA • 70809 • Telephone: 1-800-225-2775 or (213) 439-2191



**Dealer Inquiries Invited.**  
CIRCLE NO. 217 ON READER SERVICE CARD  
Marketing and Sales by CSSL, Inc.

\*This product is in no way associated with or has origination in Fisher Scientific or Allied Corporation. IBM-PC, IBM-XT, IBM-AT and PC-DOS are registered trademarks of International Business Machines Corporation. MS-DOS is a registered trademark of Microsoft, Inc.



## REVELATION

clude COUNT, which counts the items that match certain criteria; SUM, which totals a multivalued field; and GRAND-TOTAL, which allows text to be printed on the grand total line.

Report formats are controlled by the dictionary entries for the fields

requested. The dictionaries contain specifications for column width and justification. Three justification rules are available: right, left, and text. Numbers must be right-justified if they are to sort properly. Text justification justifies left, but does not break the line at the col-

umn width point; it seeks the last space in the string and folds the line there, creating a much more professional presentation. If total column width of all fields requested plus intercolumn spaces is less than the width of the display device, then a columnar report is

## REVELATION OVERVIEW

### REVELATION, version G

19530 Pacific Highway South, Suite 102, Seattle, WA 98188;  
206/824-9942

**Product type.** Data management system and applications environment for business applications.

**Software environment.** Runs under MS- and PC-DOS, version 2.0 and later, and IBM's TopView.

**Network support.** IBM, Nestar, Novell, Gateway, Corvus, PCNet, Banyan Systems, and Santa Clara Systems.

**Hardware environment.** IBM PC, PC/XT, PC/AT, and IBM compatibles with a minimum of 320KB of RAM and two floppy-disk drives. Also supported are additional RAM, system-compatible hard-disk drive, and 8087 coprocessor.

**User interface.** The program is command language and menu-driven and uses macros/procedures and function/control keys. The command language, data definition, and data manipulation are all English-like.


**File limitations.** 65,000 characters per field; 65,000 characters per record; 65,000 fields per record; unlimited records per file; unlimited open files; unlimited indexes per file. The program allows a file to span multiple disk-volumes, and stores data in variable length records. Uses both relational and free-form data dictionary architectures.

**Access to system facilities.** From within the program the user has the ability to access all DOS functions.

**File modification facilities.** The program can merge two or more files into a single file, and can split a file into two or more files. The program can update a file with data from another file, and can update multiple files simultaneously. Fields can be added without loss of data in a file.

**Help facilities.** On-line, context-sensitive help, a written tutorial, and a quick reference card are provided.

**File design.** The product uses a screen-painting method of entry-screen design that allows custom



data-entry screens. The user may create multiple data-entry screens for a single file, which may be more than one screen in length. The program supports derived fields using information resulting from calculations, from another file, and from a user-supplied list or file of acceptable values. Also allowed are view-only fields, numeric fields, user-defined numeric formats, must-enter fields, and double-entry fields that force the operator to reenter information to verify accuracy.

**Data entry.** The program automatically checks for duplicate entries in a file; provides range checking functions; allows standard entry values during entry; and provides facilities for batch data entry.

**Query and sorting.** Search facilities allow for partial key search and selection and logical operators. Sorts can be performed in ascending and descending order. The program supports multiple sort operations on up to 128 fields and multiple indexes on unlimited fields. Query and ordering specifications may be saved for repeated use. Automatic updating of indexes is supported.

**Reporting.** The program produces label reports that produce two-or-more-across labels. Report formats can be edited and can contain information from two or more files. The program also produces summary reports that can include totals, subtotals, control breaks for pagination, and calculated results using four-

function math, parenthetical control of order of operations, averages, and trigonometric, transcendental, and string operations. Reports can be directed to the screen, printer, or choice of multiple printers. Print enhancements such as bold and underline are supported and the user may specify paper size, margins, etc. in the report definition.

**Security.** The program provides password-protected access to the program itself and to program fields. Multiple levels of password protection may be programmed through the dictionary.

**Utilities.** The program provides file maintenance utilities, conversion utilities for translating dBASE and Lotus files, and print-outs of report and file-design definitions.

**Applications development facilities.** Customization is possible with macros/procedures and custom menu generation. The program provides a fully programmable procedural language, links to DOS applications or other languages, and can generate turnkey applications. A runtime compiler or module is available for use with applications developed.

**Data compatibility.** Program reads DIF, Lotus, dBASE, comma-delimited ASCII, and fixed-length ASCII file formats.

**Special features.** The program provides integrated, variable length and width text windows within screen generator.

**Delivery.** Began in May 1983; current version first delivered in May 1985.

**Distribution.** Primarily through distributors, dealers, systems houses, and consultants.

**Price.** \$950; Runtime version, \$200; Network Revelation 4-user license, \$1,495; 10-user license, \$2,995; 32-user license, \$4,995.

**Support.** The product includes on-screen tutorials, sample applications, telephone support, demonstration disk, and end-user training. An update/maintenance plan is available for \$50. Backups are allowed for personal use.



generated. Otherwise the system goes to vertical format, where one record at a time is displayed with each field requested on a separate line.

Another task in the sample application was to print some labels. R/FORM could accomplish that in only a few moments, but with one drawback: duplicates could not be easily eliminated. An R/BASIC program had to be written in order to meet the specified criteria. The end user must decide if eliminating some duplicate labels is worth this extra programming time.

REFORMAT, an undocumented verb that is on the system but not working completely, could be a solution to this problem. When available, REFORMAT will make a selection of one file and write it to another file or the same file in an inverted format, with a new record key and consisting only of the fields specified in the command. In the example, the system could eventually REFORMAT the selected list of authors' names to a file with the author names as keys and the address information as fields, so duplicates would overwrite one another. Then that file would be used to print the labels.

Once a report is constructed as desired, and if it is a routine report, the sentence that creates it may be saved in the master dictionary of the account as just another verb that, when typed, displays the entire report. For this purpose, a sentence may be constructed to prompt for a desired value, making the report more generic. The sentence

**SORT ARTICLE FILE**  
**WITH ISSUE EQ "ISSUE?"**  
**BREAK-ON AUTHOR**  
**TOTAL PAYMENT TOTAL PAGES**

could be saved as PAYMENT.REPORT (no spaces), and all the end user needs to do is type the verb, answer the prompt ISSUE?, and get the report.

As an aid to using and developing R/LIST sentences, the system command processor keeps a stack of the last 10 commands. These are available for inspection by entering .L. Any command can be brought to the terminal buffer by .Xn; it may then be edited as necessary with Ins, Del, and arrow keys before being executed. Once a sentence is correct, it may be saved in the master dictionary with the command .Sn name. Thereafter, that name is a verb that will run the sentence just as if it were typed at the terminal.

In the above sentence, the word FILE was used as a throwaway word to increase the readability of the sentence. In this location in the sentence it is

ignored by the command processor. Other throwaway words are A, ANY, AN, HAS, OF, THAN, THE. Thus, the following sentence also is acceptable:

**SORT THE ARTICLE FILE**  
**WITH ISSUE EQ '3\*4'**  
**IF THE AUTHOR HAS A LAST.NAME OF**  
**'Wheeler'**

### **MULTIUSER APPLICATIONS**


Cosmos has a novel approach to integrating multiuser features into Revelation. The product has its origins in minicomputer, realtime, multiuser operating systems; thus, all necessary syntax has been available in R/BASIC since inception. Single-user applications ignore the locking logic, so the programmer can design systems with multiuser environments in mind from the start.

Cosmos has attempted to carry system design forward with the same spirit in which the PICK system was invented: to be hardware independent as much as possible. Therefore, the LAN interface is a generalized I/O interface that can support any of several types of LAN hardware, including Novell, Nestar, and 3COM. Revelation can handle the retrieval of files from a remote device without the operator knowing where the data reside. Cosmos has provided

an improvement to standard PICK BASIC in this area; many minicomputers lock the group in which the data reside, but R/LAN locks the record. The lock is only for update, so several users can read the record at one time, but only the user who has set the semaphore lock can write the data to disk.

Data entry with R/DESIGN can be prompted either at the bottom of the screen or at a particular place on the screen. Screen forms can be made in color and use some line drawing characters, although this is a little tricky. An interesting feature of R/DESIGN is what Cosmos calls *ticker-tape display* of text fields. The dictionary specification for the field being entered determines the display width on the screen, but because the data fields have no length restrictions, entering more data than the window size can accommodate causes the line to scroll to the left until a carriage return is entered. The user may scroll back and forth within the field and change the entry as needed.

All Revelation commands must be entered in uppercase, an incongruous requirement on the PC. This is one feature that has migrated down to the PC that should have stayed at the minicomputer level. Revelation uses the keyboard of the PC thoughtfully.



**We firmly believe that  
Vitamin C is the best data  
entry and windowing package  
available - bar none. In fact, we  
are so confident that once you see  
Vitamin C you'll agree, we are offering a**

**100% MONEY BACK GUARANTEE**

Finally! A library of high level C functions (not just a bunch of building blocks) designed to increase your productivity and help develop superior applications in dramatically less time! How? Well, VITAMIN C automatically coordinates complex tasks and leaves the programmer free to be creative! With VITAMIN C, for example, you'll never even have to think about saving or restoring portions of the screen when a window is opened, moved, or closed. Simply call wopen(), wmove(), or wclose() and VITAMIN C takes care of the complexities. It's just that easy! This philosophy of relieving the programmer from so many details as possible runs throughout VITAMIN C. As a result, jobs that used to take days to code can be finished in a matter of hours!

**Complete input formatting • Unlimited validation • Full attribute control  
Insert & delete • First/last/next/previous field • Field sensitive help interface  
Multiple virtual windows • Automatic overlay and restore • Full collision protection  
Animated "zoom" windows • Move, grow, or shrink windows at the press of a button  
Bordered or borderless windows • Automatic or manual scrolling • Hide and show  
Print to or scroll background windows without hurting foreground**

**PLUS: All data entry features are already interfaced with windows for  
effortless data entry windows, display windows & pop-up menus!**

**Vitamin C \$149.95 +**

\$3 Ground, \$6 Air, \$15 Next day. Texas add 6 1/8 % sales tax.  
Specify Microsoft v3, Lattice, Computer Innovations, DeSmet,  
Aztec, Mark Williams. Call about UNIX, TI-Pro, and others!

- 100% source code • Reference manual •
- Step by step Tutorial • Examples •
- Sample Programs •

**For orders or information, call...**

**(214)243-6197**

**Or write...**

**Creative Programming**

**Box 112097**

**Carrollton, Tx 75011-2097**



The latest release of Revelation comes with some very handy tools for moving data into and out of Revelation in foreign formats. A program supplied on the utility disk called PORTER moves Revelation files to DOS ASCII files or to Lotus 1-2-3-compatible DIF format files and back again. This program is easy to run and allows considerable flexibility in moving DOS files, either with fixed-length fields or comma-delimited fields, into Revelation. It allows rearrangement of fields as the file is loaded, and any field can be chosen to be the Revelation file key. A conversion program also is supplied to move dBASE II files into Revelation format, including creation of the data dictionaries. dBASE III files can be moved with the program PORTER.

If the task is somewhat more difficult, R/BASIC has two functions, called OSBREAD and OSBWRITE, that read in a DOS file as a string up to 65,000 characters long; then from R/BASIC the file can be manipulated as necessary and written out again.

The Revelation documentation, which consists of two full binders, is among the best available for this type of system, but even a knowledgeable user will have some difficulty finding the references needed to answer all questions. The index could well benefit from a

**TABLE 2: Benchmark Results**

BENCHMARK TASK	TIME (secs)
Add 900 records to an empty database	157
Index database on two fields (7 bytes)	—
Document and tally codes from one field	66
Mass change of one field (28 records of 900)	51
Extract selected records to create a test file	50

Revelation has a lot of overhead associated with simple tasks and may not be the best choice if speed is crucial, the database small, and Revelation's flexibility is not needed. Revelation will perform best with a large database and will be most useful when the application must be flexible and special features are needed.

doubling in size. Several excellent sections describe the theory and philosophy of the design; these should be read carefully first. The tutorial is a sample accounts receivable system. The example programs are straightforward and probably the best way to learn R/BASIC. The sections on R/DESIGN should allow a novice to produce effective results fairly quickly. On-line help is available at the system level for information about various commands.

## BENCHMARKS

Five benchmarks were run for this article, as they were for the other data managers that have been reviewed in

this series (see *PC Tech Journal* issues beginning in August 1985). The results are shown in table 2. All of the performance benchmarks in the data manager series have been run on the same PC/AT at *PC Tech Journal's* editorial offices. The same fixed-disk partition is reserved for running the benchmarks so that each set of tests is run from the same portion of the disk.

In the first benchmark, loading a Revelation file with 900 records from a DOS diskette, the PORTER program was used to read the diskette and load 900 records of the author file. It worked well and was easy to run. However, the processing time was reduced by 32 percent by writing an R/BASIC program designed for this task, using the R/BASIC ability to read the DOS file directly into a memory buffer and the R/BASIC statement CONVERT to convert the DOS delimiters, double quote and comma, to Revelation system delimiters. Compared to some other data managers previously reviewed, this is not especially fast or unnecessarily slow, but it does illustrate that a generic program written to be flexible and user friendly will invariably have more overhead than one written for the task with an eye for efficiency.

In designing this file, using the names of the authors or their Social Security Numbers as the record key would seem to make the most sense; however, a sequential number was used for this test. Because the system performs a hashing algorithm on the record ID to decide where to store it, the goal in a larger file is a uniform distribution of records throughout the file. Sequential numbers work best in this case. Also, the fewer characters in the key, the less time spent with the hashing algorithm. One last consideration is that R/DESIGN will maintain an index if so desired, so the user would always be able to find an author by last name also.

The second benchmark, reindexing the author database, is really not appli-

## New from TLM!

**Revolutionary, Affordable "C" Language Screen Generator paints a screen as easily as a word processor writes a page**

**Get the picture now on a DEMO DISKETTE RISK-FREE**

At last, "C" language software developers have a super-efficient productivity tool that saves hours over writing programs from scratch. With TLM's revolutionary new Screen Generator, just paint what you want the screen to look like in real time, and it automatically becomes a program you can use. Proven in systems for ATT, Pacific Telesis, Johnson & Johnson...here's the competitive edge you need at a price you can afford to pay. So full-featured, powerful and easy to operate it was used to develop Bellcor's *Exact PC*. Clients see your screens before you write them up, so it pays for itself over and over again in valuable time and customer visits saved.

### Features include:

- on-line hold
- 3270 features
- full screen editor
- data dictionary
- field validation

### Required environment:

- IBM PC, XT or 100% compatibles
- Lattice "C", Computer Innovation or Digital Research
- 256K

### Prove it to yourself risk-free:

Send just \$10 for your DEMO DISKETTE today. If you don't agree that TLM's Screen Generator is the best "C" language screen painter in its price category, sure to save you many times its \$395 purchase price, just return the diskette within 30 days and your \$10 will be promptly refunded. Or, order the full program and we'll apply your \$10 to the purchase price. Either way, your trial costs you nothing! Supplies are limited, so write for your demo diskette without delay. No salesman will call.

**For fastest action** on MasterCard, VISA and COD orders, telephone (914) 937-4508. Or write TLM, Inc., Dept. C, One N. Broadway, White Plains, NY 10601.



cable because Revelation is not an index-driven system. Creating a list of records that met the qualifications specified would be a comparable task; if this task were to be repeated in the foreseeable future the list could be saved so that another selection process would not have to take place.

Note that the system will not maintain these lists itself if records are added or deleted. In real life, however, selections are made with constantly varying requirements, so the philosophy behind Revelation is that some overhead may exist in a system that does not require indexes, and in return no restrictions are placed on the kind of select or sort that can be performed on the file data. Because of this feature, an index never has to be corrupted; every selected list is correct as of that moment. R/DESIGN, however, can maintain cross-reference index files if so desired. This would be a good idea only if the entire application were to be done with R/DESIGN, and the overhead of additional files was acceptable.

The third benchmark, counting the number of occurrences of the state codes and reporting them in alphabetical order, took 66 seconds. It is an illustration of alternative methods available to the R/BASIC programmer. In a typical indexed database system, the file would be sorted by state first and then read sequentially, keeping a running count of the state codes. With R/BASIC and the ability to build sorted dynamic arrays in

**W**ith R/BASIC and the ability to build sorted dynamic arrays in realtime, the process can skip the sort of the entire file and simply read the file sequentially.

realtime, the process can skip the sort of the entire file and simply read the file sequentially. Whenever a state code is encountered, a memory list is checked that is built as the program progresses, and a counter is incremented in a second parallel array representing the total count for that state. When done, the array of state codes is in alphabetical order, and the corresponding counts are in the matching array element. After all state codes have

been read once, sorting stops and only memory addition continues. The R/BASIC code for this benchmark is shown in listing 1.

Changing the state field in selected records from CO to CL, was the fourth benchmark, which took 51 seconds. The test would have run faster using a pre-selected list of records with state equaling CO, but fetching the records from the database first is much more representative of a real-world problem.


The last benchmark combined a select, a sort, and the creation of an exter-

nal DOS file. The test was to find all authors with California addresses, sorted by zip code, and to write the records to a DOS ASCII file. More or less the reverse of the first test, it is a good example of moving data out of Revelation for use by another program. The time of 50 seconds was longer, by far, than any other data manager tested so far.

Benchmarks are instructive if they are representative of the intended use of the product. Revelation has a lot of overhead associated with simple tasks and may not be the best choice if speed

## Leap MS-DOS Software With A Single File!!

It's



More powerful than Prokey™ or Superkey™!  
Stops integration nightmares with its bare bits!

SuperBatch™ is a powerful utility program that creates batch files that drive almost any program (LOTUS 1-2-3™, Wordstar™, etc.). It also continues execution from program to program. Common uses include:

- Integration of individual programs to form a system.
- Creation of self running demo systems.
- Inserting repetitive procedures into a SuperBatch™ file for simple execution.

Please send ☐ Info ☐ SuperBatch

Name

Addr

Addr

Addr

City

State  Zip  Tele

Please mail or call 313-645-5280 to place your order.

\$79.95 with a 30 day Money Back Guarantee

Canadian orders add \$10.00 for shipping.

copies x 79.95 **Merrill Street Software**  
MI res. add 3.20 sales tax per  Division of BCC Inc.  
Total  251 Merrill Street  
Birmingham, MI 48011

Payment ☐ Visa ☐ MC ☐ Chk ☐ PO ☐ Bank Draft ☐ COD

Name Cr Card

Cr Card No.  Card Exp.

Prokey™ is a registered trademark of RoseSoft, Inc. Superkey™ is a registered trademark of Borland International.  
Lotus 1-2-3™ is a registered trademark of Lotus Development Corp. Wordstar™ is a registered trademark of Micropro International.  
SuperBatch™ is a registered trademark of BCC, Inc. SuperBatch™ requires MS-DOS 2.0 or greater.

CIRCLE NO. 106 ON READER SERVICE CARD




## REVELATION

is crucial, if the flexibility it offers is not needed, and if the database is small. Revelation performs best in relative timings when the database is large (10,000 records or more) and when the application must be extremely flexible and the special features are needed.

Revelation is indeed an extremely powerful and flexible data management

tool; between R/BASIC, R/LIST, and the dictionaries, any given task may be accomplished in several ways. From a developer's standpoint, the more complex the application, the more useful Revelation will become.

After several years of proving and refining its concepts on thousands of PICK-based minicomputers, Revelation

appears to be relatively bulletproof and should be an excellent development platform for serious projects. 

*Kent Phelps has several years experience with the PICK operating system and has worked with Revelation since it was introduced. He currently is manager of technical support for General Automation, a manufacturer of super micros and minicomputers using PICK.*

### LISTING 1: BENCH3.LST

```
*** COUNT THE OCCURRENCES OF STATE CODES AND PRINT THEM
***
***      KENT PHELPS 10/85
***

OPEN "","AUTHOR" TO AUTHOR ELSE STOP
*****
*
* initialize
*
  ARRAY = '';ARRAY1=''
  REC = 0
*
  PRINT "START ":TIMEDATE()
  START = TIME()
*
START:
*
  REC += 1
* keep the user informed
  IF MOD(REC,10) = 0 THEN
    PRINT @ (0,22):'RECORDS SO FAR ':REC
  END
*
  READ ITEM FROM AUTHOR,REC ELSE GOTO FINISH; * none left
  STATE = ITEM<5> ; * get variable from rec dynamic array
  LOCATE STATE IN ARRAY BY 'AR' USING @FM SETTING POS ELSE
```

```
* if not presently in my state list then add
  ARRAY<POS> = STATE
  END
* now increment the corresponding counter
  ARRAY1<POS> = ARRAY1<POS>+1
* keep going
  GOTO START:
*
FINISH:
*
* clear the screen
  PRINT @(-1):"STATE POPULATION RECS IN THE AUTHOR FILE "
  PRINT
  PRINT "STATE OCCURRENCES"
  FOR I = 1 TO COUNT(ARRAY,@FM) + 1 ; * number of elements
    * format the items left justified, field of nine spaces
    * a string of asterisks as a histogram for fun
    PRINT ARRAY<I> "L#9":ARRAY1<I> "L#9":STR('!',ARRAY1<I>)
  NEXT I
  PRINT "FINISHED !! ":TIMEDATE()
* get current system time, figure the total elapsed
  ELAPSED.TIME = TIME() - START
* convert internal time difference to output format
  PRINT "ELAPSED TIME :":CONV(ELAPSED.TIME,"MTS")
  PRINT
* pause for a moment so the user can write down the results!
  PRINT "PRESS <CR> TO CONTINUE ":INPUT Q
  END
```

## A Full C Compiler For \$49.95



The Ecosoft Eco-C88 compiler for the 8088 and MSDOS is going to set a new standard for price and performance. Consider the evidence:

Compiler	Eco-C88	Lattice (1)	C86 (1)
Seive	13	11	13
Fib	44	58	46
Deref	13	13	-
Matrix	21	29	27
Price	\$49.95	\$500.00	\$395.00

(1) **Computer Language**, Feb., 1985, pp.73-102. Reprinted by permission. Eco-C88 Rel. 2.83, on IBM PC with 2 floppy disks, 256K. Benchmarks from Feb., 1985 **Computer Language**.

Eco-C88 includes:

- \* All operators and data types (except bit fields)
- \* Error messages in English with page numbers that reference the **C Programming Guide** - a real plus if you're just getting started in C.
- \* Over 180 library functions, including color and transcendental
- \* New Library functions for treating memory as a file
- \* User-selectable ASM or OBJ output (no assembler required)
- \* 8087 support with 8087 sensed at runtime
- \* cc and "mini-make" for easy compiles (with source)
- \* Fast, efficient code for all IBM-PC, XT, AT and compatibles using MSDOS 2.1 or later.
- \* Complete user's manual

If ordered with the compiler, the C library source code (excluding transcendental) is \$10.00 and the ISAM file handler (as published in the **C Programmer's Library**, Que Corp) in OBJ format is an additional \$15.00. Please add \$4.00 for shipping and handling. To order, call or write:

### Ecosoft Inc.

6413 N. College Avenue  
Indianapolis, IN 46220  
(317) 255-6476 • 8:30-4:30


1-800-952-0472  
(orders only)

CIRCLE NO. 131 ON READER SERVICE CARD

Trademarks: Eco-C88, Microstat (Ecosoft), CP/M (Digital Research), MSDOS (Microsoft), PC-DOS (IBM), Z80 (Zilog), 8086, 8087, 8088 (Intel).



## New Release 4.1



We've continually improved Microstat since it was introduced in 1978, and the latest release includes many new features you've wanted.

Interactive and Batch Processing	Data sets that can exceed memory
Expanded Data Management Subsystem with New Data Transforms	Multiple Regression (including Stepwise)
Reading data files created by other programs (e.g., Lotus)	Scatterplots (including best fit regression)
3 types of Analysis of Variance	Correlation Analysis
Time Series	12 Nonparametric tests
Crosstabs and Chi-Square	8 Probability Distributions
Factorials, Permutations, and Combinations	Descriptive Statistics
Hypothesis Tests	Easy Installation

Microstat's algorithms have been designed to prevent numeric overflow errors and yield unsurpassed accuracy. Microstat's price is \$375.00 including the user's manual and is available for the Z80, 8086, 8088 CPU's and CP/M80, CP/M86, MS-DOS, and PC-DOS. To order, call or write.





# TAS<sup>TM</sup>

## the "Hard-nosed" Relational Database

# \$122.

## the Database + Integrated Accounting

# \$349.

### If You Liked DBase III, You'll Flip Over TAS<sup>TM</sup>

Hard-nosed business owners have been asking for the power of DBase III<sup>TM</sup> and RBase 5000<sup>TM</sup> but without the high price. That's why Business Tools, Inc. created TAS<sup>TM</sup>.

Compare TAS with DBase III and RBase 5000. You'll see why we think TAS is the best "Hard-nosed" value around. TAS includes a data dictionary. TAS includes a true procedural language. TAS includes a run-time compiler. Plus TAS can be upgraded to multi-user for \$100.

TAS lets you develop your own professional menu-driven business applications. And not just simple ones either. TAS applications can hold up to 17 million records. And because TAS compiles them, they run fast.

### Get TAS Accounting Software for \$349

But why stop with just a database? For just \$349, you get TAS Relational Database/Language plus General Ledger, Accounts Receivable and Accounts Payable. And for \$499 you get all the above plus Inventory, Sales Order Entry, Purchase Order Entry, and Payroll.

Source code is included FREE! So you can even modify the accounting to fit your business.

	TAS <sup>TM</sup>	DBase III	RBase 5000
Multi-User	\$100	No	\$1400
Data Dictionary	Yes	No	Yes
Procedural Language	Yes	Yes	Yes
Compiler	Yes	No	Yes
Records Per File	Unlimited	Unlimited	Unlimited
Files Open	16	10	40
Fields Per File	Unlimited	128	400
File Size	Unlimited	Unlimited	Unlimited
Record Size	10,254	4,000	1,530
Field Size	254	254	1,530
Prices	\$199	\$696	\$700

And TAS is no new comer. TAS was written by Phil Mickelson, the same "Hard-nosed" business person who created The Sensible Solution<sup>TM</sup> (relational database) in 1982.

TAS comes with a 30 day money back guarantee (less handling fee of \$15 Level 1, \$30 Level 2, \$45 Level 3 and \$10 Multi-User). TAS is available for the IBM PC/XT/AT<sup>TM</sup>, Compaq<sup>TM</sup>, AT&T 6300<sup>TM</sup>, Tandy 1000, 1200, 2000<sup>TM</sup> and most MS-DOS<sup>TM</sup>, CP/M<sup>TM</sup> and MP/M<sup>TM</sup> systems. Multi-user and LAN versions also available.

**Call Today 1-800-648-6258**  
**Ask for operator 44**

Call our Toll-Free Hotline. Use your VISA or MasterCard to order today. Outside Washington call 1-800-648-6258. Washington residents call 1-206-644-2015.

**Dealer Inquiries Welcome.**



4038-B 128th Ave. SE  
Suite 266  
Bellevue, WA 98006

The following are registered trademarks of these companies: TAS, Accounting Solution, Business Tools Inc; RBase 5000, Microm Inc; DBase III, Ashton-Tate Inc; CP/M and MP/M, Digital Research Inc; IBM PC/XT/AT, International Business Machines Corp; Compaq, Compaq Computer Corp; AT&T 6300, AT&T Information Systems Inc; Tandy 1000, 1200, 2000, Tandy Corp; MS-DOS, Microsoft Corp; The Sensible Solution trademark rights are claimed by O'Hanlon Computer Systems Inc.

© Copyright 1985 Business Tools Inc.

CIRCLE NO. 145 ON READER SERVICE CARD

## TAS<sup>TM</sup>

**"Affordable Software For Your Business Needs"**

NOT COPY-PROTECTED

**Describe your computer system:**

☐ 8 bit                      ☐ 16 bit

CP/M, MP/M                      MS-DOS

TurboDOS                      PC-DOS

**Disk size is:**

☐ 5 1/4"    ☐ 8"

**Computer name/model is:** \_\_\_\_\_

**Name:** \_\_\_\_\_

**Street:** \_\_\_\_\_

**City:** \_\_\_\_\_ **Zip:** \_\_\_\_\_

**State:** \_\_\_\_\_ **Phone:** \_\_\_\_\_

4038-B 128th Ave. SE  
Suite 266  
Bellevue, WA 98006

**Quantity:**

\_\_\_ TAS Database/Language—\$199

\_\_\_ Level 2 Accounting (TAS, GL, AR, AP)—\$349

\_\_\_ Level 3 Accounting (Level 2, SO, PO, INV, PAY)—\$499

\_\_\_ Multi-user upgrade—\$100

**Subtotal (WA add 7.8% tax)** \_\_\_\_\_

**Shipping (USA—\$5.00 ea.)** \_\_\_\_\_

(Foreign—\$20.00 ea.) \_\_\_\_\_

**Total Enclosed:** \_\_\_\_\_

**Payment:** ☐ VISA ☐ MC ☐ Cashier's Check  
(All amounts are payable in U.S. funds only.)

**Credit Card Expiration Date:** \_\_\_\_\_


**Card Number:** \_\_\_\_\_

**Name on card:** \_\_\_\_\_

**Signature:** \_\_\_\_\_









# SOME THINGS CAN NEVER BE SHARED. OTHER THINGS SHOULD BE.

The people who make database software have some strange logic. They tell you information is the most valuable thing in the world. And then they design their products for single-user systems. Which means that every time different people actually need to use your data, they have to stand in line for it.

## INTRODUCING R:BASE™ 5000 MULTI-USER.

At Microrim, we have a much better idea of the way offices work. So we've developed a multi-user version of R:base 5000 that lets users update their database while other people analyze it. And we've made this new version fully compatible with our single-user version. Which means any application you develop on the single-user version today can be run on our multi-user version tomorrow.

## DATAPRO RANKS R:BASE 5000 #1.

Of course, we gave the multi-user version all the features that convinced the Datapro Research Corporation to rate our single-user version as the best DBMS on the market. But we've also designed it to make optimum use of all the extra capabilities offered by the IBM PC Network (IBM PC DOS 3.1). To optimize data sharing, R:base 5000 Multi-User takes full advantage of the front end processing power of the PC. As

a result, multiple users will be able to work with the same database at the same time.


While editing, data integrity is protected by a locking mechanism that operates at the item level. This important feature lets the other users work with columns and rows of the same table. Instead of making them wait around for the other guy to finish his editing job.

## SEE FOR YOURSELF: 1-800-547-4000.

The full price is \$1500, complete with three sets of documentation. But if you believe in common sense as much as we do, you won't make a decision this big till you get your hands on a copy and see for yourself. And that's just what we'd like you to do. For only \$50, we'll send you a copy of the program that has all the features, one set of documentation, and all the functionality of the full product, except for limitations on the numbers of rows, columns and tables.

Just call 1-800-547-4000 and ask for Dept. 000. From Oregon, or outside the U.S., call 1-503-684-3000, Dept. XXX. Or head straight for a leading software store or computer dealer.

And see how nice it is to take advantage of information. Instead of taking turns at it.



# R:BASE 5000 MULTI-USER FROM MICRORIM

IT ALL COMES DOWN TO COMMON SENSE.



# "I Program In BetterBASIC And I Recommend It"

"Lifeboat Associates," has expanded its philosophy of endorsing structured programming languages to include a truly superior product—BetterBASIC. More than just a BASIC, BetterBASIC offers use of the full memory of the computer, true procedures and functions, modularity and more. BetterBASIC has the advantages of the C language on which Lifeboat built its reputation and appeals to the wide audience of programmers who already program in BASIC. I liked BetterBASIC so much, I decided "Lifeboat" should publish it. I program in BetterBASIC and I recommend it."

Dr. Edward Currie, President—Lifeboat Assoc.—New York, NY

## ACCESS FULL MEMORY—

BetterBASIC accesses the full memory of the computer enabling you to overcome Microsoft's 64K barrier.

## INTERACTIVE

**COMPILER**—BetterBASIC compiles to an intermediate code giving you five to six times the speed of traditional BASICs. There is immediate feedback on line entry.

**COMPATIBLE**—Version 2.0 of BetterBASIC is GW-BASIC, PC-BASICA compatible when running on IBM

PCs. BetterBASIC is easy to learn because the syntax is the same.

**STRUCTURE**—Create well-organized programs using procedures and functions that are easily identified and understood.

**NOT COPY PROTECTED**—Install BetterBASIC on your hard disk. BetterBASIC is licensed to the programmer, so you can compute at work and at home using the same copy of BetterBASIC.

**USER DEFINED KEYWORDS**—The BetterBASIC language can be extended by adding your own procedures and functions to the language as keywords.

**RUNTIME SYSTEM**—Creates stand-alone EXE. files. Developers can distribute their programs written in BetterBASIC without royalties.



**SAMPLE DISK**—Contains a tutorial, a demo, and allows you to use an abbreviated form of BetterBASIC. It also contains a 60 page on-line mini manual.

**AND MORE**—Such as DOS and BIOS ROM calls, Chaining, Overlays, Local and Global Variables, Recursion—Graphics and Windows—You can define up to five windows.

Optional 8087/80287 Math Chip Support.

**LIBRARIES**—Write reusable code.

**TECHNICAL SUPPORT**—

Available to all registered users.

**BetterBASIC** Runs on IBM PC, XT, AT and all IBM-compatibles. Ask your local dealer for BetterBASIC or call **1-800-225-5800**.

In Canada call 416-469-5244. Also available for the Tandy 1000, 1200 and 3000 at Tandy/Radio Shack stores.

## PRICES:

Better BASIC	\$199
8087/80287 Math Module	\$99
Runtime System	\$250
Sample Disk with Tutorial	\$10

*Better*  
**BASIC.**

**Because It's The Best.**

CIRCLE NO. 195 ON READER SERVICE CARD

**Summit Software Technology, Inc.™**

106 Access Road, Norwood, MA 02062

MasterCard, Visa, Checks, Money Order, C.O.D. accepted and P.O. on approval.

BetterBASIC is a registered trademark of Summit Software Technology Inc.

IBM PC, XT, AT, are registered trademarks of International Business Machines Corp. Tandy is a registered trademark of Tandy Corp.

(If you're using BetterBASIC and would like to be featured in one of our ads, please write to the Director of Advertising at Summit.)



# Filters and Finite Machines

*UNIX-borrowed programming concepts help the DOS user find answers to otherwise complicated problems.*

**F**ilters and finite machines are time-tested programming concepts. The former comes from the UNIX environment, the latter forms the core of compilers and many other big programs. Together, they provide some useful ways to think about programming.

Consider the author writing a book. He decides to break each chapter into its own file; this resolves many difficulties but creates a new one. The author needs a simple way to count the words he has produced. Publishers use such data to enforce word limits and gauge an author's progress. If the author knows how many total characters are in the file, dividing by 6 produces a very good approximation of the number of words. This, however, is where the problem arises. The DOS DIR command gives character counts for individual files but not for groups of files. DIR's output must be sent to a utility that will sum the file size column.

In DOS 1.0 and 1.1, no easy way existed to place the output of system commands (such as DIR) into a file. The designers of DOS 2.0 and 2.1, however, borrowed from UNIX the concept of pipes and filters. A *pipe* is a convention that allows several programs to share an I/O stream; a *filter* is a program designed to perform I/O through pipes. Pipes and filters provide the solution to the problem.

The author must use a SORT program on the data output by DIR. SORT is a filter the author can maintain separately to perform sorting on any other project. (The SORT discussed here is included with DOS 2.x.) But how does SORT know where the input comes from and where it is going? In DOS 1.0, sending data to and from a disk file looks different than sending it back and forth to the asynchronous card and so on; each interface is different. DOS 2.0, however, uses one interface and two special pipe files: *standard input* and *standard output*. The user tells DOS

which kind of I/O these standard files represent by the way he types a command. Because DOS makes all sources look the same, SORT is relieved of the recognition responsibility.

The standard input file is a stream of characters that could have originated from the keyboard, a disk file, the asynchronous card, or the output of a previous program. Standard output can be sent to the screen, a disk file, the asynchronous card, the printer, or the standard input of the next program.

## FILTERING

To produce a DIR listing sorted by file name, the author types DIR RRET\*. \* | SORT (figure 1). When the DOS 2.x DIR command executes, it places the output into standard output. Also, DOS sees the | (vertical bar), which indicates that DIR's standard output will become standard input for the next program. SORT, ignorant of what the input actually is, simply divides the character stream into records in the usual way and sorts them in ascending sequence. It sends the sorted version into standard output. Because the command does not contain another vertical bar or indication of where the SORT output should go, DOS assigns it to default: the screen.

To capture that output to a file, the author could type DIR RRET\*. \* | SORT

> A:DISK.FIL. DOS interprets the > character as a request to *redirect* the output of SORT into the diskette file A:DISK.FIL instead of onto the screen. DIR RRET\*. \* > LPT1: sends the output of the regular DIR command to the printer. If the user typed DIR RRET\*. \* > A:MYDIR.FIL to save the current directory values, he could later sort that data by typing SORT < A:MYDIR.FIL. The result would appear, in sorted order, on the screen. The < character tells DOS to use A:MYDIR.FIL, instead of the keyboard, for standard input. Typing SORT < A:MYDIR.FIL > LPT1: sends the same output to the printer.

In a formal UNIX sense, the vertical bar character represents piping: sending standard output from one program as standard input to the other. The < and > functions indicate redirection: character streams are received from or sent to a location other than the DOS defaults (the keyboard and screen respectively). The UNIX nomenclature is used, but the UNIX function and the DOS function are different. In the DOS environment, an underlying unity exists between a piped file and a redirected file.

Writing filters can be easy. In BASIC, for example, the programmer would employ regular INPUT and PRINT statements, which use standard input and output. Thus, any program





ILLUSTRATION • MACIEK ALBRECHT



# FASTCARD IV

## TWO MEGABYTES FOR YOUR PC—AND MORE!



The power of the Lotus® Expanded Memory Specification is now available in an intelligent, multifunction expansion board—THESYS' FASTCARD IV™.

FASTCARD IV's Intelligent Memory System (IMS) makes it possible for IBM® PC and XT users to enjoy the benefits of up to two megabytes of expanded memory with *all* the software in their libraries—not just programs written especially for expanded memory.

THESYS' IMS features include:

- **Disk Enhancement**—Frequently accessed disk information is stored in system RAM or expanded memory where it may be rapidly retrieved.
- **Printer Enhancement**—IMS allocates memory to serve as a holding area for information waiting to be printed.
- **Automatic Memory Allocation**—IMS monitors the computer's operations and allocates the system and expanded memory as needed for disk enhancement, printer enhancement, or other applications.

In addition, FASTCARD IV offers Data Security features vital to PC users:

- **Custom Password Security** enables the user to define a password that must be entered *before the computer will boot*.
- **Built-in Diagnostics and Auto Fault Tolerance** identify faulty memory and bypass it until it can be replaced.

FASTCARD IV is Multifunction, featuring:

- **Serial and Parallel Ports and Game Port Interface**
- **Battery-Powered Clock/Calendar**
- **Easy-to-use Installation Software.**



For ordering information, contact:  
THESYS Memory Products Corporation  
7345 East Acoma Drive  
Scottsdale, AZ 85260  
(800)-327-8345  
(602)-991-7356



**FIGURE 1: Sample DIR Listing**

```
C>dir b:rret.* | sort
```

25 File(s)		29696 bytes free	
Directory of B:\			
Volume in drive B is BOOK #1			
RRET1	EWf	17408	6-06-85 4:39p
RRET10	EWf	4864	6-08-85 10:40p
RRET11	EWf	8448	6-06-85 9:31p
RRET12	EWf	10368	6-06-85 9:42p
RRET13	EWf	10496	6-06-85 9:51p
RRET14	EWf	11392	6-06-85 10:13p
RRET15	EWf	18688	6-08-85 10:36p
RRET16	EWf	13312	6-06-85 7:18p
RRET17	EWf	8576	6-06-85 7:27p
RRET18	EWf	9472	6-06-85 8:12p
RRET19	EWf	12032	6-06-85 8:25p
RRET2	EWf	13696	6-08-85 9:21p
RRET20	EWf	18304	6-11-85 6:41a
RRET21	EWf	5632	6-11-85 10:15p
RRET22	EWf	11008	6-14-85 10:12a
RRET23	EWf	4224	6-20-85 9:02p
RRET24	EWf	6528	6-20-85 11:33p
RRET3	EWf	12032	6-08-85 9:37p
RRET4	EWf	8832	6-06-85 5:35p
RRET5	EWf	16768	6-08-85 10:02p
RRET5A	EWf	16768	6-08-85 10:23p
RRET6	EWf	17920	6-08-85 2:05p
RRET7	EWf	16640	6-08-85 3:30p
RRET8	EWf	15744	6-08-85 3:26p
RRET9	EWf	15616	6-06-85 9:24p

C>

The listing above is output from a filter. It first arranges the characters in the standard input stream into records, then sorts them, and, finally, deposits them in the standard output stream. In this example, the character stream is piped from DIR to SORT.

can be a filter, and its output could be sent to any program that follows it. However, most compilers have trouble with DOS 2.x. Compiler designers continue to use DOS 1.x interfaces to avoid selling and maintaining two different versions. But their customers expect their compilers still to be functional when they buy DOS 2.x. So, DOS 2.x provides all DOS 1.x interfaces. Most compilers, therefore, use the old keyboard and screen interfaces instead of standard input and standard output.

A method is needed to invoke the new standard DOS interfaces. Many languages accept small assembly language programs that would do so; a few, such as Turbo Pascal, can execute DOS interfaces directly. Listing 1, ADDR.EC.PAS, is a Turbo Pascal program that uses the standard I/O of DOS 2.x. The routines are called GETSTDIN and PUTSTDOU. Turbo Pascal's INTR function allows DOS and BIOS interrupt handlers to be reached without assembly language. GETSTDIN gets the next byte of input (or, if none, returns the value 255) and PUTSTDOU puts the next byte into

standard output. These subroutines are used in place of WRITELN and READLN to write the utility.

Conceptually, the filter program can be thought of as a "machine" that processes the input and writes the output, one byte at a time. In this case, assume that the input (a stream of bytes) always looks like the output of the DIR command. No set relationship exists between when an input byte is read and when an output byte is written. SORT reads all the input bytes, manipulates them inside the machine of its storage, and outputs them all at once. Another filter might read a single byte, perform its function, and output a byte before reading the next byte.

### FINITE STATE MACHINES

When the workings of such a filter program machine are made up of many similar machines, it is a *finite state machine* and satisfies these criteria:

- It is a collection of a fixed number of preprogrammed smaller machines called *states*.
- Each state examines one input at a time and expects the input to be one of several particular values.
- The state may (or may not) take a special action based on the input and

its being in that state. After any such action, the state then gives control of the machine to another state.

SORT does not match this model well, but the original problem of summing file sizes does, especially the part that involves parsing the input.

*Parsing*—dividing the input into groups—is very well suited to the finite state machine model. Notice in figure 1 that the output of the DIR command has two kinds of records. The first provides background information—the volume label, bytes free, and so on. The second, which contains the information important to this example, consists of a file name (in the first eight spaces), then a few spaces, the file extension, a few more spaces, then the size of the file (the concern of this exercise), more spaces, the creation date, more spaces, and the creation time.

Before the resolution of this problem, consider a simpler example. The finite state machine of figure 2 performs the binary function AND. State number 1 examines the first input. If the input is 1, nothing is output and state 2 gets control. If the input is 0, state 3 gets control. In state 3, whether the next input is 1 or 0 (and it must be read), the output will be 0. In state 2,

## MS-DOS, UNIX, APPLE MAC, CP/M, NETWORKS and MORE. ONE c-tree ISAM DOES THEM ALL!

The creator of Access Manager™ brings you the most powerful C source code, B+ Tree file handler: **c-tree™**

- multi-key ISAM and low-level B+ Tree routines
- complete C source code written to K&R standards
- single-user, network and multi-tasking capabilities
- fixed and variable record length data files
- virtually opened files accommodate limited file descriptors
- no royalties on application programs

### \$395 COMPLETE

Specify diskette format:

- 5¼" MS-DOS
- 8" CP/M
- 3½" Mac
- 8" RT-II



For VISA, MC and COD orders call (314) 445-6833


FairCom  
2606 Johnson Drive  
Columbia, MO 65203

© 1985 FairCom

The following are trademarks: c-tree and the circular disk logo—FairCom; MS—Microsoft Inc.; CP/M and Access Manager—Digital Research Inc.; Unix—AT&T; Apple—Apple Computer Co.



# THE MASTER DIRECTORY OF PRODUCTS FOR YOUR PC, PCXT and PCjr!



From the publisher of PC, PCjr., PC TECH JOURNAL and PC WEEK. Nearly 400 pages with listings for over 5,000 products and 2,000 vendors, services, and support systems, assembled into one comprehensive and easy-to-use guide. PC BUYERS GUIDE is the quickest and most reliable way to locate exactly what you need to expand the usefulness of your IBM or compatible PC. Because it's published in February, May, August and November, you'll receive the most current information and product listings available anywhere! Find out the level of skill you'll require to get maximum performance, and a full accurate description of each peripheral, software package and:

- Accessories
- Consultants
- Literature
- Professional Societies
- User Groups
- Computer Camps
- Insurance Services
- AND MUCH MORE!

Mail the enclosed coupon today for your copy of PC BUYERS GUIDE!

**Phone TOLL FREE 9 am-5 pm EST:**  
**1-800-526-0790**  
**(In NJ only 1-201-540-0445)**

Also available at your local newsstand and computer store.

## PC BUYERS GUIDE

CN 1914, Morristown, NJ 07960

Please send me the latest edition of PC BUYERS GUIDE. Enclosed is \$9.50 (\$7.95\* plus \$1.55 postage and handling). Outside USA \$11. US funds only. \*Residents of CA, CO, CT, DC, FL, IL, MA, MI, MO, NJ and NY State add applicable sales tax.

### Charge my:

☐ AmEx ☐ Visa ☐ MasterCard

Card No. \_\_\_\_\_

Exp. Date \_\_\_\_\_

Mr./Mrs./Ms. \_\_\_\_\_  
please print full name


Address \_\_\_\_\_

City \_\_\_\_\_

State/Zip \_\_\_\_\_

AN37

**FIGURE 2:** Simple Finite State Machine



The binary function AND is represented above as a finite state machine. The arrows represent possible paths from start (state 1) to finish (state 4).

the output is the same as the input, 1 or 0, respectively. Notice that after the second input, all states go to state 4, the only state that does not ask for input. This final state indicates that the machine has stopped. The lower section of figure 2 charts the machine's handling of the sample input string of 1, 0.

The machine for the directory problem is more complex (see figure 3). The first concern is simply graphical—a diagram that explains a parsing operation can become cluttered if keys are not used. Various groups of input are acceptable in parsing. Instead of an arc for each group, it is better to have one arc that represents all of the groups and to key it as such. In addition, the action does not always entail outputting a byte to the standard output. That, too, must be described. The key for this example, located at the bottom of figure 3, describes the actions for each state. Only states 6, 7, and 8 have a special action; the others simply go on to the next state. In some cases, the next state is the same state; this is used to con-


sume unimportant input or for other looping operations.

State 1 has three jobs. Besides detecting end of input, it divides records into two types: those that contain file names and sizes (the target records in this example) and those that contain background information. All records of the second sort begin with a space character. When state 1 detects an initial space character, it enters state 2. State 2 reads in the rest of the characters in the record and puts the machine back into state 1 when a new record begins. States 3, 4, and 5 consume the file name and file type. State 6 absorbs leading spaces, leaving the file size column for state 7; these states read in the number from the record and convert it from a string of characters (which are numbers) to a floating-point number that can be totaled. When the string of numbers in the record ends, the machine goes back to state 2, which consumes the remainder of the record.

A finite state machine can be coded in various ways. Many have elaborate




**FIGURE 3:** Example Finite State Machine



STATE	SPECIAL ACTION
6	Initialize grand total to input
7	If input is number, multiply grand total by 10 and add input to grand total
8	Halt. Print out result onto standard output.
LEGEND	INDICATES
a	Any letter upper- or lowercase. Any character, punctuation, etc., not described below.
5	Any number 0-9.
!	Carriage return or line feed character.
@	Space character (ASCII 32).
EOI	End of input.


This diagram shows how to use a finite state machine to sum the sizes of all files in a directory. This machine reads characters from the input stream. Input characters can be either letters, numbers, or control codes.

## LOOKING FOR AT PERFORMANCE FROM YOUR PC?



**EARTH HAS IT FOR  
LESS THAN \$1,000!**

**YOUR SEARCH IS OVER!!** EARTH COMPUTERS' exciting new high-speed, 80286 accelerator card, **TurboACCEL-286™**, is just what you've been looking for. The **TurboACCEL-286** will boost your PC performance up to **Five times...** its completely software transparent...and its only **\$995!** **TurboACCEL-286** will function with most operating systems and application programs (unlike other so-called accelerator boards).



The **TurboACCEL-286** features a high-speed, 8MHz, 80286 processor, 512Kbytes of RAM (expandable to 1Mbytes), a switch for 8088 operation, and facilities for an 80287 math coprocessor. It occupies one expansion slot, is completely compatible with most PCs and is software transparent. End your search for AT performance. Order the **TurboACCEL-286** today! Call or write:



**EARTH COMPUTERS**

P.O. Box 8067, Fountain Valley, CA 92728  
TELEX: 910 997 6120 EARTH FV

**(714) 964-5784**

Ask about EARTH COMPUTERS' other fine PC and S-100 compatible products.



tables and very little code. For this example, each state was coded as an individual case block in a case statement (except the final state, which is simply the end of the program). Compare the code in listing 1 with figure 3. The routine GETSTDY calls GETSTDIN, but also returns the particular character seen and its type. Another routine, OUTANS, converts a string of numbers to characters. While WRITELN easily could have been used for the final output, OUTANS and PUTSTDOUT are more complete. Finally, the program assumes well-formed input. If ADDREC is sent something other than DIR output, it will produce meaningless results (but it will terminate).

ADDREC requires file extensions. If state 4 encounters no extension, it absorbs all spaces before the file size column. State 5 consumes this number, leaving state 7 at the date column. To avoid this, modify the program so it ignores the first 11 characters then absorbs spaces until the file size column is reached. In finite machine language, replace states 3 through 5 with 11 states that absorb a character and increment the state variable. In the ADDREC.PAS listing, replace cases 3, 4, and 5 with 3...13:state:=state+1;. Former states 6

**FIGURE 4: ADDREC.PAS**

```
C>dir b:\ret*. * | a:addrac
0304768
C>dir b:*. * | find /v"RRET"

Volume in drive B is NOVEL #1
Directory of B:\

FILTER  EWF  14720  6-22-85  5:58p
FILTER1  EWF  1536  6-22-85  5:37p
FILTER2  EWF  1664  6-22-85  5:44p
      28 File(s)      24576 bytes free

C>dir b:*. * | find /v"RRET" | a:addrac

0017920
C>
```

Wild-card specifiers and search strings can be used to specify any group of files when DIR output is filtered through FIND and ADDREC.

and 7 become states 14 and 15, respectively, in the new program.

This ADDREC modification corrects a subtle bug: ADDREC can choke on the standard input and standard output temporary files when it operates in a root directory. The temporary files have zero length but lack file name exten-

sions, so the original ADDREC reports an incorrect total file size.

Finite state machines also offer an additional benefit: a good documentation of their design. For this program, the finite state machine diagram aids debugging far more than a flowchart, and to some extent, more even than the code itself. Figure 4 shows some sample runs of ADDREC. The last run is the most complex; it executes a DIR, then uses the DOS-provided FIND filter to eliminate all records matching the string, then invokes the sample filter, ADDREC. In this last case, ADDREC gets the total of all files that are not part of the author's book.

Filters enable the user to create simple building blocks that can be mixed and matched to uncover complex answers without a lot of coding. The finite state machine provides a good way to design and document individual filters needed to solve many problems. Together they can help the user avoid long searches through the inner workings of DOS.

*Larry W. Loen has had a variety of assignments in software development during his 11-year career in the field. He is currently a manager of systems programmers.*

## THE BEST PC TEXT EDITOR JUST GOT BETTER.

### ANNOUNCING SPF/PC™ 1.82

The best full screen editor for the IBM PC now extends support for large files to all PC's, not just the IBM/AT. Invoke your favorite program/compiler from within Edit at any time regardless of file size. CTC's SPF/PC™ 1.82 still looks like its mainframe cousin but executes faster with more options.

#### NEW FEATURES

- **PAGING** - Editing limited only by capacity of expanded/extended memory or hard disk.
- **SPEED** - Search 1,500,000 byte file with IBM AT in less than 13 seconds. By comparison, the IBM 3081 mainframe takes 48 seconds.

**\$195**

UPGRADES only \$50  
ADD \$6 shipping  
Canada \$10, Foreign \$15



Payment in U.S. funds by check or bank wire (Bank of America, San Francisco account 05583-05454).  
Net 30 to D&B rated firms.

- Compatible with IBM and Novell Networks
- Modifiable HEX display
- Line length to 954 bytes

Minimum Requirements:  
DOS 2.00-3.10, 192KB memory,  
any IBM PC or true compatible  
or TI Professional.



**Command Technology Corporation**  
1900 Mountain Boulevard  
Oakland, California 94611

TO ORDER Telephone: (415) 339-3530  
SPF/PC..... Telex: 509330 COMMAND TECH



# Program faster, debug faster.

**NEW!**

SOURCE PRINT Utility outlines your program structure nesting...indents by nesting level...prints key words in bold face...adds a table of contents to your listings...paginates...extracts routines by name, from one or more files. SOURCE PRINT creates new files from selected routines. And can automatically re-indent your source files...index/cross-reference list.

- Simple one-line commands
- For Pascal, C, BASIC, Modula-2, dBASE II, III, III+
- For IBM PC, XT, AT, all compatibles. DOS 2.xx, 3.xx, ≥128K

All for **\$97.00**

## Source Print

Structured Formatting Utility

Call now for technical brochure!  
or to order.

Outside CA: 800-257-5773

Inside CA: 800-257-5774

(415) 283-7084

CIRCLE NO. 109 ON READER SERVICE CARD

Immediate delivery  
from

**Aldebaran**  
Laboratories Inc.

Developers of High-Speed Professional Software

3738 Mt. Diablo Blvd., #312

Lafayette, CA 94549

(415) 283-7101

dBASE, dBASE II, and dBASE III are  
trademarks of Ashton Tate.

Pascal

12-15-85 14:46:04 a:shell.pas Shell Sort  
Mon 12-16-85 14:54:25

```
1 procedure shellsort; (* <s> Shell Sort *)
2 label 1;
3 var ind1, ind2, hint, vect: integer;
4
5 begin
6   hint := 1;
7   repeat
8     hint := 3 * hint - 1
9   until hint > STEPS;
10  repeat
11    hint := hint div 3;
12    for ind1 := hint - 1 to STEPS do
13      begin
14        vect := array[ind1];
15        while array[ind2-hint] > vect do
16          begin
17            array[ind2]:=array[ind2-hint];
18            ind2 := ind2 - hint;
19            if ind2 <= hint then
20              goto 1;
21          end;
22          i: array[ind2] := vect
23        end;
24      until hint = 1
25    end;
26 end;
```

Wed 12-11-85 04:10:20	1	CONTENTS	Page	Line
12-11-85 04:06:32 c1.c	MAIN EXECUTIVE	1	1	
12-11-85 04:06:32 c1.c	control variables	1	46	
12-11-85 04:06:32 c1.c	graphics variables	2	74	
12-11-85 04:06:32 c1.c	Processing routines	6	266	
12-11-85 04:06:32 c1.c	initials initialize after parsing	14	691	
12-11-85 04:06:32 c1.c	File Handling	16	800	
12-11-85 04:06:32 c1.c	control loop over files	16	803	
12-11-85 04:06:32 c1.c	chexaw check extract flag	22	1142	
12-11-85 04:06:32 c1.c	inpline	24	1247	
12-11-85 04:06:32 c1.c		37	1966	

12-11-85 04:08:26 c2.c	Language Recognition Module	38	1
12-11-85 04:08:26 c2.c	external variables	38	21
12-11-85 04:08:26 c2.c	internal static variables	38	52
12-11-85 04:08:26 c2.c	Parsing Routines	40	129
12-11-85 04:08:26 c2.c	proclini executes the parsers	40	130
12-11-85 04:08:26 c2.c	pparse - Parser for C	41	170
12-11-85 04:08:26 c2.c	pparse - Parser for Pascal	43	294
12-11-85 04:08:26 c2.c	bparse - Parser for BASIC	47	512
12-11-85 04:08:26 c2.c	dparse - Parser for dBASE	50	685
12-11-85 04:08:26 c2.c	Table Access Routines	52	807
12-11-85 04:08:26 c2.c	dcdbold probe hash table	52	809

12-15-85 14:44:42 a:shell.bas Shell Sort  
Mon 12-16-85 14:52:05

```
10 REM ***** <s> Shell Sort *****
20 H = 1
30 H = 3 * H - 1
40 IF H <= N THEN GOTO 30
50 H = INT(H / 3)
60 FOR I = H + 1 TO N
70   V = A(I) : J = I
80   WHILE A(J - H) > V
90     A(J) = A(J - H)
100    J = J - H
110    IF J <= H THEN GOTO 130
120  END
130 A(J) = V
140 NEXT I
150 IF H <> 1 THEN GOTO 50
```

BASIC





# LISTING 1: ADDREC.PAS

```
PROGRAM addrec;

( Prints total number of bytes contained in group of files. Pipe
  directory to addrec with "A>dir | addrec". The declared types
  are all involved in the get/put of the standard input and output. )

TYPE
  regpack = record
    ax,bx,cx,dx,bp,si,di,ds,es,flg : integer
  end ;
  ary = byte;
  xpt = record
    case integer of
      1: (ptx : ^ary) ;
      2: (qq,rr : integer)
    end;
  end;

VAR
  register : regpack;
  xx : ary;
  here : xpt;
  ip,itype : byte;      ( value and type of the input character )
  state : integer ;     ( Keeps track of the current state number )
  tot,gtot : real;      ( Used to add up the actual answer )

( Input and Output procedures follow. Interface to standard I/O included. )

procedure putstdout(wr: byte);

( Procedure to put the next byte of Standard Output out to
  MS DOS 2.x Standard Output file. )

begin
  here.ptx := addr(xx);
  xx := wr;
  register.ds := here.rr;
  register.dx := here.qq;
```

```
  register.cx := 1;
  register.bx := 1;
  register.ax := $4000;
  intr($21,register);
end;

procedure outans(gtot: real);
(
  This procedure puts out the answer. Each power of 10
  starting with a million is subtracted from the passed value
  and then put out. The last digit, the 1's position, has a little
  adjustment because of floating point rounding errors which may
  accrue.
)
VAR digit : byte;
    decnum : real;
begin
  ( Write the answer to the Standard Output device. )
  decnum := 1000000.0 ; gtot:=gtot+ 0.5;
  while decnum >= 1.0 do
    begin
      digit:= ord('0');
      while gtot> decnum do
        begin
          digit := digit+1 ; gtot:=gtot- decnum
        end;
      putstdout(digit); decnum:=decnum/10.0
    end;
  end;

procedure getstdin(var ip: byte);
(
  Procedure to get next byte of input from DOS 2.0, 2.1
  Standard Input file. This filter uses only ascii characters
  (maximum decimal value 127) so 255 was chosen as the
  end-of-input flag.
)
)
```

## TURBO MATRIX

Don't Be Stopped by the 64K Static Data Limit  
Imposed by Turbo Pascal\*

### USE ALL 640K BYTES OF MEMORY IN YOUR PC FOR MATRIX OPERATIONS

Turbo Matrix provides techniques for creating large arrays at run time and for recovering that memory for other uses when the arrays are no longer needed. Arrays can have up to 8192 rows and up to 4096 columns of real numbers or 16384 columns of integers.

- Procedures included in the package:
  - Scalar and matrix multiplication - matrix addition.
  - Transpose inverse and determinant of a matrix.
  - Copy all or part of a matrix.
  - Read or write a matrix
  - Solution to linear equations.
- Notation is easy to use and easy to retrofit into existing programs using the Turbo Pascal\* editor.
- Structure can be generalized to other types of large arrays - an example of handling large string arrays is included.

Carefully documented source code  
for IBM PC/XT/AT\* and compatibles

**\$9900**

MC and Visa Accepted.

In Texas Add Sales Tax



**InterLink Systems, Inc.**

4189 Bellaire Blvd., Suite 256  
Houston, Texas 77025

**(713)664-6861**


\*Turbo Pascal is a trademark of Borland International. IBM PC XT and AT are trademarks of International Business Machines, Inc.

## nine track tape users Micro to Mainframe Connection

The Model TC-50 1/2-inch tape subsystem provides a standard medium for transmission of mainframe data base information to PC users, while maintaining mainframe isolation and data integrity. Use ODI subsystems to import data to data base programs like dBase III.

The TC-50 subsystem also provides fast back-up capability as well as a device driver and interface software for popular compilers.


The TC-50 subsystem includes tape drive controller, cables and documentation. All ODI products carry a 30 day unconditional money-back guarantee, and are warranted for one year, parts and labor.



**Overland Data, Inc.**

5644 Kearny Mesa Road  
San Diego, CA 92111  
Tel. (619) 571-5555  
Telex 754923 OVERLAND

Also Available —  
XENIX tape  
subsystems  
for the  
IBM AT





# LINKS FASTER THAN YOU CAN READ THIS AD


New GeneLink™ is up  
to 20 times as fast as other  
linker/locators. Enough said.\*

\*Time's up, but we  
could use a few extra seconds  
to tell you it provides a new  
level of debugging information  
for GeneScope™, our true source  
level debugger. Plus intermod-  
ule type checking and cross  
referencing. Supports overlays  
and unlimited program sizes  
too. Call us.

(415) 964-9001



**Genesis™**  
Microsystems



196 Castro Street  
Mountain View, CA 94901

CIRCLE NO. 113 ON READER SERVICE CARD

INTERNATIONAL DISTRIBUTORS • Germany—München: Instrumatic, Tel: 089/85 802-0 • Spain—Madrid: Instrumatic, Tel: 1/455 81 12 • Switzerland—Zurich: Instrumatic, Tel: 1/723 14 10—  
Geneva: Instrumatic, Tel: 022/36 08 30 • United Kingdom—High Wycombe: Instrumatic, Tel: 0494 450 336 • Italy—Milano: Winline, Tel: (2)984 7616  
Australia—Oakleigh: Datic Digital Systems, Tel: 03 568 6922



```

begin
  here.ptx := addr(xx);
  register.ds := here.rr;
  register.dx := here.qq;
  register.cx := 1;
  register.bx := 0;
  register.ax := $3F00;
  intr($21,register);
  if register.ax = 0 then ip:= 255;
  if register.ax <>0 then ip:= xx;
end;

procedure getstdty(var ip,itype: byte);
(
  Procedure to get the next byte from DOS 2.0 file
  Standard Input AND find out what "itype" it is to simplify
  the finite state machine's logic.
)
var iq : byte;
begin
  getstdin(iq);
  ip := iq;
  itype := 0;
  if ip= 32 then itype := ord('a');
  if (ip= ord('A')) and (ip<= ord('Z')) then itype := ord('a');
  if (ip= ord('0')) and (ip<= ord('9')) then itype := ord('5');
  if ip = 255 then itype := 255;
  if (ip= 13) or (ip=10) then itype:=ord('');
  if itype = 0 then itype := ord('a');
end;

begin
  ( Here's where the main program begins. We start in "state 0" by
  initializing a few variables. Grand total is the final answer.
  Total is set for each record. Start with grand total as zero.
  The first real state is state number 1, so set STATE = 1 )

```

```

gtot := 0;
itype :=0;
state := 1;

( This loop executes the finite state machine. When the standard
input file is empty, exit. )

while itype<> 255 do
begin
  getstdty(ip,itype); ( Always get the input )

  case state of ( Which state were we last in? )

    1: begin ( State Number 1 )
        if itype = ord('a') then state :=2;
        if itype = ord('5') then state :=3;
        if itype =ord('a') then state := 3;
        (if itype = 255, then handle by falling through WHILE loop )
        (if itype = ord(''), then state still = 1)
        end;

    2: begin ( State Number 2 )
        if itype = ord('') then state := 1;
        ( else state still 2 )
        end;

    3: begin ( State Number 3 )
        if itype = ord('a') then state := 4;
        (else state still equals 3 )
        end;

    4: begin ( State Number 4 )
        if itype = ord('a') then state :=5;
        if itype = ord('5') then state := 5;
        end;

    5: begin ( State Number 5 )
        if itype = ord('a') then state := 6;
        end;

    6: begin ( State Number 6 )
        if itype = ord('5') then
          begin ( State 6 initializes total as a special action )
            state := 7; ( go to state 7 next )
            tot := ip-ord('0');
          end;
        end;

    7: begin ( State Number 7 )
        if itype = ord('5') then
          begin ( If still a digit, continue conversion in tot )
            tot:= (tot*10) + ip - ord('0');
          end ;
        if itype = ord('a') then
          begin ( If a space, number is converted, add to total)
            state := 2;
            gtot := gtot + tot;
          end;
        end;

    end; ( end case statement )
  end; ( end while statement )

  ( State 8: The terminal state of the machine. )
  ( And, now, at last, put out the answer )

  outans(gtot);
end.

```

**IEEE 488 \$299**  
INCLUDING SOFTWARE



Real Time Devices' GP100 is a full capability GPIB (IEEE 488) interface for the IBM® PC that includes high-speed software for the single quantity price of \$299.

- Over 40 high and low level GPIB commands
- Fast assembly language extensions to BASIC
- DMA and interrupt capability
- Comprehensive tutorial/instruction manual
- No hidden software, cabling, or documentation charges
- Supports up to 15 devices
- FORTRAN, PASCAL, and FORTH extensions available

Even if you're not familiar with GPIB interfacing, the GP100 will have you controlling this powerful bus in no time at all, allowing you to focus on your application requirements.

So if you've been intimidated by the complexity or cost of other GPIB implementations for the IBM PC call on us to help — you'll be pleasantly surprised.

**Real Time Devices, Inc.**





1930 PARK FOREST AVENUE  
P.O. BOX 906  
STATE COLLEGE, PA 16804  
(814) 234-8087

CIRCLE NO. 165 ON READER SERVICE CARD



Why crawl  
when you can  
sprint with  
APPLICATION 1 ?



Assembler speed in IBM Basic and Microsoft "C".  
Mainframe power for your IBM PC.  
Create network applications.\*  
Choice of file or record locking.


Today's programmers want more than development tools and Data Base Managers that merely crawl when they need to sprint. APPLICATION 1's rich assembler routines combined with IBM Basic or Microsoft "C", sprints during the creation and execution mode of your software...and that means up to 6 times faster and more!

Its remarkable efficiency is a result of this unique file system. Achieve unperceivable performance differences from files containing 300 to as many as 80,000 records or more. Design screens in minutes with Genscr, our full screen editor. And most important, APPLICATION 1 opens up the door to file sharing in update mode. Now.

Conserve precious disk space with variable length record and key indexes. With unlimited files, fields, records and 8087/80287 support, APPLICATION 1 has it all.

You can grow with us because we bring no limitation to your imagination and future requirements.

We've prepared a "Demonstration Kit" for Application 1. This includes complete documentation and demo disk. Order yours today for \$49.95 (US) which is refundable on the purchase of the \$595.00 (US) full version. Contact Logiquest at 514-397-9631.



## LOGIQUEST

Logiquest Inc.  
555 Dorchester West, Suite 1616  
Montreal, Quebec, Canada H2Z 1B1  
1-514-397-9631

Required:  
PC DOS 2.1 and up  
PC DOS 3.1 and up for networking  
256k Ram.  
IBM PC, XT, AT, and compatible  
IBM Network Cards presently supported\*

©APPLICATION 1 is a trademark of Logiquest Inc., Montreal. IBM, IBM Basic are products and trademarks of International Business Machines. Microsoft is a trademark of Microsoft Corporation.



# LAN

## Power

...FOR THE PRODUCTIVITY MINDED.

**MDBS III**  
ABSOLUTE POWER

Add real power to your local area network with MDBS III LAN. These features will give you productivity like you've never had before—

- Recovery and transaction logging
- Active and passive locking of records (not just files)
- Formalized structure report writing
- Debugging for the application developer
- 27 host programming languages to call subroutines
- SQL query language
- Forms development tools
- Multiple data structure support—including relational, network and hierarchical
- Unsurpassed speed

The MDBS III LAN is unrivaled. Get its power today. Available for networks from Nestar Systems, Novell, 3Com, and IBM under PC DOS, and from 3Com for Texas Instruments.

**KNOWLEDGE<sup>™</sup>**  
**man/2**  
THE UNIVERSAL KNOWLEDGE MANAGEMENT SYSTEM


Get everyone in your department in on the universal knowledge management system, KnowledgeMan/2.

From data management to spreadsheet to statistical analysis, KnowledgeMan/2 is ready. Share your resources, consolidate your applications, programs, utilities and data with the most advanced integration available. KnowledgeMan/2 LAN allows several users to share a data base and still protect data integrity.

Help your department become more efficient and productive. KnowledgeMan/2 generates the power—LAN distributes it.

KnowledgeMan/2 LAN versions are available for networks made by Novell, 3Com and IBM.

Get the power of LAN with MDBS III, KnowledgeMan/2 or both. MDBS III and KnowledgeMan/2 can even be used together, for phenomenal application development power.



Micro Data Base Systems, Inc. • P.O. Box 248 • Lafayette, IN 47902 • 317/463/2581 • Telex 209147 ISE UR

CIRCLE NO. 207 ON READER SERVICE CARD

KnowledgeMan/2, MDBS III, mdbbs and their respective logos are registered trademarks of Micro Data Base Systems, Inc. 3Com is a registered trademark of 3Com Corp. IBM and PC DOS are trademarks of International Business Machines. MSDOS of Microsoft, Novell of Novell, Inc. ©1985, Micro Data Base Systems, Inc.



# The Total Solution

*Limits must be placed on consultants who intimidate their customers into buying all hardware, software, and peripherals from a single source: the consultant.*

A lawyer in my office wears both a belt and suspenders. He is also one of the most cautious legal planners in the world. In this month's column, I will look at a consultant who had a belt and suspenders, but in the process of applying epoxy for good measure, he took his pants off.

The following is hypothetical (but only slightly so).

A consultant sold \$100,000 worth of equipment and custom software. The documentation of the transaction had the commonplace disclaimers of every type of liability. Shortly after the sale the client received a letter from the consultant saying "your warranty will expire in 90 days and we will be happy to continue to maintain it if you will sign the enclosed agreement and forward the fee." A review of the agreement confirmed that the warranty did expire after 90 days, and the client was convinced that the hardware maintenance fee was money well spent.

The next letter from the consultant suggested that the client, to be really safe, should complete his "total solution" by buying a software maintenance contract as well. This sent the client back to the agreement, which stated:

"We will install the software on the computer equipment...and shall thereafter keep or maintain (the software) in good working order for a period of 90 days from the date of installation...We make no warranties, either express or implied, with respect to any computer, equipment, or supplies," [a fair limitation for a software vendor] "or as to the software system, of their quality, performance merchantability or fitness for any particular use or purpose other than those warranties which are offered by the manufacturers of these products."

"But," the client protested, "you manufactured the software product."

"True," the consultant replied, "and because we disclaim all warran-

ties, it follows that we are making none. That is why you should buy a service contract on the software."

At this point a fair question would be what type of "service" software might need. It has no moving parts to wear out, nothing to get out of adjustment. It either works or it does not, and if it does not, it is probably because it never did. Not wanting to hurt the consultant's feelings, the client did not raise the argument. Instead, he purchased a "total solution" package of hardware and software maintenance.

All went well until a service representative noticed a standby power supply unit that was not on the list of items covered by maintenance. The client explained that it had been purchased before the hardware maintenance agreement had been signed (and before the client appreciated the importance of a "total solution" approach to computers). Shortly thereafter, a letter from the consultant arrived:

"The standby power unit currently in use...was, as you explained, purchased locally before signing our hardware maintenance agreement. You should be aware that failure or incorrect operation of this unit which causes damage to the computer or the data on it cannot be our responsibility. If we feel that the unit has directly or indirectly

caused a problem we must charge for our services in any recovery needed."

Despite the menacing undertone, the consultant's position seemed fair. If the client bought equipment not covered by maintenance, he would have to take the consequences. The general trend of the relationship was, however, beginning to worry the client. Anxious not to create a disaster unwittingly, the client inquired about the limits of his ability to do anything that would not void a warranty.

The consultant replied that the various parts of a system could not be separated: "computer, printer, software, ribbons, diskettes, etc. all are constituent parts working together toward a planned result."

"Just what precisely is that result?" the client asked.

This prompted another letter in which the consultant proclaimed his frustration with the situation. After all, "while the purchase of a dust cover via mail order is inconsequential in the scheme of things it will lead to diskettes, printers, cables, ribbons, and, finally, complete machines." The consultant could cite a particular case in which one of his clients had independently bought a dust cover, then left it on a machine with the power on, resulting in severe overheating and "you




ILLUSTRATION • MACIEK ALBRECHT



# SHELF CONSCIOUS?

## Now you can organize your copies of PC TECH JOURNAL

Now your magazines can be a handsome addition to your decor, well organized, and easy to find, thanks to these durable library-quality cases or binders. They're made of luxury-look leatherette over high-quality binder board. And both styles are custom-designed for this or any other magazine you save, with size, color and imprint selected by the publisher. FREE transfer foil included for marking dates and volumes.



### Magazine binders

holds your issues on individual snap-in rods, combining them into one volume. \$7.95 each; 3 for \$22.50; 6 for \$42.95. Mixed titles OK for quantity prices.



### Open-back cases

store your issues for individual reference. \$6.95 each; 3 for \$19.75; 6 for \$37.50. Mixed titles OK for quantity prices.



**OR CALL**  
**1-212-503-5319**

### PC Tech Journal

P.O. Box 5120, Philadelphia, PA 19141

Please send: ☐ Cases ☐ Binders

TITLE \_\_\_\_\_ QUANTITY \_\_\_\_\_

PC Tech Journal \_\_\_\_\_

Other: \_\_\_\_\_

☐ PAYMENT ENCLOSED \$ \_\_\_\_\_ \* Add \$1.00 per order for postage and handling. Outside USA add \$2.50 per unit ordered; send US funds only.

☐ CHARGE (Minimum \$10):

☐ American Express ☐ MasterCard  
☐ Visa

Card No. \_\_\_\_\_ Exp. Date \_\_\_\_\_

Signature \_\_\_\_\_

Print Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_

State/Zip \_\_\_\_\_

\*Residents of PA add 6% sales tax.

## LEGAL BRIEF

can use your imagination to think of what kind of damage." The consultant, however, did not charge the client for the replacement because the poor dolt was a valued customer "who would not dream of ordering so much as a diskette from another vendor." (Then where did the dust cover come from?)

"Do you mean," the client asked, "that if I so much as buy a diskette from someone else you will not support your system?"

"It is not that we will not support our software. Under circumstances where a third party has responsibility for the equipment, it is simply that we cannot with any degree of certainty. The interaction between hardware and software in a sophisticated...environment is such that it would be catastrophic to have two vendors involved."

Several lessons can be learned here. First, it is true that buying equipment from a single source can simplify life for a customer. Assuming the single source is reliable and competent, the customer does not have to worry about who is responsible for a problem: hardware, software, peripherals, whatever. That is the consultant's problem.

Conversely, if the client chooses to buy from another vendor, he takes two risks: if that product malfunctions it is his problem, and if anything malfunctions he will have to establish that it was not due to the independently purchased product.

Surely, however, limits must be placed on how much fear a consultant should try to instill to keep control over all of the client's purchases.


One such limitation is set by the federal antitrust law, which frowns on conditioning the sale of one product to the purchase of another: a *tying arrangement*. A manufacturer of PCs may not restrict its sale of PCs to only those individuals who agree to buy their printer and all of their future requirements for fan-fold paper from the PC manufacturer. The analysis becomes more complicated when a service and goods are tied together, but if the situation is anticompetitive, the potential still exists for an antitrust violation. The less significant a company's market power, the more latitude it has; perhaps a small consultant can legally demand that his clients do not make a move without his approval (and profit).

A second constraint must also be addressed: the increasing sophistication of computer users. To an increasing number of users, phrases such as "due to the complicated interrelationship of

hardware and software we cannot ..." are as likely to convey ineptitude as menace. Their attitude is, "Maybe you can't maintain your software if I buy my printer ribbons elsewhere, but there are other consultants who can."

If the tie were justified by a reason other than the consultant's desire for profit from the sale of additional products, it would be defensible both from a customer relations and antitrust point of view. The consultant might be concerned that the purchase of inferior quality diskettes could result in lost data, increased downtime, and excessive service requirements for the disk drives. If so, he could require, as a condition of the warranty, that the customer purchase "double-sided, quad density diskettes from among the manufacturers listed on Exhibit A," or "finest quality diskettes from a reputable manufacturer," or he could specify a brand name. A not-so-subtle distinction exists between those requirements and the requirement that the client purchase his diskettes solely from the consultant. Although a creative consultant might do some random quality control testing to try to justify his involvement, the consultant would be hard pressed to explain the requirement that he be the middleman on the diskette purchase.

Finally, the potential danger in the common practice of copying from someone else's agreement form should be noted. Copying is cheaper than having a customized form prepared (chances are it would look like the one that would have been copied anyway). However, defending an agreement is difficult if it contains provisions the consultant does not understand. A salesman (eager to make a sale) or an executive (backed against the wall by the absurdity of what the form seems to say) may be tempted to state that the meaning of the agreement doesn't matter because the company doesn't enforce it. Adopting such an unreasonable position increases the chances that, somewhere in the process, someone will make a statement that will compromise all of the consultant's careful legal drafting.

The demand for computer consultants is enormous, and it is penetrating to the level of very small businesses. A consultant who feels that the only way to keep customers is to intimidate them would profit more from a long, hard look at its own services. 

*Max Stul Oppenheimer, PC, is a partner in the law firm of Venable, Baetjer & Howard, located in Baltimore, Maryland.*



# fileMASTER THE DISK UTILITY

```

FileMASTER
Filename: sample.txt Segment:00000
Offset 0 1 2 3 4 5 6 7 8 9 A B C D E F 0123456789ABCDEF
0000 54 68 69 73 28 69 73 28 61 20 73 61 60 70 6C 65 This is a sample
0010 20 6F 66 20 74 68 65 20 44 69 73 70 6C 61 79 20 of the Display
0020 53 63 72 65 65 6E 2E 20 20 45 61 63 68 20 20 20 Screen. Each
0030 62 79 74 65 20 69 73 20 73 68 6F 77 6E 20 69 6E byte is shown in
0040 48 45 58 41 44 45 43 49 4D 41 4C 20 6F 6E 20 20 HEXADECIMAL on
0050 74 68 65 20 6C 65 66 74 20 61 6E 64 20 69 6E 20 the left and in
0060 41 53 43 49 49 20 69 6E 20 74 68 69 73 20 20 20 ASCII in this
0070 61 72 65 61 2E 20 54 68 65 20 4F 66 66 73 65 74 area. The Offset
0080 64 69 73 70 6C 61 63 65 60 65 64 74 20 69 6E 20 values provide
0090 74 6F 20 74 68 65 20 73 65 67 60 65 6E 74 2E 20 displacement in-
00A0 54 6F 20 63 68 61 6E 67 65 20 64 74 61 2C 20 to the segment.
00B0 6A 75 73 74 20 74 79 70 65 20 6F 76 65 72 20 20 To change data,
00C0 74 68 65 20 48 45 58 20 6F 72 20 41 53 43 49 49 just type over
00D0 64 61 74 61 2E 20 20 20 20 20 20 20 20 20 20 the HEX or ASCII
00E0 00 01 02 03 04 05 06 07 08 09 0A 0B 0C 0D 0E 0F data.
Values: Hex=54 Bin=01010100 Dec=004 Asc=T
1 Hex 2 Ascii 3 Display 4 Edit 5 Find 6 Go To 7 Print 8 Help 9 Write 0 Undo

```

**FINALLY!!** A Disk Utility for the IBM-PC that's fast and easy to use.

- FILE MODE
- DISPLAY
- PRINT
- MODIFY
- HARD DISK
- SECTOR MODE
- BROWSE
- SEARCH
- DOS 1.1 to 3.1
- FLOPPY DISK

ONLY \$39.95 +\$3.00 SHIPPING, CA +6.5% TAX

**J. L. SCHULLER & ASSOCIATES** (818) 366-6934  
148 Rinaldi St., Suite 6, Mission Hills, CA 91345

CIRCLE NO. 232 ON READER SERVICE CARD


# PERSTOR™

Removable Hard Disk Cartridge  
Expansion Systems

**BERNOULLI ALTERNATIVE!**

■ High Performance Fixed and Removable from 10 to 560 mbyte

■ Internal or external mount



■ The only

Removable Hard Disk Cartridge Drive that attaches directly to the IBM PC-AT Controller\*

PERSTOR® products provide portability, storage and backup for IBM-PC, AT, XT and compatibles.

**DOS, Xenix, Multi-User and Networks**

SYSTEMS & SOFTWARE, INC.  
7825 East Redfield Road  
Scottsdale, AZ 85260  
(602) 948-7313



\*Patent Pending Copyright 1985 Perstor® is a trademark of Systems and Software, Inc. IBM-PC, AT, XT, are registered trademarks of International Business Machines Corp.

CIRCLE NO. 228 ON READER SERVICE CARD

## ADALAB-PC™


**Adds Lab Data Acquisition To Your IBM® PC For \$595**  
An ideal interface for chromatography, spectrophotometry, process control, etc.

ADALAB-PC includes ① a 13-bit integrating A/D, ② a 12-bit fast A/D (up to 20 kHz, add \$250), ③ a 12-bit D/A voltage output, ④ a second 12-bit D/A (add \$50), ⑤ 32 digital I/O bits, ⑥ four 16-bit timers or counters, and ⑦ a terminator board which has a 4-channel multiplexer and convenient screw terminals (16-channel differential analog multiplexer with programmable gains from 1 to 256, add \$300).

⑧ Versatile ADAPT software and manual (free with ADALAB-PC) works with BASIC, FORTRAN or PASCAL, includes self-test and data acquisition software. Supports fast DMA sampling, extended memory storage, scrolling stripchart display.

⑩ LABTECH NOTEBOOK software \$895.

⑪ IMI is an IBM Value Added Dealer. **COMPLETE ADALAB-PC SYSTEMS at \$3505**, including 256K IBM PC, 360KB disk, PC DOS 3.0, green monitor, color/graphics adapter, Epson printer with adapter & cable, ADALAB-PC, ADAPT software, plus IMI's Scientific Plotter-PC (\$95) and Curve Fitter-PC software (\$95) **FREE** with systems!



© Trademark of International Business Machines Corp.

**IMI INTERACTIVE MICROWARE, INC.**  
P.O. Box 139, Dept. 237 Telex: 705250  
State College, PA 16804 (814) 238-8294

CIRCLE NO. 209 ON READER SERVICE CARD

FEBRUARY 1986

## MAINFRAME TSO/SPF EDITOR ON A PC

**HCS/EDITOR  
only \$49.95**

shipping & handling  
\$5.00 U.S., \$7.00 Canada, \$13.00 foreign

**TSO/SPF editor created by IBM, improved by HCS.**

Emulates TSO/SPF editor to a high degree, even split screen, automatic recovery and file name selection from a sorted directory.

**Heuristic  
Computer  
Systems**

853 Hickory Drive  
Carmel, IN 46032  
(312) 848-8981

IBM is a registered trademark of International Business Machines

CIRCLE NO. 144 ON READER SERVICE CARD



## VT100/VT52 & Tektronix™ 4010/4014 Terminal Emulator

Excellent emulation and the features you want:

VTEK™ 3.0

- use 4096 x 3120 resolution
- zoom, pan, and window plots
- high resolution printer dumps
- choose text and plot color
- transfer files with XMODEM and Kermit protocols
- scroll last 4 pages of text
- 132 column VT100 capability
- 18 User-definable keys
- capture plots and text on disk
- full or half duplex
- access to DOS commands
- all VT100 keypad commands
- command line editing
- fast direct screen access
- password security


VTEK makes your PC better than a terminal  
\$150 from Scientific Endeavors

## Presentation Quality Graphics for Scientific and Technical Applications

GraphiC™ 2.1

- linear, log, & polar plots
- bar charts & Smith charts
- contour plots with labels
- 3-D curves, 3-D surfaces with hidden line removal
- 4 curve types, 8 markers
- 12 fonts, font editor
- multiple levels of superscripts
- 4096 x 3120 resolution
- zoom, pan, window plots
- multiple plots on a page
- high resolution printer dumps, full or half page
- plotter support

Over 100 routines can be called by your C program. SOURCE INCLUDED for private use only. \$250. Demo \$8.  
For DeSmet, C-86, Lattice, and Microsoft C compilers.



## Scientific Endeavors


Route 4, Box 79; Kingston, TN 37763  
(615) 376-4146

For 256k IBM and Corona PCs, DOS 2.xx,3.xx.  
Epson, Okidata, Toshiba, Prowriter printers.  
Hewlett Packard, Houston, Sweet-P plotters.  
Corona Laser printer, Amdek, IBM, IBM  
Enhanced, Tecmar, Hercules, Corona graphics.

THIS AD WAS MADE USING GraphiC™

CIRCLE NO. 187 ON READER SERVICE CARD

## PC ↔ MAINFRAME VIA 9-TRACK TAPE



## For Information Interchange — Backup Archival Storage ...

IBM format compatible 9-track, 1/2 inch magnetic tape is the universally accepted media for mainframes and minicomputers. Now Catamount offers *Low Cost, Lightweight* 9-track Tape Subsystems for the IBM-PC/XT/AT computers which allow:

- Reading tapes generated on mainframes and minicomputers.
- Writing tapes to be read on mainframes and minis.
- ASCII, EBCDIC and Binary tapes accommodated.
- 800 bpi NRZI, 1600/3200 bpi PE, and 6250 bpi GCR format systems available.
- Storage capacities up to 180 MB on a single reel.

Systems come complete with comprehensive DOS command syntax oriented software and an Installable Device Driver. For OEM applications, the tape controller is available separately.

**CATAMOUNT  
CORPORATION**



2243 Agate Ct. • Simi Valley, CA 93065-1898  
(805) 584-2233

CIRCLE NO. 111 ON READER SERVICE CARD



## New for IBM PC/XT/AT low cost mag tape subsystem

- Fast controller—40Kbytes/second
- New MAINSTREAMER™ tape drive
- Small size, lightweight

Send for our complete drive and interface manuals so you can evaluate and compare. Only \$25 for both.

Tape systems are also available for all other RS-232-C interfaces. Call or write attn: IBEX Applications Engineer today.

**IBEX**

Right for the times

**IBEX COMPUTER CORPORATION**  
20741 Marilla St., Chatsworth, CA 91311  
(818) 709-8100 TWX: 910-493-2071

CIRCLE NO. 149 ON READER SERVICE CARD

## TURBO EDITASM

Introducing the first co-resident editor assembler for the IBM PC family.

**TURBO EDITASM (TASM)** is significantly faster and easier to use than the IBM Macro-Assembler (MASM). Whether you are new to assembly language and want to quickly write a small assembly language routine, or are an experienced MASM user tired of waiting months to assemble large files, **TURBO EDITASM** will bring the excitement back to assembly language.

### TURBO EDITASM IS MUCH FASTER:

- How fast is **TASM**? The graph below shows relative assembly times for a 48K source file. For large files like this we blow MASM's doors off at 3 times their speed. For smaller 8K files we positively vaporize them at 6 times their speed.

<b>TASM</b>	(110 sec.)
<b>MASM</b>	(340 sec.)

- **TURBO EDITASM** is faster for the following reasons: (1) Written entirely in assembly language (unlike MASM). (2) Editor, assembler and source file always in memory so you can go instantly from editing to assembling and back. (3) Eliminates the time needed to LINK programs. Executable COM files can be created directly. (Also creates OBJ files compatible with the IBM linker).

### TURBO EDITASM IS EASIER TO USE:

**TASM** includes many other features to make your programming simpler.

- Listings are sent directly to screen or printer. Assemblies can be single stepped and examined without having to leave the editor.
- Access the built-in cross reference utility from the editor.
- Full support of 186 and 286 (real mode) instructions.
- Both Microsoft and 8087 floating point formats are supported. 8087 and 287 instructions supported directly without macros for faster assembly.
- Calculator mode: Do math in any radix even using symbols from the symbol table.
- Direct to memory assembly feature lets you test execute your code from editor.
- Coming soon: A coordinated symbolic debugger.

**COMPATIBILITY:** **TASM** is source code compatible with MASM and supports macros, records and structures.

**Introductory Price \$49  
With .OBJ Capability \$99**

**Speedware™**

IBM,

Microsoft trademarks of IBM Corp.,

Microsoft Corp.

Include \$5.00 shipping and handling. California residents add 6% Sales Tax.

Dealer Inquiries welcome  
916-988-7426

118 Buck Circle, Box T  
Folsom, CA 95630

CIRCLE NO. 190 ON READER SERVICE CARD



# Teaching Computers to Think

*An expert in artificial intelligence shares his many years of experience in helping machines understand their human operators.*

## ***The Cognitive Computer: on Language, Learning, and Artificial Intelligence***

Roger C. Shank (Addison-Wesley, Reading, MA 1984) 268 pages, paper, \$17.95



Roger C. Shank shares the knowledge he has gained over the past ten years while working as the head of the artificial intelligence lab at Yale in his book, *The Cognitive Computer: on Language, Learning, and Artificial Intelligence*. He frankly confesses both the successes and the failures of his attempts to teach machines to think or, as he explains the thought process, to change as a result of experience, just as human beings do.

Shank explains that humans should not always be required to learn a computer language in order to communicate with their machines. On the contrary, he believes computers should learn a human language. In addition, computers should be able to respond to conversational commands from humans such as "Type the following words in manuscript form" or "Print two double-spaced copies of the article entitled 'My Report'."

The author emphasizes that what the computer should require of the user is not specialized programming language skills, but general intelligence. The computer, he insists, can use the human experiences of the user in order to think on its own.

According to Shank, *artificial intelligence* is a misunderstood term. His definition equates artificial intelligence with "easier to use computers" that can obey human speech as easily as they now respond strokes on a keyboard. Expert systems, which are the result of artificial intelligence, should, for exam-

ple, allow a doctor approaching retirement to pass on his experience and wisdom to a younger associate.

Three important lessons, the results of the author's experience, are enumerated in the book. First, the author warns the reader that trying to squeeze every book, every index, and every fact into a computer's memory is useless. The machines are not big enough to hold all available information on any given subject, and quantity of memory can become an obstacle to quality of performance.

For example, a surgeon performs many different operations. Perhaps 80 percent of each operation is similar to all the others and requires competence from the surgeon, not expertise. A three-hour operation may require only two or three minutes of specialized hand skills or cutting procedures. However, it is these three minutes that separate the quack from the life saver, and it is these three minutes that belong in an expert system database. The other 177 minutes belong instead in a manual or on videotape.

If a half dozen surgeons were able to combine the secrets of their specialized skills into the database of an expert system, the result would be an opportunity for growth and learning now available only from advanced residence training or workshops with the world's greatest surgeons.

To aid in the selection process necessary to determining what should and what should not be included in an expert system database, Shank advocates the use of LISP. This list processor can handle lists from a variety of sources, yet it forces the user to set priorities. In addition, LISP requires that the user have the common sense to recognize situations when the list processor will not work. An expert system may require more than most lists can provide.

As his second warning to the user of an expert system, Shank points out

the futility of cramming the rules, procedures, and directions for every possible contingency of a given situation into the system's memory. Assuming that the user could conceive of every contingency, current programming languages do not allow for the algorithms necessary to generalize from rule to rule. If the user enters all the rules for all possible contingencies, the computer must treat those rules as text rather than as algorithms capable of digesting information and returning expert advice.

Instead, the user should enter only those rules he thinks will occur most frequently. This information then can be translated into the language of the computer and debugged to eliminate obvious errors. These few tested algorithms will be more useful than a long list of information.


PROLOG is a language that can be of great help to the user trying to determine which contingencies of a situation are most important and which non-essential factors should be ignored. PROLOG takes full advantage of the logical decision making capabilities available in computer software.

Shank's third lesson warns against assigning too many objectives to one expert system. Artificial intelligence must be treated as a useful but limited tool. Robots of the 1980s are able to perform many complicated tasks. In the 1960s, however, they were able to perform only very simple tasks. Twenty years were required to make this transition from simple to complex. Likewise, artificial intelligence programs will require time to evolve before they will be able to handle complex responsibilities.

Shell programs, such as ExSy, can aid in this evolution process, Shank says. A shell program contains no rules of its own; the user provides the program with all the rules it will require to proceed to some logical consequence. If the consequence of a rule is unexpected or incorrect, the user must ex-



# IMT opens SideKick-style windows



for **Window-Weaver** call  
or send \$49.95 U.S.

to  
**IMT Integrated Micro Technology**  
P.O. Box 698, Stn. J, (403) 293-5972  
Calgary, Alberta T2A 4X8

*SideKick is a registered Trademark of Borland International  
IBM is a registered Trademark of International Business Machines*


CIRCLE NO. 159 ON READER SERVICE CARD

## The First Idea-Processor For Programmers. **FirstTime™**

Has features no other editor has.

- ☐ Fast program entry through single keystroke statement generators
- ☐ Fast editing through syntax oriented cursor movements
- ☐ Dramatically reduced debugging time through immediate syntax checking.
- ☐ The error checking is thorough and includes semantics • Undefined variables, types and constants • Assignment statements with mismatched types • Errors in include files and macro expansions
- ☐ Automatic program formatter (you specify the rules)
- ☐ Split Screen editing
- ☐ Reading a file with errors moves cursor automatically to point of error
- ☐ Unique programmer-oriented features
  - zoom command gives top-down view of program logic
  - view macro command shows expansion of a C macro in the editor
  - view/update include file allows you to view and update an include file
  - transform command allows you to transform statements to related ones
  - search for next error command

Requires MS DOS, 256k (384 recommended) & 5.25" drive



To Order Call: (201) 741-8188 or write:  
**SPRUCE TECHNOLOGY CORPORATION**



P.O. Box 7948  
Shrewsbury, NJ 07701

FirstTime for Turbo Pascal \$ 74.95  
FirstTime for dBase III \$125.00  
FirstTime for MS-Pascal \$245.00  
FirstTime for C \$295.00

FirstTime is a trademark of Spruce Technology Corporation • MS-DOS is a trademark of Microsoft Corporation • IBM is a trademark of International Business Machines Inc • Turbo Pascal is a trademark of Borland International • dBase III is a trademark of Ashton-Tate

CIRCLE NO. 242 ON READER SERVICE CARD

# Wizard C

*Discover the powers of Wizard C  
for yourself!*

"...written by someone who has been in the business a while. This especially shows in the documentation."

Computer Language  
February, 1985

" Wizard's got the highest marks for support."

"The Wizard compiler had excellent diagnostics; it would be easier writing portable code with it than with any other compiler we tested."

Dr. Dobb's Journal  
August, 1985

Full Lint checking, six memory models, 8087 support, in-line assembly language, ROMable data support, full library source code. Cross-compilers are available on VAX/VMS and UNIX machines.

(617) 641-2379

Only \$450.



SYSTEMS SOFTWARE, INC.

11 Willow Court  
Arlington, MA 02174



CIRCLE NO. 221 ON READER SERVICE CARD

## SCIENTIFIC CALCULATOR

How Many Times Have You Had To Reach For A  
Hand Held Calculator While using Your PC?

**WE'LL REACH NO MORE!**

Introducing The KSH-1 Full Function Scientific  
Calculator - The Calculator With A Difference.

No longer do you have to contend with just 4 functions on a calculator. The KSH-1 calculator provides all the functions available on the HP-11C plus more:

- Calculations to 18 digits (17 displayable)
- Ability to insert result directly in foreground program
- Graphically presented (no reference cards needed)
- Program steps and error messages displayed in English
- All stack registers viewable simultaneously
- Operates in hex, binary, octal and decimal modes
- Save/recall programs to disk
- All KSH-1 calculator software is RAM resident (~ 40 to 50K)

Requirements: IBM PC, XT, AT, or true compatible with 128 K; monochrome or color, 1 drive, DOS 2.0 or later

Price: \$49.95 (either plain or 8087 version)  
\$59.95 (both versions)

Terms: \$3 shipping, Visa, Mastercard, M.O., check  
Tenn. add 7.25% sales tax



**K Software House**  
Software, Service, Consulting  
Rt. 2 Box 8381  
Unionville, TN 37180  
(615) 294-5090

CIRCLE NO. 146 ON READER SERVICE CARD



plain the rule to the shell again and again until the consequence is as desired. This shell approach to artificial intelligence forces the user, as well as the computer, to consider the consistent, logical, and impartial results of a particular rule in a particular situation.

The obvious limitation of shell systems is the intelligence of the user. The system can act only upon the rules as explained by the user. The user must inform the shell if more than one solution is possible and, after the computer has acted, must determine the appropriateness of the solutions reached.

Shell programs, however, are very useful in answering routine and tested questions, and they leave the user free to consider new and innovative questions. Shank emphasizes that expert systems do not replace the user; they allow the user to spend time on challenge rather than routine.

Working to implement artificial intelligence is a calculated risk and not advisable in all situations. Shank helps technical managers determine the odds of the success of an expert system given their particular circumstances. In some instances, even when working with first-rate equipment, experts, and supplies the costs of implementing such a system might outweigh the benefits.

To make the implementation of an artificial intelligence system as easy and beneficial as possible, Shank advises that the manager of the project must guide his coworkers through the change. He must explain specific goals and emphasize why each is important to an overall increase in productivity. In addition, he must make clear the benefits of an expert system to the employees themselves, such as improved working conditions, less worker stress, and the elimination of tedious procedures through the gradual introduction of automation. Documentation provided by the workers involved of the importance of each goal can help the manager motivate the coworkers to achieve that goal, according to Shank.

The author goes on to say that opposition to change is based upon fear and ignorance, not stupidity or stubbornness. Therefore, the manager must be ready to explain patiently the changes involved with the implementation of an artificial intelligence system. He should treat each instance of opposition as a symptom pointing to an invisible need. At first, some goals may seem impossible to obtain. However, the manager's attention to the needs of the workers will prove this not so.

As Shank points out, an expert system implemented on a personal computer cannot solve all problems. For example, if an office or factory has 25 people taking 10 orders per hour during an 8-hour day, the result is 2,000 orders. A single worker using a PC could not handle all of these transactions. Equipping each of the 25 workers with a PC might help, but then problems arise with each computer trying to access a common database, such as an inventory availability program. The solu-


tion in this instance would be a main-frame system, not a set of PCs.

Shank is clear and practical in his examination of the question, "What can the PC do to help the office or factory implement artificial intelligence?" He is genuinely concerned about how the computer touches our lives. He explains, "We will be on our way to understanding ourselves...when our machines understand us."

—PEG CADY



# NEW! Object-Oriented Programming on a PC!



**Objective-C™** is an object-oriented programming language and a fully documented library of reusable components...adding messages, objects and inheritance to C language. Applications written in Objective-C are fully compatible with other Objective-C compilers running under UNIX, VMS or AOS.

Objective-C provides the productivity of object-oriented programming, while

retaining the portability and efficiency of C. PPI also provides comprehensive technology transfer to insure that your programmers fully understand this exciting new technology.

PPI's Objective-C compiler generates C code, which requires the Microsoft V3 C compiler running under MS/DOS.

At \$500 Objective-C is affordable. Order today!

**PRODUCTIVITY PRODUCTS INTERNATIONAL**  
27 Glen Road, Sandy Hook, CT 06482. (203) 426-1875.





# TECH BOOK

## ACCESSORIES/SUPPLIES

### DISK SALE

DS/DD for IBM-PC & compatibles w/sleeves & labels—10/\$8.50—bulk 100/\$67. DS/HIGH DENSITY for IBM-AT w/sleeves & labels 10/\$24.00—bulk 100/\$215. PREMIUM QUALITY, LIFETIME WARRANTY! MONEY-BACK SATISFACTION GUARANTEE! send check or pay by MC/VISA/AE. \$3 shipping +\$2 if COD. Unitech  
20 Hurley St.  
Cambridge, MA 02141  
(617) UNI-TECH

## BUS. OPPORTUNITIES

Personal Computer Owners  
**CAN EARN \$1,000 TO \$5,000**  
monthly selling simple services performed by their computer. Work at home-in spare time. Get free list of 100 best services to offer. Write: C.I.L.B.Q.  
PO Box 60369  
San Diego, CA 92106-8369

## DISKETTE COPY SERVICES

### BLANKET SERVICES

• Diskette duplication • Stocking/Drop shipping • Packaging • Fulfillment • 48 hour delivery. Place a blanket order with releases as you need them for any quantity at a fixed price. Superlok • Lifetime guarantee. • No mastering fee • No chg for standard labels. Print no more sleeves than you actually need.  
Star-Byte, Inc.  
2564 Industry Lane  
Norristown, PA 19403  
(800) 243-1515 (215) 539-4300

## RATES AND INFORMATION

Standard listings consist of a bold lead line (23 characters maximum); 7 lines of body copy (45 characters per line); 4 lines for company name, address and telephone number. \$140 per insertion—3 issue minimum. Additional charge for extra lines and company logos. Prepayment and frequency discounts available. American Express, MasterCard, Visa accepted. Copy subject to publishers approval. Send typewritten or printed copy, reproducible logo art (if applicable) and remittance to Kathryn Cumberlander, Classified Sales Manager, Ziff-Davis Publishing Company, One Park Avenue, New York, NY 10016. For additional information, assistance, or to place an order by phone, call collect (212) 503-5115.

## HARDWARE/ADD-ON BOARDS

### SPEECH SYNTHESIS

SynPhonix: TRUE Unlimited Speech Synthesizer for IBM-PC/XT/AT/jr & compatibles. This low power short card includes an SSI263 speech chip, amplifier and speaker. Software includes Text-to-Speech, Phonetic Editor, Talking Clock & demos. Can be programmed with BASIC and other languages. Prices start below \$200.

## SynPhonix

Electronic Speech Articulator

Artic Technologies  
2234 Star Court  
Auburn Heights, Michigan 48057  
(313) 852-8344

## HARDWARE/COOLING DEVICES

### LESS NOISE! MORE COOLING!

Does your PC sound like a high speed turbine? Does it use expansion cards that create extra heat? Solve your noise & cooling problems with the SILENCER from PC Cooling Systems. Each model utilizes a super quiet, West German, all metal, 4 1/2" fan. Model SQ cools with 84% less noise than the standard fan it replaces! Model HP provides over 100% more cooling! Mounts to existing holes on the back of the IBM PC or XT. Immed. shipping. \$79.95 + \$4 s/h VISA/MC/CK.  
PC COOLING SYSTEMS  
31510 Via Ararat Dr.  
Bonsall, CA 92003  
(619) 723-9513

## HARDWARE/DISK DRIVES

### 8 INCH DISKETTE SYSTEM

Read, write and format diskettes from IBM mainframes, minicomputers, data entry equipment, etc. Complete easy to use software handles EBCDIC conversion. Can read and write CP/M 8-inch diskettes (many formats). You also can use 8-inch drives for PC DOS files; 1200 KB per diskette! \$1150 complete.  
MicroTech Exports  
644 Emerson St. Suite 8  
Palo Alto, CA 94301  
(415) 324-9114

## HARDWARE/PERIPHERALS

### A/D TO RS232 CONVERTER

Low cost stand-alone data acquisition board for any 8 bit RS 232 port. 8 channels, 8 bit conversion. 0-5V input, 300-9600 baud. Small size, 4" x 5", with wall plug power supply. Easy-to-use, includes sample driven software listings. Kit w/all parts & PS, \$59.95 + \$4 shipping. Assembled & tested is \$89.95 + \$4.  
TPS SYSTEMS  
14820 Elmore Road  
Anchorage, AK 99516  
(907) 345-6730

### SCSI-PC HOST ADAPTER

Plug & Play installation for SCSI Optical/Hard disk and tape peripherals. Wide selection of SCSI peripherals selectable by manufacturer and model No. via menu window. Absolutely NO driver software need be written by the user. Price is \$249. for board, SCSI bios prom and floppy based configuration data.  
Advanced Storage Concepts, Inc.  
9660 Hillcroft #325  
Houston, TX 77096  
1-800-423-9175 (713) 729-6388

### NEW! ... CIP/35 CONTROLLER

- 8-300 bolt 20 amp SPDT relays.
- 8 Opto-isolated digital input.
- 8 Bit A/D Converter w/Mux capability.
- RS-232 or PTL serial—Remote Reset func.
- 6 Mhz 8035 CPU—Emergency Halt function.
- LED indicators—12 volt AC/DC operation.
- Price is ONLY \$225.00—same day shipping.

Many more features, call for complete details.  
Data Management Systems, Inc.  
2141 Centennial Rd.  
Salina, KS 67401  
(913) 823-6440

### NEW! AT-SPEED SWITCHER™

- Select 6 speeds of operation 4,6,8,9,10 and 11 Mhz (39 to 70% speed increase).
- Allows proper operation of PC software to run on an AT—100% AT software compatible.
- Speeds up your entire software library.
- No expansion slot needed—easy to install.
- No software required—1 year warranty.
- Price is only \$125.00—same day shipping.

Data Management Systems, Inc.  
2141 Centennial Rd.  
Salina, KS 67401  
(913) 823-6440

### NEW! OVERTHRUSTER™

- Actual 60% Speed Increase (7.38 Mhz).
- 100% Compatible with all PC software
- Includes 8Mhz 8088-2 CPU and Hardware reset.
- Supports 8Mhz 8087-2 Math Coprocessor chip.
- No expansion slot needed—easy to install.
- No software required—1yr warranty.
- Price is ONLY \$295.00—same day shipping.

Data Management Systems Inc.  
2141 Centennial Rd.  
Salina, KS 67401  
(913) 823-6440

### 640K YOUR MOTHERBOARD!!


Put 640K of RAM on Your Motherboard! NO SLOT! NO ADD-ON BOARDS!—NO SOLDERING! Complete w/ALL Hardware, Memory Chips and Instructions. Easy PLUG-IN Installation. Avail for: IBM XT, IBM Portable, COMPAQ & COMPAQ PLUS Portables. Only \$144.95 + \$5 S/H, Specify computer when ordering. Dlr. inquiries invited. CK/MO/VISA/MC  
J S & J Software  
1281 S. King St. Suite 6A  
Honolulu, Hawaii 96814  
24/hr Orders: (800) 821-5226 ext. 435

### PC SPEEDUP

Up to 45% speed improvement for IBM PC and clones. 100% compatible, easy installation. Kit includes NEC V20 or V30 Chip, Tool, User Guide, Warranty, free Multiuser BBS Access. V20-5 mhz for PC, V20-8 and V30 in stock. V30 replaces 8086. Call for Turbo 7 and VP/IM.  
From \$4 to \$89. Tech info 414-242-2165  
Exec-PC, Inc.  
PO Box 11191 Shorewood, WI 53211 Order on BBS:  
Orders: 414-242-2173 414-964-5160

### TURBO START YOUR PC!!!

FOR IBM PC's ONLY!! The PC-INMATE, a Firmware ROM Module for the IBM-PC!!! Features: BOOT within 10 SECONDS!!! BREAK the 640K BARRIER!!! Access up to 704K of RAM!!! (Lotus, DOS, etc.) SCREEN RELIEF—protects your monitor, and MORE!!! Easily PLUGS IN—NO SLOT! Only \$49.95 + \$3 S/H. Dlr. inquiries accepted CK/MO/VISA/MC.



JS&J Software  
1281 S. King St. Suite 6A  
Honolulu, HI 96814  
24 hr Orders Only: (800) 821-5226 ext. 435

## HARDWARE/SECURITY

### STILL WAITING? INSECURE?

QUICKON—Instant Turn-on module—\$69.95.  
LOCKIT I—Password Boot-Up module—\$129.95. User selectable PW & Boot-only-from-HD mode. PC RESET—Reboot w/o cycling power—\$21.95. Easy to install. No slot, specify PC/XT/AT LOCKIT II—PW protection for sub-directories, for DOS 2.0 & up.—\$79.95. MC/VISA Security Microsystems Consultants  
16 Flagg Place Suite 102 TJ  
Staten Island, NY 10304  
(718) 667-1019



# TECH BOOK

## SOFTWARE/BAR CODING

### BAR CODE PRINTING/READERS

PRINT Bar Codes on PC and Epson/Okidata or IBM Proprinter—Code 39, I 2of5, UPC, MSI, LOGMARS, AIAG, HIBC. Graphics chs up to 1". Labels, Catalogs from disk files. Subroutines for BASIC, Pascal, T-Pascal, C. Programs \$49-\$299. Readers/portable (\$350), fixed (\$595). Worthington Data Solutions  
130 Crespi Court  
Santa Cruz, CA 95060  
(408) 458-9938

## SOFTWARE/COMPILER

### DeSmet-C - \$109

Full K&R C compiler, linker, librarian, fullscreen editor, profiler, overlays, example software, 140 page manual. BOTH 8087 and floating point libraries. OUTSTANDING PRICE/PERFORMANCE. Consistently rated 1st or 2nd in published benchmarks. PC/MSDOS. No royalties on generated code. Newsletter. Updates \$20 ea. \$109 shipping included. Symbolic (C source level). Debugger Option \$50 extra. C-Compiler for the Macintosh \$150. C-WARE CORPORATION  
Dept. PCTJ  
P.O. Box C  
Sunnyvale, CA 94087  
(408) 720-9696

## SOFTWARE/COMMUNICATIONS

### KERMIT, Xmodem, VT100/102

Order now and receive free CommSpeak update when available, or send for more information. Find out why informed buyers at Abbott Labs, Hughes Aircraft, Lawrence Livermore Labs, Stanford University, and The University of Arizona have all purchased multiple Versa-Com-licenses. Costs \$55.00 plus \$5 s/h. Solution Software  
3421 North 1st Avenue #120  
Tucson, AZ 85719  
(602) 323-0841

## SOFTWARE/DATA ENTRY

### DATA ENTRY EMULATOR

Full speed heads-down data entry with two-pass verification for the PC/XT/AT & compatibles. Easy screen formatting by your data entry operators in minutes. Loaded with features like: Auto dup & skip, verify bypass, constant fields, range checks, table lookups, full screen paging, & field totals. Fully menu driven only \$395. Call for free 30 day trial period.  
Computer Keyes  
6519 193 SW  
Lynwood, WA 98036  
(206) 776-6443

## SOFTWARE/DEVELOPMENT TOOLS

### TURBO-PLUS™

Turbo-Plus™ is a set of external procedures crafted in assembler language and designed specifically for Turbo Pascal's interactive environment. Turbo-Plus™ includes: File Handle Disk Access Method, Instant Memory Mapped Text Display, Expanded Text Display. \$34.95 plus \$5 s&h.  
NOSTRADAMUS  
5320 South 900 East  
Salt Lake City, UT 84121  
(801) 261-0769

### COLOR, CURSOR CONTROL

DATE/TIME, KEYBOARD, PEEK, POKE, COMMAND LINE ACCESS, and more available for IBM/MS FORTRAN, IBM/MS PASCAL, and GENERIC (MS) BASIC on PC/DOS and many MS/DOS machines. No redistribution fees. \$47 U.S. MN residents add 6% sales tax. BARTSUBS by BARTSOFT  
3210 Lake Shore Boulevard  
Wayzata, MN 55391  
(612) 473-4032

### REVISION CONTROL SYSTEM

The Software Revision Management System™ stores all versions of source/documentation in a single ASCII file. Allows retrieval of any version of source and application of changes, while recording when, why and where changes were made with no duplication of common code. MS/PC-DOS 2.0 \$99.95 + . \$5 s/h. (MN + 6%.) MC/Visa.  
QUILT™ COMPUTING  
7048 Stratford Rd.  
Woodbury, Minnesota 55125  
(612) 739-4650

### CONTEXT-SENSITIVE HELP

TRUE/Helper adds context-sensitive help to existing programs. No access to program source is necessary. Works as a pop-up under the target program. Help text can be built using any editor. Text is compressed to reduce space. Works with most custom and off-the-shelf software. \$39.95  
GRW Software  
P.O. Box 440007  
Houston, Texas 77244  
(713) 556-9878

### ROMable CODE ON PC!

PCLOCATE allows PC users to develop ROM-based software from MS-DOS "Exe" files. The user specifies the physical location of all segments. Output files are compatible with most PROM programmers. PCLOCATE supports the 8086, 8088, 80186, 80188, and 80286 processors. MC/VISA.  
ALDIA SYSTEMS INCORPORATED  
P.O. Box 37634  
Phoenix, AZ 85069  
(602) 866-1786

### SOURCE CODE LIBRARY

... "Structuring BASIC Programs" comes with:  
..... BASIC examples on DOS 2.0. Diskette.  
..... BASIC Check Writing Program.  
..... BASIC Source Code Library  
..... HOW to Structure Package only \$9.95.  
FREE Fact Sheets.  
FREE Contract Programmer Registration.  
TULSA COMPUTER CONSORTIUM (TCC)  
P.O. Box 707  
Owasso, OK 74055  
(918) 747-0151  
Requires 100% compatible, DOS 2-3, Turbo Pascal 2-3 for compatibles.

### TURBO EXECUTIVE™

For Real-Time Multi-tasking, control applications. Interrupt driven, Turbo Pascal source code includes a background ASYNC COM task, memory resident code example, windowing, video and directory utilities!  
• Non Pre-emptive version \$64.95  
• Pre-emptive (time slice) version \$164.95  
• Call or write for FREE brochure consulting and programming service available.  
Clear Creek Computing  
2107 Audubon  
League City, TX 77573  
(713) 332-9940

### MATIS/T FOR TURBO: \$29.95

Create large virtual screens; formatted input field; windows for single or multiple screen display. Total control of video attributes. Memory resident Assembler routines used as PROCEDURES in TURBO PASCAL. Also available for BASIC, C, MS-PASCAL, & Assembler: MATIS \$49.95. Royalty FREE. Add \$5 s/h. VISA/MC. CA add tax.  
SOFTWAY, INC.  
500 Sutter St. Suite 222TL  
San Francisco, CA 94102  
(415) 397-4666

### REALIA COBOL SITES

REALFORM is the Screen Handler you have been looking for. It features interactive screen design, an on-line forms editor, relief of cursor control, expedites screen generation, supports numerous data field types, is easy to use and offers powerful data entry functionality. \$395. US.  
CHARANDON COMPUTER SYSTEMS INC.  
1600 Laperriere Avenue  
Ottawa, Ontario, Canada K1Z 8P5  
(613) 729-3003

### COBOL SCREEN-UTILITY

Formaker for the IBM PC or compatibles. Interactive Screen design utility for MS/PC COBOL or CIS/Level II COBOL. Save time—clean screens in minutes, not hours. Features: Maintainable screen files; user assigned field names; auto generation of Screen Section and/or W/S copy files; much more. Specify Compiler type. \$95.  
Logicware Data Systems, Inc.  
Box 9C Sunnybrook Road  
Jackson, NJ 08527

### TURBO LIBRARY

Cut development time. Use Input, windows, quick screen output, screen save and restore, menus, fill-in templates, template editor, reports and string utilities. For IBM PCjr, PC, XT, AT with Turbo Pascal V2.0 and higher. Money back if not satisfied. Documented source code on disk \$49.95.  
PLATTWARE  
P.O. Box 2626  
Del Mar, CA 92014

### INSIDE—DISASSEMBLER

Get INSIDE your PC, XT, and AT software with the disassembler for the 8088/8086, 80186, 80286, 8087 & 80287. INSIDE generates address labels, listings and X-REF table. Write code to disk in "macroassembler" form. Command driven; simple to use. INSIDE and manual only \$49.95 plus \$3.00 s/h (IA res. add 4% tax.)

*Inside*  
DisAssembler

BLACKRIDGE CORPORATION  
P.O. Box 385  
Bettendorf, IA 52722  
(319) 355-4465

### BETTERTOOLS FOR BETTERBASIC

BetterTOOLS™ 100 procedures & functions that speed BetterBASIC™ development. Sorting, scrolling, extended math functions, video routines, disk directories, formatted screen display, on-line error descr., input w/full editing & extended code trapping, much more. Better-TOOLS™ w/source & manual, \$89. Write:  
Software Associates  
6220 W. Airport Blvd.  
Houston, TX 77035  
(713) 726-0706

### CPM-80 LIVES ON YOUR PC

CP/Mulator puts a 4mhz 8 bit CP/M emulator in your IBM PC for \$99.  
—A great 8 bit development system  
—Saves expensive CPM-80 applications  
—Increases PC speed 10% for 8088 programs  
—Priced less than most software only products  
—Used no valuable board slots  
Source Information  
P.O. Box 2974  
Warminster, PA 18974  
Phone: (215) 628-4719

### CPU MONITOR—\$33.75

Selectively monitors and reports CPU usage for application programs, DOS, ROM'S and BIOS. Command and application program interfaces provided. Bar chart output (mono or color). On-line HELP. Documentation with examples. Less than 1% overhead and 1K of resident memory. Check or Money order.  
Syba Corp.  
P.O. Box 272938  
Tampa, FL 33688-2938  
(813) 885-1972

### TOOLS FOR CB80 & CB86

BDOS, DOS, and BIOS calls from CB80 and CB86! CBC Tools includes functions for directory access, string ops, a debugger, radix conversion, command line parsing, quicksorts, bit and byte ops, and much more. Available for CP/M-80, CP/M-86, and PC-DOS for \$180.00.  
Minnow Bear Computers  
P.O. Box 2233 Sta. A  
Champaign, IL 61820-8233  
(217) 398-6883



# TECH BOOK

## BTTREES IN C SOURCE

BTree.....\$75.00  
 • fast and portable  
 • duplicate keys  
 • variable length records  
 ISAM.....\$40.00  
 • works with BTree  
 • simple, powerful application file system.  
 Snake.....\$59.00  
 • Similar to UNIX make  
 • supports nested macro, file name expansion.  
 All three.....\$149.00  
 ALL SOURCE CODE INCLUDED, NO ROYALTY FEES. Call or write for more information.

## SOFTFOCUS

Softfocus  
 1343 Standbury Drive  
 Oakville, Ontario, Canada L6L 2J5  
 416-825-0903

## FIRMWARE PRODUCTION ON PC

LINK&LOCATE enables PC users to produce ROM-based firmware for 8086/87/186 from object files generated by C, PL/M compilers & MASM. Provides full control of segments placement anywhere in memory. Supports output of INTEL hex file for PROM programmer, absolute object file for symbolic debugger & ICE, and MS-DOS EXE file. Includes an INTEL compatible linker, locator, librarian and hex formatters. \$350. Systems & Software, Inc.  
 3303 Harbor Blvd., C11  
 Costa Mesa, CA 92626  
 (714) 241-8650

## DISK DRIVE DIAGNOSTIC

Memory Minder, from J & M Systems, is a disk diagnostic program for the IBM PC, PCjr, & IBM compatibles. It checks your drives for head alignment, spindle speed, hysteresis, azimuth & more. And, you can use Memory Minder to actually align your disk drives! \$99 plus \$4 shipping.



J & M Systems, Ltd.  
 15100-A Central SE  
 Albuquerque, NM 87123  
 (605) 292-4182

## ASSEMBLY PROGRAMMERS, YOUR LIBRARY IS HERE.

Graphics, Floating Point Math, Trigonometry, Widows, 8087 Support, and much more. Over 160 functions for the DOS 2.x environment. Written in MS Assembly Language. No Royalties Required. Now included FREE, FSEdit - Full screen editor. The programmer's file editor. Required IBM PC/XT/AT or compatible, ASMLIB with complete source code and 211+ page manual and FSEdit \$195.00. Call or write for information.  
 BC Associates  
 13073 Springdale St., Suite 134, Dept PT  
 Westminster, CA 92683  
 (714) 741-3015

## MACROKEY 2.0

Imagine: 720-key keyboard, 65536-char macro buffer, 4 modes of definition, KB security, reset information, powerful macro commands windows popup instantly from any program to perform virtually any Prokey, Superkey features and more. Check/money order. \$49.95 or \$160 W/ASM source. PC/XT/AT true compatibles. COMPUTEK  
 40 West 32nd Street. P.O. Box 20211  
 New York, NY 10001-9992  
 (212) 206-6303

## ADVANCED FULLSCREEN DEBUG

THE user-friendly debugger that shows all information on a well structured screen. RESIDENT operation and extensive conditional breakpoint feature. Pop-up by Ctrl-Esc, INT-3, conditional breakpoints, or NMI-signal. Fast conditional trace, recording instructions and register contents. Full 286 on-line assembler & disassembler with scroll up/down. Send trace records, disassembled code, and data to printer or file. 1 or 2 monitor operation. Keyboard macro support. Written in MASM, fast & compact (64K). DOS 2.0, IBM PC/XT/AT. \$110 + \$5 s&h.  
 PUTTKAMMER Software  
 242 RD 1 Hillcrest LA. Nelkenstr 4  
 Rhinebeck, NY 12572 7031 Weil-3W.  
 Germany  
 (Germany) 7031-52256  
 (914) 876-7830

## NEW MS-DOS DISASSEMBLER

MASTER\*KEY is intelligent: instantly and automatically producing fully-documented assembly language segmented source files from any COM or EXE file. MASTER\*KEY has a Cross-Reference identifying all branch addresses, labels, symbols, functions and interrupts. \$49.95 + \$3 s/h (+6 1/2% tax in CA) VISA/MC  
 Sharpe Systems Corp.  
 2310 "E" Street  
 La Verne, CA 91750  
 (714) 593-9998

## REPORT WRITER

All-language qPLEX-IV lets you select or sort your own special forms, reports, labels, bar graphs or queries. Exports your reports to spreadsheets and wordprocessors. Reads Basic, Assembler, Pascal, C, Fortran, Cobol, ASCII, Data Base Managers and more. Dealer demos available.  
 MS-DOS, XENIX, UNIX  
 Snow Software Corporation  
 3330 Fisher Road  
 Clearwater, FL 33519  
 (813) 784-8899

## C-INDEX

C-INDEX is a state-of-the-art data management library for C. Designed for serious product development. No Royalties. B+Tree, variable length records, multiple keys, and transportable source code. Call for our free info packet.

C-INDEX/PRO	\$195 Partial Source
C-INDEX/PLUS	\$395 Full Source

TRIO SYSTEMS  
 2210 Wilshire Blvd. Suite 289  
 Santa Monica, CA 90403  
 213-394-0796

## COPY PROTECTION BY MSD

The ULTIMATE diskette copy protection system designed for software developers and publishers. All IBM PC and XT environments are supported which includes DOS, BASIC (compiled and interpretive) Pascal, P-System, dBASE II and stand-alone systems. Customized systems available. Requires 64K, two disk drives.



MICRO SOFTWARE DEVELOPERS, INC.  
 214 1/2 West Main St.  
 St. Charles, IL 60174  
 (312) 377-5151

## SOFTWARE/EDIT

### POEDIT

Full-screen editor, EDLIN alternative for the PC family. With: 4-way cursor, insert/delete/replace char, 4-way scroll, split/join lines, add/copy/move/delete lines, search/replace strings, get/put to disk, help screens. Edit multiple files at same time. Needs 128K and MS-DOS. \$45 (+\$1.80 tax in VA) + \$2 shipping.  
 ADAM Systems Corporation  
 5919 Munson Court, Dept. 404  
 Falls Church, VA 22041  
 (703) 379-0669

### ZED—THE EVERYTHING EDITOR

A Full-Screen Editor with four-way cursor control. Disk repair, binary file edit, hidden file edit. Create your own copy protection, modify existing object modules quickly and easily with ZED. Edit in Hex or Text or BOTH. Search for Hex or ASCII strings. On-line HELP screen. \$39.95 + \$1.60 (tax in GA) + \$2 shipping.  
 Dickens Data Systems  
 6065 Atlantic Blvd.  
 Norcross, GA 30071  
 (404) 448-6177

### SED-SCREEN EDITOR

Versatile full screen editor loads ANY file. Write programs, design screens, fix non-text files, edit anything! Has key macros, search/replace, block print, undelete, scroll up/dn, much more. Runs on compatibles. Written in C. Not copy protected. Site licensing available. Only \$19 + \$2 shipping. Call for our flyer.  
 DISC (Data Integration Services Corporation)  
 1725 K Street, N.W., Suite 614  
 Washington, DC 20006  
 (202) 785-8585

### Lil'Jake

"The WORLD'S GREATEST Editor." That's what our users say about Lil'Jake.  
 • Edit multiple files  
 • DOS commands  
 • Comprehensive (terse/verbose) online help  
 • Programming support BASIC, DOS & BIOS  
 • MACRO facility  
 We're so sure you'll like it, we want to send you a copy for a free 60-day evaluation. \$49.95 + s/h To order: Write or CALL NOW!  
 Fooks Matthewson Company  
 P.O. Box 2424 (Oper-28)  
 Arlington, VA 22202  
 (703) 684-8284

## SOFTWARE/ENGINEERING

### smARTWORK®

Printed-circuit artwork editor for double-sided boards up to 10" by 16", runs on an IBM-PC. Color display allows complete interactive control over the placement and routing process. 2X artwork can be made on a dot-matrix printer or pen-and-ink plotter, \$895. Write or call for a brochure.



WINTEK Corporation  
 1801 South Street  
 Lafayette, IN 47904-2993  
 (317) 742-8428

### METAL FABRICATORS

PC/Cutlist takes input from your bill of material—Detail drawing and calculates the best cutting combination for any length stock and prints a shop ready cutting list and scrap report. Also an optimization feature finds best mult length for mill orders. Price \$300. Demo Disk \$25.00  
 THE JOSEPH ALBERT CO.  
 P.O. Box 611  
 Blue Island, Illinois 60406  
 (312) 349-9032

### PC/8087 ARRAY PROCESSING

The VECTOR87 library is written in assembler, includes 60 subroutines to speed scientific programs by 2 to 18x. FFT, vector operations, convolution, etc. 1K real FFT takes 1.2 second. Also Fortran 2D FFT, linear equation solvers. Versions for Lattice C, MS C, IBM Pro Fortran, MS Fortran. \$120 each w/source. Check/PO/VISA.  
 VECTORPLEX Data Systems Ltd.  
 P.O. Box 138 Station M  
 Calgary, Alberta, Canada T2P 2H6  
 (403) 248-1250

### CREATE PCB's EASILY

Easily create double-sided printed circuit board artwork of up to 21" square using PC-Layout on an IBM-PC. The artwork is created using a color artwork editor. The final artwork, solder mask and silk-screen (text) is produced using either a printer or a plotter. Price \$745. Demo disk/manual \$45.  
 Draco Technology  
 7210 Jordan Ave., Suite D50  
 Canoga Park, CA 91303  
 (800) 235-6646 ext. 646 (outside CA)  
 (800) 235-6647 ext. 646 (CA only)



# TECH BOOK

## SOFTWARE/FINANCIAL

### CASH FLOW MANAGER

Easy, powerful system for personal budgeting, bill paying, smart checkbook management, and cash-flow control for IBM PC and true compatibles. Take charge of your money with CashFlow Manager! 128K, one DSDD floppy, PC DOS 2.x; printer optional. \$39.95 check, Visa, MC. Tax Deductible. (add 5½% in OH)  
SINGULAR SYSTEMS  
4250 Possum Run Road  
Dayton, OH 45440

## SOFTWARE/GENERAL

### PUBLIC DOMAIN SOFTWARE IN C

Over 60 volumes of public domain software in CP/M & MS-DOS formats.

- editors & compilers
- text formatters
- communications packages
- many UNIX-like tools

Write or call for more details.



THE C USERS' GROUP  
P.O. Box 97  
McPherson, KS 67460  
(316) 241-1065

## SOFTWARE/GRAPHICS

### TEKTRONIX 4010 EMULATION

High resolution screen/printer graphics for the IBM PC. Full interactive capabilities with file transfer and cross-hair control. Utilizes PLOT 10, protocols. OFF-line review of graphics output. Supports IBM color/graphic or Hercules cards. Easy to use 4010 emulation at an affordable price. \$80.00. Demo disk \$5.  
Technological Systems Group  
5044 Haley Court  
Lilburn, GA 30247  
(404) 923-4980

### FOR PRO & NOVICE ALIKE

BOARDS: Tecmar, Hercules, IBM E/CGA, AT&T. LANGUAGES: DeSmet-C, C86, Lattice-C, MS-C, Turbo Pascal, MS-Pascal, MS-Fortran, MS-Macro86. PRINTERS: Epson, Okidata, Toshiba. FAST: 200k pixels/sec avg. TIGHT: 10K. COMPLETE: 2/3D-Lines, Bit Bks, Windows, Color, Fill, Arc, Icon, Zoom, Trig, Character, String, Mouse, Keyboard, Timers, Menu Grids, & more. PLUS: Icon Editor, Fonts. No royalties! MODULES: \$35.

**Superior High Performance Graphics Tools**

AFFINITY, INC.  
126 Normal Ave.  
Buffalo, New York 14213  
(716) 882-5077

### PRESENTATION GRAPHICS

Create transparencies, 35mm slides, printer and plotter output with Sound Presentations. Construct organization and flowcharts, maps, and floor plans using Sound Presentations' comprehensive libraries and powerful editing features. Enhance and modify Lotus charts and graphs. \$250 + \$50 for Lotus convertor.  
Communication Dynamics, Inc.  
8532 SW St. Helens  
Wilsonville, OR 97070  
(503) 682-0651

### GRAPHICS LIB FOR TECMAR

TEK-MAR lets you do high-res graphics on your TECMAR Graphics Master. TEK-MAR is a library for use with MS Fortran. Features windowing, viewporting, clipping, axis rotation. Similar to Tektronix graphics. Includes screen dump/restore, Epson screen print, support for Hewlett Packard, Western Graphtec plotter. Requires MS-FORT 3.20, 320K, GMDEV.SYS (5.2). Price: \$195.  
ADVANCED SYSTEMS CONSULTANTS  
18653 Ventura Boulevard, Suite 351  
Tarzana, California 91356  
(818) 407-1059

### SuperCAD a2.5D system.

Developed by a Columbia University graduate, it's very fast and powerful, supporting all the most advanced I/O devices and the 8087. It works like a screen oriented word processor for graphic primitives and drawings. Free 1 yr. update service available in the US. Send \$1500 by check, L/C or P/O. Dealers Welcome!  
CAD-CAM-II SRL  
Via Fornaci 1  
06034 Foligno ITALY  
Tel: (0742) 20921

### PLOTTER SOFTWARE

Presentation aides (word charts) are quick and easy to prepare using the DGI SIGNMAKER. With the DGI SIGNMAKER, your PC and plotter (IBM, HP, HI, Epson) your overheads, text slides or signs will have that professional look. \$75. For additional information, ordering or to check compatibility contact:  
Decision Graphics, Inc.  
P.O. Box 2776  
Littleton, CO 80161  
303-796-0341

### DIGITIZER SOFTWARE!

Make the most of your digitizer with Easy Digit software. Many features capture and manipulate x-y coordinates, areas, distances, etc. from graphic images on any type of document. Use output files with spreadsheets, databases or your own programs. \$495. Call today for advice on your application.  
OMNITECH, INC.  
50 Baltusrol Way  
Short Hills, NJ 07078  
(201) 376-6406

### FORTRAN GRAPHICS LIBRARY

MicroGlyph/Sciplot library provides IBM pro pr MS 3.2 FORTRAN graphics routines for high resolution IBM or Epson printers, color cards on IBM PC/XT/AT (PC DOS). Full plotting package 14 fonts, clipping, rotation, lin/log axes, multiple frames with (240 x 216) resolution. Price: \$59.95 + \$3 shipping + MA. tax.  
MicroGlyph Systems  
P.O. Box 1066  
East Arlington, MA 02174

### GRAF 3.0 PRINTER GRAPHICS

Create bar, pie, scatter, and line graphs on your Epson, C/Itoh, or IBM graphics printer. Supports 14 fill-in patterns, 8 plotting symbols, auto scaling, legend creation. Can read floating point data in a wide variety of formats. Requires DOS 2 or 3, 192K. \$69.95—includes USA shipping. No credit cards.  
MicroComputer Systems Consultants  
27-P Forest Avenue  
Port Jefferson Station, NY 11776  
(516) 928-7493

## SOFTWARE/LANGUAGES

### EASY WAY TO MASTER DOS!

New handbook shows how, why, and when to use all 44 PC & MS DOS commands quickly and easily! Lively hands-on tutorial makes learning fun, for a change. Covers basic thru advanced topics. All versions up to 3.1. Lots of practical examples. 221 pages only \$15.95 at bookstores, or send check + \$1.00 S&H to:  
LITTLE, BROWN & COMPANY PUBLISHERS  
200 West Street, Code T-368121  
Waltham, MA 02254  
1-800-343-9204 (credit cards)

### muLISP-85™ RELEASED

muLISP-85 is an integrated AI programming environment that includes over 350 Common LISP functions, a high performance compiler and interpreter, a window-oriented source file editor and debugger, an on-line tutorial system, and a detailed reference manual. Write or call for more detailed information.  
SOFT WAREHOUSE, INC.  
3615 Harding Avenue, Suite 505  
Honolulu, HI 96816  
(808) 734-5801

## SOFTWARE/OPERATING SYSTEMS

### pcSHARE MULTI-USER O/S

pcSHARE allows your IBM-XT or compatible to support up to 4 users running 123, dBASE, WordStar, etc on inexpensive serial CRTs. For the software developer, pcSHARE efficiently runs compiled Basic, Pascal & C programs with full DOS 3.0 record locking. No risk 30 day money back guarantee.  
DIGITROL COMPUTERS, INC.  
440 Phillip Street  
Waterloo, Ontario, Canada N2L 5R9  
(519) 884-4541

### CX/PC EXECUTIVE

Real-time, priority task scheduler. Functions to queue inter-task messages and pointers. Example tasks. Interrupt-driven timer, serial and parallel port interfaces. Runnable demonstration programs. DeSmet C source included; no license for generated programs. Described in June '84 IEEE Micro article. \$75. Brochure.  
INTR-SOFT CO.  
P.O. Box 351  
Bedford, MA 01730  
(617) 369-6242

## SOFTWARE/PUBLIC DOMAIN

### BEST OF PUBLIC DOMAIN

Fantastic Software at Unbelievable Prices!! We have put together 18 volumes of disk packages, all categorized and fully tested for easy selection. You may also order custom disks, with ONLY the software YOU need. Just \$4.00 for a Sampler Disk with our complete catalog, or \$1.50 for Catalog alone.  
COMP-U-SOFT  
2530 Berryessa Road, Suite 410  
San Jose, CA 95132  
(408) 272-9689

## SW/SCIENTIFIC

### MATRIX/CALCULATOR

Stand-alone programmable calculator with 70+ matrix operations, statistics, system of lin, & nonlinear & diff. eq'n's, numerical integral & 1-dim optimization. User programmable func. \$49.95 includes S&H, 100+ pg manual, 1 yr. tech support. 8087 version same price, VISA, MC accepted.  
SoftTech Inc.  
14640 La Belle  
Oak Park, MI 48237  
(313) 544-8544

## SOFTWARE/SECURITY

### SECURE AT/XT/PC

Control system access, data access! FIXT/S. Control system boot for most popular XT/PC hard disk controllers. Vfeature for AT-and-XT-compatible HD controllers segments hard disk by volumes, controls access with passwords, supports hard disk expansion. \$70-\$130 + \$3 shpg. plus CA tax.



Golden Bow Systems  
P.O. Box 3039  
San Diego, CA 92103  
(619) 298-9349

### SIDEVIEW: PC/AT MENU

Password protect your hard disk today! DOS 3.0/3.1 hard disk manager. Allows you to create color menus to run any program or DOS command. Prevent hard disk erasure. Works with XT's too. 25 pg manual. Money back guarantee. PO's & phone orders accepted. \$39 + \$3 shpg.  
Keller Software  
1825 Westcliff Drive  
Newport Beach, CA 92660  
714-642-5544



# TECH BOOK

## SOFTWARE/SERVICES

### TAPE TO DISK CONVERSIONS

Convert any 9 track magnetic tape to or from over 500 formats including 3 1/2", 5 1/4", 8" disk formats and word processors. Formats available include IBM-PC, Apple, Altos, TRS 80 8" CP/M, Displayer, IBM Sys/??, Macintosh, Wang, Lanier, OS/6 and 500 more. Disk to Disk conversions also avail. Call for more info. PIVAR COMPUTING SERVICES, INC. 47 W. Dundee Rd. Wheeling, IL 60090 (312) 459-6010

### DATA CONVERSION ON PREMISES

Keep your data confidential. To/FROM cards, disks, tapes, ASCII/EBCDIC, 800/1600/3200BPI 9-Track. For IBM-PC/XT/AT and the compatibles. Hard disk and Bernoulli Box owners, we will bring our systems and do the conversion on your premises. DP Modern Systems 804 North Reeder Avenue Covina, CA 91724 (818) 966-2628

## SOFTWARE/STATISTICS

### RATS!

RATS is the ultimate econometric software package. It is powerful, fast, accurate, and inexpensive. RATS performs regression analysis, time-series forecasting (including Box-Jenkins) and cross-section (including logit and probit). RATS supports a variety of data formats, including Lotus WKS files. RATS also offers a programming language that provides maximum flexibility and power. Spectral analysis and graphics are available as options. Base program \$200. Demo including 300 page manual \$40. MC/VISA. VAR Econometrics P.O. Box 19334 Minneapolis, MN 55419 (612) 822-9690

### DEMOGRAPHIC DATABASE

NOTHING-BUT-THE-FACTS is a general purpose database on 32 diskettes that covers all the US countries and cities of 25,000 people or more. Includes data on agriculture, banking, crime, climate, education, government, housing, income, poverty, vital statistics, and much more. Manual, county map and storage cases included. Ideal for market research. \$290 MC/VISA. Melissa Data Co. 12 Balboa Cores Newport Beach, CA 92663 (714) 650-1000

## SOFTWARE/TERMINAL EMULATION

### VT-102 & 4010 EMULATION

PC 102 turns an IBM PC/XT/AT/ir to a VT-102/100/52 terminal with printer/file transfer support. Optional: 132 col., 4010 graphics support. Guaranteed compatibility with all VT-100/52 applications including EDT, WORD II, All-In-One, & UNIX. Easy to use. 3000+ sold. From \$89. MC/VISA/COD. Call for free package! Moneyback guarantee. General Micro Systems P.O. Box 5330 Hopkins, MN 55343 (612) 944-0593

## SOFTWARE/UTILITIES

### NOBLINK™

ErGoNoMiCs! Eye strain? With just a keystroke you can change your blinking cursor into a friendly solid block reverse video cursor. If you wish you can change it back and forth (Blink/No blink) right in the middle of a program, such as your word processor. Give your eyes a rest. \$29.95 plus \$5 s&h. NOSTRADAMUS 5320 South 900 East Salt Lake City, UT 84121 (801) 261-0769

### AT/XT/PC HARD DISK EXPANSION

Replace hard disk with a bigger one, or add a second drive! Vfeature supports high capacity drives on standard AT, XT, and compatible hard disk controllers. Includes multiple volumes, security features, selectable clusters, keyboard lock. \$80-\$120 + \$3 shipping + CA tax.



GOLDEN BOW SYSTEMS  
P.O. BOX 3039  
SAN DIEGO, CA 92103  
(619) 298-9349

### DISPLAY ANY MS-DOS FILE

List ASCII and binary files. TRUE/View can be invoked as a pop-up or directly from DOS. Switch between ASCII and hex modes. View multiple files. Search for string patterns. Mark file positions for easy retrieval. Make small changes with edit feature. User configurable. \$19.95 GRW Software P.O. Box 440007 Houston, Texas 77244 (713) 556-9878

## TRUE PATH UTILITY

Never misplace files again. TRUE/Path extends the MS-DOS PATH utility to search for data files as well as programs. Unlike other path programs, TRUE/Path uses the same path given by the MS-DOS PATH command to locate data files. Works with all MS-DOS software. A perfect for inexperienced users. \$19.95 GRW Software P.O. Box 440007 Houston, Texas 77244 (713) 556-9878

### EASY AIM-30 day trial

Installs your programs on a hard disk and creates subdirectories, paths, and displays programs in a menu, all automatically. Features include time log, backup to floppy or tape, copy files to/from floppies to/from/between menu selected directories. DOS is transparent to end user. Powerful yet simple. \$84.95. LARSON SYSTEMS, INC. BOX 193 STORY CITY, IOWA 50248 (515) 733-2717

### DISK MECHANIC

THE ULTIMATE Floppy Disk Backup & Repair Utility. Can back up ALL software protected disks written on the IBM PC. Works manually or automatically. Files or sectors can be restored, searched, examined & changed. Checks disk drive speed, req. IBM PC, XT, AT, DOS 1, 2, 3, 192K + 64K if only 1 floppy drive. \$73 ppd. USA MLI MICROSYSTEMS PO BOX 825, Dept TB2 Framingham, MA 01701 USA (617) 926-2055 for info MC/VISA

### PRINTERWINDOW™

Printer utilities for IBM PC & Compatibles.

- Pop-up memory resident printer control.
- Epson & IBM printer emulation.
- Multi-size screen dumps; text formatting.
- Font editor; Wordstar installation & more.

Packages available for NEC, CITOH, OKIDATA, EPSON and other popular dot matrix printers. Info & demo disks available. \$49, VISA/MC accepted. Courtrin Enterprises, Inc. P.O. Box 231190 San Diego, CA 92123 (619) 569-8308

### CHARACTER CUSTOMIZATION

CHARGEN! works with the IBM EGA to let you modify the character set, allowing many word processors to display technical material, equations or other special characters. Also works on the Color/Graphics Adapter in graphics modes. Requires DOS 2.x or 3.x, IBM Standard or Enhanced Graphics Adapter. \$25 + \$2 s/h (MN add 6%). DK Micro Consultants P.O. Box 6714 Minneapolis, MN 55406 (612) 722-0931

## DISK MANAGER

Why not be organized? LIBBY 2.0 is a full-featured disk librarian that can fully organize any disk library—consolidates hard/floppy directories into 1 master file. Professionally written, ver. 2.0 supports hard disk/DOS 2.0 & later/numerous report & search options. 128K, 2 drives. \$29.95 USA. ADVANCED PC SYSTEMS 3080 Summerhill Court San Jose, CA 95148 (408) 270-6248 for info, VISA/MC

### 32-bit TURBO INTEGERS

We LOVE TURBO PASCAL. One SHORT complaint: NO LONG INTEGERS! We wrote a 32-bit integer package in ASSEMBLY LANGUAGE! It's SMALL, FAST, and includes RUN-TIME error CHECKING! First 100 orders get a million-record SORT package OR a \$5 rebate (please specify when ordering). \$24.95 + \$1 s&h. Cauthorn & Associates 1811 N. Kaspar Arlington Heights, IL 60004 (312) 259-3930

### EXPECT A MIRACLE

\$10

- Packed Utility Disk
- For IBM PC
- Hot Stuff!!

..... \$10 .....

## Packed Utility Disk

Micro Tools Inc. P.O. Box 357 North Chili, NY 14514 (716) 594-1088

### HARD DISK DIRECT ACCESS™ 4.0

The Ultimate Hard Disk Menu System. Organizes your software programs into a "user defined" menu system. Features single key stroke access, time usage tracking, custom applications, plus much more. Order toll free today. 30 day money back guarantee.



Delta Technology International Inc. P.O. Box 1104 Eva Claire, WI 54702 To order: 1-800-242-MENU For more info.: 715-832-0958



# TECH BOOK

## dBASE II AND dBASE III

CHECK corrects nesting and locates errors in dBASE command files. Custom configuration for all default values. Accepts dWINDOW and Clipper commands. \$49.00. REPAIR recovers data from corrupted databases by resetting the record counter, offsetting if required, and relocating the EOF marker. \$29.00.  
HILCO SOFTWARE  
304 North 17th Street  
Mount Vernon, WA 98273  
(206) 428-0475

## VM/CMS FLIST FOR IBM-XT

Full function DOS hard-disk shell. Functions like VM-ISPF mainframe mini-disk manager. Functions include definable function keys, directory sorting, online help feature, can execute PC-DOS commands & user programs from shell, and changeable screen colors. Have mainframe power on your IBM-XT. Only \$50.  
JASPER SOFTWARE  
6102 Mockingbird Lane, Suite 221  
Dallas, Texas 75214

## FSD: FULL SCREEN DOS.V2

Full Screen DIR list(s). Multi-1-day key commands. Sort 8+ ways, split-screen & resident/loaded modes. Copy/Move with Replace/No-Replace. User defined F-Keys. Interactive BAT files. Log PC usage. +Other features. Docs on disk. PC/XT/AT etc. w/128K, DOS 2.0+. \$49.95 w/hardcopy docs. \$29.95 w/disk docs. +\$5 for Non-DOSDD specify.  
TORTUS SOFTWARE  
14051 Lambeth  
Tustin, CA 92680

## RE/CALL™

The best macro-processor for PCs. Make pop-up menus to list/control macros inside any program. Unique and essential correct and step mode—like 123. Only editor that never truncates macros or becomes unavailable. "Slick. Enticing features"—Pop Cmp. "Unique step mode"—Tech Journal. "Natural and intuitive"—PC Products. "... deserves a home in every PC"—PC Week. US \$89.95. 30 day money back guarantee. VISA/MC/COD.



YES SOFTWARE INC.  
390-10991 Shellbridge Way  
Richmond, BC, Canada V6X 3C6  
(604) 270-4152

## COMPARE ASCII FILES

Is the COMP command in DOS what you expected? No? That's what we thought. Our little program CAF is a very smart utility similar to the ones in mainframes. CAF compares two ASCII files and produces a no-nonsense differences report. A must for all PC programmers & users. Only \$12.95 + \$3 s&h (Calif. + Tax). Send check or money order to:  
I.S.E. Inc.  
P.O. Box 241740  
Los Angeles, CA 90024  
(213) 398-3106

## !! IBM USES CPM DISKS!!

"The best CP/M to DOS converter" PC mag, 4/85. UniForm transfers files, formats, reads and writes DIRECTLY to 100 + CP/M disk formats on your IBM PC, XT, AT (with also 96 TPI & 8"). Uses normal DOS commands. Next day shipping. Dealers invited. UniForm by Micro Solutions. \$59.95 + \$3 S&H. MC/VIS, check, COD, no PO's.  
Blue Heron  
RR1 Box 128E  
Maple Park, IL 60151  
(815) 895-5602

## LASERDRIVE

A path to your laser printer! Loadable device driver transmits any file to laser printers via RS232. Background to foreground. Uses Xon/Xoff protocol. Also ASCII file listings, line printer emulation. Use Apple LaserWriter, Imagen, QMS, HP LaserJet Plus, Postscript, etc. MS DOS 2.1/later. \$49.95  
TEXTSET, Inc.  
P.O. Box 7993  
Ann Arbor, MI 48107-7993  
(313) 996-3566

## THE NIBBLER 2.0

Provides ultimate DATA INTEGRITY for DOS systems. Powerful, easy and up to 10X FASTER than NORTON! 2-key UNERASE. Edit-View sectors encrypt, wipe or copy files. SEARCH memory, files or disks. View and edit 1MEG of memory. Supports IBM-AT, FIXED, and RAM disks. DOS 2.x + \$49.95 + \$2.50 S&H. CA 6% CHK-MC DEALERS WELCOME!  
TACHYON SYSTEMS INC.  
2725 Congress St. Suite 2H  
San Diego, CA 92110  
(619) 574-1666

## POP-UP SHOWFILE UTILITY & POP-UP DIRECTORY SUPPORT

DK SHOWFILE is a RAM-resident or DOS loadable utility for displaying all types of DOS files. Anytime. Variable view window, string search, help key, ASCII/HEX/EBCDIC display modes & more. Instant recall feature keeps a file & view window only a keystroke away—great for debugging! \$29.95  
DK DIRECT, also RAM-resident, brings DOS sub-directory support to most programs. \$24.95.  
DK Softworks  
P.O. Box 201182  
Austin, TX 78720  
(512) 345-3684

## PreCursor

Makes the hard disk easy. Create menu pages containing applications, BASIC programs, batch files or DOS commands with ease. Then let PreCursor automatically search for the directory and path, showing you all occurrences of a program on your hard disk; no manual input required. Includes on-line help, triple level passwording, even screen color options. 30-day Moneyback Guarantee \$69.00 plus \$5 s&h. VISA/MC.



David L. Aldridge Co., Inc.  
340 Town & Country Village  
Houston, TX 77024  
(713) 464-7465

## BACKBONE

Give a PC/XT/AT BACKBONE! Customize sets of linked menus with a Menu Processor (tm): Then access any program, batch file, or submenu with a keystroke. Adds POWER, STRUCTURE, and SIMPLICITY to any system. The IDEAL hard disk organizer. Supports multiple users. Compact, Fast, Guaranteed, and Well-Supported. \$39.95 + \$4 s/h. MC/VISA.  
SYNCHRONY SYSTEMS  
4191 San Juan Ave.  
Jacksonville, FL 32210  
ORDERS: (800) 237-6360 ext. 314  
(800) 282-1152 ext. 314 FLA

## SOFTWARE/WORD PROCESSING

### FORMATH™ TEXT-FORMATTER

For technical texts. Sizes & places equations, matrices, ratios, integrals, big symbols, footnotes. Macros, multiple fonts, 158 Greek/math symbols. Automatic hyphenation, section/equation/reference numbering, indexes, table of contents. Dot-matrix, daisywheel, laser printers, plain/graphics monitors. \$400. \$50 for demo.

$$\lim_{n \rightarrow \infty} \sum_{k=1}^n \left[ \frac{1}{k(k+1)} - \frac{1}{2^k} \right] = \frac{1}{2} \left[ \int_0^1 \frac{\log(1-x)}{-x^2} dx - 1 \right]^{-1}$$

SHANTHA SOFTWARE, INC.  
50 West 97th St. Room 11N  
New York City 10025  
212-222-7647  
Touch-tone Toll-free: 950-1088-wait-FORMATH



## REPRINTS AVAILABLE

Quantity reprints of articles appearing in PC Tech Journal are available and will be prepared to meet any special requirements. Inquiries should be directed to Eileen Pfeiffer, Reprints Dept., Ziff-Davis Publishing Co., 1 Park Ave., New York, New York 10016. Phone 212-503-5447.

TECH  
JOURNAL



# TECH MART

64K ■ 128K ■ 256K  
**DRAMS**

80287-8 ■ 80287-3

8087-3 ■ 8087-2

8087-1

**BITTNER**  
**EE**  
**ELECTRONICS**

899 SOUTH COAST HIGHWAY  
LAGUNA BEACH, CA 92651  
(714) 497-6200  
CALL NOW FOR **FREE CATALOG**

CIRCLE 385 ON READER SERVICE CARD

## Learn the C Language Interactively

Step-by-Step With  
*Introducing C*

Introducing C is a powerful C language training system that combines a thorough, self-paced manual with a unique C INTERPRETER to provide a fast efficient method of learning C.

### A COMPREHENSIVE APPROACH

Introducing C covers all the essential elements of C. The Interpreter utilizes standard K&R syntax and operators - full structures and unions, arrays, pointer and data types. It provides the standard I/O library and an extended graphics library. The package has many user oriented features including a screen text editor and extensive error diagnostics (includes dynamic trace capabilities).

### INTRODUCE YOURSELF TODAY

Introducing C is available for immediate delivery. System requirements are IBM PC, XT or AT with one disk drive and 192K bytes of memory. Priced \$125.00. Not copy protected.

**TO ORDER CALL 800-922-0169**

**COMPUTER  
INNOVATIONS, INC.**

980 Shrewsbury Ave., Tinton Falls, NJ 07724 • (201) 542-5920

CIRCLE 381 ON READER SERVICE CARD

### GRAPHICS

- Text/graphics generics
- 2D interactive
- 2D plots (full support) including auto-scaling, auto-axis generation, auto-labeling, tabular/log/parametric curves, splines, bars, pies, you name it, we have it.
- 3D Plots incl. 2 hidden line removal options—not just old-fashioned wire frame.

### PEN PLOTS

- Standard plotter primitives plus
- FULL 2D support plus
- Interface to screen graphics,
- Limited 3D.

Clear and complete documentation.

**GRAFATIC** \$135.

**PLOTATIC** 135.

### MICROCOMPATIBLES

301 Prelude Drive  
Silver Spring, MD 20901  
(301) 593-0683

CIRCLE 400 ON READER SERVICE CARD

## TOPVIEW SPOOLER

**TV SPOOL** is a TopView specific program which provides printer spooling capabilities normally found on large operating systems.

**TV SPOOL** incorporates the same user-friendly menu style as TopView and enhances the TopView environment with a flexible mechanism for printing files.

- Spool Queue Management
  - 100 Entries • Disk Resident
- Previous Page Buffer
  - Backup and Advance
- Banner Processor
  - DOS 3.1 Separator Format
- Flexible Options
  - Delete After • Multiple Copies

**INTRODUCTORY PRICE IS \$60.00**  
Visa, M/C Accepted


**RIX Softworks, Inc.**

17971-E Skypark Circle • Irvine, CA 92714

**(714)261-0440**

CIRCLE 391 ON READER SERVICE CARD

Create your own  
unique PC interfaces  
in minutes!



The PD100 allows rapid development of specialized PC interfaces. It features a buffered data bus, switch-selectable address decoder, and a large prototype area (up to 40 IC sockets). The 116-page manual covers basic interfacing concepts and details implementing A/D, D/A converters, I/O ports, connection of transducers and dozens of useful circuits.

PD100 w/manual - \$99

plus \$3.50 P&H

Manual only - \$20 Postpaid

PA residents add 6%

Check, MasterCard, or VISA (814) 234-8087

**REAL TIME DEVICES**

1930 Park Forest Ave.

P.O. Box 906

State College, PA 16804

## FASTER SCREEN WRITING...

just the beginning

for a new type of program:

**FANSI~  
CONSOLE™**

The Integrated Console Utility™

As reviewed in Lotus June 85 pg 8:  
"Psychological difference is  
astonishing". For IBM-PC, XT, AT &  
clones. Shareware disk \$25 or 325p  
Manual (w/slip case) & disk \$50.

**HERSEY MICRO CONSULTING, INC.**  
Box 8276E, Ann Arbor, MI 48107  
(313) 994-3259 x363 **VISA/MC**

CIRCLE 386 ON READER SERVICE CARD

## TERMINAL EMULATION

**Softerm PC** emulates over 30 popular terminals including the:

- DEC VT102, VT220
- Data General D200, D410
- IBM 3101-20 (block mode)
- Hewlett-Packard 2622A
- Honeywell VIP7801, VIP7803

### Guaranteed Compatibility

Call for free product brief

**\$195 MC-VISA-COD**

For the IBM PC/XT/AT, DG1, NEC, Wang PC, TI Pro, Gridcase, Tandy

**SEIFTRONICS**

7899 Lexington Dr., Ste 210  
Colorado Springs, CO 80918  
(303) 593-9540

CIRCLE 394 ON READER SERVICE CARD

## PERFECT COPIES GUARANTEED

Why risk duplicating your important programs on your computer, when our equipment is designed solely to duplicate disks and verify their perfection 100%?

Over 600 formats. 3 1/2", 5 1/4" and 8". Plus serialization, copy protection, labeling, packaging, shrink-wrapping and fast, personalized service.



**Western  
Transdata Inc.**  
DISK DUPLICATION

1701 E. Edinger Ave.  
Building A4  
Santa Ana, California 92705  
(714) 547-3383 (Collect)

CIRCLE 396 ON READER SERVICE CARD

## Vscreen For Turbo Pascal

Vscreen - a professional virtual screen management system.

- For Turbo Pascal 3.0+ , PC's and real compatibles.
- FAST - Direct video manipulation in assembly language.
- 255 Virtual screens... up to 64k per screen.
- Windows can drag, resize, pop up, slideout, explode...
- Scroll horizontally and vertically.
- Fully automatic window overlap control.
- Formatted I/O-at-say, atget with full validation.
- Compatible with standard Turbo screen syntax.
- Mono or color-no snow, no flicker, "instant" updates.
- Flexible frame and title control.
- Mouse ready.
- Most sophisticated routine for the PC color card.
- Advanced Numeric and string formatting.
- Insert or delete lines, characters, line wrap/no wrap, recolor/highlight areas, cursor control.

Why compile hundreds or thousands of lines of Pascal source each time for a feeble, slow running windowing package when you can have a full virtual screen management system written in assembly language?

Pascal source and assembly "com" file: \$59.95  
With 100k of assembly language source: \$99.95

**Northport Software**  
1817 Domanik Dr.,lg  
Racine WI 53404

For orders call:  
414-637-7540

WI residents add 5% sales tax

Turbo Pascal is the trademark of Borland International



# TECH MART

## Sort RM/COBOL Files QISORTC

Finally, a sort utility for RM/COBOL. Using efficient algorithms in assembly language making it the fastest sort on the MS-DOS market. Qisortc supports:


- RM/COBOL Version 1.5x & 2.xx files
- Single / Dual File Indexed
- Relative and Sequential
- ASCII, COMP-1, & COMP-3 fields
- 32 sort control fields
- ascending / descending
- 32 record selection fields
- EQ, NE, GT, GE, LT, LE field constant
- implied AND, OR may be specified
- 32 output fields or total record
- CALL from RM/COBOL, when provided subroutine is linked with runtime
- Use pathnames and return codes
- Keyboard or Parameter file
- Requires MS-DOS ver 2.xx or above
- Only \$95.00 - COD, VISA, or M/C.

### Quantum Information Systems, Inc.

145 N.W. 85th St., Suite 103  
Seattle, Washington 98117  
(206) 789-2888 Telex 4941041

CIRCLE 383 ON READER SERVICE CARD

## RS-422 Communications Board



- For IBM-PC/AT/XT and compatibles
- Dual RS-422 serial interface
- Programmable to 56k baud
- Differential drivers to 4000 ft.

**\$345.00**

**QUA TECH, INC.**

478 E. Exchange St. Akron OH 44304  
(216) 434-3154 TLX: 5101012726

CIRCLE 384 ON READER SERVICE CARD

## Text Librarian

### The Perfect Answer for the Storage and Retrieval of Text Files

ORGANIZE your text files into SPACE SAVING LIBRARIES. PROGRAM SOURCE modules are a perfect example. Always up to date, the TEXT LIBRARIAN checks for most recent version during update. For EVERY DAY USE or ARCHIVING, your files are always EASILY ACCESSED and BACKED-UP for DATA SECURITY.

Extensive Library Management Features include:

CONTEXT PATTERN SEARCH OF LIBRARY CONTENTS WITH QUERY  
QUERY MODE TO EXTRACT, DELETE, LIST, UPDATE/APPEND  
ALPHA DIRECTORY DISPLAY/SEARCH WITH QUERY  
— MIX COMMANDS —

A compliment to any word processor

8086/88 MS DOS 1.25 AND UP/GENERIC

Currently on UNPROTECTED IBM format for **\$54.95**

**DATA  
VISIBLE CORPORATION**

P.O. BOX 7767, CHARLOTTEVILLE, VA 22906  
CIRCLE READER SERVICE CARD NUMBER

CIRCLE 387 ON READER SERVICE CARD

## INDEX TO ADVERTISERS

PC TECH JOURNAL FEBRUARY 1986

### READER

SERVICE NUMBER ADVERTISER PAGE

110	Advanced Computer Solutions	100
116	Advanced Logic Research	Cover 3
104	Advanced Logic Research	70
109	Aldebaran Laboratories, Inc.	187
108	Alloy Computer Products, Inc.	76
101	Alpha Computer Service, Inc.	140
103	American Small Business Computers	56
136	Arity Corporation	129
203	Atron	10

114	Blaise Computing, Inc.	162
250	Borland International	35
251	Borland International	37
145	Business Tools, Inc.	177

*	C Ware Corporation	164
162	CXI, Inc.	84-85
111	Catamount Corp.	196
156	Cauzin Systems, Inc.	8-9
121	Central Point Software	143
122	Chalcedony Software	103
142	Classic Technology Corp.	52
227	Command Technology Corp.	186
117	Concept Technologies, Inc.	94
179	Core International	152
112	Cosmos, Inc.	42-43
107	Creative Programming	173

118	DataAccess Corp.	151
215	Data Base Decisions	5

212	Earth Computers	185
131	Ecosoft, Inc.	176
170	Ellis Computing, Inc.	118
234	Emerald Technology Group, Inc.	54
158	Entelkon	141
140	Essential Software, Inc.	168
133	Everest Solutions, Inc.	Cover 2

119	FairCom	183
217	Fifth Generation Systems	145
229	Flagstaff Engineering	74
163	Floppy Disk Services, Inc.	124

113	Genesis Microsystems	189
*	Gimpel Software	144
105	Greenleaf Software	120
153	Guidance Software	119

135	Hawaiian Village Computer Software, Inc.	115
144	Heuristic Computer Systems	195

202	I-Bus Systems	148
149	IBEX Computer Corp.	196
147	IBM	104-105
132	IMPACC Associates, Inc.	23
159	Integrated Micro Technology	198
216	Intel Corp.	64-65
209	Interactive Microwave, Inc.	195
177	Interlink Systems, Inc.	188

146	K Software House	198
244	Kamerman Labs	13
188	Kimtron Corporation	157

128	Lahey Computer Systems, Inc.	149
150	LaSalle Micro	80
160	Lattice, Inc.	170
204	Logiquist, Inc.	191

*	McGraw-Hill Continuing Education Center	17-19
208	Manx Software Systems	38
139	Meridian Technology	96
106	Merrill Street Software	175
141	Micro Data Base Systems, Inc.	146
207	Micro Data Base Systems, Inc.	192

### READER

SERVICE NUMBER ADVERTISER PAGE

120	Micro Data Base Systems, Inc.	72
211	Micro Data Base Systems, Inc.	92
*	Microrim	178-179
*	Microsoft Corp.	30
*	Microsoft Corp.	41
*	Microsoft Corp.	131-138
213	Micro-Software Developers	208
167	Microstuf, Inc.	Cover 4
125	Mix Software	117
194	Mountain Computer, Inc.	106-107

226	NightOwl Software, Inc.	127
166	Novell Inc.	6-7

222	Opt-Tech Data Processing	4
185	Overland Data, Inc.	188

171	PC Brand	86-87
230	Paradise Systems	28-29
180	Pecan Software Systems, Inc.	113
138	Peter Norton	150
169	Phoenix Computer Products Corp.	171
205	Phoenix Computer Products Corp.	116
198	Pro/Am Software	150
219	Productivity Products International	199
175	Programmer's Connection	26-27
176	Programmer's Connection	25
220	Programmer's Shop	44
151	Programmer's Shop	46-47

210	Quadram Corp.	22
-----	---------------	----

157	Rainbow Technology	208
181	Rational Systems, Inc.	155
165	Real Time Devices, Inc.	190
143	Relational Data Base Systems, Inc.	142

232	Schuller & Associates	195
187	Scientific Endeavors	196
124	Seattle Telecom & Data, Inc.	60
186	Simware, Inc.	78
164	SofCap Inc.	130
214	Soft Advances	208
201	SoftCraft	2
178	SoftLogic Solutions	125
192	Software Bottling Co. of NY	21
168	Software Masters	158
152	Software Masters	16
123	Solution Systems	14
130	Solution Systems	23
126	Solution Systems	166
129	Solution Systems	166
190	Speedware	196
242	Spruce Technology Corp.	198
183	Sterling Castle	126
195	Summit Software Technology, Inc.	180
196	Summit Software Technology, Inc.	62
155	Sunny Hill Software	156
228	Systems & Software, Inc.	195

154	TLM, Inc.	174
237	TLM Systems	163
236	TLM Systems	165
238	TLM Systems	167
193	Tall Tree Systems	58
225	Tecmar	98
240	TECH. PC Personal Computers	24
184	Thesys Memory Products Corp.	182

115	Vermont Creative Software	20
-----	---------------------------	----


200	Wendin	123
221	Wizard Systems Software, Inc.	198
102	WordTech Systems	122

148	Zanthe Information, Inc.	1
134	Zedcor	121



# SOFTWARE SENTINEL™

MUCH  
MORE THAN  
JUST PROTECTION



Because its original objective was to protect software from unauthorized use, it's called the SOFTWARE SENTINEL. But maybe we'll change the name to *REVENUE GENERATOR*, since we've discovered its true value to our customers. But whatever we call it, everyone ends up with numerous benefits from this hardware key with unlimited "locks":

## SOFTWARE DEVELOPER (PC, XT, AT)

- Prohibits unauthorized use of software
- No need for copy protection
- Easily controlled site licensing
- Unbreakable protection
- Lower cost of distributing updates
- Longer product/revenue life cycle
- Trial usage/rental of software programs

## USER (PC, XT, AT)

- Unlimited backup copies
- No floppy required with hard disk
- Transportable
- Pocketsize
- Transparent
- Data security

EVALUATION KIT AVAILABLE



17971 SKYPARK CIRCLE SUITE, IRVINE, CA 92714 (714)261-0228 Ext 200  
Telex 386-078 Answer Back—RAINBOW TECH

CIRCLE NO. 157 ON READER SERVICE CARD

## Excellence

In your job, it depends on having the best tools available at your disposal. With such tools, your productivity increases and your work becomes easier.

Wisely, you keep a sharp eye open for products using the latest technology.

You have now located the source of advanced debugging technology for PC-DOS.

More powerful debugging software is not available anywhere...at any price. Yet the cost is affordable to even the smallest budget.

*DSD-86...New and innovative design combines the most sophisticated user interface with the most flexible display to create a new generation of debugging technology for the IBM PC. Only 69.95*

*SA* SoftAdvances

P.O. Box 49473 - Austin, Texas 78765 - (512) 478-4763

Visa & Mastercard Accepted.

Please include 4.00 for shipping and handling.

CIRCLE NO. 214 ON READER SERVICE CARD

NOW  
for Microsoft  
C version 3.0

## the source debugger for lattice C

Your time and convenience come first! The MSD C Debugger™ is the last, and perhaps final, word in programming assistance for Lattice C users. C Debugger produces a high level view of C programs via function names, line numbers, variable names and C data types, plus a low-level view of machine addresses and instructions for testing assembler language functions.

### More features include:

- All documentation is prepared for programmers.
- Online help screen throughout the process.
- Capability to single step through your program.
- Set break points, examine registers and variables.

\$165.00 + \$3.50 shipping



To order, call or write:  
**MICRO-SOFTWARE DEVELOPERS, INC.**  
214½ W. Main St. • St. Charles, IL 60174  
312/377-5151  
Lattice C is a trademark of Lattice, Inc.  
Microsoft is a trademark of Microsoft Corp.

CIRCLE NO. 213 ON READER SERVICE CARD

## WE DESCRIBE OVER 43,000 COMPUTER PRODUCTS SO YOU CAN FIND THE ONE THAT'S RIGHT FOR YOU


In the complex, ever-changing computer market you've got to play it smart. Which means making the right product choices without wasting time and money.

Which means **DATA SOURCES**...the one truly comprehensive reference to computer hardware and software.

**DATA SOURCES** puts information about 25,000 software packages, 18,000 hardware and data communications products and detailed profiles of 10,000 manufacturers right at your fingertips.

With a **DATA SOURCES** subscription you'll never have to worry about information being out of date.

Every three months you'll get a new two-volume edition—A *Hardware Volume* with descriptions of Computer Systems, Graphic Systems, Digitizers, Plotters, Printers, Disk and Tape Memory Equipment, CRTs, Expansion Boards and Data Communications Equipment PLUS a *Software Volume* with the most complete listings to be found anywhere on applications and systems software including database managers, utilities, and communications packages. A separate section includes company profiles for quick evaluation of vendors.




To subscribe, call toll-free 1-800-443-0100, ext. 251. We'll send your first two-volume edition on a 30-day approval basis and enter your one year (four editions) subscription for just \$230—more than 24% off the regular price.

**DATA SOURCES**  
THE ONLY COMPREHENSIVE BUYERS  
GUIDE TO THE COMPUTER INDUSTRY.  
P.O. Box 5845, Cherry Hill, N.J. 08034



CIRCLE NO. 137 ON READER SERVICE CARD





## FEBRUARY

### February 3-6 Second International Conference on Data Engineering Los Angeles, CA

Sponsor: IEEE-CS  
Contact: Second Data Engineering Conference, 1730 Massachusetts Avenue, NW, Washington, DC 20036-1903; 202/371-0101

### February 4-6 Fourth Working Symposium on Oceanographic Data Systems La Jolla, CA

Contact: Daniel Steiger, Code 5003, Naval Research Lab, Washington, DC 20375; 202/767-3265

### February 4-6 Computer Science Conference/SIGCSE Symposium Cincinnati, OH

Sponsor: Association for Computing Machinery  
Contact: Lawrence Jehn, University of Dayton; 513/229-3831

### February 4-7 UniForum International Conference of UNIX Users Anaheim, CA

Contact: usr/group, 4655 Old Ironsides Drive, Suite 200, Santa Clara, CA, 95054 408/986-8840

### February 9-12 Eleventh Annual SAS Users Group International Conference Atlanta, GA

Sponsor: SAS Users Group  
Contact: Don Henderson, ORI, Inc., Suite 250, 122 C Street, NW, Washington, DC 20001; 202/737-2666

### February 10-11 Micro-Mainframe Links Washington, DC

Sponsor: Digital Consulting Associates, Inc.  
Contact: Software Institute of America, Inc., 8 Windsor Street, Andover, MA 01810; 617/470-3880

### February 10-12 Industry Update: Manufacturing Dallas, TX

Sponsor: INFOMART  
Contact: Barbara Mooschekian, 1950 Stemmons Freeway, Dallas, TX 75207; 214/746-3500

### February 15-16 SOFTEACH San Francisco, CA

Sponsor: Softsel Computer Products, Inc.  
Contact: 800/325-9189

### February 16-19 PC Forum Phoenix, AZ

Sponsor: RElease 1.0 and EDventure Holdings Inc.  
Contact: RElease 1.0; 212/503-5500

### February 24-25 4th and 5th Generation Data Management Software Boston, MA

Sponsor: Digital Consulting Associates, Inc.  
Contact: Software Institute of America, Inc., 8 Windsor

Street, Andover, MA 01810; 617/470-3880

### February 24-28 ACM SIGAda Meeting Los Angeles, CA

Contact: Ben Grosco, Alsys, Inc., 1432 Main Street, Waltham, MA 02145; 617/890-0030

### February 26-28 Fifth Annual Phoenix Conference on Computers and Communications Phoenix, AZ

Contact: IEEE Computer Society, 1730 Massachusetts Avenue, NW, Washington, DC 20036-1903; 202/371-0101

## MARCH

### March 3-5 Relational Database Management Systems Washington, DC

Sponsor: Digital Consulting Associates, Inc.  
Contact: Software Institute of America, Inc., 8 Windsor Street, Andover, MA 01810; 617/470-3880

### March 3-6 Compcon Spring 86 San Francisco, CA

Contact: Glen G. Langdon Jr., IBM, Department K54/282, 5600 Cottle Road, San Jose, CA 95193; 408/256-6454

### March 3-6 First International Conference on CD ROM Seattle, WA

Sponsor: Microsoft Corporation

Contact: Min S. Yee, Conference Chairman, Microsoft Corporation, 10700 Northrup Way, Box 97200, Bellevue, WA 98009; 206/828-8080

### March 10-12 1986 Eastern Simulation Conferences Norfolk, VA

Contact: Society for Computer Simulation, P.O. Box 17900, San Diego, CA 92117; 619/277-3888

### March 18-20 VAR Congress '86 Dallas, TX

Sponsor: INFOMART  
Contact: Nancy Keene, 1950 Stemmons Freeway, Dallas, TX 75027, 214/746-3500

### March 19-20 IMPACT '86 Albuquerque, NM

Sponsor: Association for Information and Image Management  
Contact: Susan Law, P.O. Box 27036, Albuquerque, NM 87125; 505/846-4042

### March 24-26 OAC 86: Office Automation Conference Houston, TX

Contact: OAC 86, 1899 Preston White Drive, Reston, VA 22091; 800/OAC-1986

### March 26-28 ACM SIGUCCS Computer Center Management Symposium St. Louis, MO

Contact: Lawrence Westermeyer, 8001 Natural Bridge Road, St. Louis, 63121; 314/553-6000



RS#	PRODUCT	ADVERTISER	PAGE	RS#	PRODUCT	ADVERTISER	PAGE
<b>IBM COMPUTERS AND COMPATIBLE UNITS</b>				215	Periscope	Data Base Decisions	5
116	ALR XT and AT	Advanced Logic Research	Cover 3	158	C Library C Windows	Entelekon	141
104	ALR System 286	Advanced Logic Research	70	140	C Utility Library	Essential Software, Inc.	168
202	PC BUS	I-Bus Systems	148	133	H.E.L.P.	Everest Solutions, Inc.	Cover 2
147	IBM PC/AT	IBM	104-105	119	C-Tree	FairCom	183
240	TECH TURBO PC, XT, AT	Tech-Personal Computers	24	113	GeneLink	Genesis Microsystems	198
240	TECH, PC, XT, AT	Tech-Personal Computers	24	135	Turbo Isam Master	Hawaiian Village Computer S/W	115
<b>ACCESSORY CARDS</b>				144	HCS/Editor	Heuristic Computer Systems	195
212	Turbo Slave	Earth Computers	185	159	Window Weaver	Integrated Micro Technology	198
110	Graphax	Advanced Computer Solutions	100	177	Turbo Matrix	Interlink Systems, Inc.	188
142	16-bit Monochrome	Classic Technology Corp.	52	160	C Compiler	Lattice, Inc.	170
212	Turbo ACCEL 286	Earth Computers	185	204	APPLICATION 1	Logiqest, Inc.	191
216	Above Board	Intel Corp.	64-65	208	Aztec C86	Manx Software Systems	38
230	Modular Graphics Card	Paradise Systems, Inc.	28-29	213	MSD C Debugger	Micro Software Developers	208
169	Pfaster	Phoenix Computer Products	171	125	Mix Editor/C Compiler	Mix Software	117
210	EGA/Color	Quadram Corp.	22	222	Productivity Tools	Opt Tech Data Processing	4
165	GPiB Interface	Real Time Devices, Inc.	190	171	Various	PC Brand	86-87
124	Top Board	Seattle Telecom & Data	60	138	Norton Editor	Peter Norton Utilities	150
193	ILaser Card	Tall Tree Systems	58	205	Pfinish	Phoenix Computer Products	116
184	Fast Card IV	Thesys Memory Products Corp.	182	198	DISnDATa	Pro/Am Software	150
236	Z80H Bluestreak	TLM Systems	165	214	DSD-86	Soft Advances	208
238	68010/68000 Coprocessor	TLM Systems	167	192	Screen Sculptor	The Software Bottling Co. of NY	21
<b>MASS STORAGE HARDWARE</b>				192	Window Sculptor	The Software Bottling Co. of NY	21
108	Streamliner Series	Alloy Computer Products, Inc.	76	201	Btrieve	Softcraft, Inc.	2
111	9 Track Tape System	Catamount Corp.	196	168	The Visible Computer	Software Masters	158
179	AT Plus	Core International	152	123	BRIEF	Solution Systems	14
217	Fastback	Fifth Generation Systems	145	190	Turbo Editasm	Speedware	196
149	TS-100 for IBM PC/XT	IBEX Computer Corp.	196	242	Firsttime	Spruce Technology Corp.	198
209	Data Acquisition Card	Interactive Microware, Inc.	195	183	Basic Prog. Tools	Sterling Castle	128
244	MASTERFLIGHT	Kammerman Labs	13	157	Turbo Professional	Sunny Hill Software	156
194	20MB Drive Card	Mountain Computer, Inc.	106-107	192	Flashcode	The Software Bottling Co. of NY	21
185	TC-PC and TC-50	Overland Data, Inc.	188	154	Screen Generator	TLM, Inc.	174
186	Micro to Mainframe	Simware, Inc.	78	115	Windows for C	Vermont Creative Software	20
228	Perstor	Systems & Software, Inc.	195	102	WordTech Compiler	WordTech Systems, Inc.	122
237	VCR Backup	TLM Systems	163	134	Zbasic	Zedcor	121
<b>ALTERNATE INPUT DEVICES</b>				135	Turbo Screen Master	Hawaiian Village Computer S/W	115
105	C Library/Greenleaf Functions	Greenleaf Software	120	135	Turbo Menu Master	Hawaiian Village Computer S/W	115
<b>INTEGRATED CIRCUITS</b>				<b>SOFTWARE UTILITIES</b>			
121	Copy II PC	Central Point Software	143	146	Scientific Calculator	K Software House	198
<b>SECURITY DEVICES</b>				106	SuperBatch	Merrill Street Software	175
157	Sentinel	Rainbow Technologies	208	232	File Master	Schuller & Associates	195
<b>COMMUNICATIONS HARDWARE</b>				164	HD Tune-up	SoftCap Inc.	130
234	PC/5251/PLUS	Emerald Technology Group, Inc.	54	178	Disk-Optimizer	SoftLogic Solutions	125
188	KT-7\PC	Kimtron	157	152	'Flash'	Software Masters	16
<b>COMMUNICATIONS</b>				<b>GRAPHICS SOFTWARE</b>			
162	CXI Micro to Mainframe	CXI, Inc.	84-85	103	Pro Design II	American Small Business Computers	56
150	BackComm	LaSalle Micro	80	117	Graphcard	Concept Technologies, Inc.	94
139	Carbon Copy	Meridian Technology	96	187	Graphic C	Scientific Endeavors	196
167	Transporter	Microstuf	Cover 4	<b>DATABASE MANAGEMENT SOFTWARE</b>			
226	MEX-PC	NightOwl Software, Inc.	127	251	Reflex	Borland International	37
166	SFT NetWare	Novell, Inc.	6-7	145	TAS'	Business Tools, Inc.	177
130	ZAP	Solution Systems	23	112	Revelation	Cosmos Inc.	42-43
225	5251 Emulator	Tecmar, Inc.	98	118	DataFlex	DataAccess Corp.	152
<b>SOFTWARE FOR PROFESSIONALS</b>				153	CCSM	Guidance Software, Inc.	190
101	The Statistician	Alpha Computer Service	140	211	MDBS III	Micro Data Base Systems, Inc.	92
156	Softstrip System	Cauzin Systems, Inc.	8-9	120	Knowledge Man 2	Micro Data Base Systems, Inc.	72
229	The Tape Connection	Flagstaff Engineering	74	143	Multi User R-BASE	Microrim	178-179
<b>LANGUAGES</b>				148	ZIM	Relational Data Base Systems, Inc.	142
136	Arity Prolog Compiler	Arity Corporation	129	<b>ARTIFICIAL INTELLIGENCE</b>			
250	Pascal Family	Borland International	35	141	Guru	Micro Data Base Systems, Inc.	146
122	PROLOG Interpreter	Chalcedony Software	103	<b>OPERATING SYSTEMS</b>			
131	'Ecosoft C'	Ecosoft, Inc.	176	200	PCVMS PCUNIX	Wendin, Inc.	123
170	Utah Software	Ellis Computing, Inc.	118	<b>NETWORKING PRODUCTS</b>			
132	Interactive-C	Gimpel Software	144	207	LAN Power	Micro Data Base Systems, Inc.	192
128	F77L Fortran Compiler	IMPACC Associates, Inc.	23	<b>LITERATURE</b>			
180	UCSD Pascal	Lahey Computer Systems, Inc.	149	•	Newsletter	Microsoft Corp.	28
219	Objective C	Microsoft Corp.	131-138	•	Book	Microsoft Press	23
181	Instant C	Pecan Software Systems, Inc.	113	<b>TRAINING PROGRAMS</b>			
126	PROLOG-86	Productivity Products, Inc.	199	•	Programming & Software Design	McGraw-Hill Continuing Education Center	17-19
129	LISP-86	Rational Systems, Inc.	155	<b>OTHER SERVICES</b>			
195	Better BASIC	Solution Systems	166	•	Newsletter	Microsoft Corp.	30
196	Better BASIC	Summit Software	180	•	CD ROM Conference	Microsoft Corp. (Press)	41
221	Wizard C-Compiler	Summit Software	62	<b>MAIL ORDER</b>			
<b>PROGRAMMER'S TOOLS</b>				163	Mail Order	Floppy Disk Services, Inc.	124
109	Source Print Utility	Aldebaran Laboratories, Inc.	187	176	Prog. Connection	Programmer's Connection	25
203	PC PROBE	Atron	10	175	Prog. Connection	Programmer's Connection	26-27
114	Performance Package	Blaise Computing, Inc.	162	220	Mail Order	Programmer's Shop	44
•	De Smet C	C Ware Corporation	164	220	Mail Order	Programmer's Shop	46-47
227	SPF/PC	Command Technology Corp.	186				
107	Vitamin C	Creative Programming Consultants	173				



# Upward Mobility

## ADVANCED LOGIC RESEARCH

### XT—ALR'S MOST POPULAR SYSTEM

On the Advanced XT Turbo System,, ALR has installed all the features leaving little need for add-ons.

The Advanced XT System has a 65% faster CPU, with 640K RAM and a 20 megabyte hard disk. Parallel, serial and clock/calendar ports are all standard. The swivel and tilt monitor and video controller provide sharp characters plus 720 x 350 graphics.



### AT—THE ALR SYSTEM 286

The ALR System 286 is based on the advanced 80286-8 16 bit microprocessor with a system clock rate of 8MHz. This performance results in running most IBM PC or XT software up to 350% faster. In seconds you'll be able to recalculate large spreadsheets and instantly load files.

#### THE DEAL:

**\$6,995**

To help you start your network system, ALR has packaged a powerful AT Tower, with two turbo XT workstations all networked and ready to perform.



**SPECIFICATIONS** — IBM PC AT Compatible, 80286-8 MHz CPU, 1 Mb RAM, opt 2 Mb RAM (On Board), 1.2 Mb Floppy, 30 Mb Hard Disk (FAST 40 MS Access) Printer Port (On Board), Dual Network Port (On Board), 720 x 350 Mono. Graphics, 83 Key Keyboard, 6 Unused Expansion Slots.

### ADVANCED LOGIC RESEARCH—ALR

At ALR our systems all have UPWARD MOBILITY built in. We start by designing the maximum flexibility in our advanced main system boards, resulting in more valuable expansion slots left free for your future growth. ALR's years of expertise in providing demanding OEM's with IBM compatible systems results in outstanding products for all phases of your growing business.

**THE AT TOWER**—Big System Performance—The AT Tower gives you the best return on your hardware investment. Its floor standing package provides up to 4 full height drive subsystems to meet the most demanding requirements.

The heart of the AT Tower is an advanced IBM PC AT compatible computer with 33% more processing speed, 33% more hard disk storage and four times more RAM memory than the IBM's most powerful PC.

**THE NETWORK—ALR STAR NET**—Make It Simple—The ALR Star Net uses the low cost, quick connect telephone cords (RJ11) to link ALR XT workstations or IBM PCs to the resources of the AT Tower.

The ALR Star Net's local hook-up can be an incredible 1,000 feet and remote networking with modem support can be across the country. Software support of the Star Net provides you with the security of passwords and user ID, along with priority network access to maintain full control of resource sharing.

**ADVANCED LOGIC RESEARCH, INC.**

**2991 E. WHITE STAR AVE.**

**ANAHEIM, CA 92806**

**(714) 666-2951**


# ALR

IBM is a registered trademark of IBM Corporation.  
Xenix is a registered trademark of Microsoft Corporation.

CIRCLE 116 ON READER SERVICE CARD



# The Transporter Night Shift



## Long After Your Staff Goes Home, We Keep Your PC Making Calls, Sending and Receiving Files, and Keeping a Log

Your microcomputer doesn't go home at five. Why not keep it working?

TRANSPORTER keeps your PC communicating almost as well as your staff could do it. Just load it with a "task list" before you go home. It can automatically call other computers, log in, repeat calls if necessary, send and receive files, and more.

It can do it overnight, when phone rates are lowest.

The next morning, TRANSPORTER gives you a report of what it has accomplished during its night shift.

So you can start the day ahead of the game.

TRANSPORTER comes with our popular CROSSTALK data communications program added on. It communicates with any other system running TRANSPORTER or CROSSTALK. For details, see your retailer or write for a brochure.

**MICROSTUF**<sup>®</sup>

1000 Holcomb Woods Parkway  
Roswell, Georgia 30076

For the IBM Personal Computer. Requires 128K RAM, two disk drives, PC-DOS, Asynchronous Communications interface or equivalent RS232 connection, and a modem compatible with the 'AT' command set.

# TRANSPORTER<sup>™</sup>

CIRCLE 167 ON READER SERVICE CARD